\$125 Suggested Price

## RCA

# Receiving Tube Manual





RADIO CORPORATION of AMERICA

Electronic Components and Devices Harrison, N. J.

## Contents

| ELECTRONS, ELECTRODES, AND ELECTRON TUBES Electrons, Cathodes, Generic Tube Types, Diodes, Triodes, Tetrodes, Pentodes, Beam Power Tubes, Multi-Electrode and Multi-Unit Types, Receiving Tube Structure, Television Picture Tubes   |      |
|--|------|
| ELECTRON TUBE CHARACTERISTICS  | . 13 |
| ELECTRON TUBE APPLICATIONS   |      |
| FILECTRON TUBE INSTALLATION  Filament and Heater Power Supply, Heater-to-Cathode Connection, Plate Voltage Supply, Grid Voltage Supply, Screen-Grid Voltage Supply, Shielding, Dress of Circuit Leads, Filters, Output-Coupling Devices, High-Fidelity Systems, High-Voltage Considerations for Television Picture Tubes, Picture-Tube Safety Considerations |      |
| INTERPRETATION OF TUBE DATA  | . 74 |
| APPLICATION GUIDE FOR RCA RECEIVING TUBES  | . 80 |
| TECHNICAL DATA FOR RCA TUBE TYPES  | . 89 |
| PICTURE-TUBE CHARACTERISTICS CHART   |      |
| RCA VOLTAGE-REGULATOR AND  |      |
| VOLTAGE-REFERENCE TUBES  | 558  |
| ELECTRON TUBE TESTING  | 559  |
| RESISTANCE-COUPLED AMPLIFIERS  | 563  |
| OUTLINES   | 572  |
| CIRCUITS   | 576  |
| INDEX  | 603  |

Information furnished by RCA is believed to be accurate and reliable. However, no responsibility is assumed by RCA for its use; nor for any infringements of patents or other rights of third parties which may result from its use. No license is granted by implication or otherwise under any patent or patent rights of RCA.

Copyright 1964 by Radio Corporation of America (All Rights Reserved)




## RCA Receiving Tube Manual

THIS MANUAL, like its preceding editions, has been prepared to assist those who work or experiment with home-entertainment-type electron tubes and circuits. It will be found valuable by engineers, service technicians, educators, experimenters, radio amateurs, hobbyists, students, and many others technically interested in electron tubes.

The material in this edition has been augmented and revised to include the recent technological advances in the electronics field. Many tube types widely used in the design of new electronic equipment only a few years ago are now chiefly of interest for renewal purposes. Consequently, in the Tube Types Section, information on many older types is limited to basic essential data; information on newer and more important types is given in greater detail.

## RADIO CORPORATION OF AMERICA



## Electrons, Electrodes and Electron Tubes

THE electron tube is a marvelous device. It makes possible the performing of operations, amazing in conception, with a precision and a certainty that are astounding. It is an exceedingly sensitive and accurate instrument—the product of coordinated efforts of engineers and craftsmen. Its construction requires materials from every corner of the earth. Its use is world-wide. Its future possibilities, even in the light of present-day accomplishments, are but dimly foreseen, for each development opens new fields of design and application.

The importance of the electron tube lies in its ability to control almost instantly the flight of the millions of electrons supplied by the cathode. It accomplishes this control with a minimum of energy. Because it is almost instantaneous in its action, the electron tube can operate efficiently and accurately at electrical frequencies much higher than those attainable with rotating machines.

### Electrons

All matter exists in the solid, liquid, or gaseous state. These three forms consist entirely of minute divisions known as molecules, which, in turn, are composed of atoms. Atoms have a nucleus which is a positive charge of electricity, around which revolve tiny charges of negative electricity known as electrons. Scientists have estimated that electrons weigh only 1/30-billion, billion, billion, billionths of an ounce, and that they may travel at speeds of thousands of miles per second.

Electron movement may be accelerated by the addition of energy. Heat is

one form of energy which can be conveniently used to speed up the electron. For example, if the temperature of a metal is gradually raised, the electrons in the metal gain velocity. When the metal becomes hot enough, some electrons may acquire sufficient speed to break away from the surface of the metal. This action, which is accelerated when the metal is heated in a vacuum, is utilized in most electron tubes to produce the necessary electron supply.

An electron tube consists of a cathode, which supplies electrons, and one or more additional electrodes, which control and collect these electrons, mounted in an evacuated envelope. The envelope may be made of glass, metal, ceramic, or a combination of these materials.

## Cathodes

A cathode is an essential part of an electron tube because it supplies the electrons necessary for tube operation. When energy in some form is applied to the cathode, electrons are released. Heat is the form of energy generally used. The method of heating the cathode may be used to distinguish between the different forms of cathodes. For example, a directly heated cathode, or filament-cathode, is a wire heated by the passage of an electric current. An indirectly heated cathode, or heatercathode, consists of a filament, or heater, enclosed in a metal sleeve. The sleeve carries the electron-emitting material on its outside surface and is heated by radiation and conduction from the heater.

A filament, or directly heated cathode, such as that shown in Fig. 1 may be further classified by identifying the filament or electron-emitting material. The materials in regular use are tungsten, thoriated tungsten, and metals which have been coated with alkaline-earth oxides. Tungsten filaments are made from the pure metal. Because they must operate at high temperatures (a dazzling white) to emit sufficient electrons, a relatively large amount of filament power is required.

Thoriated-tungsten filaments are made from tungsten impregnated with thorium oxide. Due to the presence of thorium, these filaments liberate electrons at a more moderate temperature of about 1700°C (a bright yellow) and are, therefore, much more economical of filament power than are pure tungsten filaments.

Alkaline earths are usually applied as a coating on a nickel-alloy wire or ribbon. This coating, which is dried in a relatively thick layer on the filament, requires only a relatively low temperature of about 700-750°C (a dull red) to produce a copious supply of electrons. Coated filaments operate very efficiently and require relatively little filament power. However, each of these cathode materials has special advantages which determine the choice for a particular application.

Directly heated filament-cathodes require comparatively little heating power. They are used in tube types designed for battery operation because it is, of course, desirable to impose as small a drain as possible on the batteries. They are also used in rectifiers such as the 1G3GT/1B3GT and the 5Y3GT.

An indirectly heated cathode, or heater-cathode, consists of a thin metal sleeve coated with electron-emitting material such as alkaline-earth oxides. The emissive surface of the cathode is maintained at the required temperature (approximately 1050°K) by resistance-heating of a tungsten or tungsten-alloy wire which is placed inside the cathode sleeve and electrically insulated from it, as shown in Fig. 2. The heater is used only for the purpose of heating the cathode sleeve and sleeve coating to an electron-emitting temperature.

Useful emission does not take place from the heater wire.

A new dark heater insulating coating developed by RCA has better heat transfer than earlier aluminum-oxide coatings, and makes it possible to operate heaters at lower temperatures for given power inputs. Because the tensile strength of the heater wire increases at the lower operating temperatures, tubes using dark heaters have increased reliability, stability, and life.




Fig. 1—Filament or directly heated cathode.

Fig. 2—Indirectly heated cathode or heater-cathode.

The heater-cathode construction is well adapted for use in electron tubes intended for operation from ac power lines and from storage batteries. The use of separate parts for emitter and heater functions, the electrical insulation of the heater from the emitter, and the shielding effect of the sleeve may all be utilized in the design of the tube to minimize the introduction of hum from the ac heater supply and to minimize electrical interference which might enter the tube circuit through the heater-supply line. From the viewpoint of circuit design, the heater-cathode construction offers advantages in connection flexibility because of the electrical separation of the heater from the cathode.

Another advantage of the heatercathode construction is that it makes practical the design of a rectifier tube having close spacing between its cathode and plate, and of an amplifier tube having close spacing between its cathode and grid. In a close-spaced rectifier tube, the voltage drop in the tube is low, and, therefore, the regulation is improved. In an amplifier tube, the close spacing increases the gain obtainable from the tube. Because of the advantages of the heater-cathode construction, almost all present-day receiving tubes designed for ac operation have heater-cathodes.

## **Generic Tube Types**

Electrons are of no value in an electron tube unless they can be put to work. Therefore, a tube is designed with the parts necessary to utilize electrons as well as those required to produce them. These parts consist of a cathode and one or more supplementary electrodes. The electrodes are enclosed in an evacuated envelope having the necessary connections brought out through air-tight seals. The air is removed from the envelope to allow free movement of the electrons and to prevent injury to the emitting surface of the cathode.

When the cathode is heated, electrons leave the cathode surface and form an invisible cloud in the space around it. Any positive electric potential within the evacuated envelope offers a strong attraction to the electrons (unlike electric charges attract; like charges repel). Such a positive electric potential can be supplied by an anode (positive electrode) located within the tube in proximity to the cathode.

## **Diodes**

The simplest form of electron tube contains two electrodes, a cathode and an anode (plate), and is often called a diode, the family name for a two-electrode tube. In a diode, the positive potential is supplied by a suitable electrical source connected between the plate terminal and a cathode terminal, as shown in Fig. 3. Under the influence of the positive plate potential, electrons




Fig. 3-Basic diode circuit.

flow from the cathode to the plate and return through the external plate-battery circuit to the cathode, thus completing the circuit. This flow of electrons is known as the plate current.

If a negative potential is applied to the plate, the free electrons in the space surrounding the cathode will be forced back to the cathode and no plate current will flow. If an alternating voltage is applied to the plate, the plate is alternately made positive and negative. Because plate current flows only during the time when the plate is positive, current flows through the tube in only one direction and is said to be rectified. Fig. 4 shows the rectified output current produced by an alternating input voltage.




Fig. 4—Current characteristics of rectifier circuit.

Diode rectifiers are used in ac receivers to convert the ac supply voltage to de voltage for the electrodes of the other tubes in the receiver. Rectifier tubes having only one plate and one cathode, such as the 35W4, are called half-wave rectifiers, because current can flow only during one-half of the alternating-current cycle. When two plates and one or more cathodes are used in the same tube, current may be obtained on both halves of the ac cycle. The 6X4, 5Y3GT, and 5U4GB are examples of this type and are called full-wave rectifiers.

Not all of the electrons emitted by the cathode reach the plate. Some return to the cathode, while others remain in the space between the cathode and plate for a brief period to produce

an effect known as space charge. This charge has a repelling action on other electrons which leave the cathode surface and impedes their passage to the plate. The extent of this action and the amount of space charge depend on the cathode temperature, the distance between the cathode and the plate, and the plate potential. The higher the plate potential, the less is the tendency for electrons to remain in the space-charge region and repel other electrons. This effect may be noted by applying increasingly higher plate voltages to a tube operating at a fixed heater or filament voltage. Under these conditions, the maximum number of available electrons is fixed, but increasingly higher plate voltages will succeed in attracting a greater proportion of the free electrons.

Beyond a certain plate voltage, however, additional plate voltage has little effect in increasing the plate current because all of the electrons emitted by the cathode are already being drawn to the plate. This maximum current, illustrated in Fig. 5, is called saturation current. Because it is an indication of the total number of electrons emitted, it is also known as emission current or simply emission.




Fig. 5—Current characteristic of diode tube.

Although tubes are sometimes tested by measurement of their emission current, it is generally not advisable to measure the full value of emission because this value would be sufficiently large to cause change in the tube characteristics or even to damage the tube. Consequently, while the test value of emission current is somewhat larger than the maximum current which will be required from the cathode in the

use of the tube, it is ordinarily less than the full emission current. The emission test, therefore, is used to indicate whether the cathode can supply a sufficient number of electrons for satisfactory operation of the tube.

If space charge were not present to repel electrons coming from the cathode, the same plate current could be produced at a lower plate voltage. One way to make the effect of space charge small is to make the distance between plate and cathode small. This method is used in rectifier types having heater-cathodes, such as the 5V4GA and the 6AX5GT. In these types the radial distance between cathode and plate is only about two hundredths of an inch.

Another method of reducing spacecharge effect is utilized in mercuryvapor rectifier tubes. When such tubes are operated, a small amount of mercury contained in the tube is partially vaporized, filling the space inside the bulb with mercury atoms. These atoms are bombarded by electrons on their way to the plate. If the electrons are moving at a sufficiently high speed, the collisions tear off electrons from the mercury atoms. The mercury atom is then said to be "ionized," i.e., it has lost one or more electrons and, therefore, has a positive charge. Ionization is evidenced by a bluish-green glow between the cathode and plate. When ionization occurs, the space charge is neutralized by the positive mercury atoms so that increased numbers of electrons are made available. Mercury-vapor tubes are used primarily for power rectifiers.

Ionic-heated-cathode rectifiers depend on gas ionization for their operation. These tubes are of the full-wave design and contain two anodes and a coated cathode sealed in a bulb containing a reduced pressure of inert gas. The cathode becomes hot during tube operation, but the heating effect is caused by bombardment of the cathode by ions within the tube rather than by heater or filament current from an external source.

The internal structure of an ionicheated-cathode tube is designed so that when sufficient voltage is applied to the tube, ionization of the gas occurs be-

tween the anode which is instantaneously positive and the cathode. Under normal operating voltages, ionization does not take place between the anode that is negative and the cathode, so that the requirements for rectification are satisfied. The initial small flow of current through the tube is sufficient to raise the cathode temperature quickly to incandescence, whereupon the cathode emits electrons. The voltage drop in such tubes is slightly higher than that of the usual hot-cathode gas rectifiers because energy is taken from the ionization discharge to keep the cathode at operating temperature. Proper operation of these rectifiers requires a minimum flow of load current at all times to maintain the cathode at the temperature required to supply sufficient emission.

## **Triodes**

When a third electrode, called the grid, is placed between the cathode and plate, the tube is known as a triode, the family name for a three-electrode tube. The grid usually consists of relatively fine wire wound on two support rods (siderods) and extending the length of the cathode. The spacing between turns of wire is large compared with the size of the wire so that the passage of electrons from cathode to plate is practically unobstructed by the grid. In some types, a frame grid is used. The frame consists of two siderods supported by four metal straps. Extremely fine lateral wire (diameter of 0.5 mil or less) is wound under tension around the frame. This type of grid permits the use of closer spacings between grid wires and between tube electrodes. and thus improves tube performance.

The purpose of the grid is to control the flow of plate current. When a tube is used as an amplifier, a negative dc voltage is usually applied to the grid. Under this condition the grid does not draw appreciable current.

The number of electrons attracted to the plate depends on the combined effect of the grid and plate polarities, as shown in Fig. 6. When the plate is positive, as is normal, and the dc grid voltage is made more and more negative, the plate is less able to attract electrons to it and plate current decreases. When the grid is made less and less negative (more and more positive), the plate more readily attracts electrons to it and plate current increases. Hence, when the voltage on the grid is varied in accordance with a signal, the plate current varies with the signal. Because a small voltage applied to the grid can control a comparatively large amount of plate current, the signal is amplified by the tube. Typical three-electrode tube types are the 6C4 and 6AF4A.




Fig. 6—Basic triode circuit.

The grid, plate, and cathode of a triode form an electrostatic system, each electrode acting as one plate of a small capacitor. The capacitances are those existing between grid and plate, plate and cathode, and grid and cathode. These capacitances are known as interelectrode capacitances. Generally, the capacitance between grid and plate is of the most importance. In high-gain radio-frequency amplifier circuits, this capacitance may act to produce undesired coupling between the input circuit, the circuit between grid and cathode, and the output circuit, the circuit between plate and cathode. This coupling is undesirable in an amplifier because it may cause instability and unsatisfactory performance.

## **Tetrodes**

The capacitance between grid and plate can be made small by mounting an additional electrode, called the screen grid (grid No. 2), in the tube. With the addition of the grid No. 2, the tube has four electrodes and is, accordingly, called a tetrode. The screen

grid or grid No. 2 is mounted between the grid No. 1 (control grid) and the plate, as shown in Fig. 7, and acts as an electrostatic shield between them, thus reducing the grid-to-plate capacitance. The effectiveness of this shielding action is increased by a bypass




Fig. 7-Basic tetrode circuit.

capacitor connected between screen grid and cathode. By means of the screen grid and this bypass capacitor, the grid-plate capacitance of a tetrode is made very small. In practice, the grid-plate capacitance is reduced from several picofarads (pf) for a triode to 0.01 pf or less for a screen-grid tube.

The screen grid has another desirable effect in that it makes plate current practically independent of plate voltage over a certain range. The screen grid is operated at a positive voltage and, therefore, attracts electrons from the cathode. However, because of the comparatively large space between wires of the screen grid, most of the electrons drawn to the screen grid pass through it to the plate. Hence the screen grid supplies an electrostatic force pulling electrons from the cathode to the plate. At the same time the screen grid shields the electrons between cathode and screen grid from the plate so that the plate exerts very little electrostatic force on electrons near the cathode.

So long as the plate voltage is higher than the screen-grid voltage, plate current in a screen-grid tube depends to a great degree on the screen-grid voltage and very little on the plate voltage. The fact that plate current in a screen-grid tube is largely independent of plate voltage makes it possible to obtain much higher amplification with a tetrode than with a triode. The

low grid-plate capacitance makes it possible to obtain this high amplification without plate-to-grid feedback and resultant instability. In receiving-tube applications, the tetrode has been replaced to a considerable degree by the pentode.

## **Pentodes**

In all electron tubes, electrons striking the plate may, if moving at sufficient speed, dislodge other electrons. In two- and three-electrode types, these dislodged electrons usually do not cause trouble because no positive electrode other than the plate itself is present to attract them. These electrons, therefore, are drawn back to the plate. Emission caused by bombardment of an electrode by electrons from the cathode is called secondary emission because the effect is secondary to the original cathode emission.

In the case of screen-grid tubes, the proximity of the positive screen grid to the plate offers a strong attraction to these secondary electrons, and particularly so if the plate voltage swings lower than the screen-grid voltage. This effect reduces the plate current and limits the useful plate-voltage swing for tetrodes.

The effects of secondary emission are minimized when a fifth electrode is placed within the tube between the screen grid and plate. This fifth electrode is known as the suppressor grid (grid No. 3) and is usually connected to the cathode, as shown in Fig. 8. Because of its negative potential with respect to the plate, the suppressor grid retards the flight of secondary electrons and diverts them back to the plate.




Fig. 8-Basic pentode circuit.

The family name for a five-electrode tube is "pentode." In power-output pentodes, the suppressor grid makes possible higher power output with lower grid-driving voltage; in radio-frequency amplifier pentodes, the suppressor grid makes possible high voltage amplification at moderate values of plate voltage. These desirable features result from the fact that the plate-voltage swing can be made very large. In fact, the plate voltage may be as low as, or lower than, the screen-grid voltage without serious loss in signal-gain capability. Representative pentodes used for power amplification are the 6CL6 and 6K6GT; representative pentodes used for voltage amplification are the 6AU6A, 6BA6, and 5879.

### **Beam Power Tubes**

A beam power tube is a tetrode or pentode in which directed electron beams are used to increase substantially the power-handling capability of the tube. Such a tube contains a cathode, a control grid (grid No. 1), a screen grid (grid No. 2), a plate, and, optionally, a suppressor grid (grid No. 3). When a beam power tube is designed without an actual suppressor grid, the electrodes are so spaced that secondary emission from the plate is suppressed by space-charge effects between screen grid and plate. The space charge is produced by the slowing up of electrons traveling from a high-potential screen grid to a lower-potential plate. In this low-velocity region, the space charge produced is sufficient to repel secondary electrons emitted from the plate and to cause them to return to the plate.

Beam power tubes of this design employ beam-confining electrodes at cathode potential to assist in producing the desired beam effects and to prevent stray electrons from the plate from returning to the screen grid outside of the beam. A feature of a beam power tube is its low screen-grid current. The screen-grid and the control grid are spiral wires wound so that each turn of the screen grid is shaded from the cathode by a grid turn. This alignment of the screen

grid and control grid causes the electrons to travel in sheets between the turns of the screen grid so that very few of them strike the screen grid. Because of the effective suppressor action provided by space charge and because of the low current drawn by the screen grid, the beam power tube has the advantages of high power output, high power sensitivity, and high efficiency.

Fig. 9 shows the structure of a beam power tube employing spacecharge suppression and illustrates how




Fig. 9—Structure of beam power tube showing beam-confining action.

the electrons are confined to beams. The beam condition illustrated is that for a plate potential less than the screen-grid potential. The high-density space-charge region is indicated by the heavily dashed lines in the beam. Note that the edges of the beam-confining electrodes coincide with the dashed portion of the beam. In this way the space-charge potential region is extended beyond the beam boundaries and stray secondary electrons are prevented from returning to the screen grid outside of the beam. The spacecharge effect may also be obtained by use of an actual suppressor grid. Examples of beam power tubes are 6AQ5A, 6L6GC, 6V6GTA, and 50C5.

## Multi-Electrode and Multi-Unit Tubes

Early in the history of tube devel-

opment and application, tubes were designed for a general service; that is, a single tube type—a triode—was used as a radio-frequency amplifier, an intermediate-frequency amplifier, an audio-frequency amplifier, an oscillator, or a detector. Obviously, with this diversity of application, one tube did not meet all requirements to the best advantage.

Later and present trends of tube design are the development of "specialty" types. These types are intended either to give optimum performance in a particular application or to combine in one bulb functions which formerly required two or more tubes. The first class of tubes includes such examples of specialty types as the 6CB6A and 6BY6. Types of this class generally require more than three electrodes to obtain the desired special characteristics and may be broadly classed as multielectrode types. The 6BY6 is an especially interesting type in this class. This tube has an unusually large number of electrodes, namely seven, exclusive of the heater. Plate current in the tube is varied at two different frequencies at the same time. The tube is designed primarily for use as a combined sync separator and sync clipper in television receivers.

The second class includes multiunit tubes such as the twin-diode triodes 6CN7 and 6AV6, as well as triode-pentodes such as the 6U8A and 6X8. This class also includes class A twin triodes such as the 6CG7 and 12AX7A, and types such as the 6CM7 containing dissimilar triode units used primarily as combined vertical oscillators and vertical deflection amplifiers in television receivers. Full-wave rectifiers are also multi-unit types.

A third class of tubes combines features of each of the other two classes. Typical of this third class are the pentagrid-converter types 6BE6 and 6SA7. These tubes are similar to the multielectrode types in that they have seven electrodes, all of which affect the electron stream; and they are similar to the multi-unit tubes in that they perform simultaneously the double function of oscillator and mixer in superheterodyne receivers.

## **Receiving Tube Structure**

Receiving tubes generally utilize a glass or metal envelope and a base. Originally, the base was made of metal or molded phenolic material. Types having a glass envelope and a molded phenolic base include the "octal" types such as the 5U4GB and the 6SN7GTB. Types having a metal envelope and molded phenolic octal base include the 6F6 and the 6L6. Many modern types utilize integral glass bases. Present-day conventional tube designs utilizing glass envelopes and integral glass bases include the seven-pin and nine-pin miniature types, the nine-pin novar and neonoval types, and the twelve-pin duodecar types. Examples of the seven-pin miniature types are the 6AU6A and 6BN6. Examples of the nine-pin miniature types are the 12AU7A and 6EA8. Examples of the novar types are the 6BH3 and 7868. The nine-pin base for the novar types has a relatively large pin-circle diameter and long pins to insure firm retention of the tube in its socket.

The nuvistor concept provided a new approach to electron tube design. Nuvistor tubes utilize a light-weight cantilever-supported cyclindrical electrode structure housed in a ceramic-metal envelope. These tubes combine new materials, processes, and fabrication techniques. Examples of the nuvistor are the 6CW4 and the 6DV4.

## **Television Picture Tubes**

The picture tube, or kinescope, is a multi-electrode tube used principally in television receivers for picture display. It consists essentially of an electron gun, a glass or metal-and-glass envelope and face-plate combination, and a fluorescent screen.

The electron gun includes a cathode for the production of free electrons, one or more control electrodes for accelerating the electrons in the beam, and, optionally, a device for "trapping" unwanted ions out of the electron beam.

Focusing of the beam is accomplished either electromagnetically by

means of a focusing coil placed on the neck of the tube, or electrostatically, as shown in Fig. 10a, by means of a focusing electrode (grid No. 4) within the envelope of the tube. The screen is a white-fluorescing phosphor P4 of either the silicate or the sulfide type.

Deflection of the beam is accomplished either electrostatically by means of deflecting electrodes within the envelope of the tube, or electromagnetically by means of a deflecting yoke placed on the neck of the tube. Fig. 10a shows the structure of the gun section of a picture tube and illustrates how the electron beam is formed and how the beam is deflected by means of an electromagnetic deflecting yoke. In this type of tube, ions in the beam are prevented from damaging the fluorescent screen by an aluminum film on the gun side of the screen. This film not only "traps" unwanted ions, but also improves picture contrast. In many types of non-aluminized tubes, ions are separated from the electron beam by means of a tilted-gun and ion-trapmagnet arrangement.

Color television picture tubes are similar to black-and-white picture tubes, but differ in three major ways. (1) The light-emitting screen is made up of trios of phosphor dots deposited in an interlaced pattern. Each dot of a trio is capable of emitting light in one of the three primary colors (red, green, or blue). (2) A shadow mask mounted near the screen of the tube contains over 300,-000 apertures, one for each of the phosphor dot trios. This mask provides color separation by shadowing two of the three phosphor dots of each trio. (3) Three closely spaced electron guns, built as a unit, provide separate beams for excitation of the three different color-phosphor-dot arrays. Thus it is possible to control the brightness of each of the three colors independently of the other two. Fig. 10b shows a cutaway view of a color television picture tube.

The three electron guns mounted with their axes tilted toward the central axis of the envelope, and are spaced 120 degrees with respect to each other. The focusing electrodes of the three guns are interconnected internally, and their potential is adjusted to cause the separate beams to focus at the phosphor-dot screen. All three beams must be made to converge at the screen while they are simultaneously being deflected. Convergence is accomplished by the action of static and




Fig. 10a-Structure of television-picture-tube electron gun.

dynamic magnetic fields set up by the radial-converging magnet assembly mounted on the neck of the tube. These fields are coupled into the radial-converging pole pieces within the tube. Another pair of pole pieces in the tube is activated by the lateral-converging magnet also mounted on the neck of the tube. These pole pieces permit lateral shift in position of the blue beam in opposition to the lateral shift of the green and red beams.

A purifying magnet is used with color picture tubes to provide a magnetic field, adjustable in magnitude and direction, to effect register over the entire area of the screen. A magnetic shield is used to minimize the effects of the earth's magnetic field.

Deflection of the three beams is accomplished simultaneously by a deflecting yoke using four electromagnetic coils similar to the deflecting yoke used for black-and-white picture tubes.




Fig. 10b-Cutaway view of color television picture tube.

## Electron Tube Characteristics

THE term "characteristics" is used to identify the distinguishing electrical features and values of an electron tube. These values may be shown in curve form or they may be tabulated. When the characteristics values are given in curve form, the curves may be used for the determination of tube performance and the calculation of additional tube factors.

Tube characteristics are obtained from electrical measurements of a tube in various circuits under certain definite conditions of voltages. Characteristics may be further described by denoting the conditions of measurements. For example, Static Characteristics are the values obtained with different dc potentials applied to the tube electrodes, while Dynamic Characteristics are the values obtained with an ac voltage on a control grid under various conditions of dc potentials on the electrodes. The dynamic characteristics, therefore, are indicative of the performance capahilities of a tube under actual working conditions.

Static characteristics may be shown by plate characteristics curves and transfer (mutual) characteristics curves. These curves present the same information, but in two different forms to increase its usefulness. The plate characteristic curve is obtained by varying plate voltage and measuring plate current for different grid-bias voltages, while the transfer-characteristic curve is obtained by varying grid-bias voltage and measuring plate current for different plate voltages. A plate-characteristic family of curves is shown in Fig. 11. Fig. 12 gives the transfer-characteristic family of curves for the same tube. Dynamic characteristics include amplification factor, plate resistance, control-grid—plate transconductance, and certain detector characteristics, and may be shown in curve form for variations in tube operating conditions.




Fig. 11—Family of plate-characteristics curves.

The amplification factor, or  $\mu$ , is the ratio of the change in plate voltage to a change in control-electrode voltage in the opposite direction, under the condition that the plate current remains




Fig. 12—Family of transfer-characteristics curves.

unchanged and that all other electrode voltages are maintained constant. For example, if, when the plate voltage is made 1 volt more positive, the control-electrode (grid-No. 1) voltage must be made 0.1 volt more negative to hold plate current unchanged, the amplification factor is 1 divided by 0.1, or 10. In other words, a small voltage variation in the grid circuit of a tube has the same effect on the plate current as a large plate-voltage change—the latter equal to the product of the grid-voltage change and amplification factor. The  $\mu$  of a tube is often useful for calculating stage gain. This use is discussed in the Electron Tube Applications section.

Plate resistance (r<sub>p</sub>) of an electron tube is the resistance of the path between cathode and plate to the flow of alternating current. It is the quotient of a small change in plate voltage divided by the corresponding change in plate current and is expressed in ohms, the unit of resistance. Thus, if a change of 0.1 milliampere (0.0001 ampere) is produced by a plate-voltage variation of 1 volt, the plate resistance is 1 divided by 0.0001, or 10000 ohms.

Control-grid—plate transconductance, or simply transconductance (g<sub>m</sub>), is a factor which combines in one term the amplification factor and the plate resistance, and is the quotient of the first divided by the second. This term has also been known as mutual conductance. Transconductance may be more strictly defined as the quotient of a small change in plate current (amperes) divided by the small change in the control-grid voltage producing it, under the condition that all other voltages remain unchanged. Thus, if a grid-

voltage change of 0.5 volt causes a plate-current change of 1 milliampere (0.001 ampere), with all other voltages constant, the transconductance is 0.001 divided by 0.5, or 0.002 mho. A "mho" is the unit of conductance and was named by spelling ohm backwards. For convenience, a millionth of a mho, or a micromho (μmho), is used to express transconductance. Thus, in the example. 0.002 mho is 2000 micromhos.

Conversion transconductance (gc) is a characteristic associated with the mixer (first detector) function of tubes and may be defined as the quotient of the intermediate-frequency (if) current in the primary of the if transformer divided by the applied radio-frequency (rf) voltage producing it; more precisely, it is the limiting value of this quotient as the rf voltage and if current approach zero. When the performance of a frequency converter is determined. conversion transconductance is used in the same way as control-grid-plate transconductance is used in single-frequency amplifier computations.

The plate efficiency of a power amplifier tube is the ratio of the ac power output  $(P_o)$  to the product of the average dc plate voltage  $(E_b)$  and dc plate current  $(I_b)$  at full signal, or

Plate efficiency = 
$$\frac{P_o \text{ watts}}{E_b \text{ volts } \times I_b \text{ amperes}} \times 100$$

The power sensitivity of a tube is the ratio of the power output to the square of the input signal voltage (E<sub>1n</sub>), and is expressed in mhos as follows:

Power sensitivity (mhos) =  $\frac{P_0 \text{ watts}}{(E_{10}, \text{ rms})^2}$ 

## Electron Tube Applications

THE diversified applications of an electron receiving tube have, within the scope of this section, been treated under seven headings. These are: Amplification, Rectification, Detection, Automatic Volume or Gain Oscillation, Frequency Conversion, and Automatic Frequency Control. though these operations may take place at either radio or audio frequencies and may involve the use of different circuits and different supplemental parts, the general considerations of each kind of operation are basic.

## **Amplification**

The amplifying action of an electron tube was mentioned under Triodes in the section on Electrons, Electrodes, and Electron Tubes. This action can be utilized in electronic circuits in a number of ways, depending upon the results desired. Four classes of amplifier service recognized by engineers are covered by definitions standardized by the Institute of Radio Engineers (now the Institute of Electrical and Electronics Engineers). This classification depends primarily on the fraction of input cycle during which plate current is expected to flow under rated full-load conditions. The classes are class A, class AB, class B, and class C. The term "cutoff bias" used in these definitions is the value of grid bias at which plate current is very small.

## Classes of Service

A class A amplifier is an amplifier in which the grid bias and alternating grid voltages are such that plate current in a specific tube flows at all times.

A class AB amplifier is an amplifier in which the grid bias and alternating grid voltages are such that plate current in a specific tube flows for appreciably more than half but less than the entire electrical cycle.

A class B amplifier is an amplifier in which the grid bias is approximately equal to the cutoff value, so that the plate current is approximately zero when no exciting grid voltage is applied, and so that plate current in a specific tube flows for approximately one-half of each cycle when an alternating grid voltage is applied.

A class C amplifier is an amplifier in which the grid bias is appreciably greater than the cutoff value, so that the plate current in each tube is zero when no alternating grid voltage is applied, and so that plate current flows in a specific tube for appreciably less than one-half of each cycle when an alternating grid voltage is applied.

The suffix 1 may be added to the letter or letters of the class identification to denote that grid current does not flow during any part of the input cycle. The suffix 2 may be used to denote that grid current flows during part of the cycle.

For radio-frequency (rf) amplifiers which operate into a selective tuned circuit, as in radio transmitter applications, or under requirements where distortion is not an important factor, any of the above classes of amplifiers may be used, either with a single tube or with a push-pull stage. For audio-frequency (af) amplifiers in which distortion is an important factor, only class A amplifiers permit single-tube operation. In this case, operating con-

ditions are usually chosen so that distortion is kept below the conventional 5 per cent for triodes and the conventional 7 to 10 per cent for tetrodes or pentodes. Distortion can be reduced below these figures by means of special circuit arrangements such as that discussed under inverse feedback. With class A amplifiers, reduced distortion with improved power performance can be obtained by using a push-pull stage for audio service. With class AB and class B amplifiers, a balanced stage using two tubes is required for audio service.

## Class A Voltage Amplifiers

As a class A voltage amplifier, an electron tube is used to reproduce gridvoltage variations across an impedance or a resistance in the plate circuit. These variations are essentially of the same form as the input signal voltage impressed on the grid, but their amplitude is increased. This increase is accomplished by operation of the tube at a suitable grid bias so that the applied grid input voltage produces plate-current variations proportional to the signal swings. Because the voltage variation obtained in the plate circuit is much larger than that required to swing the grid, amplification of the signal is obtained.

Fig. 13 gives a graphical illustration of this method of amplication and shows, by means of the grid-voltage vs. plate-current characteristics curve, the effect of an input signal (S) applied to the grid of a tube. The output signal (O)




Fig. 13—Current characteristics of class A amplifier.

is the resulting amplified plate-current variation.

The plate current flowing through the load resistance (R) of Fig. 14 causes a voltage drop which varies directly with the plate current. The ratio of this voltage variation produced in the load resistance to the input signal voltage is




Fig. 14-Triode amplifier circuit.

the voltage amplification, or gain, provided by the tube. The voltage amplification due to the tube is expressed by the following convenient formulas:

Voltage amplification = 
$$\frac{\mu \times R_L}{R_L + r_p}$$

or 
$$\frac{g_m \times r_p \times R_L}{1000000 \times (r_p + R_L)}$$

where  $\mu$  is the amplification factor of the tube,  $R_L$  is the load resistance in ohms,  $r_P$  is the plate resistance in ohms, and  $g_m$  is the transconductance in micromhos.

From the first formula, it can be seen that the gain actually obtainable from the tube is less than the tube amplification factor, but that the gain approaches the amplification factor when the load resistance is large compared to the tube plate resistance. Fig. 15 shows graphically how the gain approaches the amplification factor of the tube as the load resistance is increased. From the curve it can be seen that a high value of load resistance should be used to obtain high gain in a voltage amplifier.

In a resistance-coupled amplifier, the load resistance of the tube is approximately equal to the resistance of the plate resistor in parallel with the grid resistor of the following stage. Hence, to obtain a large value of load resistance, it is necessary to use a plate resistor and a grid resistor of large




Fig. 15-Gain curve for triode amplifier circuit.

resistance. However, the plate resistor should not be too large because the flow of plate current through the plate resistor produces a voltage drop which reduces the plate voltage applied to the tube. If the plate resistor is too large, this drop will be too large, the plate voltage on the tube will be too small, and the voltage output of the tube will be too small. Also, the grid resistor of the following stage should not be too large, the actual maximum value being dependent on the particular tube type. This precaution is necessary because all tubes contain minute amounts of residual gas which cause a minute flow of current through the grid resistor. If the grid resistor is too large, the positive bias developed by the flow of this current through the resistor decreases the normal negative bias and produces an increase in the plate current. This increased current may overheat the tube and cause liberation of more gas which. in turn, will cause further decrease in bias. The action is cumulative and results in a runaway condition which can destroy the tube.

A higher value of grid resistance is permissible when cathode-resistor bias is used than when fixed bias is used. When cathode-resistor bias is used, a loss in bias due to gas or grid-emission effects is almost completely offset by an increase in bias due to the voltage drop across the cathode resistor. Typical values of plate resistor and grid resistor for tube types used in resistance-coupled circuits, and the values of gain obtainable, are shown in the Resistance-Coupled Amplifier section.

The input impedance of an electron tube (that is, the impedance between grid and cathode) consists of (1) a reactive component due to the capacitance between grid and cathode, (2) a resistive component resulting from the time of transit of electrons between cathode and grid, and (3) a resistive component developed by the part of the cathode lead inductance which is common to both the input and output circuits. Components (2) and (3) are dependent on the frequency of the incoming signal. The input impedance is very high at audio frequencies when a tube is operated with its grid biased negative. In a class A<sub>1</sub> or AB<sub>1</sub> transformer-coupled audio amplifier, therefore, the loading imposed by the grid on the input transformer is negligible. As a result, the secondary impedance of a class A<sub>1</sub> or class AB<sub>1</sub> input transformer can be made very high because the choice is not limited by the input impedance of the tube; however, transformer design considerations may limit the choice.

At the higher radio frequencies, the input impedance may become very low even when the grid is negative, due to the finite time of passage of electrons between cathode and grid and to the appreciable lead reactance. This impedance drops very rapidly as the frequency is raised, and increases input-circuit loading. In fact, the input impedance may become low enough at very high radio frequencies to affect the gain and selectivity of a preceding stage appreciably. Tubes such as the "acorn" and "pencil" types and the high-frequency miniatures have been

developed to have low input capacitances, low electron-transit time, and low lead inductance so that their input impedance is high even at the ultrahigh radio frequencies. Input admittance is the reciprocal of input impedance.

A remote-cutoff amplifier tube is a modified construction of a pentode or a tetrode type designed to reduce modulation-distortion and cross-modulation in radio-frequency stages. Crossmodulation is the effect produced in a radio or television receiver by an interfering station "riding through" the carrier of the station to which the receiver is tuned. Modulation-distortion is a distortion of the modulated carrier and appears as audio-frequency distortion in the output. This effect is produced by a radio-frequency amplifier stage operating on an excessively curved characteristic when the grid bias has been increased to reduce volume. The offending stage for cross-modulation is usually the first radio-frequency amplifier, while for modulation-distortion the cause is usually the last intermediate-frequency stage. The characteristics of remote-cutoff types are such as to enable them to handle both large and small input signals with minimum distortion over a wide range of signal strength.

Fig. 16 illustrates the construction of the grid No. 1 (control grid) in a remote-cutoff tube. The remote-cutoff




Fig. 16-Structure of remote-cutoff grid.

action is due to the structure of the grid which provides a variation in amplification factor with change in grid bias. The grid No. 1 is wound with open spacing at the middle and with close spacing at the ends. When weak signals and low grid bias are applied to the tube, the effect of the non-uniform turn spacing of the grid on cathode emission and tube characteristics is essentially the same as for uniform spacing. As the grid bias is made more negative to handle larger input signals, the electron flow from the sections of the cathode enclosed by the ends of the grid is cut off. The plate current and other tube characteristics are then dependent on the electron flow through the open section of the grid. This action changes the gain of the tube so that large signals may be handled with minimum distortion due to cross-modulation and modulation-distortion.

Fig. 17 shows a typical plate-current vs. grid-voltage curve for a remote-cutoff type compared with the curve




Fig. 17—Plate-current curves for triodes having remote-cutoff and uniformly spaced grids.

for a type having a uniformly spaced grid. It will be noted that while the curves are similar at small grid-bias voltages, the plate current of the remote-cutoff tube drops quite slowly with large values of bias voltage. This slow change makes it possible for the tube to handle large signals satisfactorily. Because remote-cutoff types can accommodate large and small signals, they are particularly suitable for use in sets having automatic volume control. Remote-cutoff tubes also are known as variable-mu types.

## Class A Power Amplifiers

As a class A power amplifier, an electron tube is used in the output stage of a radio or television receiver to supply a relatively large amount of power

to the loudspeaker. For this application, large power output is of more importance than high voltage amplification; therefore, gain possibilities are sacrificed in the design of power tubes to obtain power-handling capability.

Triodes, pentodes, and beam power tubes designed for power amplifier service have certain inherent features for each structure. Power tubes of the triode type for class A service are characterized by low power sensitivity, low plate-power efficiency, and low distortion. Power tubes of the pentode type are characterized by high power sensitivity, high plate-power efficiency and, usually, somewhat higher distortion than class A triodes. Beam power tubes have higher power sensitivity and efficiency than triode or conventional pentode types.

A class A power amplifier is also used as a driver to supply power to a class AB<sub>2</sub> or a class B stage. It is usually advisable to use a triode, rather than a pentode, in a driver stage because of the lower plate impedance of the triode.

Power tubes connected in either parallel or push-pull may be employed as class A amplifiers to obtain increased output. The parallel connection (Fig. 18) provides twice the output of a single tube with the same value of grid-signal voltage. With this connection,




Fig. 18—Power amplifier with tubes connected in parallel.

the effective transconductance of the stage is doubled, and the effective plate resistance and the load resistance required are halved as compared with single-tube values.

The push-pull connection (Fig. 19), although it requires twice the grid-

signal voltage, provides increased power and has other important advantages




Fig. 19—Power amplifier with tubes connected in push-pull.

over single-tube operation. Distortion caused by even-order harmonics and hum caused by plate-voltage-supply fluctuations are either eliminated or decidedly reduced through cancellation. Because distortion for push-pull operation is less than for single-tube operation, appreciably more than twice single-tube output can be obtained with triodes by decreasing the load resistance for the stage to a value approaching the load resistance for a single tube.

For either parallel or push-pull class A operation of two tubes, all electrode currents are doubled while all de electrode voltages remain the same as for single-tube operation. If a cathode resistor is used, its value should be about one-half that for a single tube. If oscillations occur with either type of connection, they can often be eliminated by the use of a non-inductive resistor of approximately 100 ohms connected in series with each grid at the socket terminal.

Operation of power tubes so that the grids run positive is inadvisable except under conditions such as those discussed in this section for class AB and class B amplifiers.

## Power-Output Calculations

Calculation of the power output of a triode used as a class A amplifier with either an output transformer or a choke having low de resistance can be made without serious error from the plate family of curves by assuming a resistance load. The proper plate current, grid bias, optimum load resistance, and per-cent second-harmonic distortion can also be determined. The calculations are made graphically and are illustrated in Fig. 20 for given conditions. The procedure is as follows:

(1) Locate the zero-signal bias point P by determining the zero-signal bias Ec. from the formula:

Zero-signal bias (Ec<sub>o</sub>) =  $-(0.68 \times E_b)/\mu$ 

where  $E_b$  is the chosen value in volts of dc plate voltage at which the tube is to be operated, and  $\mu$  is the amplification factor of the tube. This quantity is shown as negative to indicate that a negative bias is used.

- (2) Locate the value of zero-signal plate current, I., corresponding to point P.
- (3) Locate the point  $2I_0$ , which is twice the value of  $I_0$  and corresponds to the value of the maximum-signal plate current  $I_{max}$ .
- (4) Locate the point X on the dc bias curve at zero volts,  $E_c=0$ , corresponding to the value of  $I_{max}$ .

(5) Draw a straight line XY through X and P.

Line XY is known as the load resistance line. Its slope corresponds to the value of the load resistance. The load resistance in ohms is equal to  $(E_{max} - E_{min})$  divided by  $(I_{max} - I_{min})$ , where E is in volts and I is in amperes.

It should be noted that in the case of filament types of tubes, the calculations are given on the basis of a dcoperated filament. When the filament is ac-operated, the calculated value of dc bias should be increased by approximately one-half the filament voltage rating of the tube.

The value of zero-signal plate current I. should be used to determine the plate dissipation, an important factor influencing tube life. In a class A amplifier under zero-signal conditions, the plate dissipation is equal to the power input, i.e., the product of the dc plate voltage E<sub>o</sub> and the zero-signal dc plate current Io. If it is found that the platedissipation rating of the tube is exceeded with the zero-signal bias Ec. calculated above, it will be necessary to increase the bias by a sufficient amount so that the actual plate dissipation does not exceed the rating before proceeding further with the remaining calculations.

For power-output calculations, it is assumed that the peak alternating grid voltage is sufficient (1) to swing the grid from the zero-signal bias value  $E_{\rm c}$  to zero bias ( $E_{\rm c}=0$ ) on the positive swing and (2) to swing the grid to a value twice the zero-signal bias value on the negative swing. During the negative swing, the plate voltage and plate current reach values of  $E_{\rm max}$  and  $I_{\rm min}$ ; during the positive swing, they reach values of  $E_{\rm min}$  and  $I_{\rm max}$ . Because power is the product of voltage and current, the power output  $P_{\rm o}$  as shown by a watt-meter is given by

$$P_o = \frac{(I_{max} - I_{min}) \times (E_{max} - E_{min})}{2}$$

where E is in volts, I is in amperes, and  $P_0$  is in watts.

In the output of power-amplifier triodes, some distortion is present. This distortion is due predominantly to second harmonics in single-tube amplifiers. The percentage of second-harmonic distortion may be calculated by the following formula:




Fig. 20—Graphic calculations for class A amplifier using the 2A3 power triode.

$$\% \ distortion = \frac{\frac{I_{max} + I_{m1n}}{2} - I_o}{\frac{I_{max} - I_{m1n}}{I_{max}} \times 100}$$

where I<sub>0</sub> is the zero-signal plate current in amperes. If the distortion is excessive, the load resistance should be increased or, occasionally, decreased slightly and the calculations repeated.

Example: Determine the load resistance, power output, and distortion of a triode having an amplification factor of 4.2, a plate-dissipation rating of 15 watts, and plate-characteristics curves as shown in Fig. 20. The tube is to be operated at 250 volts on the plate.

Procedure: For a first approximation, determine the operating point P from the zero-signal bias formula, Ec.  $= -(0.68 \times 250) / 4.2 = -40.5$  volts. From the curve for this voltage, it is found that the zero-signal plate current is 0.08 ampere and, therefore, the platedissipation rating is exceeded (0.08 × 250 = 20 watts). Consequently, it is necessary to reduce the zero-signal plate current to 0.06 ampere at 250 volts. The grid bias is then -43.5 volts. Note that the curve was taken with a de filament supply; if the filament is to be operated on an ac supply, the bias must be increased by about onehalf the filament voltage, or to -45volts, and the circuit returns made to the mid-point of the filament circuit.

Point X can then be determined. Point X is at the intersection of the dc bias curve at zero volts with  $I_{max}$ , where  $I_{max} = 2I_0 = 2 \times 0.06 = 0.12$  ampere. Line XY is drawn through points P and X.  $E_{max}$ ,  $E_{min}$ , and  $I_{min}$  are then found from the curves. When these values are substituted in the power-output formula, the following result is obtained:

(0.12 = 0.012) × (365 = 105)

$$P_0 = \frac{(0.12 - 0.012) \times (365 - 105)}{8} = 3.52 \text{ watts}$$

The resistance represented by load line XY is

$$\frac{(365 - 105)}{(0.12 - 0.012)} = 2410 \text{ ohms}$$

When the values from the curves are substituted in the distortion formula, the following result is obtained:

$$\frac{0.12 + 0.012}{2} - 0.06$$
% distortion =  $\frac{2}{0.12 - 0.012} \times 100 = 5.5\%$ 

It is customary to select the load resistance so that the distortion does not exceed five per cent. When the method shown is used to determine the slope of the load-resistance line, the second-harmonic distortion generally does not exceed five per cent. In the example, however, the distortion is excessive and it is desirable, therefore, to use a slightly higher load resistance. A load resistance of 2500 ohms will provide a distortion of about 4.9 per cent. The power output is reduced only slightly to 3.5 watts.

Operating conditions for triodes in push-pull depend on the type of operation desired. Under class A conditions, distortion, power output, and efficiency are all relatively low. The operating bias can be anywhere between that specified for single-tube operation and that equal to one-half the grid-bias voltage required to produce plate-current cutoff at a plate voltage of 1.4E<sub>0</sub>, where E<sub>0</sub> is the operating plate voltage. Higher bias than this value requires higher grid-signal voltage and results in class AB<sub>1</sub> operation, which is discussed later.

The method for calculating maximum power output for triodes in pushpull class A operation is as follows: Erect a vertical line at  $0.6~E_{\circ}$  (see Fig. 21), intersecting the  $E_{c}=0$  curve at the point  $I_{max}$ . Then,  $I_{max}$  is determined from the curve for use in the formula

$$P_0 = (I_{max} \times E_0)/5$$

If  $I_{max}$  is expressed in amperes and  $E_o$  in volts, power output is in watts.

The method for determining the proper load resistance for triodes in push-pull is as follows: Draw a load line through  $I_{max}$  on the zero-bias curve and through the  $E_{\circ}$  point on the zero-current axis. Four times the resistance represented by this load line is the plate-to-plate load  $(R_{pp})$  for two triodes in a class A push-pull amplifier. Expressed as a formula,

$$R_{pp} = 4 \times (E_o - 0.6E_o)/I_{max}$$

where  $E_0$  is expressed in volts,  $I_{max}$  in amperes, and  $R_{pp}$  in ohms.

Example: Assume that the plate voltage (E<sub>0</sub>) is to be 300 volts, and the plate-dissipation rating of the tube is 15




Fig. 21—Graphic calculations for push-pull class A amplifier using the 2A3 power triode.

watts. Then, for class A operation, the operating bias can be equal to, but not more than, one-half the grid bias for cutoff with a plate voltage of  $1.4 \times 300$ = 420 volts. (Since cutoff bias is approximately -115 volts at a plate voltage of 420 volts, one-half of this value is -57.5 volts bias.) At this bias, the plate current is found from the plate family to be 0.054 ampere and, therefore, the plate dissipation is  $0.054 \times$ 300 or 16.2 watts. Since -57.5 volts is the limit of bias for class A operation of these tubes at a plate voltage of 300 volts, the dissipation cannot be reduced by increasing the bias and it becomes necessary to reduce the plate voltage.

If the plate voltage is reduced to 250 volts, the bias will be found to be -43.5 volts. For this value, the plate current is 0.06 ampere, and the plate dissipation is 15 watts. Then, following

the method for calculating power output, erect a vertical line at  $0.6E_o = 150$  volts. The intersection of the line with the curve  $E_c = 0$  is  $I_{max}$  or 0.2 ampere. When this value is substituted in the power formula, the power output is  $(0.2 \times 250)/5 = 10$  watts. The load resistance is determined from the load formula: Plate-to-plate load  $(R_{pp}) = 4 \times (250 - 150)/0.2 = 2000$  ohms.

Power output for a pentode or a beam power tube as a class A amplifier can be calculated in much the same way as for triodes. The calculations can be made graphically from a special plate family of curves, as illustrated in Fig. 22.

From a point A at or just below the knee of the zero-bias curve, draw arbitrarily selected load lines to intersect the zero-plate-current axis. These lines should be on both sides of the operating point P, whose position is




Fig. 22—Graphic calculations for class A amplifier using a pentode or beam power tube.

determined by the desired operating plate voltage,  $E_0$ , and one-half the maximum-signal plate current. Along any load line, say  $AA_1$ , measure the distance  $AO_1$ . On the same line, lay off an equal distance,  $O_1A_1$ . For optimum operation, the change in bias from A to  $O_1$  should be nearly equal to the change in bias from  $O_1$  to  $A_1$ . If this condition can not be met with one line, as is the case for the line first chosen, then another should be chosen. When the most satisfactory line has been selected, its resistance may be determined by the following formula:

Load resistance (R<sub>L</sub>) = 
$$\frac{E_{max} - E_{min}}{I_{max} - I_{min}}$$

The value of  $\mathbf{R}_{\rm L}$  may then be substituted in the following formula for calculating power output.

$$P_{o} = \frac{[I_{max} - I_{min} + 1.41 (I_{x} - I_{y})]^{2} R_{L}}{32}$$

In both of these formulas, I is in amperes, E is in volts,  $R_L$  is in ohms, and  $P_0$  is in watts.  $I_x$  and  $I_y$  are the current values on the load line at bias voltages of  $Ec_1 = V - 0.707V = 0.293V$  and  $E_{c1} = V + 0.707V = 1.707V$ , respectively.

Calculations for distortion may be made by means of the following formulas. The terms used have already been defined.

% 2nd-harmonic distortion = 
$$\frac{I_{\text{max}} + I_{\text{min}} - 2 I_{\text{o}}}{I_{\text{max}} - I_{\text{min}} + 1.41 (I_{\text{x}} - I_{\text{y}})} \times 100$$
% 3rd-harmonic distortion = 
$$\frac{I_{\text{max}} - I_{\text{min}} - 1.41 (I_{\text{x}} - I_{\text{y}})}{I_{\text{max}} - I_{\text{min}} + 1.41 (I_{\text{x}} - I_{\text{y}})} \times 100$$
% total (2nd and 3rd) harmonic distortion =

## $\sqrt{(\% \text{ 2nd})^2 + (\% \text{ 3rd})^2}$ Conversion Factors

Operating conditions for voltage values other than those shown in the published data can be obtained by use of the **nomograph** shown in Fig. 23 when all electrode voltages are changed simultaneously in the same ratio. The nomograph includes conversion factors for current (F<sub>1</sub>), power output (F<sub>p</sub>), plate resistance or load resistance (F<sub>r</sub>),

and transconductance  $(F_{\rm gm})$  for voltage ratios between 0.5 and 2.0. These factors are expressed as functions of the ratio between the desired or new voltage for any electrode  $(E_{\rm des})$  and the published or original value of that voltage  $(E_{\rm pub})$ . The relations shown are applicable to triodes and multigrid tubes in all classes of service.

To use the nomograph, simply place a straight-edge across the page so that it intersects the scales for  $E_{des}$  and  $E_{pub}$  at the desired values. The desired conversion factor may then be read directly or estimated at the point where the straight-edge intersects the  $F_1$ ,  $F_p$   $F_r$ , or  $F_{gm}$  scale.

For example, suppose it is desired to operate two 6L6GC's in class A<sub>1</sub> push-pull, fixed bias, with a plate voltage of 200 volts. The nearest published operating conditions for this class of service are for a plate voltage of 250 volts. The operating conditions for the new plate voltage can be determined as follows:

The voltage conversion factor,  $F_e$ , is equal to 200/250 or 0.8. The dashed lines on the nomograph of Fig. 23 indicate that for this voltage ratio  $F_1$  is approximately 0.72,  $F_p$  is approximately 0.57,  $F_r$  is 1.12, and  $F_{gm}$  is approximately 0.892. These factors may be applied directly to operating values shown in the tube data, or to values calculated by the methods described previously.

Because this method for conversion of characteristics is necessarily an approximation, the accuracy of the nomograph decreases progressively as the ratio E<sub>des</sub>/E<sub>pub</sub> departs from unity. In general, results are substantially correct when the value of the ratio E<sub>des</sub>/E<sub>pub</sub> is between 0.7 and 1.5. Beyond these limits, the accuracy decreases rapidly, and the results obtained must be considered rough approximations.

The nomograph does not take into consideration the effects of contact potential or secondary emission in tubes. Because contact-potential effects become noticeable only at very small dc grid-No. 1 (bias) voltages, they are generally negligible in power tubes.




Fig. 23—Nomograph of tube conversion factors.

Secondary emission may occur in conventional tetrodes, however, if the plate voltage swings below the grid-No. 2 voltage. Consequently, the conversion factors shown in the nomograph apply to such tubes only when the plate voltage is greater than the grid-No. 2 voltage. Because secondary emission may also occur in certain beam power tubes at very low values of plate current and plate voltage, the conversion factors shown in the nomograph do not apply when these tubes are operated under such conditions.

## Class AB Power Amplifiers

A class AB power amplifier employs two tubes connected in push-pull with a higher negative grid bias than is used in a class A stage. With this higher negative bias, the plate and screen-

grid voltages can usually be made higher than for class A amplifiers because the increased negative bias holds plate current within the limit of the tube plate-dissipation rating. As a result of these higher voltages, more power output can be obtained from class AB operation.

Class AB amplifiers are subdivided into class AB<sub>1</sub> and class AB<sub>2</sub>. In class AB<sub>1</sub>, there is no flow of grid current. That is, the peak signal voltage applied to each grid is not greater than the negative grid-bias voltage. The grids therefore are not driven to a positive potential and do not draw current. In class AB<sub>2</sub>, the peak signal voltage is greater than the bias so that the grids are driven positive and draw current.

Because of the flow of grid current in a class AB<sub>2</sub> stage, there is a loss of power in the grid circuit. The sum of this loss and the loss in the input transformer is the total driving power required by the grid circuit. The driver stage should be capable of a power output considerably larger than this required power in order that distortion introduced in the grid circuit be kept low. The input transformer used in a class AB<sub>2</sub> amplifier usually has a stepdown turns ratio.

Because of the large fluctuations of plate current in a class AB<sub>2</sub> stage, it is important that the plate power supply have good regulation. Otherwise the fluctuations in plate current cause fluctuations in the voltage output of the power supply, with the result that power output is decreased and distortion is increased. To obtain satisfactory regulation, it is usually advisable to use a low-drop rectifier, such as the 5V4GA, with a choke-input filter. In all cases, the resistance of the choke and transformers should be as low as possible.

## Class AB1 Power Amplifiers

In class AB<sub>1</sub> push-pull amplifier service using triodes, the operating conditions may be determined graphically by means of the plate family if E<sub>0</sub>, the desired operating plate voltage, is given. In this service, the dynamic load line does not pass through the operating point P as in the case of the single-tube amplifier, but through the

point D in Fig. 24. Its position is not affected by the operating grid bias provided the plate-to-plate load resistance remains constant.

Under these conditions, grid bias has no appreciable effect on the power output. Grid bias cannot be neglected, however, since it is used to find the zero-signal plate current and, from it, the zero-signal plate dissipation. Because the grid bias is higher in class AB, than in class A service for the same plate voltage, a higher signal voltage may be used without grid current being drawn and, therefore, higher power output is obtained.

In general, for any load line through point D, Fig. 24, the plate-toplate load resistance in ohms of a pushpull amplifier is  $R_{pp} = 4E_o/I'$ , where I' is the plate-current value in amperes at which the load line as projected intersects the plate-current axis, and Eo is in volts. This formula is another form of the one given under pushpull class A amplifiers, R<sub>pp</sub> = 4(E<sub>o</sub> -0.6E<sub>o</sub>)/I<sub>max</sub>, but is more general. Power output =  $(I_{max}/\sqrt{2})^2 \times R_{pp}/4$ , where Imax is the peak plate current at zero grid volts for the load chosen. This formula simplified is  $(I_{max})^2 \times R_{pp}/8$ . The maximum-signal average plate current is 2I<sub>max</sub>/π or 0.636 I<sub>max</sub>; the maximum-signal average power input is  $0.636 I_{max} \times E_o$ .

It is desirable to simplify these




Fig. 24—Graphic calculations for class AB<sub>1</sub> amplifier using the 2A3 power triode.

Fig. 25—Instantaneous curve for class AB<sub>1</sub> amplifier.

formulas for a first approximation. This simplification can be made if it is assumed that the peak plate current,  $I_{mix}$ , occurs at the point of the zero-bias curve corresponding approximately to  $0.6~E_{\rm o}$ , the condition for maximum power output. The simplified formulas are:

 $P_0$  (for two tubes) =  $(I_{max} \times E_0)/5$  $R_{pp} = 1.6E_0/I_{max}$ 

where  $E_o$  is in volts,  $I_{max}$  is in amperes,  $R_{nn}$  is in ohms, and  $P_o$  is in watts.

It may be found during subsequent calculations that the distortion or the plate dissipation is excessive for this approximation; in that case, a different load resistance must be selected, using the first approximation as a guide, and the process repeated to obtain satisfactory operating conditions.

**Example:** Fig. 24 illustrates the application of this method to a pair of 2A3's operated at  $E_0 = 300$  volts. Each tube has a plate-dissipation rating of 15 watts. The method is to erect a vertical line at  $0.6E_0$ , or at 180 volts, which intersects the  $E_c = 0$  curve at the point  $I_{max} = 0.26$  ampere. Using the simplified formulas, the following values are obtained:

 $R_{pp} = (1.6 \times 300)/0.26 = 1845$  ohms  $P_0 = (0.26 \times 300)/5 = 15.6$  watts

At this point, it is well to determine the plate dissipation and to compare it with the maximum rated value. From the average-plate-current formula (0.636 Imax) mentioned previously, the maximum-signal average plate current is 0.166 ampere. The product of this current and the operating plate voltage is 49.8 watts, the average input to the two tubes. From this value, subtract the power output of 15.6 watts to obtain the total dissipation for both tubes. which is 34.2 watts. Half of this value, 17 watts, is in excess of the 15-watt rating of the tube and it is necessary, therefore, to assume another and higher load resistance so that the plate-dissipation rating will not be exceeded.

It will be found that at an operating plate voltage of 300 volts the 2A3's require a plate-to-plate load resistance of 3000 ohms. From the formula for  $R_{pp}$ , the value of I' is found to be 0.4

ampere. The load line for the 3000-ohm load resistance is then represented by a straight line from the point I' = 0.4 ampere on the plate-current ordinate to the point  $E_o = 300$  volts on the plate-voltage abscissa. At the intersection of the load line with the zerobias curve, the peak plate current,  $I_{max}$ , can be read at 0.2 ampere. Then

 $P_0 = (I_{max}/\sqrt{2})^2 \times R_{pp}/4$ =  $(0.2/1.41)^2 \times 3000/4$ = 15 watts

Proceeding as in the first approximation, it is found that the maximum-signal average plate current,  $0.636I_{max}$ , is 0.127 ampere, and the maximum-signal average power input is 38.1 watts. This input minus the power output is 38.1 - 15 = 23.1 watts. This value is the dissipation for two tubes; the value per tube is 11.6 watts, a value well within the rating of this tube type.

The operating bias and the zerosignal plate current may then be found by use of a curve which is derived from the plate family and the load line. Fig. 25 is a curve of instantaneous values of plate current and dc grid-bias voltages taken from Fig. 24. Values of grid bias are read from each of the grid-bias curves of Fig. 24 along the load line and are transferred to Fig. 25 to produce the curved line from A to C. A tangent to this curve, starting at A, is drawn to intersect the grid-voltage abscissa. The point of intersection, B, is the operating grid bias for fixed-bias operation. In the example, the bias is -60 volts. Refer back to the plate family at the operating conditions of plate volts = 300 and grid bias = -60volts; the zero-signal plate current per tube is seen to be 0.04 ampere.

This procedure locates the operating point for each tube at P. The plate current must be doubled, of course, to obtain the zero-signal plate current for both tubes. Under maximum-signal conditions, the signal voltage swings from zero-signal bias voltage to zero bias for each tube on alternate half cycles. Hence, in the example, the peak of signal voltage per tube is 60 volts, or the grid-to-grid value is 120 volts.

As in the case of the push-pull class A amplifier, the second-harmonic dis-

tortion in a class AB, amplifier using triodes is very small and is largely canceled by virtue of the push-pull condistortion, Third-harmonic however, which may be larger than permissible, can be found by means of composite characteristic curves. A complete family of curves can be plotted, but for the present purpose only the one corresponding to a grid bias of one-half the peak grid-voltage swing is needed. In the example, the peak grid voltage per tube is 60 volts, and the half value is 30 volts. The composite curve, since it is nearly a straight line, can be constructed with only two points (see Fig. 24). These two points are obtained from deviations above and below the operating grid and plate voltages.

In order to find the curve for a bias of -30 volts, a deviation of 30 volts from the operating grid voltage of -60 volts is assumed. Next assume a deviation from the operating plate voltage of, say, 40 volts. Then at 300 -40 = 260 volts, erect a vertical line to intersect the (-60) - (-30) = -30volt bias curve and read the plate current at this intersection, which is 0.167 ampere; likewise, at the intersection of a vertical line at 300 + 40 = 340volts and the (-60) + (-30) = -90volt bias curve, read the plate current. In this example, the plate current is estimated to be 0.002 ampere. The difference of 0.165 ampere between these two currents determines the point E on the 300 - 40 = 260-volt vertical. Similarly, another point F on the same composite curve is found by assuming the same grid-bias deviation but a larger plate-voltage deviation, say, 100

These steps provide points at 260 volts and 0.165 ampere (E), and at 200 volts and 0.045 ampere (F). A straight line through these points is the composite curve for a bias of -30 volts, shown as a long-short dash line in Fig. 24. At the intersection of the composite curve and the load line, G, the instantaneous composite plate current at the point of one-half the peak signal swing is determined. This current value, designated I<sub>0.5</sub> and the peak plate current, I<sub>max</sub>, are used in the following formula

to find the peak value of the thirdharmonic component of the plate current.

$$Ih_0 = (2I_{0.5} - I_{max})/3$$

In the example, where  $I_{0.5}$  is 0.097 ampere and  $I_{max}$  is 0.2 ampere,  $I_{h3} = (2 \times 0.097 - 0.2)/3 = (0.194 - 0.2)/3 = -0.006/3 = -0.002$  ampere. (The fact that  $I_{h3}$  is negative indicates that the phase relation of the fundamental (first-harmonic) and third-harmonic components of the plate current is such as to result in a slightly peaked wave form.  $I_{h3}$  is positive in some cases, indicating a flattening of the wave form.)

The peak value of the fundamental or first-harmonic component of the plate current is found by the following formula:

$$Ih_1 = 2/3 \times (I_{max} + I_{0.5})$$

In the example,  $I_{\rm hi}=2/3\times(0.2+0.097)=0.198$  ampere. Thus, the percentage of third-harmonic distortion is  $(I_{\rm hi}/I_{\rm hi})\times100=(0.002/0.198)\times100=1$  per cent approx.

## Class AB: Power Amplifiers

A class AB<sub>2</sub> amplifier employs two tubes connected in push-pull as in the case of class AB<sub>1</sub> amplifiers. It differs in that it is biased so that plate current flows for somewhat more than half the electrical cycle but less than the full cycle, the peak signal voltage is greater than the dc bias voltage, grid current is drawn, and, consequently, power is consumed in the grid circuit. These conditions permit high power output to be obtained without excessive plate dissipation.

The sum of the power used in the grid circuit and the losses in the input transformer is the total driving power required by the grid circuit. The driver stage should be capable of a power output considerably larger than this required power in order that distortion introduced in the grid circuit be kept low. In addition, the internal impedance of the driver stage as reflected into or as effective in the grid circuit of the power stage should always be as low as possible in order that distortion may be kept low. The input transformer used

in a class AB<sub>2</sub> stage usually has a stepdown ratio adjusted for this condition.

Load resistance, plate dissipation, power output, and distortion determinations are similar to those for class AB.. These quantities are interdependent with peak grid-voltage swing and driving power; a satisfactory set of operating conditions involves a series of approximations. The load resistance and signal swing are limited by the permissible grid current and power and the distortion. If the load resistance is too high or the signal swing is excessive, the plate-dissipation rating will be exceeded, distortion will be high, and the driving power will be unnecessarily high.

Class B Power Amplifiers

A class B amplifier employs two tubes connected in push-pull, so biased that plate current is almost zero when no signal voltage is applied to the grids. Because of this low value of no-signal plate current, class B amplification has the same advantage as class AB<sub>2</sub>, i.e., large power output can be obtained without excessive plate dissipation. Class B operation differs from class AB<sub>2</sub> in that plate current is cut off for a larger portion of the negative grid swing, and the signal swing is usually larger than in class AB<sub>2</sub> operation.

Because certain triodes used as class B amplifiers are designed to operate very close to zero bias, the grid of each tube is at a positive potential during all or most of the positive halfcycle of its signal swing. In this type of triode operation, considerable grid current is drawn and there is a loss of power in the grid circuit. This condition imposes the same requirement in the driver stage as in a class AB<sub>2</sub> stage; i.e., the driver should be capable of delivering considerably more power output than the power required for the grid circuit of the class B amplifier so that distortion will be low. Similarly, the interstage transformer between the driver and the class B stage usually has a step-down turns ratio. Because of the high dissipations involved in class B operation at zero bias, it is not feasible to use tetrodes or pentodes in this type of class B operation.

Determination of load resistance, plate dissipation, power output, and distortion is similar to that for a class AB<sub>2</sub> stage.

Power amplifier tubes designed for class A operation can be used in class AB<sub>2</sub> and class B service under suitable operating conditions. There are several tube types designed especially for class B service. The characteristic common to all of these types is a high amplification factor. With a high amplification factor, plate current is small even when the grid bias is zero. These tubes, therefore, can be operated in class B service at a bias of zero volts so that no bias supply is required. A number of class B amplifier tubes consist of two triode units mounted in one tube. The two units can be connected in push-pull so that only one tube is required for a class B stage.

## High-Fidelity Amplifiers

Several high-fidelity amplifiers are shown in the Circuits section. The performance capabilities of such amplifiers are usually given in terms of frequency response, total harmonic distortion, maximum power output, and noise level.

To provide high-fidelity reproduction of audio program material, an amplifier should have a frequency response which does not vary more than 1 db over the entire audio spectrum. General practice is to design the amplifier so that its frequency response is flat within 1 db from a frequency below the lowest to be reproduced to one well above the upper limit of the audible region.

Harmonic distortion and intermodulation distortion produce changes in program material which may have adverse effects on the quality of the reproduced sound. Harmonic distortion causes a change in the character of an individual tone by the introduction of harmonics which were not originally present in the program material. For high-fidelity reproduction, total harmonic distortion (expressed as a percentage of the output power) should not be greater than about 1 per cent at the

desired listening level. Types such as the 6973, 7027A and 7868 are designed to provide extremely low harmonic distortion in suitably designed push-pull amplifier circuits.

Intermodulation distortion is a change in the waveform of an individual tone as a result of interaction with another tone present at the same time in the program material. This type of distortion not only alters the character of the modulated tone, but may also result in the generation of spurious signals at frequencies equal to the sum and difference of the interacting frequencies. Intermodulation distortion should be less than 2 per cent at the desired listening level. In general, any amplifier which has low intermodulation distortion will have very low harmonic distortion.

The maximum power output which a high-fidelity amplifier should deliver depends upon a complex relation of several factors, including the size and acoustical characteristics of the listening area, the desired listening level, and the efficiency of the loudspeaker system. Practically, however, it is possible to determine amplifier requirements in terms of room size and loudspeaker efficiency.

The acoustic power required to reproduce the loudest passages of orchestral music at concert-hall level in the average-size living room is about 0.4 watt. Because high-fidelity loudspeakers of the type generally available for home use have an efficiency of only about 5 per cent, the output stage of the amplifier should therefore be able to deliver a power output of at least 8 watts. Because many wide-range loudspeaker systems, particularly those using frequencydivider networks, have efficiencies of less than 5 per cent, output tubes used with such systems must have correspondingly larger power outputs. The 6973, 7027A, 7189, and 7868 can provide ample output for most systems when used in suitable push-pull circuits.

The noise level of a high-fidelity amplifier determines the range of volume the amplifier is able to reproduce, i.e., the difference (usually expressed in decibels) between the loudest

and softest sounds in program material. Because the greatest volume range utilized in electrical program material at the present time is about 60 db, the noise level of a high-fidelity amplifier should be at least 60 db below the signal level at the desired listening level.

## Cathode-Drive Circuits

The preceding text has discussed the use of tubes in the conventional grid-drive type of amplifier—that is, where the cathode is common to both the input and output circuits. Tubes may also be employed as amplifiers in circuit arrangements which utilize the grid or plate as the common terminal. Probably the most important of these amplifiers are the cathode-drive circuit, which is discussed below, and the cathode-follower circuit, which will be discussed later in connection with inverse feedback.

A typical cathode-drive circuit is shown in Fig. 26. The load is placed in




Fig. 26—Cathode-drive circuit.

the plate circuit and the output voltage is taken off between the plate and ground as in the grid-drive method of operation. The grid is grounded, and the input voltage is applied across an appropriate impedance in the cathode circuit. The cathode-drive circuit is particularly useful for vhf and uhf applications, in which it is necessary to obtain the low-noise performance usually associated with a triode, but where a conventional grid-drive circuit would be unstable because of feedback through the grid-to-plate capacitance of the tube. In the cathode-drive circuit, the grounded grid serves as a capacitive shield between plate and cathode and permits stable operation at frequencies higher than those in which conventional circuits can be used.

The input impedance of a cathode-drive circuit is approximately equal to  $1/g_m$  when the load resistance is small compared to the  $r_p$  of the tube. A certain amount of power is required, therefore, to drive such a circuit. However, in the type of service in which cathode-drive circuits are normally used, the advantages of the grounded-grid connection usually outweigh this disadvantage.

### Inverse Feedback

An inverse-feedback circuit, sometimes called a degenerative circuit, is one in which a portion of the output voltage of a tube is applied to the input of the same or a preceding tube in opposite phase to the signal applied to the tube. Two important advantages of feedback are (1) reduced distortion from each stage included in the feedback circuit and (2) reduction in the variations in gain due to changes in line voltage, possible differences between tubes of the same type, or variations in the values of circuit constants included in the feedback circuit.

Inverse feedback is used in audio amplifiers to reduce distortion in the output stage where the load impedance on the tube is a loudspeaker. Because the impedance of a loudspeaker is not constant for all audio frequencies, the load impedance on the output tube varies with frequency. When the output tube is a pentode or beam power tube having high plate resistance, this variation in plate load impedance can, if not corrected, produce considerable frequency distortion. Such frequency distortion can be reduced by means of inverse feedback. Inverse-feedback circuits are of the constant-voltage type and the constant-current type.

The application of the constant-voltage type of inverse feedback to a power-output stage using a single beam power tube is illustrated in Fig. 27. In this circuit,  $R_1$ ,  $R_2$ , and C are connected as a voltage divider across the output of the tube. The secondary winding of the grid-input transformer is returned to a

point on this voltage divider. Capacitor C blocks the dc plate voltage from the grid. However, a portion of the tube af output voltage, approximately equal to the output voltage multiplied by the




Fig. 27—Power-output stage using constant-voltage inverse feedback.

fraction  $R_2/(R_1 + R_2)$ , is applied to the grid. This voltage reduces the source impedance of the circuit and a decrease in distortion results which is explained in the curves of Fig. 28.

Consider first the amplifier without the use of inverse feedback. Suppose that when a signal voltage e, is applied to the grid the af plate current i'n has an irregularity in its positive half-cycle. This irregularity represents a departure from the waveform of the input signal and is, therefore, distortion. For this plate-current waveform, the af plate voltage has a waveform shown by e'n. The plate-voltage waveform is inverted compared to the plate-current waveform because a plate-current increase produces an increase in the drop across the plate load. The voltage at the plate is the difference between the drop across the load and the supply voltage; thus, when plate current goes up, plate voltage goes down; when plate current goes down, plate voltage goes up.

Now suppose that inverse feedback is applied to the amplifier. The voltage fed back to the grid has the same waveform and phase as the plate voltage, but is smaller in magnitude. Hence, with a plate voltage of waveform shown by e'p, the feedback voltage appearing on the grid is as shown by e'gt. This voltage applied to the grid produces a component of plate current i'pt. It is evident that the irregularity in the waveform of




Fig. 28-Voltage and current waveforms showing effect of inverse feedback.

this component of plate current would act to cancel the original irregularity and thus reduce distortion.

After inverse feedback has been applied, the relations are as shown in the curve for ip. The dotted curve shown by i'nt is the component of plate current due to the feedback voltage on the grid. The dotted curve shown by i'p is the component of plate current due to the signal voltage on the grid. The algebraic sum of these two components gives the resultant plate current shown by the solid curve of ip. Since i'p is the plate current that would flow without inverse feedback, it can be seen that the application of inverse feedback has reduced the irregularity in the output current. In this manner inverse feedback acts to correct any component of plate current that does not correspond to the input signal voltage, and thus reduces distortion.

From the curve for i<sub>p</sub>, it can be seen that, besides reducing distortion, inverse feedback also reduces the amplitude of the output current. Consequently, when inverse feedback is applied to an amplifier there is a decrease in gain or power sensitivity as well as a decrease in distortion. Hence, the application of inverse feedback to an amplifier requires that more driving voltage be applied to obtain full power output, but this output is obtained with less distortion.

Inverse feedback may also be applied to resistance-coupled stages, as

shown in Fig. 29. The circuit is conventional except that a feedback resistor,  $R_3$ , is connected between the plates of tubes  $T_1$  and  $T_2$ . The output signal voltage of  $T_1$  and a portion of the output signal voltage of  $T_2$  appear across  $R_2$ . Because the distortion generated in the plate circuit of  $T_2$  is applied to its grid out of phase with the input signal, the distortion in the output of  $T_2$  is comparatively low. With sufficient inverse feedback of the constant-voltage type




Fig. 29—Resistance-coupled stages using feedback resistor.

in a power-output stage, it is not necessary to employ a network of resistance and capacitance in the output circuit to reduce response at high audio frequencies. Inverse-feedback circuits can also be applied to push-pull class A and class AB<sub>1</sub> amplifiers.

Constant-current inverse feedback is usually obtained by omitting the bypass capacitor across a cathode resistor. This method decreases the gain and the distortion but increases the source impedance of the circuit. Consequently, the output voltage rises at the resonant

frequency of the loudspeaker and accentuates hangover effects.

Inverse feedback is not generally applied to a triode power amplifier, such as the 2A3, because the variation in speaker impedance with frequency does not produce much distortion in a triode stage having low plate resistance. It is sometimes applied in a pentode stage, but is not always convenient. As has been shown, when inverse feedback is used in an amplifier, the driving voltage must be increased in order to provide full power output. When inverse feedback is used with a pentode, the total driving voltage required for full power output may be inconveniently large, although still less than that required for a triode. Because a beam power tube gives full power output on a comparatively small driving voltage, inverse feedback is especially applicable to beam power tubes. By means of inverse feedback, the high efficiency and high power output of beam power tubes can be combined with freedom from the effects of varying speaker impedance.

## Cathode-Follower Circuits

Another important application of inverse feedback is in the cathode-follower circuit, an example of which is shown in Fig. 30. In this application, the load has been transferred from the plate circuit to the cathode circuit of the tube.




Fig. 30-Cathode-follower circuit.

The input voltage is applied between the grid and ground, and the output voltage is obtained between the cathode and ground. The voltage amplification (V.A.) of this circuit is always less than unity and may be expressed by the following convenient formulas. For a triode:

V. A. = 
$$\frac{\mu \times R_L}{r_p + [R_L \times (\mu + 1)]}$$

For a pentode:

$$V. A. = \frac{g_m \times R_L}{1 + (g_m \times R_L)}$$

In these formulas,  $\mu$  is the amplification factor,  $R_L$  is the load resistance in ohms,  $r_p$  is the plate resistance in ohms, and  $g_m$  is the transconductance in mhos.

The use of the cathode follower permits the design of circuits which have high input resistance and high output voltage. The output impedance is quite low and very low distortion may be obtained. Cathode-follower circuits may be used for power amplifiers or as impedance transformers designed either to match a transmission line or to produce a relatively high output voltage at a low impedance level.

In a power amplifier which is transformer coupled to the load, the same output power can be obtained from the tube as would be obtained in a conventional grid-drive type of amplifier. The output impedance is very low and provides excellent damping to the load, with the result that very low distortion can be obtained. The peak-to-peak signal voltage, however, approaches 11/2 times the plate supply voltage if maximum power output is required from the tube. Some problems may be encountered, therefore, in the design of an adequate driver stage for a cathodefollower output system.

When a cathode-follower circuit is used as an impedance transformer, the load is usually a simple resistance in the cathode circuit of the tube. With relatively low values of cathode resistor, the circuit may be designed to supply significant amounts of power and to match the impedance of the device to a transmission line. With somewhat higher values of cathode resistor, the circuit may be used to decrease the output impedance sufficiently to permit the transmission of audio signals along a line in which appreciable capacitance is present.

The cathode follower may also be used as an isolation device to provide extremely high input resistance and low

## Electron Tube Applications

input capacitance as might be required in the probe of an oscilloscope or vacuum-tube voltmeter. Such circuits can be designed to provide effective impedance transformation with no significant loss of voltage.

Selection of a suitable tube and its operating conditions for use in a cathode-follower circuit having a specified output impedance (Z<sub>0</sub>) can be made, in most practical cases, by the use of the following formula to determine the approximate value of the required tube transconductance.

Required g<sub>m</sub> (
$$\mu$$
mhos) =  $\frac{1,000,000}{Z_0 \text{ (ohms)}}$ 

Once the required transconductance is obtained, a suitable tube and its operating conditions may be determined from the technical data given in the Technical Data section. The tube selected should have a value of transconlower than that slightly ductance obtained from the above expression to allow for the shunting effect of the cathode load resistance. The conversion nomograph given in Fig. 23 may be used for calculation of operating conditions for values of transconductance not included in the tabulated data. After the operating conditions have been determined, the approximate value of the required cathode load resistance may be calculated from the following formulas. For a triode:

Cathode 
$$R_L = \frac{Z_o \times r_p}{r_p - [Z_o \times (1 + \mu)]}$$
  
For a pentode:

Cathode 
$$R_{L} = \frac{Z_{0}}{1 - (g_{m} \times Z_{0})}$$

Resistance and impedance values are in ohms; transconductance values are in mhos.

If the value of the cathode load resistance calculated to provide the required output impedance does not provide the required operating bias, the basic cathode-follower circuit can be modified in a number of ways. Two of the more common modifications are shown in Figs. 31 and 32.

In Fig. 31 the bias is increased by adding a bypassed resistance between the cathode and the unbypassed load resistance and returning the grid to the low end of the load resistance. In Fig.




Fig. 31—Cathode-follower circuit modified for increased bias.

32 the bias is reduced by adding a bypassed resistance between the cathode and the unbypassed load resistance but, in this case, the grid is returned to the junction of the two cathode resistors so that the bias voltage is only the dc voltage drop across the added resistance. The size of the bypass capacitor should be large enough so that it has negligible reactance at the lowest frequency to be handled. In both cases the B-supply should be increased to make up for the voltage taken for biasing.




Fig. 32--Cathode-follower circuit modified for reduced bias.

Example: Select a suitable tube and determine the operating conditions and circuit components for a cathode-follower circuit having an output impedance that will match a 500-ohm transmission line.

**Procedure:** First, determine the approximate transconductance required.

Required 
$$g_m = \frac{1,000,000}{500} = 2000 \ \mu \text{mhos}$$

A survey of the tubes that have a transconductance in this order of magnitude shows that type 12AX7A is among

the tubes to be considered. Referring to the characteristics given in the technical data section for one triode unit of highmu twin triode 12AX7, we find that for a plate voltage of 250 volts and a bias of -2 volts, the transconductance is 1600 micromhos, the plate resistance is 62500 ohms, the amplification factor is 100, and the plate current is 0.0012 ampere. When these values are used in the expression for determining the cathode load resistance, the following result is obtained:

Cathode 
$$R_L = \frac{500 \times 62500}{62500 - 500 \times (100 + 1)} = 2600$$
 ohms

The voltage across this resistor for a plate current of 0.0012 ampere is  $2600 \times 0.0012 = 3.12$  volts. Because the required bias voltage is only -2volts, the circuit arrangement given in Fig. 32 is employed. The bias is furnished by a resistance that will have a voltage drop of 2 volts when it carries a current of 0.0012 ampere. The required bias resistance, therefore, 2/0.0012 = 1670 ohms. If 60 cycles per second is the lowest frequency to be passed, 20 microfarads is a suitable value for the bypass capacitor. The Bsupply, of course, is increased by the voltage drop across the cathode resistance which, in this example, is approximately 5 volts. The B-supply, therefore, is 250 + 5 = 255 volts.

Because it is desirable to eliminate, if possible, the bias resistor and bypass capacitor, it is worthwhile to try other tubes and other operating conditions to obtain a value of cathode load resistance which will also provide the required bias. If the triode section of twin diode—high-mu triode 6AT6 is operated under the conditions given in the technical data section with a plate voltage of 100 volts and a bias of -1 volt, it will have an amplification factor of 70, a plate resistance of 54000 ohms, a transconductance of 1300 micromhos, and a plate current of 0.0008 ampere. Then,

$$\frac{\text{Cathode R}_{L} = \\ \frac{500 \times 54000}{54000 - 500 \times (70 + 1)} = 1460 \text{ ohms}$$

The bias voltage obtained across this resistance is  $1460 \times 0.0008 = 1.17$  volts. Since this value is for all practical purposes close enough to the required bias, no addition bias resistance will be required and the grid may be returned directly to ground. There is no need to adjust the B-supply voltage to make up for the drop in the cathode resistor. The voltage amplification (V.A.) for the cathode-follower circuit utilizing the triode section of type 6AT6 is

V.A. 
$$=\frac{70 \times 1460}{54000 + 1460 \times (70 + 1)} = 0.65$$

For applications in which the cathode follower is used to isolate two circuits—for example, when it is used between a circuit being tested and the input stage of an oscilloscope or a vacuum-tube voltmeter-voltage output and not impedance matching is the primary consideration. In such applications it is desirable to use a relatively high value of cathode load resistance, such as 50,000 ohms, in order to get the maximum voltage output. In order to obtain proper bias, a circuit such as that of Fig. 32 should be used. With a high value of cathode resistance, the voltage amplification will approximate unity.

### Corrective Filters

A corrective filter can be used to improve the frequency characteristic of an output stage using a beam power tube or a pentode when inverse feedback is not applicable. The filter consists of a resistor and a capacitor connected in series across the primary of the output transformer. Connected in this way, the filter is in parallel with the plate load impedance reflected from the voicecoil by the output transformer. The magnitude of this reflected impedance increases with increasing frequency in the middle and upper audio range. The impedance of the filter, however, decreases with increasing frequency. It follows that, by use of the proper values for the resistance and the capacitance in the filter, the effective load impedance on the output tubes can be made practically constant for all frequencies in

the middle and upper audio range. The result is an improvement in the frequency characteristic of the output stage.

The resistance to be used in the filter for a push-pull stage is 1.3 times the recommended plate-to-plate load resistance; or, for a single-tube stage, is 1.3 times the recommended plate load resistance. The capacitance in the filter should have a value such that the voltage gain of the output stage at a frequency of 1000 cycles or higher is equal to the voltage gain at 400 cycles.

A method of determining the proper value of capacitance for the filter is to make two measurements of the output voltage across the primary of the output transformer: first, when a 400-cycle signal is applied to the input, and second, when a 1000-cycle signal of the same voltage as the 400-cycle signal is applied to the input. The correct value of capacitance is the one which gives equal output voltages for the two signal inputs. In practice, this value is usually found to be in the order of 0.05 microfarad.

Volume Compressors and Expanders

Volume compression and expansion are used in FM transmitters and receivers and in recording devices and amplifiers to make more natural the reproduction of music which has a very large volume range. For example, in the music of a symphony orchestra the sound intensity of the soft passages is very much lower than that of the loud passages. When this low volume level is raised above the background noise for transmitting or recording, the peak level of the program material may be raised to an excessively high volume level. It is often necessary, therefore, to compress the volume range of the program content within the maximum capabilities of the FM transmitter or the recording device. Exceeding a maximum peak volume level for FM modulation corresponds to exceeding the allowed bandwidth for transmission. In some recording devices, excessive peak volume levels may cause overloading and distortion.

Volume compression may be accomplished by either manual or automatic control. The types of compression used include peak limiters, volume limiters, and volume compressors. A peak limiter limits the peak power to some predetermined level. A volume limiter provides gain reduction based on an average signal level above a predetermined level. A volume compressor provides gain reduction for only the sustained loud portions of the sound level. Only volume compressors can be correctly compensated for with volume expanders.

For faithful reproduction of the original sound, the volume expander used in the FM receiver or audio amplifier should have the reverse characteristic of the volume compressor used in the FM transmitter or recording device. In general, the basic requirements for either a volume compressor or expander are shown in the block diagram of Fig. 33. In a volume compressor, the




Fig. 33—Block diagram of volume compressor or expander circuit.

variable-gain amplifier V<sub>1</sub> has greater gain for a low-amplitude signal than for a high-amplitude signal; therefore, soft passages are amplified more than loud ones. In an expander, the gain is greater for high-amplitude signals than for low-amplitude signals; therefore, loud passages are amplified more than soft ones and the original amplitude ratio is restored.

In the diagram shown in Fig. 33, the signal to be amplified is applied to  $V_1$ , and a portion of the signal is also applied to  $V_2$ . The amplified output

from  $V_2$  is then rectified by  $V_3$ , and applied as a negative (for compressors) or positive (for expanders) bias voltage to  $V_1$ . As this bias voltage varies with variations in signal amplitude, the gain of  $V_1$  also varies to produce the desired compression or expansion of the signal.

Tubes having a large dynamic range provide the best results in volume compressor or expander applications. Examples of such types are the 6BJ6 and 6BE6. Push-pull operation is generally desired for the variable-gain amplifier to prevent high distortion and other undesirable effects which may occur in volume compressors and expanders.

#### Phase Inverters

A phase inverter is a circuit used to provide resistance coupling between the output of a signal-tube stage and the input of a push-pull stage. The necessity for a phase inverter arises because the signal-voltage inputs to the grids of a push-pull stage must be 180 degrees out of phase and approximately equal in amplitude with respect to each other. Thus, when the signal voltage input to a push-pull stage swings the grid of one tube in a positive direction, it should swing the grid of the other tube in a negative direction by a similar amount. With transformer coupling between stages, the out-of-phase input voltage to the push-pull stage is supplied by means of the center-tapped secondary. With resistance coupling, the out-of-phase input voltage is obtained by means of the inverter action of a tube.

Fig. 34 shows a push-pull power amplifier, resistance-coupled by means of a phase-inverter circuit to a single-stage triode  $T_1$ . Phase inversion in this circuit is provided by triode  $T_2$ . The output voltage of  $T_1$  is applied to the grid of triode  $T_3$ . A portion of the output voltage of  $T_1$  is also applied through the resistors  $R_3$  and  $R_5$  to the grid of  $T_2$ . The output voltage of  $T_2$  is applied to the grid of triode  $T_4$ .

When the output voltage of T<sub>1</sub> swings in the positive direction, the

plate current of  $T_2$  increases. This action increases the voltage drop across the plate resistor  $R_2$  and swings the plate of  $T_2$  in the negative direction. Thus, when the output voltage of  $T_1$  swings positive, the output voltage of  $T_2$  swings negative and is, therefore,  $180^{\circ}$  out of phase with the output voltage of  $T_1$ .

In order to obtain equal voltages at  $E_a$  and  $E_b$ ,  $(R_3 + R_5)/R_5$  should equal the voltage gain of T2. Under the condition where a twin-type tube or two tubes having the same characteristics are used as T<sub>1</sub> and T<sub>2</sub>, R<sub>4</sub> should be equal to the sum of R<sub>3</sub> and R<sub>5</sub>. The ratio of  $R_3 + R_5$  to  $R_5$  should be the same as the voltage gain ratio of T2 in order to apply the correct value of signal voltage to T2. The value of R5 is, therefore, equal to R, divided by the voltage gain of T2; R3 is equal to R4 minus R5. Values of R1, R2, R3 plus R5, and R4 may be taken from the chart in the Resistance-Coupled Amplifiers section. In the practical application of this circuit, it is convenient to use a twin-triode tube combining T<sub>1</sub> and T<sub>2</sub>.




Fig. 34—Push-pull power amplifier resistance-coupled to triode by means of phase inverter.

#### Tone Controls

A tone control is a variable filter (or one in which at least one element is adjustable) by means of which the user may vary the frequency response of an amplifier to suit his own taste. In radio receivers and home amplifiers, the tone control usually consists of a resistance-capacitance network in which the resistance is the variable element.

The simplest form of tone control

is a fixed tone-compensating or "equalizing" network such as that shown in Fig. 35. This type of network is often used to equalize the low- and high-frequency response of a crystal phonograph pickup. At low frequencies the attenuation of this network is 20.8 db. As the frequency is increased, the 100-micromicrofarad capacitor serves as a bypass for the 5-megohm resistor, and the combined impedance of the resistor-capacitor network is reduced. Thus,




Fig. 35—Tone-control circuit for fixed tone compensation or "equalizing".

more of the crystal output appears across the 0.5-megohm resistor at high frequencies than at low frequencies, and the frequency response at the grid is reasonably flat over a wide frequency range. Fig. 36 shows a comparison between the output of the crystal (curve A) and the output of the equalizing network (curve B). The response curve can be "flattened" still more if the attenuation at low frequencies is increased by changing the 0.5-megohm resistor to 0.125 megohm.

The tone-control network shown in Fig. 37 has two stages with completely separate bass and treble controls. Fig. 38 shows simplified representations of




Fig. 36—Curve showing output from crystal phonograph pickup (A) and from equalizing network (B).

the bass control of this circuit when the potentiometer is turned to its extreme variations (usually labeled "Boost" and "Cut"). In this network, as in the crystal-equalizing network shown in Fig. 35, the parallel RC combination is the controlling factor. For bass "boost," the capacitor C<sub>2</sub> bypasses resistor R<sub>3</sub> so that less impedance is placed across the output to grid B at high frequencies than




Fig. 38—Simplified representations of basscontrol circuit at extreme ends of potentiometer.

at low frequencies. For bass "cut," the parallel combination is shifted so that  $C_1$  bypasses  $R_2$ , causing more high-




Fig. 37—Two-stage tone-control circuit incorporating separate bass and treble controls.

frequency than low-frequency output. Essentially, the network is a variable-frequency voltage divider. With proper values for the components, it may be made to respond to changes in the R<sub>3</sub> potentiometer setting for only low frequencies (below 1000 cycles).

Fig. 39 shows extreme positions of the treble control. The attenuation of the two circuits is approximately the same at 1000 cycles. The treble "boost" circuit is similar to the crystal-equalizing network shown in Fig. 35. In the treble "cut" circuit, the parallel RC elements serve to attenuate the signal voltage further because the capacitor by passes the resistance across the output.




Fig. 39—Simplified representations of treble-control circuit at extreme ends of potentiometer.

The effect of the capacitor is negligible at low frequencies; beyond 1000 cycles, the signal voltage is attenuated at a maximum rate of 6 db per octave.

The location of a tone-control network is of considerable importance. In a typical radio receiver, it may be inserted in the plate circuit of the power tube, the coupling circuit between the first af amplifier tube and the power tube, or the grid circuit of the first tube. In an amplifier using a beam power tube or pentode power amplifier without negative feedback, it is desirable to connect a resistancecapacitance filter across the primary of the output transformer. This filter may be fixed, with a supplementary tone control elsewhere, or it may form the tone control itself. If the amplifier incorporates negative feedback, the tone control may be inserted in the feedback network or else should be connected to a part of the amplifier which is external to the feedback loop. The overall gain of a well designed tone-control network should be approximately unity.

#### Phonograph and Tape Preamplifiers

The frequency range and dynamic range which can be recorded on a phonograph record or on magnetic tape depend on several factors, including the composition, mechanical characteristics. and speed of the record or tape, and the electrical and mechanical characteristics of the recording equipment. To achieve wide frequency and dynamic ranges, manufacturers of commercial recordings use equipment which introduces a nonuniform relationship between amplitude and frequency. This relationship is known as a "recording characteristic." To assure proper reproduction of a high-fidelity recording, therefore, some part of the reproducing system must have a frequency-response characteristic which is the inverse of the recording characteristic. Most manufacturers of high-fidelity recordings use the RCA "New Orthophonic" (RIAA) characteristic for discs and the NARTR characteristic for magnetic tape.

Some typical preamplifier stages are shown in the Circuits section. The location of the frequency-compensating network or "equalizer" in the reproducing system will depend on the types of recordings which are to be reproduced and on the pickup devices used.

A ceramic high-fidelity phonograph pickup is usually designed to provide proper compensation for the RIAA recording characteristic when the pickup is operated into the load resistance specified by its manufacturer. Because this type of pickup also has relatively high output (0.5 to 1.5 volts), it does not require the use of either an equalizer network or a preamplifier, and can be connected directly to the input of a tone-control amplifier and/or power amplifier.

A magnetic high-fidelity phonograph pickup, on the other hand, usually has an essentially flat frequency-response characteristic and very low output (1 to 10 millivolts). Because a pickup of this type merely reproduces the recording characteristic, it must be

followed by an equalizer network, as well as by a preamplifier having sufficient voltage gain to provide the input voltage required by the tone-control amplifier and/or power amplifier. Many designs include both the equalizing and amplifying circuits in a single unit.

A high-fidelity magnetic-tape pickup head, like a magnetic phonograph pickup, reproduces the recording characteristic and has an output of only a few millivolts. This type of pickup device, therefore, must also be followed by an equalizing network and preamplifier, or by a preamplifier which provides "built-in" equalization for the NARTB characteristic.

#### Limiters

An amplifier may also be used as a limiter. One use of a limiter is in receivers designed for the reception of frequency-modulated signals. The limiter in FM receivers has the function of eliminating amplitude variations from the input to the detector. Because in an FM system amplitude variations are primarily the result of noise disturbances, the use of a limiter prevents such disturbances from being reproduced in the audio output. The limiter usually follows the last if stage so that it can minimize the effects of disturbances coming in on the rf carrier and those produced locally.

The limiter is essentially an if voltage amplifier designed for saturated operation. Saturated operation means that an increase in signal voltage above a certain value produces very little increase in plate current. A signal voltage which is never less than sufficient to cause saturation of the limiter, even on weak signals, is supplied to the limiter input by the preceding stages. Any change in amplitude, therefore, such as might be produced by noise voltage fluctuation, is not reproduced in the limiter output. The limiting action, of course, does not interfere with the reproduction of frequency variations.

Plate-current saturation of the limiter may be obtained by the use of grid-No. 1-resistor-and-capacitor bias with plate and grid-No. 2 voltages which

are low compared with customary ifamplifier operating conditions.

As a result of these design features, the limiter is able to maintain its output voltage at a constant amplitude over a wide range of input-signal voltage variations. The output of the limiter is frequency-modulated if voltage, the mean frequency of which is that of the if amplifier. This voltage is impressed on the input of the detector.

The reception of FM signals without serious distortion requires that the response of the receiver be such that satisfactory amplification of the signal is provided over the entire range of frequency deviation from the mean frequency. Since the frequency at any instant depends on the modulation at that instant, it follows that excessive attenuation toward the edges of the band, in the rf or if stages, will cause distortion. In a high-fidelity receiver, therefore, the amplifiers must be capable of amplifying, for the maximum permissible frequency deviation of 75 kilocycles, a band 150 kilocycles wide. Suitable tubes for this purpose are the 6BA6 and 6BJ6.

# Television RF Amplifiers

In a radio or television receiver, noise generated in the first amplifier stage is often the controlling factor in determining the over-all sensitivity of the receiver. The "front end" of a receiver, therefore, is designed with special attention to both gain and noise characteristics.

The input circuit of an amplifier inherently contains some thermal noise contributed by the resistive elements in the input device. When an input signal is amplified, therefore, the thermal noise generated in the input circuit is also amplified. If the ratio of signal power to noise power (signal-to-noise ratio, S/N) is the same in the output circuit as in the input circuit, the amplifier is considered to be "noiseless" and is said to have a noise figure of unity, or zero db.

In practical circuits, however, all amplifier stages generate a certain amount of noise as a result of thermal agitation of electrons in resistors and other components, minute variations in the cathode emission of tubes (shot effect), and minute grid currents in the amplifier tubes. As a result, the ratio of signal power to noise power is inevitably impaired during amplification. A measure of the degree of impairment is called the **noise figure** (NF) of the amplifier, and is expressed as the ratio of signal power to noise power at the input  $(S_1/N_1)$  divided by the ratio of signal power to noise power at the output  $(S_0/N_0)$ , as follows:

 $NF = \frac{(S_i/N_i)}{(S_o/S_o)}$ 

The noise figure in db is equal to ten times the logarithm of this power ratio. For example, an amplifier having a one-db noise figure decreases the signal-to-noise ratio by a factor of 1.26, a 3-db noise figure by a factor of 2, a 10-db noise figure by a factor of 10, and a 20-db noise figure by a factor of 100.

Tuner input circuits of vhf television receivers use either a triode or a pentode in the rf amplifier stage. Such stages are required to amplify signals ranging from 55 to 216 Mc and having a bandwidth of 4.5 Mc, although the tuner is usually aligned for a bandwidth of 6 Mc to assure complete coverage of the band. In the early rf tuners, pentodes rather than triodes were used because the grid-plate capacitance of triodes created stability problems. The use of twin triodes in direct-coupled cathode-drive makes it possible to obtain stable operation along with the low-noise characteristics of triodes.

Pentodes or tetrodes do not provide the sensitivity of triodes because of the "partition noise" introduced by the screen grid. The direct-coupled cathodedrive circuit provides both the gain and the stability capabilities of the pentode and a low-noise triode input stage. Because the cathode-drive stage provides a low-impedance load to the grounded-cathode stage, its gain is very low and there is no necessity for neutralizing the grid-plate capacitance. An interstage impedance, usually an inductance in

series with the plate of the first stage and the cathode of the second stage, is often used at higher frequencies to provide a degree of impedance matching between the units. The cathode-drive portion of the circuit is matched to the input network and provides most of the stage gain. Because the feedback path of the cathode-drive circuit is the plate-cathode capacitance, which in most cases is very small, excellent isolation is provided between the antenna and the local oscillator.

Development of single triodes having low grid-plate capacitance has made possible the design of a neutralized triode rf circuit. The 6BN4 has been used commercially in neutralized triode circuits. Tubes such as the 6GK5 and 6CW4, now in common usage, were specially designed to minimize gridplate capacitance to permit easier neutralization of a grounded-cathode circuit over the wide frequency band. The bridge-neutralized rf amplifier circuit has become widely used in television tuners. In this arrangement, a portion of the output signal is returned to the grid out of phase with the feedback signal from the grid-plate capacitance. This circuit provides excellent gain and noise performance with stable operation across the band.

Video Amplifiers

The video amplifier stage in a television receiver usually employs a pentode-type tube specially designed to amplify the wide band of frequencies contained in the video signal and, at the same time, to provide high gain per stage. Pentodes are more useful than triodes in such stages because they have high transconductance (to provide high gain) together with low input and output interelectrode capacitances (to permit the broadband requirements to be satisfied). An approximate "figure of merit" for a particular tube for this application can be determined from the ratio of its transconductance, gm, to the sum of its input and output capacitances, Cin and Cout, as follows:

Figure of Merit =  $\frac{g_m}{C_{in} + C_{out}}$ 

Typical values for this figure are in the order of 500 x 10° or greater.

A typical video amplifier stage, such as that shown in Fig. 40, is connected between the second detector of the television receiver and the picture tube. The contrast control, R<sub>1</sub>, in this circuit controls the gain of the video amplifier tube. The inductance, L<sub>2</sub>, in series with the load resistor, R<sub>L</sub>, maintains the plate load impedance at a relatively constant value with increasing




Fig. 40-Typical video amplifier stage.

frequency. The inductance L<sub>1</sub> isolates the output capacitance of the tube so that only stray capacitance is placed across the load. As a result, a higher-value load resistor is used to provide higher gain without affecting frequency response or phase relations. The decoupling circuit, C<sub>1</sub>R<sub>2</sub>, is used to improve the low-frequency response. Tubes used as video amplifiers include types 6CL6 and 12BY7A, or the pentode sections of types 6AW8A and 6AN8A.

The luminance amplifier in a colortelevision receiver is a conventional video amplifier having a bandwidth of approximately 3.5 Mc. In a color receiver, the portion of the output of the second detector which lies within the frequency band from approximately 2.4 to 4.5 Mc is fed to bandpass amplifier, as shown in the block diagram in Fig. 41. The color synchronizing signal, or "burst," contained in this signal may then be fed to a "burst-keyer" tube. At the same time, a delayed horizontal pulse may be applied to the keyer tube. The output of the keyer tube is applied to the burst amplifier tube and the signal is then fed to the 3.58-Mc oscillator and to the "color-killer" stage.

The color killer applies a bias voltage to the bandpass amplifier in the absence of burst so that the color section, or **chrominance** channel, of the receiver remains inoperative during black-andwhite broadcasts. A threshold control varies the bias and controls the burst level at which the killer stage operates.

The output of the 3.58-Mc oscillator and the output of the bandpass amplifier are fed into phase and amplitude demodulator circuits. The output of each demodulator circuit is an electrical representation of a color-difference signal, i.e., an actual color signal minus the black-and-white, or luminance, signal. The two color-difference signals are combined to produce the third color-difference signal; each of the three signals then represents one of the primary colors.

The three color-difference signals are usually applied to the grids of the three electron guns of the color picture tube, in which case the black-and-white signal from the luminance amplifier may be applied simultaneously to the cathodes. The chrominance and luminance signals then combine to produce the color picture. In the absence of transmitted color information, the chrominance channel is cut off by the color killer, as described above, and only the luminance signal is applied to the picture tube, producing a black-and-white picture.




Fig. 41—Block diagram of video-amplifier section of color television receiver.

#### Television Sync Circuits

In addition to picture information, the composite video signal supplied to a television receiver contains information to assure that the picture produced on the receiver is synchronized with the picture being viewed by the camera or pickup tube. The "sync" pulses, which have a greater amplitude than the video signal, trigger the scanning generators of the receiver when the electron beam of the pickup tube ends each trace.

The sync pulses in the composite video signal may be separated from the video information in the output of the second or video detector by means of the triode circuit shown in Fig. 42. In this circuit, the time constant of the




Fig. 42-Sync-separator circuit.

network R<sub>1</sub>C<sub>1</sub> is long with respect to the interval between pulses. During each pulse, the grid is driven positive and draws current, thereby charging capacitor C1. Consequently, the grid develops a bias which is slightly greater than the cutoff voltage of the tube. Because plate current flows only during the sync-pulse period, only the amplified pulse appears in the output. This sync-separator stage discriminates against the video information. Because the bias developed on the grid is proportional to the strength of the incoming signal, the circuit also has the advantage of being relatively independent of signal fluctuations.

Because the electron beam scans the face of the picture tube at different rates in the vertical and horizontal directions, the receiver incorporates two different scanning generators. The repetition rate of the vertical generator is 60 cycles per second, and the rate of the horizontal generator is approximately 15,750 cycles per second. The composite video signal includes information which enables each generator to derive its correct triggering. One horizontal sync pulse is supplied at the end of each horizontal line scan. At the end of each frame, several pulses of longer-duration than the horizontal sync pulses are supplied to actuate the vertical generator. The vertical information is separated from the horizontal information by differentiating and integrating circuits.

In fringe areas, two conditions complicate the process of sync separation. First, the incoming signal available at the antenna is weak and susceptible to fading and other variations; second, the receiver is operating at or near maximum gain, which makes it extremely susceptible to interference from pulse-type noise generated by certain types of electrical equipment, ignition systems, switches, or the like. Some type of noise-immunity provision is almost essential for acceptable performance. Noise may be reduced or eliminated from the sync and agc circuits by gating or by a combination of gating, inversion, and cancellation. An example, of the latter method is shown in Fig. 43. In this circuit the 6GY6, which has two independent control grids, serves the dual function of agc amplifier and noise inverter. Because the sync tips of the video signal at grid No. 1 of the 6GY6 drive the tube near its cutoff region, any noise signal




Fig. 43—Typical noise-cancellation circuit.

extending above the tip level will appear inverted across the grid-No.2 load resistor R. This inverted noise signal is re-combined with the video signal and fed to the sync separator at point "A" in Fig. 43, where noise cancellation takes place. This process leaves the sync pulses relatively free of disturbing noise and results in a stable picture. To prevent reduction of receiver gain due to the effect of noise on the age amplifier, a portion of the inverted noise signal is fed to the second control grid, grid No.3, of the 6GY6 to cut off or gate the agc amplifier when a noise pulse occurs.

#### Rectification

The rectifying action of a diode finds important applications in supplying a receiver with dc power from an ac line and in supplying high dc voltage from a high-voltage pulse. A typical arrangement for converting ac to dc includes a rectifier tube, a filter, and a voltage divider. The rectifying action of the tube is explained briefly under Diodes, in the Electrons, Electrodes, and Electron Tubes section. High-voltage pulse rectification is described later under Horizontal Output Circuits.

The function of a filter is to smooth out the ripple of the tube output, as indicated in Fig. 44, and to increase rectifier efficiency. The action




Fig. 44—Voltage waveforms of full-wave rectifier circuit.

of the filter is explained in the Electron Tube Installation section under Filters. The voltage divider is used to cut down the output voltage to the values required by the plates and the other electrodes of the tubes in the receiver.

A half-wave rectifier and a full-

wave rectifier circuit are shown in Fig. 45. In the half-wave circuit, current




Fig. 45—Half-wave and full-wave rectifier circuits.

flows through the rectifier tube to the filter on every other half-cycle of the ac input voltage when the plate is positive with respect to the cathode. In the full-wave circuit, current flows to the filter on every half-cycle, through plate No. 1 on one half-cycle when plate No. 1 is positive with respect to the cathode, and through plate No. 2 on the next half-cycle when plate No. 2 is positive with respect to the cathode.

Because the current flow to the filter is more uniform in the full-wave circuit than in the half-wave circuit, the output of the full-wave circuit requires less filtering. Rectifier operating information and circuits are given under each rectifier tube type and in the Circuits section, respectively.

Parallel operation of rectifier tubes furnishes an output current greater than that obtainable with the use of one tube. For example, when two full-wave rectifier tubes are connected in parallel, the plates of each tube are connected together and each tube acts as a half-wave rectifier. The permissible voltage and load conditions per tube are the same as for full-wave service but the total load-handling capability of the complete rectifier is approximately doubled.

When mercury-vapor rectifier tubes are connected in parallel, a stabilizing resistor of 50 to 100 ohms should be connected in series with each plate lead in order that each tube will carry an equal share of the load. The value of the resistor to be used will depend on the amount of plate current that passes through the rectifier. Low plate current requires a high value; high plate current, a low value. When the plates of mercury-vapor rectifier tubes are connected in parallel, the corresponding filament leads should be similarly connected. Otherwise, the tube drops will be considerably unbalanced and larger stabilizing resistors will be required.

Two or more vacuum rectifier tubes can also be connected in parallel to give correspondingly higher output current and, as a result of paralleling their internal resistances, give somewhat increased voltage output. With vacuum types, stabilizing resistors may or may not be necessary depending on the tube type and the circuit.

A voltage-doubler circuit of simple form is shown in Fig. 46. The circuit derives its name from the fact that its




Fig. 46—Full-wave voltage-doubler circuit.


dc voltage output can be as high as twice the peak value of ac input. Basically, a voltage doubler is a rectifier circuit arranged so that the output voltages of two half-wave rectifiers are in series.

The action of a voltage doubler can be described briefly as follows. On the positive half-cycle of the ac input. that is, when the upper side of the ac input line is positive with respect to the lower side, the upper diode passes current and feeds a positive charge into the upper capacitor. As positive accumulates on the upper charge plate of the capacitor, a positive voltage builds up across the capacitor. On the next half-cycle of the ac input, when the upper side of the line is negative with respect to the lower side. the lower diode passes current so that a negative voltage builds up across the lower capacitor.


So long as no current is drawn at the output terminals from the capacitor. each capacitor can charge up to a voltage of magnitude E, the peak value of the ac input. It can be seen from the diagram that with a voltage of +E on one capacitor and -E on the other, the total voltage across the capacitors is 2E. Thus the voltage doubler supplies a no-load dc output voltage twice as large as the peak ac input voltage. When current is drawn at the output terminals by the load, the output voltage drops below 2E by an amount that depends on the magnitude of the load current and the capacitance of the capacitors. The arrangement shown in Fig. 46 is called a full-wave voltage doubler because each rectifier passes current to the load on each half of the ac input cycle.

Two rectifier types especially designed for use as voltage doublers are the 25Z6GT and 117Z6GT. These tubes combine two separate diodes in one tube. As voltage doublers, the tubes are used in "transformerless" receivers. In these receivers, the heaters of all tubes in the set are connected in series with a voltage-dropping resistor across the line. The connections for the heater supply and the voltage-doubling circuit are shown in Fig. 47.

With the full-wave voltage-doubler circuit in Fig. 47, it will be noted that the dc load circuit can not be connected to ground or to one side of the ac supply



R = HEATERS OF OTHER TUBES IN SERIES WITH VOLTAGE-DROPPING RESISTOR



R-= PROTECTIVE RESISTOR

Fig. 47—Full-wave and half-wave voltage-doubler circuits showing heater-supply connections.

line. This circuit presents certain disadvantages when the heaters of all the tubes in the set are connected in series with a resistance across the ac line. Such a circuit arrangement may cause hum because of the high ac potential between the heaters and cathodes of the tubes.

The half-wave voltage-doubler circuit in Fig. 47 overcomes this difficulty by making one side of the ac line common with the negative side of the dc load circuit. In this circuit, one half of the tube is used to charge a capacitor which, on the following half cycle, discharges in series with the line voltage through the other half of the tube. This circuit is called a half-wave voltage doubler because rectified current flows to the load only on alternate halves of the ac input cycle. The voltage regulation of this arrangement is somewhat poorer than that of the fullwave voltage doubler.

#### Detection

When speech, music, or video information is transmitted from a radio or television station, the station radiates a radio-frequency (rf) wave which is of either of two general types. In one type, the wave is said to be amplitude

modulated when its frequency remains constant and the amplitude is varied. In the other type, the wave is said to be frequency modulated when its amplitude remains essentially constant but its frequency is varied.

The function of the receiver is to reproduce the original modulating wave from the modulated rf wave. The receiver stage in which this function is performed is called the demodulator or detector stage.

#### AM Detection

The effect of amplitude modulation on the waveform of the rf wave is shown in Fig. 48. There are three different basic circuits used for the detection of amplitude-modulated waves: the diode detector, the grid-bias detector, and the grid-resistor detector. These circuits are alike in that they eliminate, either partially or completely, alternate half-cycles of the rf wave. With alternate half-cycles removed, the audio variations of the other half-cycles can be amplified to drive headphones or a loud-speaker.

A diode-detector circuit is shown in Fig. 49. The action of this circuit when a modulated rf wave is applied is





AF MODULATING



AMPLITUDE - MODULATE

Fig. 48-Waveforms showing effect of amplitude modulation on an rf wave.




Fig. 49-Basic diode-detector circuit.

illustrated by Fig. 50. The rf voltage applied to the circuit is shown in light line; the output voltage across capacitor C is shown in heavy line.

Between points (a) and (b) on the first positive half-cycle of the applied rf voltage, capacitor C charges up to the peak value of the rf voltage. Then as the applied rf voltage falls away from its peak value, the capacitor holds the cathode at a potential more positive than the voltage applied to the anode. The capacitor thus temporarily cuts off current through the diode. While the diode current is cut off, the capacitor discharges from (b) to (c) through the diode load resistor R.

When the rf voltage on the anode rises high enough to exceed the potential



Fig. 50—Waveforms showing modulated rf input (light line) and output voltage (heavy line) of diode-detector circuit.

at which the capacitor holds the cathode, current flows again and the capacitor charges up to the peak value of the second positive half-cycle at (d). In this way, the voltage across the capacitor follows the peak value of the applied rf voltage and reproduces the af modulation.

The curve for voltage across the capacitor, as drawn in Fig. 50, is somewhat jagged. However, this jaggedness, which represents an rf component in the voltage across the capacitor, is exaggerated in the drawing. In an actual circuit the rf component of the voltage across the capacitor is negligible. Hence,

when the voltage across the capacitor is amplified, the output of the amplifier reproduces the speech or music originating at the transmitting station.

Another way to describe the action of a diode detector is to consider the circuit as a half-wave rectifier. When the rf signal on the plate swings positive, the tube conducts and the rectified current flows through the load resistance R. Because the dc output voltage of a rectifier depends on the voltage of the ac input, the dc voltage across C varies in accordance with the amplitude of the rf carrier and thus reproduces the af signal. Capacitor C should be large enough to smooth out rf or if variations, but should not be so large as to affect the audio variations. Two diodes can be connected in a circuit similar to a full-wave rectifier to provide full-wave detection. However, in practice, the advantages of this connection generally do not justify the extra circuit complication.

The diode method of detection produces less distortion than other methods because the dynamic characteristics of a diode can be made more linear than those of other detectors. The disadvantages of a diode are that it does not amplify the signal, and that it draws current from the input circuit and therefore reduces the selectivity of the input circuit. However, because the diode method of detection produces less distortion and because it permits the use of simple ave circuits without the necessity for an additional voltage supply, the diode method of detection is most widely used in broadcast receivers.

A typical diode-detector circuit using a twin-diode triode tube is shown in Fig. 51. Both diodes are connected




Fig. 51—Typical diode-detector circui using a twin diode—triode tube.

together.  $R_1$  is the diode load resistor. A portion of the af voltage developed across this resistor is applied to the triode grid through the volume control  $R_3$ . In a typical circuit, resistor  $R_1$  may be tapped so that five-sixths of the total af voltage across  $R_1$  is applied to the volume control. This tapped connection reduces the af voltage output of the detector circuit slightly, but it reduces audio distortion and improves the rf filtering.

DC bias for the triode section is provided by the cathode-bias resistor  $R_2$  and the audio bypass capacitor  $C_3$ . The function of capacitor  $C_2$  is to block the dc bias of the cathode from the grid. The function of capacitor  $C_4$  is to bypass any rf voltage on the grid to cathode. A twin-diode pentode may also be used in this circuit. With a pentode, the af output should be resistance-coupled rather than transformer-coupled.

Another diode-detector circuit, called a diode-biased circuit, is shown in Fig. 52. In this circuit, the triode grid




Fig. 52—Diode-biased detector circuit.

is connected directly to a tap on the diode load resistor. When an rf signal voltage is applied to the diode, the dc voltage at the tap supplies bias to the triode grid. When the rf signal is modulated, the af voltage at the tap is applied to the grid and is amplified by the triode.

The advantage of the circuit shown in Fig. 52 over the self-biased arrangement shown in Fig. 51 is that the diode-biased circuit does not employ a capacitor between the grid and the diode load resistor, and consequently does not produce as much distortion of a signal having a high percentage of modulation.

However, there are restrictions on the use of the diode-biased circuit. Because the bias voltage on the triode depends on the average amplitude of the rf voltage applied to the diode, the average amplitude of the voltage applied to the diode should be constant for all values of signal strength at the antenna. Otherwise there will be different values of bias on the triode grid for different signal strengths and the triode will produce distortion. Because there is no bias applied to the diodebiased triode when no rf voltage is applied to the diode, sufficient resistance should be included in the plate circuit of the triode to limit its zerobias plate current to a safe value.

These restrictions mean, in practice, that the receiver should have a separate-channel automatic-volume-control (avc) system. With such an avc system, the average amplitude of the signal voltage applied to the diode can be held within very close limits for all values of signal strength at the antenna.

The tube used in a diode-biased circuit should be one which operates at a fairly large value of bias voltage. The variations in bias voltage are then a small percentage of the total bias and hence produce small distortion. Tubes taking a fairly large bias voltage are types such as the 6BF6 or 6SR7 having a medium-mu triode. Tube types having a high-mu triode or a pentode should not be used in a diode-biased circuit.

A grid-bias detector circuit is shown in Fig. 53. In this circuit, the grid is biased almost to cutoff, *i.e.*, operated so that the plate current with zero signal is practically zero. The bias voltage can be obtained from a cathode-bias resistor, a C-battery, or a bleeder




Fig. 53-Grid-bias detector circuit.

tap. Because of the high negative bias, only the positive half-cycles of the rf signal are amplified by the tube. The signal is, therefore, detected in the plate circuit. The advantages of this method of detection are that it amplifies the signal, besides detecting it, and that it does not draw current from the input circuit and therefore does not reduce the selectivity of the input circuit.

The grid-resistor-and-capacitor method, illustrated in Fig. 54, is somewhat more sensitive than the grid-bias method and gives its best results on weak signals. In this circuit, there is no negative dc bias voltage applied to the grid. Hence, on the positive half-cycles of the rf signal, current flows from grid to cathode. The grid and cathode thus




Fig. 54—Detector circuit using grid-resistorand-capacitor bias.

act as a diode detector, with the grid resistor as the diode load resistor and the grid capacitor as the rf bypass capacitor. The voltage across the capacitor then reproduces the af modulation in the same manner as has been explained for the diode detector. This voltage appears between the grid and cathode and is therefore amplified in the plate circuit. The output voltage thus reproduces the original af signal.

In this detector circuit, the use of a high-resistance grid resistor increases selectivity and sensitivity. However, improved af response and stability are obtained with lower values of grid-circuit resistance. This detector circuit amplifies the signal, but draws current from the input circuit and therefore reduces the selectivity of the input circuit.

#### FM Detection

The effect of frequency modulation on the waveform of the rf wave is shown in Fig. 55. In this type of transmission, the frequency of the rf wave deviates from a mean value, at an rf rate depending on the modulation, by an amount that is determined in the transmitter and is proportional to the amplitude of the af modulation signal.

For this type of modulation, a detector is required to discriminate between deviations above and below the mean frequency and to translate those




Fig. 55—Waveforms showing effect of frequency modulation on an rf wave.

deviations into a voltage whose amplitude varies at audio frequencies. Since the deviations occur at an audio frequency, the process is one of demodulation, and the degree of frequency deviation determines the amplitude of the demodulated (af) voltage.

A simple circuit for converting frequency variations to amplitude variations is a circuit which is tuned so that the mean radio frequency is on one slope of its resonance characteristic, as at A of Fig. 56. With modulation, the frequency swings between B and C, and the voltage developed across the circuit varies at the modulating rate. In order that no distortion will be introduced in

this circuit, the frequency swing must be restricted to the portion of the slope which is effectively straight. Since this portion is very short, the voltage developed is low. Because of these limitations, this circuit is not commonly used but it serves to illustrate the principle.




Fig. 56—Resonance curve showing desired operating range for frequency-modulation converter.

The faults of the simple circuit are overcome in a push-pull arrangement, sometimes called a discriminator circuit, such as that shown in Fig. 57. Because of the phase relationships between the primary and each half of the secondary of the input transformer (each half of the secondary is connected in series with the primary through capacitor C<sub>2</sub>), the rf voltages applied to the diodes become unequal as the rf signal swings from the resonant frequency in each direction.




Fig. 57-Basic discriminator circuit.

Because the swing occurs at audio frequencies (determined by the af modulation), the voltage developed across the diode load resistors, R<sub>1</sub> and R<sub>2</sub> connected in series, varies at audio frequencies. The output voltage depends

on the difference in amplitude of the voltages developed across R<sub>1</sub> and R<sub>2</sub>. These voltages are equal and of opposite sign when the rf carrier is not modulated and the output is, therefore, zero. When modulation is applied, the output voltage varies as shown in Fig. 58.

Because this type of FM detector is sensitive to amplitude variations in the rf carrier, a limiter stage is frequently used to remove most of the amplitude modulation from the carrier. (See Limiters under Amplification.)

Another form of detector for frequency-modulated waves is called a ratio detector. This FM detector, unlike the previous one which responds to a difference in voltage, responds only to changes in the ratio of the voltage across two diodes and is, therefore, insensitive to changes in the differences in the voltages due to amplitude modulation of the rf carrier.




Fig. 58—Output waveform of discriminator circuit.

The basic ratio detector is given in Fig. 59. The plate load for the final if amplifier stage is the parallel resonant circuit consisting of C<sub>1</sub> and the primary transformer T. The tuning and coupling of the transformer are practically the same as in the previous circuit and, therefore, the rf voltages applied to the diodes depend upon how much the rf signal swings from the resonant frequency in each direction. At this point the similarity ends.

Diode 1, R<sub>2</sub>, and diode 2 complete a series circuit fed by the secondary of the transformer T. The two diodes are connected in series so that they conduct on the same rf half-cycle. The rectified current through R<sub>2</sub> causes a negative




Fig. 59-Basic ratio-detector circuit.

voltage to appear at the plate of diode 1. Because  $C_0$  is large, this negative voltage at the plate of diode 1 remains constant even at the lowest audio frequencies to be reproduced.

The rectified voltage across C<sub>3</sub> is proportional to the voltage across diode 1, and the rectified voltage across C<sub>4</sub> is proportional to the voltage across diode 2. Because the voltages across the two diodes differ according to the instantaneous frequency of the carrier, the voltages across C<sub>3</sub> and C<sub>4</sub> differ proportionately, the voltage across C<sub>3</sub> being the larger of the two voltages at carrier frequencies below the intermediate frequency and the smaller at frequencies above the intermediate frequency.

These voltages across C<sub>3</sub> and C<sub>4</sub> are additive and their sum is fixed by the constant voltage across C<sub>6</sub>. Therefore, while the ratio of these voltages varies at an audio rate, their sum is always constant. The voltage across C<sub>4</sub> varies at an audio rate when a frequency-modulated rf carrier is applied to the ratio detector; this audio voltage is extracted and fed to the audio amplifier. For a complete circuit utilizing this type of detector, refer to the Circuits section.

#### **Automatic Value or Gain Control**

The chief purpose of automatic volume control (avc) or automatic gain control (agc) in a radio or television receiver is to prevent fluctuations in loudspeaker volume or picture brightness when the audio or video signal at the antenna is fading in and out.

An automatic volume control circuit regulates the receiver rf and if gain so that this gain is less for a strong signal than for a weak signal. In this way, when the signal strength at the antenna changes, the avc circuit reduces the resultant change in the voltage output of the last if stage and consequently reduces the change in the speaker output volume.

The avc circuit reduces the rf and if gain for a strong signal usually by increasing the negative bias of the rf, if, and frequency-mixer stage when the signal increases. A simple avc circuit is shown in Fig. 60. On each positive half-cycle of the signal voltage, when the diode plate is positive with respect to the cathode, the diode passes current.




Fig. 60—Automatic-volume-control (avc) circuit.

Because of the flow of diode current through R<sub>1</sub>, there is a voltage drop across R<sub>1</sub> which makes the left end of R<sub>1</sub> negative with respect to ground. This voltage drop across R1 is applied, through the filter R2 and C, as negative bias on the grids of the preceding stages. When the signal strength at the antenna increases, therefore, the signal applied to the avc diode increases, the voltage drop across R<sub>1</sub> increases, the negative bias voltage applied to the rf and if stages increases, and the gain of the rf and if stages is decreased. Thus the increase in signal strength at the antenna does not produce as much increase in the output of the last if stage as it would produce without avc.

When the signal strength at the antenna decreases from a previous steady value, the avc circuit acts, of course, in the reverse direction, applying less negative bias, permitting the rf and if gain to increase, and thus reducing the decrease in the signal output of the last if stage. In this way, when the signal strength at the antenna changes, the avc circuit acts to reduce change in the output of the last if stage, and thus acts to reduce change in loudspeaker volume.

The filter, C and R2 prevents the ave voltage from varying at audio frequency. The filter is necessary because the voltage drop across R<sub>1</sub> varies with the modulation of the carrier being received. If avc voltage were taken directly from R<sub>1</sub> without filtering, the audio variations in avc voltage would vary the receiver gain so as to smooth out the modulation of the carrier. To avoid this effect, the avc voltage is taken from the capacitor C. Because of the resistance R2 in series with C, the capacitor C can charge and discharge at only a comparatively slow rate. The avc voltage therefore cannot vary at frequencies as high as the audio range but can vary at frequencies high enough to compensate for most fading. Thus the filter permits the avc circuit to smooth out variations in signal due to fading, but prevents the circuit from smoothing out audio modulation.

It will be seen that an avc circuit and a diode-detector circuit are much alike. It is therefore convenient in a receiver to combine the detector and the avc diode in a single stage. Examples of how these functions are combined in receivers are shown in Circuits section.

In the circuit shown in Fig. 60, a certain amount of avc negative bias is applied to the preceding stages on a weak signal. Because it may be desirable to maintain the receiver rf and if gain at the maximum possible value for a weak signal, avc circuits are designed in some cases to apply no avc bias until the signal strength exceeds a certain value. These avc circuits are known as delayed avc or davc circuits.

A dave circuit is shown in Fig. 61. In this circuit, the diode section  $D_1$  of the 6H6 acts as detector and ave diode.




Fig. 61—Delayed avc (davc) circuit.

R<sub>1</sub> is the diode load resistor and R<sub>2</sub> and C2 are the avc filter. Because the cathode of diode D<sub>2</sub> is returned through a fixed supply of -3 volts to the cathode of D<sub>1</sub>, a dc current flows through R<sub>1</sub> and R<sub>2</sub> in series with D<sub>2</sub>. The voltage drop caused by this current places the avc lead at approximately -3 volts (less the negligible drop through D<sub>2</sub>). When the average amplitude of the rectified signal developed across R<sub>1</sub> does not exceed 3 volts, the avc lead remains at —3 volts. Hence, for signals not strongh enough to develop 3 volts across R<sub>1</sub>, the bias applied to the controlled tubes stays constant at a value giving high sensitivity.

However, when the average amplitude of rectified signal voltage across R<sub>1</sub> exceeds 3 volts, the plate of diode D<sub>2</sub> becomes more negative than the cathode of D<sub>2</sub> and current flow in diode D<sub>2</sub> ceases. The potential of the avelead is then controlled by the voltage developed across R<sub>2</sub>. Therefore, with further increase in signal strength, the avc circuit applies an increasing avc bias voltage to the controlled stages. In this way, the circuit regulates the receiver gain for strong signals, but permits the gain to stay constant at a maximum value for weak signals.

It can be seen in Fig. 61 that a portion of the -3 volts delay voltage is applied to the plate of the detector diode  $D_1$ , this portion being approximately equal to  $R_1/(R_1 + R_2)$  times -3 volts. Hence, with the circuit constants

as shown, the detector plate is made negative with respect to its cathode by approximately one-half volt. However, this voltage does not interfere with detection because it is not large enough to prevent current flow in the tube.

Automatic gain control (agc) compensates for fluctuations in rf picture carrier amplitude. The peak carrier level rather than the average carrier level is controlled by the agc voltage because the peaks of the sync pulses are fixed when inserted on a fixed carrier level. The peak carrier level may be determined by measurement of the peaks of the sync pulses at the output of the video detector.

A conventional age circuit, such as that shown in Fig. 62, consists of a diode




Fig. 62—Automatic-gain control (agc) circuit.

detector circuit and an RC filter. The time constant of the detector circuit is made large enough to prevent the picture content from influencing the magnitude of the agc voltage. The output voltage (agc voltage) is equal to the peak value of the incoming signal.

The diode detector receives the incoming signal from the last if stage of the television receiver through the capacitor C<sub>1</sub>. The resistor R<sub>1</sub> provides the load for the diode. The diode conducts only when its plate is driven positive with respect to its cathode. Electrons then flow from the cathode to the plate and thence into capacitor C<sub>1</sub>, where the negative charge is stored. Because of the low impedance offered by the diode during conduction, C<sub>1</sub> charges up to the value of the peak applied voltage.

During the negative excursion of the signal, the diode does not conduct, and  $C_1$  discharges through resistor  $R_1$ . Because of the large time constant of  $R_1C_1$ , however, only a small percentage of the voltage across  $C_1$  is lost during the interval between horizontal sync

pulses. During succeeding positive cycles, the incoming signal must overcome the negative charge stored in C<sub>1</sub> before the diode conducts, and plate current flows only at the peak of each positive cycle. The voltage across C<sub>1</sub>, therefore, is determined by the level of the peaks of the positive cycles, or the sync pulses.

The negative voltage developed across resistor R<sub>1</sub> by the sync pulses is filtered by resistor R<sub>2</sub> and capacitor C<sub>2</sub> to remove the 15,750-cycle ripple of the horizontal sync pulse. The dc output is then fed to the if and rf amplifiers as an agc voltage.

This agc system may be expanded to include amplification of the agc signal before detection of the peak level, or amplification of the dc output, or both. A direct-coupled amplifier must be used for amplification of the dc signal. The addition of amplification makes the system more sensitive to changes in carrier level.

A "keyed" agc system such as that shown in Fig. 63 is used to eliminate flutter and to improve noise immunity in weak signal areas. This system provides more rapid action than the conventional agc circuits because the filter circuit can employ lower capacitance and resistance values.




Fig. 63—"Keyed" agc circuit.

In the keyed agc system, the negative output of the video detector is fed directly to the grid No. 1 of the first video amplifier. The positive output of the video amplifier is, in turn, fed directly to the grid No. 1 of the keyed agc amplifier. The video stage increases the gain of the agc system and, in addition,

provides noise clipping. The plate voltage for the agc amplifier is a positive pulse obtained from a small winding on the horizontal output transformer which is in phase with the horizontal sync pulse obtained from the video amplifier. The polarity of this pulse is such that the plate of the age amplifier tube is positive during the retrace time. The tube is biased so that current flows only when the grid No. 1 and the plate are driven positive simultaneously. amount of current flow depends on the grid-No. 1 potential during the pulse. These pulses are smoothed out in the RC network in the plate circuit  $(R_1C_1)$ . Because the dc voltage developed across R<sub>1</sub> is negative, it is suitable for application to the grids of the rf and if tubes as an agc voltage.

#### Tuning Indication With Electron-Ray Tubes

Electron-ray tubes are designed to indicate visually by means of a fluorescent target the effects of a change in controlling voltage. One application of them is as tuning indicators in radio receivers. Types such as the 6U5, 6E5, and the 6AB5/6N5 contain two main parts: (1) a triode which operates as a dc amplifier and (2) an electron-ray indicator which is located in the bulb as shown in Fig. 64. The target is operated at a positive voltage and, therefore, attracts electrons from the cathode. When




Fig. 64—Structure of electron-ray tube. the electrons strike the target they produce a glow on the fluorescent coating of the target. Under these conditions, the target appears as a ring of light.

A ray-control electrode is mounted between the cathode and target. When the potential of this electrode is less positive than the target, electrons flowing to the target are repelled by the electrostatic field of the electrode, and do not reach that portion of the target behind the electrode. Because the target does not glow where it is shielded from electrons, the control electrode casts a shadow on the glowing target. The extent of this shadow varies from approximately 100° of the target when the control electrode is much more negative than the target to 0° when the control electrode is at approximately the same potential as the target.

In the application of the electronray tube, the potential of the control electrode is determined by the voltage on the grid of the triode section, as can be seen in Fig. 65. The flow of the triode plate current through resistor R produces a voltage drop which determines





Fig. 65—Indicating circuit using an electron-ray tube.

the potential of the control electrode. When the voltage of the triode grid changes in the positive direction, plate current increases, the potential of the control electrode goes down because of the increased drop across R, and the shadow angle widens. When the potential of the triode grid changes in the negative direction, the shadow angle narrows.

Another type of indicator tube is the 6AF6G. This tube contains only an indicator unit but employs two ray-control electrodes mounted on opposite sides of the cathode and connected to individual base pins. It employs an external dc amplifier. (See Fig. 66.) Thus, two symmetrically opposite shadow angles may be obtained by connecting the two ray-control electrodes together; or, two unlike patterns may be obtained by individual connection of each ray-control electrode to its respective amplifier.

In radio receivers, avc voltage is



R: TYPICAL VALUE IS 0.5 MEGOHM

Fig. 66—Indicating circuit using 6AF6G electron-ray tube and external dc amplifier.

applied to the grid of the dc amplifier. Because ave voltage is at maximum when the set is tuned to give maximum response to a station, the shadow angle is at minimum when the receiver is tuned to resonance with the desired station.

The choice between electron-ray tubes depends on the avc characteristic of the receiver. The 6E5 contains a sharp-cutoff triode which closes the shadow angle on a comparatively low value of avc voltage. The 6AB5/6N5 and 6U5 each have a remote-cutoff triode which closes the shadow on a larger value of avc voltage than the 6E5. The 6AF6G may be used in conjunction with dc amplifier tubes having either remote- or sharp-cutoff characteristics.

#### Oscillation

As an oscillator, an electron tube can be employed to generate a continuously alternating voltage. In present-day radio broadcast receivers, this application is limited practically to superheterodyne receivers for supplying the heterodyning frequency. Several circuits (represented in Figs. 67 and 68) may be utilized, but they all depend on feeding more energy from the plate circuit to the grid circuit than is required to equal the power loss in the grid circ




Fig. 67—Tuned-grid triode oscillator circuit using filament-type tube.

cuit. Feedback may be produced by electrostatic or electromagnetic coupling between the grid and plate circuits. When sufficient energy is fed back to more than compensate for the loss in the grid circuit, the tube will oscillate. The action consists of regular surges of power between the plate and the grid circuit at a frequency dependent on the circuit constants of inductance and capacitance. By proper choice of these values, the frequency may be adjusted over a very wide range.




Fig. 68—Tuned-grid triode oscillator circuit using heater-cathode-type tube.

#### Multivibrators

Relaxation oscillators, which are widely used in present-day electronic equipment, are used to produce non-sinusoidal waveshapes such as rectangular and sawtooth pulses. Probably the most common relaxation oscillator is the multivibrator, which may be considered as a two-stage resistance-coupled amplifier in which the output of each tube is coupled into the input of the other tube.

Fig. 69 is a basic multivibrator circuit of the free-running type. In this circuit, oscillations are maintained by the alternate shifting of conduction from one tube to the other. The cycle usually starts with one tube, V<sub>1</sub>, at zero bias, and the other, V2 at cutoff or beyond. At this point, the capacitor C1 is charged sufficiently to cut off V2. C1 then begins to discharge through the resistor R4, and the voltage on the grid of V2 rises until  $V_2$  begins to conduct. The voltage on the plate of V2 then decreases, causing V1 to conduct less and less. At the same time, the plate voltage of V<sub>1</sub> begins to rise, causing V2 to conduct still more heavily. Because of the amplification, this cumulative effect builds up extremely fast,

and conduction switches from  $V_1$  to  $V_2$  within a few microseconds, depending on the circuit components.

In this circuit, therefore, conduction switches from  $V_1$  to  $V_2$  over the interval during which  $C_1$  discharges from the voltage across  $R_4$  to the cutoff voltage for  $V_2$ . The actual transfer of conduction does not occur until cutoff is reached. Conduction switches back to  $V_1$  through a similar process to complete the cycle. The plate waveform is essentially rectangular in shape, and may be adjusted as to symmetry, frequency, and amplitude by proper choice of circuit constants, tubes, and voltages.

Although this type of multivibrator is free-running, it may be triggered by




Fig. 69—Basic multivibrator circuit of the free-running type.

pulses of a given amplitude and frequency to provide a frequency-stabilized output. Multivibrator circuits may also be designed so that they are not freeruning, but must be triggered externally to shift conduction from one tube to the other. Depending on the type of circuit, conduction may shift back to the first tube after a given time interval, or the second tube may continue conducting until another trigger signal is applied.

# Synchroguide Circuits

The "synchroguide" is a controlled type of oscillator used in television receivers to generate and control the synchronized sawtooth voltage necessary for adequate line- or horizontal-frequency scanning. A simplified synchroguide circuit is shown in Fig. 70. This circuit provides stable, noise-free control of a blocking oscillator which generates a horizontal-frequency signal. It permits comparison of the received sync pulses and the generated sawtooth voltages so




Fig. 70-Simplified synchroguide circuit.

that properly locked-in horizontal scanning results.

The triode V<sub>2</sub> in Fig. 70 is a conventional blocking oscillator which enables a sawtooth voltage to be developed across the capacitor C2. A portion of this sawtooth is fed back to the grid of the control tube, V<sub>1</sub>. The positive sync pulses are also applied to the grid of V<sub>1</sub>. The waveforms shown in Fig. 71 illustrate the sawtooth and sync pulses (A and B) and their proper "in-sync" combination (C). The sync pulse occurs partly during the portion of the sawtooth voltage in which the triode V<sub>1</sub> draws current. Any shift in sync pulse as it is superimposed on the sawtooth. therefore, will affect the amount of conduction of the control tube. A change in control-tube conduction ultimately affects the bias on the oscillatortube grid by changing the voltage to which the capacitor C<sub>1</sub> in the cathode circuit may charge. An increase in the positive bias increases the frequency of oscillation.

For example, waveform D in Fig. 71 illustrates a condition in which the sawtooth voltage is advanced in phase with respect to the sync pulses. The widening of the pulse which occurs at




Fig. 71—Sawtooth and sync pulses in synchroguide circuit.

the corner of the sawtooth waveform allows the control tube to conduct more current and, consequently, allows the capacitor  $C_1$  to charge to a higher voltage. This increased reference voltage also appears in the grid circuit of  $V_2$  and makes the grid more positive. The increased grid voltage then speeds up the frequency of oscillations until proper synchronization results.

The blocking oscillator can be made more immune to changes in frequency and noise if V<sub>2</sub> is brought out of cutoff very sharply. This effect is obtained by sine-wave stabilization. The tuned circuit L<sub>2</sub>C<sub>2</sub> in the plate circuit of Fig. 70 superimposes a shock-excited sine wave on the plate and grid waveforms, as shown in Fig. 72.

#### **Deflection Circuits**

#### Vertical Output Circuits

A modified multivibrator in which the vertical output tube is part of the oscillator circuit is used in the vertical deflection stage of many television receivers. This stage supplies the deflection energy required for vertical deflection of the picture-tube beam. A simplified combined vertical-oscillator-output stage is shown in Fig. 73. Waveshapes at critical points of the circuit are included to illustrate the development of the desired current through the vertical output transformer and deflecting yoke.

The current waveform through the deflecting yoke and output transformer




Fig. 72—Waveforms showing effect of tuned circuit L<sub>3</sub>C<sub>3</sub> in Fig. 70.

should be a sawtooth to provide the desired deflection. The grid and plate voltage waveforms of the output tube could also be sawtooth except for the effect of the inductive components in the voke and transformer. The effect of these inductive components must be taken into consideration, however, particularly during retrace. The fast rate of current change during retrace time (which is approximately 1/15 as long as trace time) causes a high-voltage pulse at the plate which could give a trapezoidal waveshape to the plate voltage and cause increased plate current, excess damping, and lengthened retrace time. However, the grid voltage is made sufficiently negative during retrace to keep the tube close to cutoff, as described below.

The frequency, and the relative deviation of the positive and negative portions of each cycle, are dependent on the values of resistors  $R_1$  and  $R_3$  and the RC combination  $R_3C_2$ , as explained previously in the section on multivibrators. The desired trapezoidal waveshape at the grid of  $V_2$  is created by capacitor  $C_1$  and resistor  $R_2$ . If  $R_2$  were equal to




Fig. 73—Simplified combined vertical-oscillator-and-output stage.

zero,  $C_1$  would cause the grid-voltage waveshape to take the form shown in Fig. 74(a). When  $R_2$  is sufficiently large,  $C_1$  does not discharge completely when  $V_1$  conducts. When  $V_1$  is cut off, therefore, the voltage on the grid of  $V_2$  immediately rises to the voltage across  $C_1$ . The resulting waveshape is shown in Fig. 74(b). The negative-going pulse of the grid-voltage waveshape prevents the high plate pulse from causing excess conductance, and thereby prevents overdamping.



Fig. 74—Waveforms showing effect of R<sub>2</sub> in Fig. 73.

This vertical deflection stage utilizes twin-triode tubes such as the 6DR7 and 6EM7. The 6EM7 is particularly suitable for this application because it incorporates dissimilar units to provide for the different operating requirements of the oscillator and output sections.

#### Horizontal Output Circuits

Fig. 75 shows a typical horizontal-output-and-deflection circuit used in television receivers. In addition to supplying the deflection energy required for horizontal deflection of the picture-tube beam, this circuit provides the high dc voltage required for the ultor of the picture tube and the "boosted" B voltage for other portions of the receiver. The horizontal-output tube is usually a beam power tube such as the 6DQ6B, 6CD6-GA, or 6GW6.

In this circuit, a sawtooth voltage from the horizontal-oscillator tube is applied to the grid No. 1 of the horizontal-output tube. When this voltage rises above the cutoff point of the output tube, the tube conducts a sawtooth of plate current which is fed through the auto-transformer to the horizontal-deflecting yoke. At the end of the horizontal-scanning cycle, which lasts for 63.4 microseconds, the sawtooth voltage on the grid suddenly cuts off the output tube. This sudden change sets up an

oscillation of about 50 to 70 Kc in the output circuit, which may be considered as an inductor shunted by the stray capacitance of the circuit. During the first half of this oscillation, a positive voltage appears across the transformer. In the second half of the cycle, the voltage swings below the plate supply voltage, and the damper diode conducts, damping out the oscillation. At the same time, the current through the deflecting yoke reverses and reaches its negative peak. As the damper-diode current decays exponentially to zero, the output tube begins to conduct again. The voke current, therefore, is composed of current resulting from damper-diode conduction followed by output-tube conduction.

When the output tube is suddenly cut off, the high-voltage pulse produced by shock excitation of the load circuit is increased by means of an extra winding on the transformer. This high-voltage pulse charges a high-voltage capacitor through the high-voltage rectifier. The output of this circuit is the dc high-voltage supply for the picture tube. The high-voltage rectifier also obtains its filament power through a separate wind-




Fig. 75—Typical horizontal-deflection and high-voltage circuit.

ing on the horizontal-output transformer.

Current flowing through the damper diode charges the "boost" capacitor through the damper portion of the transformer winding. The polarity of the charge on the capacitor is such that the voltage at the low end of the winding is increased above the plate supply voltage, or B+. This higher voltage or "boost" is used for the output-tube plate supply, and may also supply the deflection oscillators and the vertical-output circuit provided the current drain is not excessive.

#### High-Voltage Regulator Circuit

In color-television receivers, it is very important to regulate the high-voltage supply to the picture tube. A suitable circuit using the 6BK4 for regulation of the output of a high-voltage, high-impedance supply is shown in Fig. 76. In this circuit, the cathode is held at




Fig. 76—High-voltage regulator circuit for color television.

a fixed positive potential with respect to ground. Because the grid potential is kept slightly less positive by the voltage drop across resistor R<sub>2</sub>, the tube operates in the negative grid region and no grid current is drawn.


When the output voltage, eo, rises as a result of a decrease in load current, a small fraction of the additional voltage is applied to the grid of the tube by the voltage-divider circuit consisting of R<sub>1</sub> and R<sub>2</sub>. This increased grid voltage causes the tube to draw an increased current from the unregulated supply. The increased current, in turn, causes a voltage drop across the high internal impedance of the unregulated supply, R<sub>s</sub>, which tends to counteract the original rise of the voltage. If desired, the grid may be connected to a variable point on the voltage divider to allow some adjustment of the output-voltage level.

The grid voltage for the 6BK4 can also be obtained from a tap on the B-

boost voltage supply. The use of this lower voltage (about 375 volts) eliminates the need for costly and trouble-some high-voltage resistors. In this arrangement, variations in high voltage also vary the tapped-down B-boost voltage at the regulator grid, and the resulting variations in conduction of the regulator increase or decrease the loading of the high-voltage supply so that the total load remains nearly constant.

#### **Frequency Conversion**

Frequency conversion is used in superheterodyne receivers to change the frequency of the rf signal to an intermediate frequency. To perform this change in frequency, a frequency-converting device consisting of an oscillator and a frequency mixer is employed. In such a device, shown diagrammatically in Fig. 77, two voltages of different frequency, the rf signal voltage and the voltage generated by the oscillator, are applied to the input of the frequency mixer. These voltages beat, or heterodyne, within the mixer tube to produce a plate current having, in addition to the frequencies of the input voltages, numerous sum and difference frequencies.



# FREQUENCY CONVERTER

Fig. 77—Block diagram of simple frequency-converter circuit.

The output circuit of the mixer stage is provided with a tuned circuit which is adjusted to select only one beat frequency, *i.e.*, the frequency equal to the difference between the signal frequency and the oscillator frequency. The selected output frequency is known as the intermediate frequency, or if. The output frequency of the mixer tube is kept constant for all values of signal frequency by tuning the oscillator to the proper frequency.

Important advantages gained in a receiver by the conversion of signal fre-

quency to a fixed intermediate frequency are high selectivity with few tuning stages and a high, as well as stable, overall gain for the receiver.

Several methods of frequency conversion for superheterodyne receivers are of interest. These methods are alike in that they employ a frequency-mixer tube in which plate current is varied at a combination frequency of the signal frequency and the oscillator frequency. These variations in plate current produce across the tuned plate load a voltage of the desired intermediate frequency. The methods differ in the types of tubes employed and in the means of supply input voltages to the mixer tube.

A method widely used before the availability of tubes especially designed for frequency-conversion service, and currently used in many FM, television, and standard broadcast receivers, employs as mixer tube either a triode, a tetrode, or a pentode, in which oscillator voltage and signal voltage are applied to the same grid. In this method, coupling between the oscillator and mixer circuits is obtained by means of inductance or capacitance.

A second method employs a tube having an oscillator and frequency mixer combined in the same envelope. In one form of such a tube, coupling between the two units is obtained by means of the electron stream within the tube. Because five grids are used, the tube is called a pentagrid converter.

Grids No. 1 and No. 2 and the cathode are connected to an external circuit to act as a triode oscillator. Grid No. 1 is the grid of the oscillator and Grid No. 2 is the anode. These and the cathode can be considered as a composite cathode which supplies to the rest of the tube an electron stream that varies at the oscillator frequency.

This varying electron stream is further controlled by the rf signal voltage on grid No. 4. Thus, the variations in plate current are due to the combination of the oscillator and the signal frequencies. The purpose of grids No. 3 and No. 5, which are connected together within the tube, is to accelerate the electron stream and to shield grid No. 4

electrostatically from the other electrodes.

Pentagrid-converter tubes of this design are good frequency-converting devices at medium frequencies. However, their performance is better at the lower frequencies because the output of the oscillator drops off as the frequency is raised and because certain indesirable effects produced by interaction between oscillator and signal sections of the tube increase with frequency.

To minimize these effects, several of the pentagrid-converter tubes are designed so that no electrode functions alone as the oscillator anode. In these tubes, grid No. 1 functions as the oscillator grid, and grid No. 2 is connected within the tube to the screen grid (grid No. 4). The combined two grids, Nos. 2 and 4, shield the signal grid (grid No. 3) and act as the composite anode of the oscillator triode. Grid No. 5 acts as the suppressor grid.

Converter tubes of this type are designed so that the space charge around the cathode is unaffected by electrons from the signal grid. Furthermore, the electrostatic field of the signal grid also has little effect on the space charge. The result is that rf voltage on the signal grid produces little effect on the cathode current. There is, therefore, little detuning of the oscillator by avc bias because changes in avc bias produce little change in oscillator transconductance or in the input capacitance of grid No. 1.

Examples of the pentagrid converters discussed in the preceding paragraph are the single-ended types 1R5 and 6BE6. A schematic diagram illustrating the use of the 6BE6 with self-excitation is given in Fig. 78; the 6BE6 may also be used with separate excitation. A complete circuit is shown in the Circuits section.

Another method of frequency conversion utilizes a separate oscillator having its grid connected to the No. 1 grid of a mixer hexode. The cathode, triode grid, and triode plate form the oscillator unit of the tube. The cathode, hexode mixer grid (grid No. 1) hexode screen




Fig. 78—Frequency-converter circuit using the 6BE6 pentagrid converter with self-excitation.

grids (grids Nos. 2 and 4), hexode signal grid (grid No. 3), and hexode plate constitute the mixer unit. The internal shields are connected to the shell of the tube and act as a suppressor grid for the hexode unit.

The action of this tube in converting a radio-frequency signal to an intermediate frequency depends on (1) the generation of a local frequency by the triode unit, (2) the transferring of this frequency to the hexode grid No. 1, and (3) the mixing in the hexode unit of this frequency with that of the rf signal applied to the hexode grid No. 3. The tube is not critical to changes in oscillatorplate voltage or signal-grid bias and, therefore, finds important use in all-wave receivers to minimize frequency-shift effects at the higher frequencies.

A further method of frequency conversion employs a tube called a pentagrid mixer. This type has two independent control grids and is used with a separate oscillator tube. RF signal voltage is applied to one of the control grids and oscillator voltage is applied to the other. It follows, therefore, that the variations in plate current are due to the combination of the oscillator and signal frequencies.

The tube contains a heater-cathode, five grids, and a plate. Grids Nos. 1 and 3 are control grids. The rf signal voltage is applied to grid No. 1. This grid has a remote-cutoff characteristic and is suited for control by ave bias voltage. The oscillator voltage is applied to grid No. 3. This grid has a sharp-cutoff characteristic and produces a comparatively

large effect on plate current for a small amount of oscillator voltage. Grids Nos. 2 and 4 are connected together within the tube. They accelerate the electron stream and shield grid No. 3 electrostatically from the other electrodes. Grid No. 5, connected within the tube to the cathode, functions similarly to the suppressor grid in a pentode.

In the converter or mixer stage of a television receiver, stable oscillator operation is most readily obtained when separate tubes or tube sections are used for the oscillator and mixer functions. A typical television mixer-oscillator circuit is shown in Fig. 79. In such circuits, the oscillator voltage is applied to the mixer grid by inductive coupling, capacitive coupling, or a combination of the two. Tubes containing electrically




Fig. 79—Typical television mixer-oscillator circuit.

independent oscillator and mixer units in the same envelope, such as the 6U8A and 6X8, are designed especially for this application.

# **Automatic Frequency Control**

An automatic frequency control (afc) circuit provides a means of correcting automatically the intermediate frequency of a superheterodyne receiver when, for any reason, it drifts from the frequency to which the if stages are tuned. This correction is made by adjusting the frequency of the oscillator. Such a circuit will automatically compensate for slight changes in rf carrier or oscillator frequency as well as for inaccurate manual or push-button tuning.

An afc system requires two sections: a frequency detector and a variable reactance. The detector section may be essentially the same as the FM detector illustrated in Fig. 57 and discussed under **Detection**. In the afc

system, however, the output is a dc control voltage, the magnitude of which is proportional to the amount of frequency shift. This dc control voltage is used to control the grid bias of an electron tube which comprises the variable reactance section (Fig. 80).




Fig. 80—Automatic-frequency-control (afc) circuit,

The plate current of the reactance tube is shunted across the oscillator tank circuit. Because the plate current and plate voltage of the reactance tube are almost 90° out of phase, the control tube affects the tank circuit in the same manner as a reactance. The grid bias of the tube determines the magnitude of the effective reactance and, consequently, a control of this grid bias can be used to control the oscillator frequency.

Automatic frequency control is also used in television receivers to keep the horizontal oscillator in step with the horizontal-scanning frequency (15,750 cps) at the transmitter. A widely used horizontal afc circuit is shown in Fig. 81. This circuit, which is often referred to as a balanced-phase-detector or phase-discriminator circuit, is usually employed to control the frequency of a multivibrator-type horizontal-oscillator circuit. The 6AL5 detector supplies a dc control voltage to the grid of the horizontal-oscillator tube which counteracts changes in its operating frequency. The magnitude and polarity of the control voltages are determined by phase relationships in the afc circuit at a given moment.

The horizontal sync pulses obtained from the sync-separator circuit are fed through a single-triode phase-inverter or phase-splitter circuit to the two diode units of the 6AL5. Because of the action of the phase-inverter circuit, the signals applied to the two diode units are equal in amplitude but 180 degrees out of




Fig. 81—Balanced phase-detector or phasediscriminator circuit for horizontal afc.

phase. A reference sawtooth voltage obtained from the horizontal output circuit is also applied simultaneously to both units. Any change in the oscillator frequency alters the phase relationship between the reference sawtooth and the incoming horizontal sync pulses, causing one diode unit of the 6AL5 to conduct more heavily than the other, and thus producing a correction signal. The system remains balanced at all times, therefore, because momentary changes in oscillator frequency are instantaneously corrected by the action of the control voltage.

The diode units of the 6AL5 are biased so that conduction takes place only during the tips of the sync pulses. The relative position of the sync pulses on the retrace portion of the sawtooth waveform at any given instant determines which diode unit conducts more heavily, and thereby establishes the magnitude and polarity of the control voltage. The network between the diode units and the grid of the horizontal-oscillator tube is essentially a low-pass filter which prevents the horizontal-oscillator performance.

# Electron Tube Installation

THE installation of electron tubes requires care if high-quality performance is to be obtained from the associated circuits. Installation suggestions and precautions which are generally common to all types of tubes are covered in this section. Careful observance of these suggestions will do much to help the experimenter and electronic technician obtain the full performance capabilities of radio tubes and circuits. Additional pertinent information is given under each tube type and in the Circuits section.

# Filament and Heater Power Supply

The design of electron tubes allows for some variation in the voltage and current supplied to the filament or heater, but most satisfactory results are obtained from operation at the rated values. When the voltage is low, the temperature of the cathode is below normal, with the result that electron emission is limited. The limited emission may cause unsatisfactory operation and reduced tube life. On the other hand, high cathode voltage may cause rapid evaporation of cathode material and shorten tube life.

To insure proper tube operation, it is important that the filament or heater voltage be checked at the socket terminals by means of a high-resistance voltmeter while the equipment is in operation. In the case of series operation of heaters or filaments, correct adjustment can be checked by means of an ammeter in the heater or filament circuit.

The filament or heater voltage sup-

ply may be a direct-current source (a battery or a dc power line) or an alternating-current power line, depending on the type of service and type of tube. Frequently, a resistor (either variable or fixed) is used with a dc supply to permit compensation for battery voltage variations or to adjust the tube voltage at the socket terminals to the correct value. Ordinarily, a step-down transformer is used with an ac supply to provide the proper filament or heater voltage. Receivers intended for operation on both dc and ac power lines have the heaters connected in series with a suitable resistor and supplied directly from the power line.

DC filament or heater operation should be considered on the basis of the source of power. In the case of the battery supply for the 1.4-volt filament tubes, it is unnecessary to use a voltagedropping resistor in series with the filament and a single dry-cell; the filaments of these tubes are designed to operate satisfactorily over the range of voltage variations that normally occur during the life of a dry-cell. Likewise, no series resistor is required when the 1.25-volt filament subminiatures are operated from a single 1.5-volt flashlight-type dry-cell, when the 2-volt filament-type tubes are operated from a single storage cell, or when the 6.3-volt series are operated from a 6-volt storage battery.

In the case of dry-battery supply for 2-volt filament tubes, a variable resistor in series with the filament and the battery is required to compensate for battery variations. Turning the set on and off by means of the rheostat is advised to prevent over-voltage conditions after an off-period because the voltage of dry-cells rises during offperiods.

In the case of storage-battery supply, air-cell-battery supply, or dc power supply, a non-adjustable resistor of suitable value may be used. It is well to check initial operating conditions, and thus the resistor value, by means of a voltmeter or ammeter.

AC filament or heater operation should be considered on the basis of either a parallel or a series arrangement of filaments and/or heaters. In the case of the parallel arrangements, a step-down transformer is employed. Precautions should be taken to see that the line voltage is the same as that for which the primary of the transformer is designed. The line voltage may be determined by measurement with an ac voltmeter (0-150 volts).

If the line voltage measures in excess of that for which the transformer is designed, a resistor should be placed in series with the primary to reduce the line voltage to the rated value of the transformer primary. Unless this is done, the excess input voltage will cause proportionally excessive voltage to be applied to the tubes. Any electron tube may be damaged or made inoperative by excessive operating voltages.

If the line voltage is consistently below that for which the primary of the transformer is designed, it may be necessary to install a booster transformer between the ac outlet and the transformer primary. Before such a transformer is installed, the ac line fluctuations should be very carefully noted. Some radio sets are equipped with a line-voltage switch which permits adjustment of the power transformer primary to the line voltage. When this switch is properly adjusted, the seriesresistor or booster-transformer method of controlling line voltage is seldom required.

In the case of the series arrangements of filaments and/or heaters, a voltage-dropping resistance in series with the heaters and the supply line is usually required. This resistance should be of such value that, for normal line voltage, tubes wil operate at their rated heater or filament current. The method

for calculating the resistor value is given below.

When the filaments of battery-type tubes are connected in series, the total filament current is the sum of the current due to the filament supply and the plate and grid-No. 2 currents (cathode current) returning to B(—) through the tube filaments. Consequently, in a series filament string it is necessary to add shunt resistors across each filament section to bypass this cathode current in order to maintain the filament voltage at its rated value.

The filament or heater resistor required when filaments and/or heaters are operated in parallel can be determined easily by a simple formula derived from Ohm's law.

Required resistance (ohms) = supply volts — rated volts of tube type total rated filament current (amperes)

Thus, if a receiver using two IT4's, one IR5, one IU5, and one 3V4 is to be operated from a storage battery, the series resistor is equal to 2 volts (the voltage from a single storage cell) minus 1.4 volts (voltage rating for these tubes) divided by 0.3 ampere (the sum of  $4 \times 0.05$  ampere  $+ 1 \times 0.1$  ampere), i.e., approximately 2 ohms. Because this resistor should be variable to allow adjustment for battery depreciation, it is advisable to obtain the next larger commercial size, although any value between 2 and 3 ohms will be quite satisfactory.

Where much power is dissipated in the resistor, the wattage rating should be sufficiently large to prevent overheating. The power dissipation in watts is equal to the voltage drop in the resistor multiplied by the total filament current in amperes. Thus, for the example above,  $0.6 \times 0.3 = 0.18$  watt. In this case, the value is so small that any commercial rheostat with suitable resistance will be adequate.

For the case where the heaters and/or filaments of several tubes are operated in series, the resistor value is calculated by the following formula, also derived from Ohm's law.

Required resistance (ohms) = supply volts — total rated volts of tubes

rated amperes of tubes

Thus, if a receiver having one 6BE6, one 6BA6, one 6AT6, one 25L6GT, and one 25Z6GT is to be operated from a 117-volt power line, the series resistor is equal to 117 volts (the supply voltage) minus 68.9 volts (the sum of  $3 \times 6.3$  volts  $+ 2 \times 25$  volts) divided by 0.3 ampere (current rating of these tubes), i.e., approximately 160 ohms. The wattage dissipation in the resistor will be 117 volts minus 68.9 volts times 0.3 ampere, or approximately 14.4 watts. A resistor having a wattage rating in excess of this value should be chosen.

When the series-heater connection is used in ac/dc receivers, it is usually advisable to arrange the heaters in the circuit so that the tubes most sensitive to hum disturbances are at or near the ground potential of the circuit. This arrangement reduces the amount of ac voltage between the heaters and cathodes of these tubes and minimizes the hum output of the receiver. The order of heater connection, by tube function, from chassis to the rectifier-cathode side of the ac line is shown in Fig. 82.

the electron stream by the alternating magnetic field surrounding the heater. When a large resistor is used between heater and cathode (as in series-connected heater strings), or when one side of the heater is grounded, even a minute pulsating leakage current between heater and cathode can develop a small voltage across the cathode-circuit impedance and cause objectionable hum. The use of a large cathode bypass capacitor is recommended to minimize this source of hum

Much lower hum levels can be achieved when heaters are connected in parallel systems in which the center-tap of the heater supply is grounded or, preferably, connected to a positive bias source of 15 to 80 volts dc to reduce the flow of alternating current. The heater leads of the tubes should be twisted and kept away from high-impedance circuits. The balanced ac supply provides almost complete cancellation of the alternating-current components.

The balanced arrangement described above also minimizes heater-




Fig. 82—Order of series heater-string connection, by tube function, to minimize hum.

# **Heater-to-Cathode Connection**

When heater-type tubes are operated from ac, their cathodes may be returned (through resistors, capacitors, or other components) to the mid-tap on the heater supply winding, to the mid-tap of a small resistor (about 50 ohms) connected across the winding, or to one end of the heater supply winding, depending on circuit requirements. In all circuits, it is important to keep the heater-cathode voltage within the maximum ratings specified for the tube.

Heater-type tubes may produce hum as a result of conduction between heater and cathode or between heater and control grid, or by modulation of grid hum. High grid-circuit impedances should be avoided, if possible. High heater voltages should also be avoided because heater-cathode hum rises sharply when the heater voltage is increased above the published value.

Certain tube types are designed especially to minimize hum in high-quality, high-fidelity audio equipment. Examples are the 5879, 7025, and 7199.

# Plate Voltage Supply

The plate voltage for electron tubes is obtained from batteries, rectifiers, direct-current power lines, and small local generators. The maximum plate-voltage value for any tube type should

not be exceeded if most satisfactory performance is to be obtained. Plate voltage should not be applied to a tube unless the corresponding recommended voltage is also supplied to the grid.

It is recommended that the primary circuit of the power transformer be fused to protect the rectifier tube(s), the power transformer, filter capacitor, and chokes in case a rectifier tube fails.

# **Grid Voltage Supply**

The recommended grid voltages for different operating conditions have been carefully determined to give the most satisfactory performance. Grid voltage may be obtained from a fixed source such as a separate C-battery or a tap on the voltage divider of the high-voltage dc supply, from the voltage drop across a resistor in the cathode circuit, or from the voltage drop across a resistor in the grid circuit. The first method is called "fixed bias"; the second is called "cathode bias" or "self bias"; the third is called "grid-resistor bias" and is sometimes incorrectly referred to in repractice "zero-bias ceiving-tube as operation."

In any case, the object is to make the grid negative with respect to the cathode by the specified voltage. When a C-battery is used, the negative terminal is connected to the grid return and the positive terminal is connected to the negative filament socket terminal, or to the cathode terminal if the tube is of the heater-cathode type. If the filament is supplied with alternating current, this connection is usually made to the center-tap of a low resistance (20 to 50 ohms) shunted across the filament ter-

minals. This method reduces hum disturbances caused by the ac supply. If bias voltages are obtained from the voltage divider of a high-voltage dc supply, the grid return is connected to a more negative tap than the cathode.

The cathode-biasing method utilizes the voltage drop produced by the cathode current flowing through a resistor connected between the cathode and the negative terminal of the B-supply. (See Fig. 83.) The cathode current is. of course, equal to the plate current in the case of a triode, or to the sum of the plate and grid-No. 2 currents in the case of a tetrode, pentode, or beam power tube. Because the voltage drop along the resistance is increasingly negative with respect to the cathode, the required negative grid-bias voltage can be obtained by connecting the grid return to the negative end of the resistance.


The value of the resistance for cathode-biasing a single tube can be determined from the following formula:


Resistance (ohms) = desired grid-bias voltage × 1000

rated cathode current in milliamperes

Thus, the resistance required to produce 9 volts bias for a triode which operates at 3 milliamperes plate current is  $9 \times 1000/3 = 3000$  ohms. If the cathode current of more than one tube passes through the resistor, or if the tube or tubes employ more than three electrodes, the total current determines the size of the resistor.

Bypassing of the cathode-bias resistor depends on circuit-design requirements. In rf circuits the cathode resistor usually is bypassed. In af circuits the use of an unbypassed resistor will re-








Fig. 83—Typical grid-voltage supply circuits.

duce distortion by introducing degeneration into the circuit. However, the use of an unbypassed resistor decreases gain and power sensitivity. When bypassing is used, it is important that the bypass capacitor be sufficiently large to have negligible reactance at the lowest frequency to be amplified.

In the case of power-output tubes having high transconductance, such as beam power tubes, it may be necessary to shunt the bias resistor with a small mica capacitor (approximately 0.001μf) in order to prevent oscillations. The usual af bypass may or may not be used, depending on whether or not degeneration is desired. In tubes having high values of transconductance, such as the 6BA6, 6CB6, and 6AC7, input capacitance and input conductance change appreciably with plate current. When such a tube having a separate suppressor-grid connection is used as an rf amplifier, these changes may be minimized by leaving a certain portion of the cathode-bias resistor unbypassed. In order to minimize feedback when this method is used, the external grid-No. 1to-plate (wiring) capacitances should be kept to a minimum, the grid No. 2 should be bypassed to ac ground, and the grid No. 3 should be connected to ac ground.

The use of a cathode resistor to obtain bias voltage is not recommended for amplifiers in which there is appreciable shift of electrode currents with the application of a signal. In such amplifiers, a separate fixed supply is recommended.

The grid-resistor biasing method is also a self-bias method because it utilizes the voltage drop across the grid resistor produced by small amounts of grid current flowing in the grid-cathode circuit. This current is due to (1) an electromotive potential difference between the materials comprising the grid and cathode and (2) grid rectification when the grid is driven positive. A large value of resistance is required in order to limit this current to a very small value and to avoid undesirable loading effects on the preceding stage.

Examples of this method of bias are given in circuits 22-1 and 22-4 in

the Circuits section. In both of these circuits, the audio amplifier type 1U5 or 12AV6 has a 10-megohm resistor between the grid and the negative filament or cathode to furnish the required bias, which is usually less than 1 volt. This method of biasing is used principally in the early voltage-amplifier stages (usually employing high-mu triodes) of audio amplifier circuits, where the tube dissipation will not be excessive under zero-signal conditions.

A grid resistor is also used in many oscillator circuits for obtaining the required bias. In these circuits, the grid voltage is relatively constant and its magnitude is usually in the order of 5 volts or more. Consequently, the bias voltage is obtained only through grid rectification. A relatively low value of resistor, 0.1 megohm or less, is used. Oscillator circuits employing this method of bias are given in circuits 23-1 and 23-3 in the Circuits section.

Grid-bias variation for the rf and if amplifier stages is a convenient and frequently used method for controlling receiver volume. The variable voltage supplied to the grid may be obtained: (1) from a variable cathode resistor as shown in Figs. 84 and 85; (2) from a bleeder circuit by means of a potentiometer as shown in Fig. 86; or (3) from a bleeder circuit in which the bleeder current is varied by a tube




Fig. 84—Amplifier stage using a variable cathode-bias resistor for volume control.

used for automatic volume control. The latter circuit is shown in Fig. 60.

In all cases it is important that the control be arranged so that at no time will the bias be less than the recommended minimum grid-bias voltage for the particular tubes used. This requirement can be met by providing a fixed stop on the potentiometer, by connecting a fixed resistance in series with the variable resistance, or by connecting a fixed cathode resistance in series with the variable resistance used for regulation. Where receiver gain is




Fig. 85—Amplifier stage similar to Fig. 84 but using heater-cathode-type tube.

controlled by grid-bias variation, it is advisable to have the control voltages extend over a wide range in order to minimize cross-modulation and modulation-distortion. A remote-cutoff type of tube should, therefore, be used in the controlled stages.




Fig. 86—Amplifier stage using a bleeder circuit and potentiometer for volume control.

In most tubes employing a unipotential cathode, a positive grid current begins to flow when the grid is slightly negative and increases rapidly as the grid is made more positive, as shown in Fig. 87. The value of grid voltage at which the grid-current curve intercepts the horizontal axis is determined by several different physical processes, including an electrothermal effect due to the differences in temperature and in material composition of the grid and the cathode, and by the positive grid current. For values of grid potentials which are larger than this intercept, the direction of the grid current is positive (i.e., from the grid to the cathode). At smaller values of grid potential, the direction of the grid current is negative (i.e., from the cathode to the grid).

Positive grid current consists of electrons emitted from the cathode which are intercepted by the control grid. Negative grid current, which becomes appreciable only when the grid potential is more negative than the value of the intercept, is a result of the emission of electrons from the heated control grid to the cathode, the effect of gas molecules in the tube, and the influence of leakage currents between the grid and cathode and the grid and the plate.

The value of grid potential at the intercept of the grid-current curve on the horizontal axis (often mistakenly called contact potential) may be as high as 1½ volts. If the operating bias of the tube is less than this intercept, it is found that two effects are present. Direct current flows in the grid circuit, and the dynamic input resistance of the tube may be relatively low. It is generally desirable to supply the tube with a value of bias sufficiently high so that the operating point of the tube is not near the value of this intercept. If the value of the operating bias is near the value of the intercept, care should be taken to avoid undesirable effects in the grid circuit due to grid current or low input resistance.




Fig. 87—Curves showing flow of positive grid current in tubes employing unipotential cathodes.

# Screen-Grid Voltage Supply

The positive voltage for the screen grid (grid No. 2) of screen-grid tubes

may be obtained from a tap on a voltage divider, from a potentiometer, or from a series resistor connected to a high-voltage source, depending on the particular tube type and its application. The screen-grid voltage for tetrodes should be obtained from a voltage divider or a potentiometer rather than through a series resistor from a high-voltage source because of the characteristic screen-grid current variations of tetrodes. Fig. 88 shows a tetrode with its screen-grid voltage obtained from a potentiometer.

When pentodes or beam power tubes are operated under conditions where a large shift of plate and screengrid currents does not take place with the application of the signal, the screengrid voltage may be obtained through a series resistor from a high-voltage




Fig. 88—Tetrode circuit in which screengrid voltage is obtained from a potentiometer.

source. This method of supply is possible because of the high uniformity of the screen-grid current characteristic in pentodes and beam power tubes. Because the screen-grid voltage rises with increase in bias and resulting decrease in screen-grid current, the cutoff characteristic of a pentode is extended by this method of supply.

This method is sometimes used to increase the range of signals which can be handled by a pentode. When used in resistance-coupled amplifier circuits employing pentodes in combination with the cathode-biasing method, it minimizes the need for circuit adjustments. Fig. 89 shows a pentode with its screen-grid voltage supplied through a series resistor.

When power pentodes and beam power tubes are operated under conditions such that there is a large change in plate and screen-grid currents with the application of signal, the seriesresistor method of obtaining screen-grid voltage should not be used. A change in screen-grid current appears as a




Fig. 89—Pentode circuit in which screengrid voltage is supplied through a series resistor.

change in the voltage drop across the series resistor in the screen-grid circuit; the result is a change in the power output and an increase in distortion. The screen-grid voltage should be obtained from a point in the plate-voltage-supply filter system having the correct voltage, or from a separate source.

It is important to note that the plate voltage of tetrodes, pentodes, and beam power tubes should be applied before or simultaneously with the screen-grid voltage. Otherwise, with voltage on the screen grid only, the screen-grid current may rise high enough to cause excessive screen-grid dissipation.

Screen-grid voltage variation for the rf amplifier stages has sometimes been used for volume control in older-type receivers. Reduced screen-grid voltage decreases the transconductance of the tube and results in reduced gain per stage. The voltage variation is obtained by means of a potentiometer shunted across the screen-grid voltage supply. (See Fig. 88.) When the screen-grid voltage is varied, it must never exceed the rating of the tube. This requirement can be met by providing a fixed stop on the potentiometer.

#### Shielding

In high-frequency stages having high gain, the output circuit of each stage must be shielded from the input circuit of that stage. Each high-frequency stage also must be shielded from the other high-frequency stages. Unless shielding is employed, undesired feedback may occur and may produce many harmful effects on receiver performance.

To prevent this feedback, it is a desirable practice to shield separately each unit of the high-frequency stages. For instance, in a superheterodyne receiver, each if and rf coil may be mounted in a separate shield can. Baffle plates may be mounted on the ganged tuning capacitor to shield each section of the capacitor from the other section. The oscillator coil may be especially well shielded by being mounted under the chassis.

The shielding precautions required in a receiver depend on the design of the receiver and the layout of the parts. In all receivers having high-gain highfrequency stages, it is necessary to shield separately each tube in high-frequency stages. When metal tubes, and in particular the single-ended types, are used, complete shielding of each tube is provided by the metal shell which is grounded through its grounding pin as the socket terminal. The grounding connection should be short and sturdy. Many modern tubes of glass construction have internal shields, usually connected to the cathode; where present, these shields are indicated in the socket diagram.

# **Dress of Circuit Leads**


At high frequencies such as are encountered in FM and television receivers, lead dress, that is, the location and arrangement of the leads used for connections in the receiver, is very important. Because even a short lead provides a large impedance at high frequencies, it is necessary to keep all high-frequency leads as short as possible. This precaution is especially important for ground connections and for all connections to bypass capacitors and high-frequency filter capacitors. The ground connections of plate and screen-grid bypass capacitors of each tube should be kept short and made directly to cathode ground.

Particular care should be taken with the lead dress of the input and output circuits of high-frequency stages so that the possibility of stray coupling is minimized. Unshielded leads connected to shielded components should be dressed close to the chassis. As the frequency increases, the need for careful lead dress becomes increasingly important.

In high-gain audio amplifiers, these same precautions should be taken to minimize the possibility of self-oscillation.

#### **Filters**

Feedback effects also are caused in radio or television receivers by coupling between stages through common voltage-supply circuits. Filters find an important use in minimizing such effects. They should be placed in voltage-supply leads to each tube in order to return the signal current through a low-impedance path direct to the tube cathode rather than by way of the voltage-supply circuit. Fig. 90 illustrates several forms of filter circuits. Capacitor C



forms the low-impedance path, while the choke or resistor assists in diverting the signal through the capacitor by offering a high impedance to the power-

supply circuit.

The choice between a resistor and a choke depends chiefly upon the permissible dc voltage drop through the filter. In circuits where the current is small (a few milliamperes), resistors are practical; where the current is large or

regulation important, chokes are more suitable.

The minimum practical size of the capacitors may be estimated in most cases by the following rule: The impedance of the capacitor at the lowest frequency amplified should not be more than one-fifth of the impedance of the filter choke or resistor at that frequency. Better results will be obtained in special cases if the ratio is not more than one-tenth.

Radio-frequency circuits, particularly at high frequencies, require high-quality capacitors. Mica or ceramic capacitors are preferable. Where stage shields are employed, filter should be placed within the shield.

Another important application of filters is to smooth the output of a rectifier tube. (See Rectification.) A smoothing filter usually consists of capacitors and iron-core chokes. In any filter-design problem, the load impedance must be considered as an integral part of the filter because the load is an important factor in filter performance. Smoothing effect is obtained from the chokes because they are in series with the load and offer a high impedance to the ripple voltage. Smoothing effect is obtained from the capacitors because they are in parallel with the load and store energy on the voltage peaks; this energy is released on the voltage dips and serves to maintain the voltage at the load substantially constant. Smoothing filters are classified as choke-input or capacitor-input according to whether a choke or capacitor is placed next to the rectifier tube. (See Fig. 91.)

The Circuits section gives a number of examples of rectifier circuits with recommended filter constants.

If an input capacitor is used, consideration must be given to the instantaneous peak value of the ac input voltage. This peak value is about 1.4 times the rms value as measured by an ac voltmeter. Filter capacitors, therefore, especially the input capacitor, should have a rating high enough to withstand the instantaneous peak value if breakdown is to be avoided. When the inputchoke method is used, the available dc output voltage will be somewhat lower than with the input-capacitor method for a given ac plate voltage. However, improved regulation together with lower peak current will be obtained.

Mercury-vapor and gas-filled rectifier tubes occasionally produce a form of local interference in radio receivers through direct radiation or through the power line. This interference is generally identified in the receiver as a broadly tunable 120-cycle buzz (100 cycles for 50-cycle supply line, etc.). It is usually caused by the formation of a steep wave front when plate current within the tube begins to flow on the positive half of each cycle of the ac supply voltage.

There are several ways of eliminating this type of interference. One is to shield the tube. Another is to insert an rf choke having an inductance of one millihenry or more between each plate and transformer winding and to connect high-voltage, rf bypass capacitors between the outside ends of the transformer winding and the center tap. (See Fig. 92.) The rf chokes should be placed within the shielding of the tube. The rf bypass capacitors should have a voltage rating high enough to withstand the peak voltage of each half of the secondary, which is approximately 1.4 times the rms value.





Fig. 91—Typical smoothing filters for rectifier tubes.



C=RF BYPASS CAPACITOR,MICA L=RF CHOKE

Fig 92—Filter circuit used to eliminate interference produced by mercury-vapor or gas-filled rectifier tubes.

Transformers having electrostatic shielding between primary and secondary are not likely to transmit rf disturbances to the line. Often the interference may be eliminated simply by making the plate leads of the rectifier extremely short. In general, the particular method of interference elimination must be selected by experiment for each installation.

### **Output Coupling Devices**

An output-coupling device is used in the plate circuit of a power output tube to keep the comparatively high de plate current from the winding of an electromagnetic speaker and, also, to transfer power efficiently from the output stage to a loudspeaker of either the electromagnetic or dynamic type.

Output-coupling devices are of two types, (1) choke-capacitor and (2) transformer. The choke-capacitor type includes an iron-core choke having an inductance of not less than 10 henries which is placed in series with the plate and B-supply. The choke offers a very low resistance to the dc plate current component of the signal voltage but opposes the flow of the fluctuating component. A bypass capacitor of 2 to 6 microfarads supplies a path to the speaker winding for the signal voltage. The choke-coil output coupling device, however, is now only of historical interest.

The transformer type is constructed with two separate windings, a primary and a secondary wound on an iron core. This construction permits designing each winding to meet the requirements of its position in the circuit. Typical

arrangements of each type of coupling device are shown in Fig. 93. Examples of transformers for push-pull stages are shown in several of the circuits given in the Circuits section.




Fig. 93—Typical output-coupling devices.

### **High-Fidelity Systems**

The results achieved from any high-fidelity amplifier system depend to a large degree upon the skill and care with which the system is constructed. Improper placement of transformers, other components, and wiring, and attempts to achieve excessive compactness, can only result in instability, oscillation, hum, and other operating difficulties, as well as in damage to components by overheating. It is important, therefore, that construction of high-fidelity amplifier systems be undertaken only by persons who have had some experience in the layout, mechanical construction, and wiring of audio equipment.

It is impractical to give specific construction data for various amplifiers and supplementary units because the best arrangement for each unit or combination of units will depend on the requirements of the user. It is possible, however, to list some general considerations which should be observed in the construction of any high-fidelity amplifier system.

Any amplifier having two or more stages should be constructed with a straight-line layout so that maximum separation is provided between the signal input and output circuits and terminals. Power-supply connections, particularly those carrying ac, should be

isolated as far as possible from signal connections, especially from the input connection. Signal-carrying conductors. even when shielded, should not be cabled together with power-supply conductors. Internal wiring for ac-operated tube heaters, switches, pilot-light sockets, and other devices, should be twisted and placed flat against the chassis. All connections to the ground side of the circuit in each unit should be made to a common bus of heavy wire. This bus should be connected to the chassis only at the point of minimum signal voltage, i.e., at the signal-input terminal of the unit.

All internal wiring that carries signal voltages should be as short as possible, and as far as possible above the chassis, to minimize losses at the higher audio frequencies due to stray shunt capacitance. All connections between units should be made with shielded cable having a capacitance of not more than 30 picofarads per foot, such as Alpha Type 1249 or 1704, Belden Type 8401 or 8410, or equivalent cable.

Because power amplifiers and power-supply units of high-fidelity systems normally dissipate large amounts of heat, they should be constructed and installed in such a manner as to assure adequate ventilation for the tubes and other components. A beam power tube or rectifier tube should be separated from any other tube or component on the same side of the chassis by at least 1½ tube diameters.

Power amplifiers and power-supply units which are to be installed horizontally (i.e., with the tubes vertical) in cabinets or on shelves should be provided with mounting feet, perforated bottom covers, and a number of small holes around each tube socket to permit relatively cool air to enter from below and provide ventilation for the under side of the chassis and tubes.

If a power amplifier, tone-control amplifier, and one or more preamplifiers are to be constructed on the same chassis, the mechanical layout should be planned so that the circuits operating at the lowest signal levels are farthest from the output stage and

power supply. Amplifier units which normally operate at comparable signal levels but are not used simultaneously (such as preamplifiers for tape pickup heads and magnetic phonograph pickups) may be installed side by side on the same chassis without danger of interaction. Units which operate simultaneously, however (such as the channels of a stereophonic system), should not be installed side by side on the same chassis without careful consideration to placement of components and wiring, and the possible use of shielding to prevent interaction.

When an amplifier, preamplifier, mixer, or other unit requiring heater power is located more than five or six feet from its power-supply unit, the heater-current conductors in the powersupply cable must be large enough to assure that each tube receives its rated heater voltage. In cases where very large heater currents or very long power-supply cables are involved, it may be desirable to install a heatersupply transformer on or near the amplifier unit. If such a transformer is installed on or near a preamplifier for a magnetic-tape pickup head, a magnetic phonograph pickup, or a dynamic microphone, the transformer should be completely shielded and positioned to prevent its field from inducing hum in the pickup device.

### High-Voltage Considerations for Television Picture Tubes

Like other high-voltage devices, television picture tubes require that certain precautions be observed to minimize the possibility of failure caused by humidity, dust, and corona.

Humidity Considerations. When humidity is high, a continuous film of moisture may form on the glass bulb immediately surrounding the anode cavity cap of all-glass picture tubes or on the glass part of the envelope of metal picture tubes. This film may permit sparking to take place over the glass surface to the external conductive coating or to the metal shell. Such sparking may introduce noise into the

receiver. To prevent such a possibility, the uncoated bulb surface around the cap and the glass part of the envelope of metal picture tubes should be kept clean and dry.

Dust Considerations. The accumulation of dust on the uncoated area of the bulb around the anode cap of all-glass picture tubes or on the glass part of the envelope or insulating supports for metal picture tubes will decrease the insulating qualities of these parts. The dust usually consists of fibrous materials and may contain soluble salts. The fibers absorb and retain moisture; the soluble salts provide electrical leakage paths that increase in conductivity as the humidity increases. The resulting high leakage currents may overload the high-voltage power supply.

It is recommended, therefore, that the uncoated bulb surface of all-glass picture tubes and the coated glass surface and insulating supports for metal picture tubes be kept clean and free from dust or other contamination such as finger-prints. The frosted Filterglass faceplate of the metal picture tubes may be cleaned with a soapless detergent, such as Dreft, then rinsed with clean water, and immediately dried.

Corona Considerations. A highvoltage system may be subject to corona, especially when the humidity is
high, unless suitable precautions are
taken. Corona, which is an electrical
discharge appearing on the surface of
a conductor when the voltage gradient
exceeds the breakdown value of air,
causes deterioration of organic insulating materials through formation of
ozone, and induces arc-over at points
and sharp edges. Sharp points or other
irregularities on any part of the highvoltage system may increase the possibility of corona and should be avoided.

In the metal-shell picture tubes,

the metal lip at the maximum diameter has rounded edges to prevent corona. Adequate spacing between the lip and any grounded element in the receiver. or between the small end of the metal shell and any grounded element, should be provided to preclude the possibility of corona. Such spacing should not be less than 1 inch of air. Similarly, an air space of 1 inch, or equivalent, should be provided around the body of the metal shell. As a further precaution to prevent corona, the deflecting-yoke surface on the end adjacent to the shell should present a smooth electrical surface with respect to the small end of the metal shell or the anode terminal of all-glass tubes.

# Picture-Tube Safety Considerations

Tube Handling. Breakage of picture tubes, which contain a high vacuum, may result in injury from flying glass. Do not strike or scratch the tube or subject it to more than moderate pressure when installing it in or removing it from electronic equipment.

High-Voltage Precautions. In picture-tube circuits, high voltages may appear at normally low-potential points in the circuit because of capacitor breakdown or incorrect circuit connections. Therefore, before any part of the circuit is touched the power-supply switch should be turned off, the power plug disconnected, and both terminals of any capacitors grounded.

X-Ray Radiation Precautions. All types of picture tubes may be operated at voltages (if ratings permit) up to 16 kilovolts without producing harmful x-ray radiation or danger of personal injury on prolonged exposure at close range. Above 16 kilovolts, special x-ray shielding precautions may be necessary.

# Interpretation of Tube Data

THE tube data given in the following Technical Data section include ratings, typical operation values, characteristics, and characteristic curves.

The values for grid-bias voltages, other electrode voltages, and electrode supply voltages are given with reference to a specified datum point as follows: For types having filaments heated with dc, the negative filament terminal is taken as the datum point to which other electrode voltages are referred. For types having filaments heated with ac, the mid-point (i.e., the center tap on the filament-transformer secondary, or the mid-point on a resistor shunting the filament) is taken as the datum point. For types having unipotential cathodes indirectly heated, the cathode is taken as the datum point.

Ratings are established on electron tube types to help equipment designers utilize the performance and service capabilities of each tube type to best advantage. Ratings are given for those characteristics which careful study and experience indicate must be kept within certain limits to insure satisfactory performance.

Three rating systems are in use by the electron-tube industry. The oldest is known as the Absolute Maximum system, the next as the Design Center system, and the latest and newest as the Design Maximum system. Definitions of these systems have been formulated by the Joint Electron Device Engineering Council (JEDEC) and standardized by the National Electrical Manufacturers Association (NEMA) and the Electronic Industries Association (EIA) as follows:

Absolute Maximum ratings are

limiting values which should not be exceeded with any tube of the specified type under any condition of operation. These ratings are used only in rare instances for receiving types, but are generally used for transmitting and

industrial types.

Design Center ratings are limiting values which should not be exceeded with a tube of the specified type having characteristics equal to the published values under normal operating conditions. These ratings, which include allowances for normal variations in both tube characteristics and operating conditions, were used for most receiving tubes prior to 1957. Unless otherwise specified, ratings given in the Technical Data section are based on the Design Center System.

Design Maximum ratings are limiting values which should not be exceeded with a tube of the specified type having characteristics equal to the published values under any conditions of operation. These ratings include allowances for normal variations in tube characteristics, but do not provide for variations in operating conditions. Design Maximum ratings were adopted for receiving tubes in 1957.

Electrode voltage and current ratings are in general self-explanatory, but a brief explanation of other ratings will aid in the understanding and interpre-

tation of tube data.

Heater warm-up time is defined as the time required for the voltage across the heater to reach 80 per cent of the rated value in the circuit shown in Fig. 94. The heater is placed in series with a resistance having a value 3 times the nominal heater operating resistance  $(R = 3 E_t/I_t)$ , and a voltage having a value 4 times the rated heater voltage  $(V = 4 E_t)$  is then applied. The warmup time is determined when  $E = 0.8 E_t$ .




Fig. 94—Test circuit for measuring heater warm-up time.

Plate dissipation is the power dissipated in the form of heat by the plate as a result of electron bombardment. It is the difference between the power supplied to the plate of the tube and the power delivered by the tube to the load.

Grid-No. 2 (Screen-grid) Input is the power applied to the grid-No. 2

electrode and consists essentially of the power dissipated in the form of heat by grid No. 2 as a result of electron bombardment. With tetrodes and pentodes, the power dissipated in the screengrid circuit is added to the power in the plate circuit to obtain the total B-supply input power.

When the screen-grid voltage is supplied through a series voltage-dropping resistor, the maximum screen-grid voltage rating may be exceeded, provided the maximum screen-grid dissipation rating is not exceeded at any signal condition, and the maximum screen-grid voltage rating is not exceeded at the maximum-signal condition. Provided these conditions are fulfilled, the screen-grid supply voltage may be as high as, but not above, the maximum plate voltage rating.

For certain voltage amplifier types, as listed in the data section, the maximum permissible screen-grid (grid-No. 2) input varies with the screen-grid voltage, as shown in Fig. 95. (This curve cannot be assumed to apply to




Fig. 95-Grid-No.2 input rating curve.

types other than those for which it is specified in the data section.) Full rated screeen-grid input is permissible at screen-grid voltages up to 50 per cent of the maximum rated screen-grid supply voltage. From the 50-per-cent point to the full rated value of supply voltage, the screen-grid input must be decreased. The decrease in allowable screen-grid input follows a curve of the parabolic form. This rating chart is useful for applications utilizing either a fixed screen-grid voltage or a series screen-grid voltage-dropping resistor. When a fixed voltage is used, it is necessary only to determine that the screen-grid input is within the boundary of the operating area on the chart at the selected value of screen-grid voltage to be used. When a voltagedropping resistor is used, the minimum value of resistor that will assure tube operation within the boundary of the curve can be determined from the following relation:

 $R_{g2} = \frac{E_{e2} (E_{ee2} - E_{e2})}{P_{ee}}$ 

where R<sub>22</sub> is the minimum value for the voltage-dropping resistor in ohms, E<sub>c2</sub> is the selected screen-grid voltage in volts, E<sub>c2</sub> is the screen-grid supply voltage in volts, and P<sub>c2</sub> is the screengrid input in watts corresponding to E<sub>c2</sub>.

Peak heater-cathode voltage is the highest instantaneous value of voltage that a tube can safely stand between its heater and cathode. This rating is applied to tubes having a separate cathode terminal and used in applications where excessive voltage may be introduced between heater and cathode.

Maximum dc output current is the highest average plate current which can be handled continuously by a rectifier tube. Its value for any rectifier tube type is based on the permissible plate dissipation of that type. Under operating conditions involving a rapidly repeating duty cycle (steady load), the average plate current may be measured with a dc meter.

The nomograph shown in Fig. 96 can be used to determine tube voltage drop or plate current for any diode unit when values for a single plate-

voltage, plate-current condition are available from the data. It can also be used to compare the relative perveance  $(G = I_b/E_b^{3/2})$  of several diodes. Perveance can be considered a figure of merit for diodes; high-perveance units have lower voltage drop at a fixed current level.




Fig. 96—Diode perveance nomograph.

Tube voltage drop or plate current for a specific diode unit can be determined as follows: First, convenient values are selected for the plate-voltage and plate-current scales of the nomograph. The published plate-current and plate-voltage values are then located on the scales and connected with a straight edge. The intersection of the connecting line with the perveance scale is then used as a pivot point to determine the value of tube voltage drop corresponding to a desired current value, or the value of plate current corresponding to a desired tube voltage drop. Because the pivot point for a specific diode unit represents its perveance, the pivot points for several units (plotted to the same scales) can be used to compare their relative perveance.

For example, type 5U4GB has a tube voltage drop (per plate) of 44 volts at a plate current of 225 milliamperes. Convenient scales for this type are from 1 to 100 volts for plate voltage and from 10 to 1000 milliamperes for plate current. The points 44 volts and 225 milliamperes are then connected with a straight line to determine the pivot point. Using this pivot point, it is easy to determine such values as a plate current of 150 milliamperes at a tube voltage drop of 23 volts, or a voltage drop of 25 for a current of 100 milliamperes.

For readings in the order of one volt and/or one milliampere, the nomograph is not accurate because of the effects of contact potential and initial electron velocity.

Maximum peak plate current is the highest instantaneous plate current that a tube can safely carry recurrently in the direction of normal current flow. The safe value of this peak current in hot-cathode types of rectifier tubes is a function of the electron emission available and the duration of the pulsating current flow from the rectifier tube in each half-cycle.

The value of peak plate current in a given rectifier circuit is largely determined by filter constants. If a large choke is used at the filter input, the peak plate current is not much greater than the load current; but if a large capacitor is used as the filter input, the peak current may be many times the load current. In order to determine accurately the peak plate current in any rectifier circuit, measure it with a peak-indicating meter or use an oscillograph.

Maximum peak inverse plate voltage is the highest instantaneous plate voltage which the tube can withstand recurrently in the direction opposite to that in which it is designed to pass current. For mercury-vapor tubes and gasfilled tubes, it is the safe top value to prevent arc-back in the tube operating within the specified temperature range.

Referring to Fig. 97, when plate A

of a full-wave rectifier tube is positive, current flows from A to C, but not from B to C, because B is negative. At the instant plate A is positive, the filament is positive (at high voltage) with respect to plate B. The voltage between the positive filament and the negative plate




Fig. 97—Schematic diagram of full-wave rectifier tube and circuit connections.

B is in inverse relation to that causing current flow. The peak value of this voltage is limited by the resistance and nature of the path between plate B and filament. The maximum value of this voltage at which there is no danger of breakdown of the tube is known as maximum peak inverse voltage.

The relations between peak inverse voltage, rms value of ac input voltage, and dc output voltage depend largely on the individual characteristics of the rectifier circuit and the power supply. The presence of line surges or any other transient, or wave-form distortion, may raise the actual peak voltage to a value higher than that calculated for sine-wave voltages. Therefore, the actual inverse voltage, and not the calculated value, should be such as not to exceed the rated maximum peak inverse voltage for the rectifier tube. A calibrated cathode-ray oscillograph or a peakindicating electronic voltmeter is useful in determining the actual peak inverse voltage.

In single-phase, full-wave circuits with sine-wave input and with no capacitor across the output, the peak inverse voltage on a rectifier tube is approximately 1.4 times the rms value of the plate voltage applied to the tube. In single-phase, half-wave circuits with sine-wave input and with capacitor input to the filter, the peak inverse volt-

age may be as high as 2.8 times the rms value of the applied plate voltage. In polyphase circuits, mathematical determination of peak inverse voltage requires the use of vectors.

The Rating Chart for full-wave rectifiers presents graphically the relationships between maximum ac voltage input and maximum de output current derived from the fundamental ratings for conditions of capacitor-input and choke-input filters. This graphical presentation provides for considerable latitude in choice of operating conditions.

The Operation Characteristics for a full-wave rectifier with capacitor-input filter show by means of boundary line the limiting current and voltage relationships presented in the Rating Chart.

The Operation Characteristics for a full-wave rectifier with choke-input filter not only show by means of boundary line the limiting current and voltage relationships presented in the Rating Chart, but also give some information as to the effect on regulation of various sizes of chokes. The solid-line curves show the dc voltage outputs which would be obtained if the filter chokes had infinite inductance. The long-dash lines radiating from the zero position are boundary lines for various sizes of chokes as indicated. The intersection of one of these lines with a solid-line curve indicates the point on the curve at which the choke no longer behaves as though it had infinite inductance. To the left of the choke boundary line, the regulation curves depart from the solid-line curves as shown by the representative short-dash regulation curves.

Typical Operation Values. Values for typical operation are given for many types in the Technical Data section. These typical operating values are given to show concisely some guiding information for the use of each type. These values should not be confused with ratings, because a tube can be used under any suitable conditions within its maximum ratings, according to the application.

The power output value for any operating condition is an approximate tube output—that is, plate input minus plate loss. Circuit losses must be sub-

tracted from tube output in order to determine the useful output.

Characteristics are covered in the Electron Tube Characteristics section and such data should be interpreted in accordance with the definitions given in that section. Characteristic curves represent the characteristics of an average tube. Individual tubes, like any manufactured product, may have characteristics that range above or below the values given in the characteristic curves.

Although some curves are extended well beyond the maximum ratings of the tube, this extension has been made only for convenience in calculations. Do NOT operate a tube outside of its maximum ratings.

Interelectrode capacitances are direct capacitances measured between specified elements or groups of elements in electron tubes. Unless otherwise indicated in the data, all capacitances are measured with filament or heater cold, with no direct voltages present, and with no external shields. All electrodes other than those between which capacitance is being measured are grounded. In twin or multi-unit types, inactive units are also grounded.

The capacitance between the input electrode and all other electrodes, except the output electrode, connected together is commonly known as the input capacitance. The capacitance between the output electrode and all other electrodes, except the input electrode, connected together is known as the output capacitance.

Hum and noise characteristics of high-fidelity audio amplifier tube types such as the 7025 and the 7199 are tested in an amplifier circuit such as that shown in Fig. 98. The output of the test circuit is fed into a low-noise amplifier. The bandwidth of this amplifier depends on the characteristic being measured. If hum alone is being tested, a relatively narrow bandwidth is used to include both the line frequency and the major harmonics generated by the tube under test. In noise or combination hum-and-noise measurements, the bandwidth is defined in the registration of the tube type.




Fig. 98—Test circuit for measuring hum and noise characteristics of high-fidelity audio-amplifier tubes.

The amplifier gain is calibrated so that the vacuum-tube voltmeter measures hum and noise in microvolts referenced to the grid of the tube under test. A pentode can also be evaluated in this manner by the addition of a screengrid supply adequately bypassed at the

tube screen-grid pin connection. Powersupply ripple at the plate of the tube under test must be negligible compared to its hum and noise output. Extraordinary shielding of both the test socket and the associated operating circuit is required to minimize capacitances between heater leads and high-impedance connections.

The test-circuit components are determined by the tube type being tested and the type of hum to be controlled. Heater-cathode hum can be eliminated from the measurement by closing the switch S. The circuit can also be made more or less sensitive to heater-grid hum by increasing or decreasing the grid resistance  $R_{\rm g}$ . No circuit changes affect the component of magnetic hum generated by the tube.

# Application Guide for RCA Receiving Tubes

In the Application Guide on the following pages, RCA receiving tubes are classified in two ways: (a) by function, and (b) by structure (diode, triode, etc.). The functional classification covers 42 principal types of application, as listed below.

Tube types are grouped by structure under each classification; they are also keved to indicate miniature, octal. nuvistor, duodecar, and novar types.

Triodes are designated as low, medium-, or high-mu types on the following basis: low, less than 10; medium. 10 or more, but less than 50; high, 50 or more. Where applicable, tubes are designated as sharp-, semiremote, or remote-cutoff on the basis of the ratio, in per cent, of the negative control-grid voltage to the screen-grid voltage (or, for triodes, the plate voltage) as given in the characteristics or typical operation values. These terms are defined as follows: sharp, less than 10 per cent; semiremote, 10 or more, but less than 20 per cent; remote, 20 per cent or more.

For more complete data on these types, refer to the Technical Data For RCA Receiving Tubes starting page 89.

### **APPLICATIONS**

- 1. Audio-Frequency **Amplifiers**
- 2. Automatic Gain Control (AGC and AVC) Circuits
- 3. Bandpass Amplifiers (Color TV)
- 4. Burst Amplifiers
- 5. Cathode-Drive RF Amplifiers (Grounded-Grid) 6. Color Killers
- 7. Color Matrixing Circuits
- 8. Complex-Wave Generators
- 9. Converters
- 10. Dampers
- 11. Demodulators (Color TV)
- 12. Detectors
- 13. DC Restorers
- 14. Discriminators

- 15. Frequency Dividers
- 16. FM Detectors
- 17. Gated Noise, AGC, and Sync Amplifiers
- 18. Grounded-Grid RF
- Amplifiers
- 19. Harmonic Generators 20. Horizontal-Deflection
- Circuits 21. Intermediate-Frequency
- Amplifiers 22. Keyed AGC Amplifiers
- 23. Limiters
- 24. Mixers-RF
- 25. Mixer-Oscillators---RF
- 26. Multivibrators 27. Noise Inverters
  - (Noise Immune Circuits)

- 28. Oscillators
- 29. Phase Inverters
- 30. Phase Splitters
- 31. Radio-Frequency Amplifiers
- 32. Reactance Circuits
- 33. Rectifiers

- 34. Regulators
  35. Relay Control Circuits
  36. Remote-Tuning Circuits
- 37. Sync Amplifiers
- 38. Sync Clippers 39. Sync Separators
- 40. Tuning Indicators 41. Vertical-Deflection
  - Circuits (Oscillator and Amplifier)
- 42. Video Amplifiers

### 1. AUDIO-FREQUENCY **AMPLIFIERS**

Voltage Amplifiers

Medium-Mu Triode with Twin Diode 6BF6

Medium-Mu Twin Triode

• 5J6 • 7AU7

o 12SN7GTA 19J6

• 6J6A   9AU7 • 17CU5

Medium-Mu Triode-Sharp-Cutoff Pentode

Miniature

o Octal

△ Nuvistor

A Novar

• 7199+

+ For high-fidelity equipment

| High-Mu Tric        | de with Twin I      | Diođe              | Twin Diode-           | -Medium Mu T       | [riode            |
|---------------------|---------------------|--------------------|-----------------------|--------------------|-------------------|
| • 3AV6              | • 6BN8              | • 12AV6            | • 6SR7                | ⊚ 12SR7            |                   |
| • 4AV6              | • 6CN7              | o 12SQ7            |                       |                    | _                 |
| • 6AT6              | o 6SQ7              | • 14GT8            | į.                    | -High-Mu Triod     | le                |
| • 6AV6              | • 12AT6             | • 18FY6A           | • 3AV6                | • 6AV6             | • 12AV6           |
|                     |                     |                    | • 4AV6                | • 6SQ7             | o 12SQ7           |
| High-Mu Trio        | de with Triple D    | iode               | • 6AT6                | • 12AT6            | • 18FY6A          |
| • 5T8               | • 6T8A              | • 19T8             | Medium-Mu             | Triode—Sharp-C     | utoff Pentode     |
| - 310               | · UIOA              | • 1910             | • 5AN8                | • 6BA8A            | • 6GH8A           |
|                     |                     |                    | • 5GH8                | • 6BH8             | • 8BA8A           |
| High-Mu Twi         | n Triode            |                    | • 6AN8A               | • 6CH8             | • 8BH8            |
| • 6EU7†             | • 12AZ7A            | • 20EZ7            | • 6AZ8                | • 6CU8             |                   |
| ⊙ 6SL7GT            | • 12BZ7             | • 7025†            | High-Mu Tric          | odeSharp-Cuto      | ff Pentode        |
| • 12AX7A†           | o 1 <b>2SL7GT</b>   |                    | _                     | • 6JV8             | • RJV8            |
| Cl Cl. 4 . Cl. 1    | D4 1                |                    | • 6AW8A<br>• 6HF8     | • 8AW8A            | • 10HF8           |
| Sharp-Cutoff        |                     |                    |                       |                    | · IVALE O         |
| • 3DT6A*            | • 6DT6A*            | • 5879†            | Sharp-Cutoff          | Twin Pentode       |                   |
| • 4DT6A*<br>• 5GX6* | • 6GX6*<br>• 6HZ6*  | • 7543†            | • 3BU8                | • 4BU8             | • 6BU8            |
| ◆ 3GA0*             | • 0HZ0"             |                    | • 3GS8                | • 4HS8             | • 6HS8            |
| Damote-Cutoff       | Pentode with Di     | lode               | • 3HS8                |                    |                   |
| • 12CR6             | remode with D       | iouc               | 2 DANIDD              | ASS AMPLIF         | TED               |
| • 12CR0             |                     |                    | (COLOR                |                    | IER               |
| P                   | ower Amplifie       | rs                 | Į.                    |                    | 0.4.5570.4        |
|                     |                     |                    | • 6AW8A<br>• 6HL8     | • 6LF8<br>• 6KT8   | • 8AW8A           |
| Beam Power 7        |                     |                    | UILLO                 | · OILIG            |                   |
| • 5AQ5              | ⊙ 6L6               | • 25C5             | 4. BURST              | <b>AMPLIFIERS</b>  | 5                 |
| • 5CZ5              | ⊙ 6L6GC†            | • 25F5A            | i                     |                    |                   |
| o 5V6GT<br>• 6AQ5A  | o 6V6<br>o 6V6GTA   | • 34GD5A<br>• 35B5 |                       | Triode—Sharp-C     |                   |
| • 6AS5              | ⊙ 6W6GT             | • 35C5             | • 5EA8                | • 6EA8             | • 6GH8A           |
| • 6CM6              | ⊙ 6Y6G              | o 35L6GT           | • 5GH8                |                    |                   |
| • 6CU5              | • 12AB5             | • 50B5             | Medium-Mu             | Triode—Semiren     | note-Cutoff       |
| • 6CZ5              | • 12AQ5             | • 50C5             | Pentode               |                    |                   |
| o 6DG6GT            | • 12CA5             | 50FE5              | • 6LM8                |                    |                   |
| • 6DS5              | • 12CU5/12C5        |                    | 771-1-34 . To-1-      | a                  |                   |
| • 6FE5              | o 12V6GT            | • 6973†            | 1 -                   | de with Twin D     | piodes            |
| ^ 6GC5              | o 12W6GT<br>• 17CU5 | o <b>7408†</b>     | • 6BN8                | • 8BN8             |                   |
| o 6HG5              | • 17005             |                    | 5. CATHOI             | DE-DRIVE R         | F AMPLI.          |
| Beam Power          | Tube—Sharp-Cuto     | off Pentode        |                       |                    |                   |
| ‡ 6AL11             | ‡ 10AL11            | ‡ 12AL11           | FIERS (GROUNDED-GRID) |                    |                   |
|                     |                     |                    | Medium-Mu 7           | riode              |                   |
| Power Pentode       |                     |                    | • 6BC4                |                    |                   |
| • 6BQ5              | • 8BQ5              | • 50EH5            | Medium-Mu 1           | Twin Triode        |                   |
| • 6EH5              | • 12EH5             | • 50FK5            | <b>I</b>              |                    | CD.O.T.4          |
| o 6F6               | • 12FX5             | • 60FX5            | • 4BC8<br>• 4BO7A     | • 5BK7A<br>• 5BO7A | • 6BQ7A<br>• 6BS8 |
| • 6GK6<br>o 6K6GT   | • 25EH5<br>• 35EH5  | • 7189†<br>▲ 7868† | • 4BQ/A               | • 6BC8             | • 6BZ7            |
| OOKOGI              | • JSENS             | - /0007            | • 4BZ7                | • 6BK7A            | · UDZ1            |
| Pentode—Bean        | 1 Power Tube        |                    |                       |                    |                   |
| ± 6J10              | ‡ 13J10             |                    | High-Mu Trio          |                    |                   |
| •                   | •                   |                    | △ 2CW4                | • 6AB4             | △ 6DS4            |
| 2 ATITOM            | ATIC GAIN C         | ONTROL             | △ 2DS4                | △ 6CW4             | △ 13CW4           |
|                     |                     |                    | High-Mu Twin          | 1 Triode           |                   |
| CIRCUIT             | S (AGC & A          | /C)                | • 6DT8                | • 12AZ7A           | • 12DT8           |
| -                   | Cutoff Pentode      |                    | • 12AT7               |                    |                   |
| • 6KL8              | • 12KL8             |                    | 6. COLOR KILLERS      |                    |                   |
| Diode-Remote        | e-Cutoff Pentode    |                    | Quadruple Die         | ode                |                   |
| • 6EQ7              | • 12EQ7             |                    | • 6JU8                | • 6JU8A            |                   |
| •                   | -                   |                    |                       |                    |                   |

<sup>•</sup> Miniature  $\ddagger$  Duodecar  $\circ$  Octal  $\, {}_\Delta$  Nuvistor  $\, {}^\Delta$  Novar  $\, *$  Dual-control grids  $\dagger$  For high-fidelity equipment

### 7. COLOR MATRIXING CIRCUITS

#### Medium-Mu Twin Triode

 6CG7 • 6GU7 • 8FO7 6FQ7 8CG7 12BH7A

### 8. COMPLEX-WAVE GENERATORS

High-Mu Twin Double-Plate Triode

12FO8

Sharp-Cutoff Twin-Plate Tetrode-Diode • 6FA7

Sharp-Cutoff Three-Plate Tetrode-Diode 6KM8

Three-Plate Tetrode-Medium-Mu Triode 6FH8

### 9. CONVERTERS

Medium-Mu Triode-Sharp-Cutoff Pentode

• 5EA8 • 5X8 6KZ8 5GH8 6EA8 6U8A 5KE8 6GH8A • 6X8 • 5U8 6KE8 19X8

High-Mu Twin Triode

• 6DT8 • 12AZ7A 12DT8

• 12AT7

Sharp-Cutoff Pentode

 3AU6 6AU6A 18GD6A 4AU6 • 12AU6

Pentagrid

• 3RE6 o 6SA7 o 12SA7 • 6BA7 • 12BE6 • 18FX6A 6BE6

### 10. DAMPERS

### Half-Wave (Diode)

 6AU4GTA **▲ 17BS3** 6AX4GTB 4 6DW4 o 17D4 o 6W4GT 4 6AY3 ○ 17DE4 o 12AX4GTA ▲ 6BA3 o 19AU4 ▲ 6BH3 ▲ 22BH3 ▲ 12AY3 4 6BS3 o 22DE4 6CQ4 4 12BS3 • 25AX4GTA o 6DÃ4 o 12D4 4 17AY3 o 6DE4 o 17AX4GTA ▲ 17BH3

6DM4

### 11. DEMODULATORS (COLOR TV)

Medium-Mu Twin Triode • 12BH7A

High-Mu Twin Triode 12AZ7A

Sharp-Cutoff Pentode 3BY6 6GY6

Pentagrid Amplifier

12. DETECTORS

6BY6

Diode-Sharp-Cutoff Pentode

• 5AM8 6AM8A 6KL8 • 5AS8 • 6AS8 12KL8

6JH8

Diode-Remote-Cutoff Pentode

 6CR6 • 12CR6 12EQ7 • 6EQ7

Twin Diode

 3AL5 o 6H6 o 12H6 6AL5 • 12AL5

Twin Diode-High-Mu Triode

• 3AV6 • 6CN7 • 12AV6 4AV6 6SO7 o 12SO7 • 6AT6 • 8BN8 • 14GT8 6AV6 12AT6 18FY6A

 6BN8 Triple Diode

• 6BJ7 Triple Diode-High-Mu Triode

•5T8 • 6T8A

Quadruple Diode

 6JU8 • 6JU8A

Sharp-Cutoff Pentode

 3DT6A\* • 5GX6\* • 6GX6\* 4DT6A\* 6DT6A\* 6HZ6\*

### 13. DC RESTORERS

Diode-Sharp-Cutoff Pentode

 5AM8 • 6AM8A • 6A58 5AS8

Triple Diode

6BJ7

### 14. DISCRIMINATORS

FM

Twin Diode 3AL5

 6AL5 • 12AL5

Twin Diode-High-Mu Triode 6BN8 • 14GT8

Triple Diode-High-Mu Triode

• 5T8 6T8A • 19T8

 Miniature Octal A Nuvistor A Novar

\* Dual-control grids

### Beam Tube

• 3BN6

4BN6

6BN6

Beam Power Tube-Sharp-Cutoff Pentode **#12AL11 #17BF11** 

Pentode-Beam Power Tube **# 6J10** ± 13310

FM Ouadrature-Grid

#### Sharp-Cutoff Pentode

 3DT6A\* 5GY6\* 6GX6\* 4DT6A\* 6DT6A\* 6HZ6\* • 5GX6\*

### Beam Tube

3BN6

4BN6

6BN6

### Horizontal AFC

Twin Diode-High-Mu Triode

• 6RNS • 8BN8 8CN7 • 6CN7

### 15. FREQUENCY DIVIDERS

High-Mu Twin Double-Plate Triode • 12FQ8

16. FM DETECTORS (See 14. Discriminators)

### 17. GATED NOISE, AGC, AND SYNC AMPLIFIERS

High-Mu Triode-Sharp-Cutoff Pentode · SKAS

• 6KA8 6LC8

Sharp-Cutoff Pentode

6GY6\*

### Sharp-Cutoff Twin Pentode

• 3BU8 4BU8 6BU8 • 3GS8 • 4HS8 6HS8 • 3HS8

### Pentagrid Amplifier

• 3RV6 4CS6 6C56 3CS6 • 6BY6

### 18. GROUNDED-GRID RF AMPLIFIERS

(See 5. Cathode-Drive RF Amplifiers)

### 19. HARMONIC GENERATORS

(See 8. Complex-Wave Generators) Miniature o Octal △ Nuvistor 4 Novar

#### \* Dual-control grids ‡ Duodecar

### 20. HORIZONTAL-DEFLECTION **CIRCUITS**

### Oscillators

Medium-Mu Triode-Sharp-Cutoff Pentode • 5GH8 6GH8A

#### Medium-Mu Twin Triode

 6CG7 8CG7 • 12AU7A 6FQ7 8FO7 • 12BH7A o 6SN7GTB 9AU7 o 12SN7GTA • 7AU7

### **Amplifiers**

### Beam Power Tube

o 6AU5GT 4 6JG6 4 17GJ5 o 6AV5GA ▲ 6JG6A 4 17GJ5A 4 6JT6 o 6BG6GA 4 17GT5 o 6BQ6GTB/ o 12AV5GA o 17GW6 6CU6 o 12BO6GTB/ ▲ 17JB6 • 6CB5A 12CU6 **▲ 17JG6** o 12DO6B ▲ 17JT6 o 6CD6GA ▲ 22JG6 o 6DO5 ▲ 12GT5 o 6DO6B o 12GW6 o 25AV5GA 4 6GJ5 ▲ 12JB6 o 25BO6GTB/ ▲ 6GT5 **▲ 12JT6** 25CU6 o 6GW6 o 17BQ6GTB o 25CD6GB o 17DQ6B o 25DN6 ▲ 6JB6 **▲ 6JE6** 

### 21. INTERMEDIATE-FREQUENCY **AMPLIFIERS**

Medium-Mu Triode-Sharp-Cutoff Tetrode • 5CQ8 • 6CO8

### Medium-Mu Triode-Sharp-Cutoff Pentode

• 5AN8 6AZ8 6CH8 6AN8A • 6BH8 6CU8

### High-Mu Triode-Sharp-Cutoff Pentode

 6AW8A 6KV8 • 10GN8 • 6GN8 8AW8A 10HF8 6HF8 8GN8 • 10JA8 6JV8 • 8JV8 • 11KV8 6KT8

### Sharp-Cutoff Pentode

• 3AU6 4JC6 6DK6 3BC5 4JD6= 6EJ7 3CB6 5EW6 • 6EW6 3CF6 6AG5 6HS6 3DK6 6AK5 6JC6 3JC6 6AU6A • 6JD6\* 3JD6= 6BC5 • 12AU6 4AU6 6CB6 12AW6 4CB6 6CB6A 12DK6 4DE6 • 6CF6 18GD6A 4DK6 6DC6 19HS6 4EW6 6DE6

 Approaches semiremote-cutoff characteristics; used in first-if amplifier applications

• Miniature

o Octal

△ Nuvistor

^ Novar

\* Dual-control grids

‡ Duodecar

|                          |                  |                            | •   |
|--------------------------|------------------|----------------------------|---|
| Sharp-Cutoff             | Pentode with I   | Diode                      | High-Mu Twin Triode                         |
| • 5AM8                   | • 6AM8A          | • 6KL8                     | • 6DT8 • 12AT7 • 12DT8                      |
| • 5AS8                   | • 6AS8           | • 12KL8                    | Triode-Hexode                               |
| Samiramata               | Cutoff Pentode   |                            | ○ 6K8 ○ 12K8                                |
| • 3BZ6                   | • 5GM6           | • 6HR6                     | 0 0A6 0 12A6                                |
| • 3EH7                   | • 6BZ6           | • 6JH6                     | 26. MULTIVIBRATORS                          |
| <ul> <li>4BZ6</li> </ul> | • 6EH7           | • 12BZ6                    | Medium-Mu Triode-Sharp-Cutoff Pentode       |
| • 4EH7                   | • 6GM6           | • 19HR6                    | • 5GH8 • 6GH8A                              |
| • 4GM6                   |                  |                            |   |
| Remote-Cuto              | ff Pentode       |                            | Medium-Mu Twin Triode                       |
| • 3BA6                   | • 12BA6          | <ul> <li>18FW6A</li> </ul> | • 6CG7 • 7AU7 • 12SN7-<br>• 6GU7 • 8CG7 GTA |
| • 6BA6                   | • 18FW6          |                            | • 6GU7 • 8CG7 GTA<br>○ 6SN7GTB • 9AU7       |
| Remote-Cuto              | off Pentode with | Diode                      | • 12AU7A                                    |
| • 6EO7                   | • 12EO7          | Diode                      |   |
| · ULQ!                   | 1220             |                            | High-Mu Twin Triode                         |
|                          |                  |                            | • 12AX7A                                    |
| 22. KEYE                 | D AGC AME        | PLIFIERS                   | 27. NOISE INVERTERS (NOISE                  |
| (See 1                   | 7. Gated Nois    | se, AGC, and               | IMMUNE CIRCUITS)                            |
|                          | Amplifiers)      | se, iide, une              | ,   |
| D) III                   | . ixiiipiiiicis, |                            | High-Mu Triode—Sharp-Cutoff Pentode         |
|                          |                  |                            | • 6KA8 • 8KA8 • 8LC8<br>• 6LC8              |
| 23. LIMIT                | ERS              |                            |   |
| Deam Take                |                  |                            | Sharp-Cutoff Pentode                        |
| Beam Tube                | 4007             | CD216                      | • 6GY6*                                     |
| • 3BN6                   | • 4BN6           | • 6BN6                     | 28. OSCILLATORS                             |
| Sharp-Cutoff             | Pentode          |                            |   |
|                          | • 6AU6A          | • 6HZ6                     | Radio Frequency—UHF                         |
| • 4AU6                   | • 6GX6           | • 12AU6                    | Medium-Mu Triode                            |
| • 5GX6                   | • 6HS6           | • 19HS6                    | • 2AF4B • 3AF4A • 6AF4A                     |
| Sharp-Cutoff             | Pentode with Di  | ode                        | △ 2DV4 • 3DZ4 △ 6DV4                        |
| • 6KL8                   | • 12KL8          |                            | • 2DZ4 • 6AF4 • 6DZ4                        |
| D                        |                  |                            | Radio Frequency—VHF                         |
|                          | de—Beam Power    | r lube                     | Medium-Mu Twin Triode                       |
| ‡ <b>6J10</b>            | ‡ 13 <b>J</b> 10 |                            | • 5J6 • 6J6A                                |
|                          |                  |                            | TYING ME. Waterda                           |
| 24. MIXEF                | RS—RF            |                            | High-Mu Triode                              |
|                          |                  |                            | • 6AB4                                      |
| Medium-Mu                |                  |                            | Power Triode                                |
| • 5J6                    | • 6J6A           |                            | • 6C4 (Class C)                             |
| High-Mu Tric             | )de              |                            |   |
| △ 2CW4                   | △ 6CW4           | △ 13CW4                    | Low Frequency, Sweep Type                   |
| • 6AB4                   |                  |                            | Medium-Mu Triode—Sharp-Cutoff Pentode       |
|                          |                  |                            | • 5AN8 • 6BA8A • 8AU8                       |
| 25. MIXER                | R-OSCILLATO      | PC_PF                      | • 6AN8A • 6BH8 • 8BA8B                      |
| ZUI IVIRIBZI             | COSCILLATIO      | ALC:                       | • 6AU8A • 6CH8 • 8BH8                       |
| Medium-Mu                | Triode—Sharp-Cı  | itoff Tetrode              | • 6AZ8                                      |
| • 5CL8A                  | • 6CL8A          | • 19CL8A                   | High Mu Triode with Twin Diode              |
| • 5CQ8                   | • 6CQ8           |                            | • 6BN8 • 8BN8 • 8CN7                        |
| Medium-M.:               | Triode—Sharp-Cu  | toff Pentode               | • 6CN7                                      |
| • 5AT8                   | • 5X8            | • 6KZ8                     |   |
| • 5B8                    | • 6AT8A          | • 6NZ8<br>• 6U8A           | High-Mu Twin Triode                         |
| • 5BR8                   | • 6BR8A          | • 6X8                      | • 12AX7A                                    |
| • 5CG8                   | • 6CG8A          | • 9EA8                     | 20 DUACE INVENTEDE                          |
| • 5EA8<br>• 5FG7         | • 6EA8<br>• 6FG7 | • 9U8                      | 29. PHASE INVERTERS                         |
| • 5KE8                   | • 6HB7           | • 19EA8<br>• 19X8          | Medium-Mu Triode-High-Mu Triode             |
|                          |                  | -/0                        | <del>-</del>                                |

• Miniature

| P P                                     | 0                |                        |                   |                                      | 0,                 |
|---|------------------|------------------------|-------------------|--------------------------------------|--------------------|
| Medium-Mu T                             | win Triode       |                        | Sharp-Cutoff      | Tetrode                              |                    |
| • 6CG7                                  | • 7AU7           | • 12AU7A               | • 2CY5            |                                      | . CEUC             |
| • 6GU7                                  | • 8CG7           | o 12SN7-               | 3CY5              | • 4CY5<br>• 6CY5                     | • 6FV6             |
| o 6SN7GTB                               | • 9AU7           | GTA                    | - 3013            | • 0013                               |                    |
|   |                  |                        | Sharp-Cutoff      | Pentode                              |                    |
| High-Mu Trio                            | de-Sharp-Cuto    | ff Pentode             | • 3AU6            | • 6AK5                               | • 6DE6             |
| • 6AW8A                                 | • 8AW8A          | • 10GN8                | • 3BC5            | • 6AU6A                              | o 6SH7             |
| • 6EB8                                  | • 8EB8           | • 10HF8                | • 3CB6            | • 6BC5                               | o 6SJ7             |
| • 6GN8                                  | • 8GN8           | • 10JA8                | • 3CF6            | • 6BH6                               | • 12AU6            |
| • 6HF8                                  |                  |                        | • 4AU6<br>• 4CB6  | <ul><li>6CB6</li><li>6CB6A</li></ul> | • 12AW6            |
| High-Mu Twin                            | Triode           |                        | 0 4DE6            | • 6CF6                               | o 12SH7<br>o 12SJ7 |
| o 6SL7GT                                | o 12SL7GT        | • 7025                 | • 6AG5            | • 6DC6                               | • 18GD6A           |
| • 12AX7A                                | 0 125L/G1        | • 1025                 |                   |                                      |                    |
|   |                  |                        | Sharp-Cutoff      | Pentode with D                       | iode               |
|   |                  |                        | • 6KL8            | • 12KL8                              |                    |
| 30. PHASE                               | <b>SPLITTERS</b> |                        |                   |                                      |                    |
| *************************************** |                  |                        | Remote-Cutofi     | Pentode                              |                    |
| Medium-Mu T                             | riode—Sharp-C    | utoff Tetrode          | • 3BA6            | • 6BJ6                               | • 12BA6            |
| • 5CQ8                                  | • 6CQ8           |                        | • 6BA6            | o 6SK7GT                             | • 18FW6A           |
|   |                  |                        |                   |                                      |                    |
|   | riode—Sharp-C    |                        | 1                 | Pentode with                         | Diode              |
| • 5AN8                                  | • 6BA8A          | • 8BA8A                | • 6EQ7            | • 12EQ7                              |                    |
| • 6AN8<br>• 6AZ8                        | • 6CH8<br>• 6CU8 | • 7199                 |                   |                                      |                    |
| · UALO                                  | • 000            |                        | 32. REACT         | ANCE CIRC                            | THE                |
| High-Mu Trio                            | de-Sharp-Cuto    | ff Pentode             |                   | THE CLIC                             | .0110              |
| • 6AW8A                                 | • 8AW8A          |                        | Medium-Mu         | Triode—Sharp-Co                      | utoff Pentode      |
|   |                  |                        | • 5AN8            | • 6BA8A                              | • 6CU8             |
|   |                  |                        | • 6AN8A           | • 6CH8                               | • 8BA8A            |
| 31. RADIO                               | FREQUENC         | Y                      | • 6AZ8            |                                      |                    |
| AMPLII                                  | -                |                        | High-Mu Tric      | ode with Twin                        | Diodes             |
|   |                  |                        | • 6CN7            | • 8CN7                               | Diones             |
| Medium-Mu T                             | riode            |                        | - 00117           | - 00117                              |                    |
| • 2BN4A                                 | • 6BC4           | • 6BN4A                | High-Mu Tric      | de-Sharp-Cuto                        | ff Pentode         |
| • 3BN4A                                 |                  |                        | • 6AW8A           | • 8AW8A                              |                    |
|   |                  |                        |                   |                                      |                    |
|   | riode—Sharp-C    | utoff Tetrode          | 33. RECTII        | ETEDE                                |                    |
| • 5CQ8                                  | • 6CQ8           |                        | 33. RECTH         | TERS                                 |                    |
|   |                  |                        | Power-S           | upply Types-                         | Vacuum             |
| Medium-Mu T                             |                  |                        | 10/10/-5          | uppiy Types-                         | —r ucuum           |
| • 4BC8<br>• 4BQ7A                       | • 5BQ7A<br>• 5J6 | • 6BS8<br>• 6BZ7       | Half-Wave (D      | iode)                                |                    |
| • 4B58                                  | • 6BC8           | • 6J6A                 | • 35W4            | <ul> <li>36AM3B</li> </ul>           | • 50DC4            |
| • 4BZ7                                  | • 6BK7B          | • 12AV7                | o 35Z5GT          |                                      |                    |
| • 5BK7A                                 | • 6BQ7A          |                        |                   |                                      |                    |
|   |                  |                        | Full-Wave (Tv     |                                      |                    |
| High-Mu Trio                            | ie               |                        | © 3DG4<br>© 5AS4A | o 5V3A                               | o 5Z4              |
| △ 2CW4                                  | • 3GK5           | • 6ER5                 | A 5BC3            | o 5VG4<br>o 5V4GA                    | • 6CA4<br>• 6X4    |
| △ 2DS4                                  | • 3HM5/3HA       |                        | o 5DJ4            | o 5XG4                               | ∘ 6X5GT            |
| • 2ER5                                  |                  | • 6FQ5A                | ⊙ 5U4G            | o 5Y3GT                              | • 12CA4            |
| • 2FH5<br>• 2GK5                        | • 6AB4<br>△ 6CW4 | • 6GK5<br>• 6HM5/6HA5  | o 5U4GB           |                                      | • 12X4             |
| • 3ER5                                  | 4 6DS4           | • 0HM5/0HA5<br>△ 13CW4 |                   |                                      | • 25CA4            |
| • 3FH5                                  | -20.             | 100.17                 | Triate Triate     | . T                                  |                    |
|   |                  |                        |                   | e Types (For                         |                    |
| High-Mu Twin                            | Triode           |                        | puised lo         | w-current appl                       | ucations)—         |
| • 6DT8                                  | • 12AZ7A         | • 12DT8                |                   | Vacuum                               |                    |
|   |                  |                        | Half-Wave (D      | iode)                                |                    |
| Power Triode                            |                  |                        | o 1G3GT/          | o 1K3/1J3                            | • 1X2B             |
| • 6C4 (Class                            | C)               |                        | 1B3GT             | • 1V2                                | • 3A2              |
|   |                  |                        |                   |                                      |                    |

o Octal

▲ Nuvistor

4 Novar

### 34. REGULATORS (HIGH VOLT-AGE, LOW CURRENT)

Sharp-Cutoff Beam Triode o 6BK4 6BK4A

### 35. RELAY CONTROL CIRCUITS

Medium-Mu Twin Triode

• 12FV7

High-Mu Twin Triode

• 6EV7

### 36. REMOTE-TUNING CIRCUITS (See 35. Relay Control Circuits)

### 37. SYNC AMPLIFIERS

Medium-Mu Triode-Sharp-Cutoff Pentode • 6AU8A • 6CX8 8CX8

 6AZ8 8AU8

Medium-Mu Twin Triode 6CG7 8CG7

12AU7A

High-Mu Triode with Twin Diode

 6CN7 • 8CN7

High-Mu Triode-Sharp-Cutoff Pentode

 6AW8A 6JV8 · RIVE

 8AW8A • 10HF8 6HF8

High-Mu Twin Triode

• 12BZ7

• 7AU7

### 38. SYNC CLIPPERS

Medium-Mu Triode-Sharp-Cutoff Tetrode • 5CO8 • 6CO8

### Medium-Mu Triode-Sharp-Cutoff Pentode

• 5AN8 6AZ8 6CX8 6AN8A 6CH8 8CX8 6AU8A 6CU8 8AU8

### High-Mu Triode-Sharp-Cutoff Pentode • 8JV8

 6AW8A 6HF8 6EB8 6JV8 • 10GN8 • 8AW8A 6GN8 10HF8 6GW8/ • 10JA8 8EB8 **ECI.86** · SCNS

### High-Mu Twin Triode

• 12B7.7

Miniature

### Sharp-Cutoff Twin Pentode

• 3RUS • 4RII8 • 6BUS 3GS8 4HS8 6HS8 3HS8

#### Pentagrid Amplifier

 3BY6 4CS6 3CS6

6BY6

### 39. SYNC SEPARATORS

Medium-Mu Triode-Sharp-Cutoff Tetrode 5CO8 6CO8

Medium-Mu Triode-Sharp-Cutoff Pentode 5AN8 6AZ8 • 5GH8 • 6CU8 • 6GH8A

• 8AU8 6AN8A 6CX8 6AU8A 6GH8 8CX8

### Medium-Mu Twin Triode

• 6CG7 8CG7 12AU7A • 7AU7

High-Mu Triode with Twin Diode

 6CN7 8CN7

### High-Mu Triode-Sharp-Cutoff Pentode

 6AW8A 6KV8 • 8KA8 6ER8 6LC8 8LC8 6GN8 • 8AW8A 10GN8 6HF8 8EB8 10HF8 6JV8 8GN8 • 10JA8 • 6KA8 RIVR 11KV8

High-Mu Twin Triode

12BZ7

### Sharp-Cutoff Twin Pentode

 3BU8 4BU8 6BU8 3GS8 4GS8/4BU8 6HS8 3HS8 4HS8

### Pentagrid Amplifier

 3BY6 4CS6 6CS6 3CS6 6BY6

### 40. TUNING INDICATORS

Indicator with Triode Unit 6E5

Twin Indicator Units o 6AF6G

### 41. VERTICAL-DEFLECTION CIRCUITS

Oscillators and Amplifiers (Combined) Medium-Mu Triode-Low-Mu Triode

• 6DE7 • 10DE7 13DE7 • 6EW7

Medium-Mu Dual Triode

 6CM7 8CM7 8CS7 6CS7

### High-Mu Triode-Low-Mu Triode

▲ 6GF7 4 10GF7 • 6CY7 4 6GF7A o 11CY7 6DR7 6GL7 13DR7 6EA7 o 6EM7 10DR7 o 13EM7 ▲ 13FD7 4 6FD7 o 10EM7

#### High-Mu Triode-Beam Power Tube

4 6KY8 4 15KY8 4 15KY8A 4 6KY8A


△ Nuvistor

4 13GF7

6CS6

|   | Amplifiers        | 7                           | High-Mu Tric  | de—Sharp-Cuto   | ff Pentode  |
|---|-------------------|-----------------------------|---|---|---|
| Low-Mu Tric • 12B4A Medium-Mu • 6S4A Beam Power | ode<br>Triode     |                             | • 6AW8A<br>• 6EB8<br>• 6GN8<br>• 6HF8<br>• 6JV8<br>• 6KT8 | • 6KV8<br>• 6LF8<br>• 8AW8A<br>• 8EB8<br>• 8GN8<br>• 8JV8 | • 10GN8<br>• 10HF8<br>• 10JA8<br>• 11KV8<br>• 12KV8 |
| • 5AQ5<br>• 5CZ5<br>• 5V6GT                     | • 6AQ5A<br>• 6CM6 | • 6EM5<br>• 8EM5<br>• 12AQ5 | Sharp-Cutoff • 12BY7A                                     | Pentode   |   |
| Power Pentod<br>o 6K6GT                         | ie<br>AMPLIFIE    | RS                          | Sharp-Cutoff  • 5AM8  • 5AS8                              | Pentode with Di • 6AM8A                                   | • 6AS8  |
|   | Triode—Sharp-C    |                             | Beam Power  • 6BK5  Power Pentod  • 6AG7  • 6CL6          | • 25BK5   | • 16GK6   |
| • Miniature                                     |                   | o Octal                     | ▲ Nuv   | istor   | ^ Novar   |

For information on picture tubes, refer to the RCA Picture Tube Characteristics Chart at the end of the Technical Data section.



- 1—Glass Envelope
- 2—Internal Shield
- 3-Plate
- 4—Grid No. 3 (Suppressor)
- 5-Grid No. 2 (Screen)
- 6-Grid No. 1 (Control Grid)
- 7—Cathode
- 8-Heater
- 9-Exhaust Tip
- 10-Getter
- 11 Spacer Shield Header
- 12—Insulating Spacer
- 13-Spacer Shield
- 14-Inter-Pin Shield
- 15-Glass Button-Stem Seal
- 16-Lead Wire
- 17-Base Pin
- 18—Glass-to-Metal Seal

Structure of a Miniature Tube

# Technical Data for RCA Tube Types

THIS section contains technical descriptions of RCA tubes used in standard broadcast, FM, and television receivers, in audio amplifiers, and in many other diverse applications. It includes detailed data on current types, including characteristics curves in many cases. Essential information on types intended primarily for renewal use and on discontinued types in which there may still be some interest is given in chart form at the end of the section. Characteristics charts for RCA television picture tubes for renewal use and for RCA voltage-regulator and voltagereference tubes are given in the following section.

In choosing tube should refer to the im-

mediately preceding


Tube types are li calnumerical sequence see inside back cover.

| types for the design of new electronic equence of the design of new electronic equence of this section.  It is section. It is section according to the new of their type designations. For Key: Ba | bes in the pages i |
|--|--|
| FULL-WAVE GAS RECTIFIER Renewal types; see chart at end of section for tabulated data.   | 0Z4<br>0Z4G  |
| <b>DIODE</b> Renewal type; see chart at end of section for tabulated data.   | 1A3  |
| REMOTE-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.   | 1A4P   |
| POWER PENTODE  Renewal type; see chart at end of section for tabulated data.   | 1A5GT  |
| PENTAGRID CONVERTER Discontinued type; see chart at end of section for tabulated data.   | 1 <b>A</b> 6   |
| PENTAGRID CONVERTER Renewal type; see chart at end of section for tabulated data.  | 1A7GT  |
| POWER PENTODE  Discontinued type; see chart at end of section for tabulated data.  | 1AC5   |

### HALF-WAVE VACUUM RECTIFIER

1AD2

Duodecar type used to supply power to the anode of the picture tube in television receivers. Outline 9A, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Socket



terminals 4 and 10 may be used as tie points for components at or near filament potential. Filament volts (ac/dc), 1.25; amperes, 0.2.

| Pulsed F | lectifier |
|----------|-----------|
|----------|-----------|

|                           | Pulsed Rectifier  |           |      |
|---------------------------|---|-----------|------|
|                           | or operation in a 525-line, 30-frame system   | m         |      |
| MAXIMUM RATINGS (D        |   |           |      |
|                           | e#  |           | olts |
|                           |   |           | ma   |
| Average Plate Current     |   | . 0.5 max | ma   |
| CHARACTERISTICS, Inst     |   | ***       |      |
| Tube voltage Drop for pla | ate current of 7 ma   | . 225 v   | olts |
|                           | age pulse must not exceed 15 per cent<br>ame system, 15 per cent of one horizon       |           |      |
| ■ The dc component must r | not exceed 22000 volts.   |           |      |
| <b>1AD5</b> D             | SHARP-CUTOFF PENTODE Discontinued type; see chart at en of section for tabulated data | d         |      |

section for tabulated data.

### **1AX2**

### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

### 1B3GT

### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

### 1B4P

### SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

## 1B5/25S

### TWIN DIODE-MEDIUM-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

### 1B7GT

### PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

### 1C5GT

### POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

### 1C6

### PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

### 1C7G

### PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

| 1D5GF          | REMOTE-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.  |
|----------------|---|
| 1D5G1          | REMOTE-CUTOFF PENTODE  Discontinued type; see chart at end of section for tabulated data.   |
| 1D7G           | PENTAGRID CONVERTER  Discontinued type; see chart at end of section for tabulated data.   |
| 1D8G1          | DIODE—TRIODE— POWER PENTODE Discontinued type; see chart at end of section for tabulated data.  |
| 1DN5           | DIODE—<br>SEMIREMOTE-CUTOFF PENTODE<br>Renewal type; see chart at end of<br>section for tabulated data.   |
| 1E5GP          | SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.   |
| 1E7GT          | TWIN POWER PENTODE  Discontinued type; see chart at end of section for tabulated data.  |
| 1 <b>E</b> 8   | PENTAGRID CONVERTER  Discontinued type; see chart at end of section for tabulated data.   |
| 1 <b>F</b> 4   | POWER PENTODE Discontinued type; see chart at end of section for tabulated data.  |
| 1F5G           | POWER PENTODE Discontinued type; see chart at end of section for tabulated data.  |
| 1F6            | TWIN DIODE— SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.   |
| 1F7G           | TWIN DIODE— SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.   |
|                | HALF-WAVE VACUUM RECTIFIER  |
| 1G3GT<br>1B3G1 | Glass octal type used in high-voltage, low-current applications such as the rectifier in a high-voltage, rf-operated power supply or as a rectifier of high-voltage pulses produced in television scanning systems. |
|                |   |

| Filament Voltage (ac/dc)   | 1.25*    | volts        |
|--|----------|--------------|
| Filament Current   | 0.2      | ampere       |
| Direct Interelectrode Capacitance (Approx.):                                       |          | · ·          |
| Plate to Filament and Internal Shield  | 1.3      | pf           |
| * Under no circumstances should the filament voltage be less than 1.05 1.45 volts. | volts or | greater than |

### **Pulsed Rectifier**

| For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|---|-----------|-------|
| Peak Inverse Plate Voltage#   | 26000 max | volts |
| Peak Plate Current  | 50 max    | ma    |
| Average Plate Current   | 0.5 max   | ma    |
| CHARACTERISTICS, Instantaneous Value:   |           |       |
| Tube Voltage Drop for plate current of 7 ma   | 100       | volts |
| Radio-Frequency Rectifier   |           |       |

| riumio i roducino, ricocinio.                                       |                  |       |
|---|------------------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):                            |                  |       |
|   |                  |       |
| Peak Inverse Plate Voltage  | 33000 max        | volts |
| Peak Plate Current  | 35 max           | ma    |
| Average Plate Current   | 1.1 max          | ma    |
| Frequency Range of Supply Voltage                                   | 1.5 to 100       | Kc    |
| #The duration of the voltage pulse must not exceed 15 per cent of a | ma harizantal ca |       |

#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

• The dc component must not exceed 22000 volts.

### Installation and Application

Type 1G3GT/1B3GT requires an octal socket and may be mounted in any position. Plate connection is cap at top of bulb. Socket terminals 1, 3, 4, 5, 6, and 8 may be connected to socket terminal 7 or to a corona shield which is connected to socket terminal 7. Socket terminals 4 and 6 may be used as tie points for components at or near filament potential. This type may be supplied with pins 1, 4, and/or 6 omitted. Outline 14B, Outlines section.

The high voltages at which the 1G3GT/1B3GT is operated are very dangerous. Great care should be taken to prevent coming in contact with these high voltages. In those circuits where the filament circuit is not grounded, the filament circuit operates at de potentials which can cause fatal shock. Extreme precautions must be taken when the filament voltage is measured. These precautions must include safeguards which definitely eliminate all hazards to personnel. The filament transformer, where it is of the iron-core or the air-core type, must be sufficiently insulated.

The voltages employed in some television receivers and other high-voltage equipment may be sufficiently high to cause high-voltage rectifier tubes such as the 1G3GT/1B3GT to produce soft X-rays which can constitute a health hazard unless the tubes are adequately shielded. Relatively simple shielding should prove adequate, but the need for this precaution should be considered.

### MEDIUM-MU TRIODE 1G4GT

**1G5G** 

1G6GT

1H4G

Discontinued type; see chart at end of section for tabulated data.

### POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

### HIGH-MU TWIN POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

### MEDIUM-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

DIODE-HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

1H5GT

TWIN DIODE—
MEDIUM-MU TRIODE
Discontinued type; see chart at end

1**H**6**G** 

of section for tabulated data.

HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

**1J3** 

POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

1**J**5**G** 

HIGH-MU TWIN POWER TRIODE

Discontinued types; see chart at end of section for tabulated data.

1J6G 1J6GT

HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

**1K3** 





Glass octal type used as a rectifier of high-voltage pulses produced in the scanning systems of black-andwhite television receivers. Tube requires octal socket and may be mounted in any position. Plate con-

1K3/ 1J3

nection is cap at top of bulb. Socket terminals 1, 3, 4, 5, 6, and 8 may be connected to socket terminal 7 or to a corona shield which is connected to socket terminal 7. Socket terminals 4 and 6 may be used as tie points for components at or near filament potential. Outline 14B, Outlines section. For high-voltage considerations, see type 1G3GT/1B3GT.

| Filament Voltage (ac/dc) Filament Current  | 1.25*<br>0.2 | volts<br>ampere |
|--|--------------|-----------------|
| Direct Interelectrode Capacitance (Approx.): Plate to Filament and Internal Shield | 1.6          | pf              |

\*Under no circumstances should the filament voltage be less than 1.05 volts or greater than 1.45 volts.

### **Pulsed Rectifier**

#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

<sup>•</sup> The dc component must not exceed 22000 volts.

| 1 <b>L</b> 6 | PENTAGRID CONVERTER Renewal type; see chart at end of section for tabulated data.              |
|--------------|--|
| 1LA4         | POWER PENTODE  Discontinued type; see chart at end of section for tabulated data.              |
| 1LA6         | PENTAGRID CONVERTER Renewal type; see chart at end of section for tabulated data.              |
| 1LB4         | POWER PENTODE  Renewal type; see chart at end of section for tabulated data.                   |
| 1LC5         | SHARP-CUTOFF PENTODE  Discontinued type; see chart at end of section for tabulated data.       |
| 1LC6         | PENTAGRID CONVERTER  Discontinued type; see chart at end of section for tabulated data.        |
| 1LD5         | DIODE— SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data. |
| 1LE3         | MEDIUM-MU TRIODE  Discontinued type; see chart at end of section for tabulated data.           |
| 1LG5         | REMOTE-CUTOFF PENTODE  Discontinued type; see chart at end of section for tabulated data.      |
| 1LH4         | DIODE—HIGH-MU TRIODE Renewal type; see chart at end of section for tabulated data.             |
| 1LN5         | SHARP-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.             |
| 1N2A         | HALF-WAVE VACUUM RECTIFIER Discontinued type; see chart at end of section for tabulated data.  |
| 1N5GT        | SHARP-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.             |
| 1N6G         | DIODE—POWER PENTODE Discontinued type; see chart at end of section for tabulated data.         |

| REMOTE-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.  | P5GT         |
|---|--------------|
| BEAM POWER TUBE  Discontinued type; see chart at end of section for tabulated data.   | Q5G1         |
| PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  | 1 <b>R</b> 5 |
| POWER PENTODE  Renewal type; see chart at end of section for tabulated data.  | 154          |
| DIODE— SHARP-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.   | 155          |
| REMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.   | 1 <b>T</b> 4 |
| BEAM POWER TUBE  Discontinued type; see chart at end of section for tabulated data.   | T5GT         |
| DIODE— SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.  | 1 <b>T</b> 6 |
| SHARP-CUTOFF PENTODE  Renewal type; see chart at end of section for tabulated data.   | 1U4          |
| DIODE— SHARP-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.   | 1U5          |
| HALF-WAVE VACUUM RECTIFIER Renewal type; see chart at end of section for tabulated data.  | 1V           |
| HALF-WAVE VACUUM RECTIFIER  |              |
| Miniature type used in high voltage, low-current applications such as the rectifier in high-voltage, pulse-operated voltage-doubling power supplies for kinescopes. The very low power required by the filament permits the a rectifier transformer having small size and light weight. | 1V2          |
| a totalion demotorinor maring omen one ene light weight   |              |

0.725 volt.

| Filament Voltage (ac)  | 0.625=  | volt         |
|--|---------|--------------|
| Filament Current   | 0.3     | ampere       |
| Direct Interelectrode Capacitance:                                     |         |              |
| Plate to Filament (Approx.)  | 0.8     | pf           |
| • Under no circumstances should the filament voltage be less than 0.52 | volt or | greater than |

**Pulsed Rectifier** 

| For operation in a 525-line, 30-frame system |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |          |       |
| Peak Inverse Plate Voltage *                 | 8250°max | volts |
| Peak Plate Current                           | 11 max   | ma    |
| Average Plate Current                        | 0.6 max  | ma    |
|  |          | _     |

The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle.
In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
The dc component must not exceed 7000 volts.

### Installation and Application

Type 1V2 requires a miniature nine-contact socket and may be mounted in any position. The socket should be made of material having low leakage and should have adequate insulation between its filament and plate terminals to withstand the maximum peak inverse plate voltage. To provide the required insulation in miniature nine-contact sockets designed with a cylindrical center shield, it is necessary to remove the center shield. In addition, socket terminals 2, 3, 7, and 8 shall not be used. Socket terminal 6 may be used as a tie point for components at or near filament potential. Outline 6B, Outlines section.

The filament is of the coated type and is designed for operation at 0.625 volt. The filament windings on the pulse transformer should be adjusted to provide the rated voltage under average line-voltage conditions. When the filament voltage is measured, it is recommended that an rms voltmeter of the thermal type be used. The meter and its leads must be insulated to withstand 15000 volts and the stray capacitances to ground should be minimized.

The high voltages at which the 1V2 is operated are very dangerous. Great care should be taken to prevent coming in contact with these high voltages. Particular care against fatal shock should be taken in measuring the filament voltage in those circuits where the filament is not grounded. Precautions must include safeguards which definitely eliminate all hazards to personnel.

### 1**X2**A

### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

### HALF-WAVE VACUUM RECTIFIER

**1X2B** 

Miniature type used in high-voltage, low-current applications such as the rectifier in a high-voltage, rf-operated power supply, or as the rectifier of high-voltage pulses produced in television scanning systems. Outline 7A,



Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Socket terminals 3 and 7 may be used as tie points for components at or near filament potential. For high-voltage considerations, refer to type 1G3GT/1B3GT.

| Filament Voltage (ac) Filament Current   | 0.2 | volts<br>ampere |
|--|-----|-----------------|
| Direct Interelectrode Capacitance: Plate to Filament and Internal Shield (Approx.) | 1.0 | pf              |

• Under no circumstances should the filament voltage be less than 1.05 volts or greater than 1.45 volts.

| Pii | hasi | Rec | tifier |
|-----|------|-----|--------|
|     |      |     |        |

| For operation in a 525-line, 30-frame system  |                                |                   |
|---|--------------------------------|-------------------|
| MAXIMUM RATINGS (Design-Maximum Values): Peak Inverse Plate Voltage* Peak Plate Current Average Plate Current | 22000 max<br>45 max<br>0.5 max | volts<br>ma<br>ma |
| CHARACTERISTICS, Instantaneous Value: Tube Voltage Drop for plate current of 7 ma                             | 100                            | volts             |
| The dc component must not exceed 18000 volts.   | 100                            | ¥0113             |
| POWER TRIODE  |                                |                   |

**2A3** Renewal type; see chart at end of section for tabulated data.

### POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

### TWIN DIODE ... HIGH-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

### PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

### MEDIUM-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

### MEDIUM-MU TRIODE


Miniature type identical with type 6AF4A except for heater ratings; refer to 6AF4A for data

### **2ΔF4R**

**2A5** 

**2**46

**2**ΔF4Δ



### HALF-WAVE VACUUM RECTIFIER

Duodecar type used to supply high voltage to the anode of picture tubes in television receivers. Outline 9A. Outlines section. Tube requires 12contact socket and may be mounted in any position. Socket terminals 2.

**2AH2** 

3, 5, 6, 7, 8, 9, and 11 should not be used as tie points; terminals 4 and 10 may be used as tie points for components at or near cathode potential. For highvoltage and X-ray safety considerations, refer to type 1G3GT/1B3GT. Heater volts (ac/dc), 2.5; amperes, 0.3.

#### **Pulsed Rectifier**

For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values): Peak Inverse Plate Voltage ..... 300000 max volts Peak Plate Current ..... 80 max ma Average Plate Current ..... 1.5 max ma CHARACTERISTICS, Instantaneous Value: Tube Voltage Drop for plate current of 7 ma ...... 100

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds,


The dc component must not exceed 24000 volts.

### HALF-WAVE VACUUM RECTIFIER

**2AS2** 

Tube Voltage Drop for plate current of 7 ma

Duodecar type used to supply high voltage to the anode of picture tubes in television receivers. Outline 9B. Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Socket



terminals 4, 7, and 10 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety considerations, refer to type 1G3GT/ 1B3GT. Heater volts (ac/dc), 2.5; amperes, 0.33.

Pulsed Rectifier

| For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values): |                                |                   |
|---|--------------------------------|-------------------|
| Peak Inverse Plate Voltage Peak Plate Current Average Plate Current                   | 30000°max<br>80 max<br>1.5 max | volts<br>ma<br>ma |
| CHARACTERISTICS. Instantaneous Value:   | 1.0                            |                   |

□ The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds. • The dc component must not exceed 24000 volts,

|     | TWIN DIODE—                         |
|-----|-------------------------------------|
| 2B7 | REMOTE-CUTOFF PENTODE               |
| LU/ | Discontinued type; see chart at end |

MEDIUM-MU TRIODE **2BN4** Discontinued type; see chart at end of section for tabulated data.

### MEDIUM-MU TRIODE Miniature type identical with type 6BN4A except for heater ratings; 2BN4A refer to 6BN4A for data.

HIGH MU TRIODE Nuvistor type identical with type **2CW4** 6CW4 except for heater ratings; refer to 6CW4 for data.

### SHARP-CUTOFF TETRODE Miniature type identical with type 6CY5 except for heater ratings; refer **2CY5**

to 6CY5 for data.

### HIGH-MU TRIODE Nuvistor type identical with type **2DS4** 6DS4 except for heater ratings; refer to 6DS4 for data.

MEDIUM-MU TRIODE Miniature type identical with type **2DV4** 6DV4 except for heater ratings; refer to 6DV4 for data.

|             | <sup>2</sup> a  |
|-------------|---|
| 2DZ4        | MEDIUM-MU TRIODE Nuvistor type identical with type 6DZ4 except for heater ratings; refer to 6DZ4 for data.      |
| <b>2E</b> 5 | ELECTRON-RAY TUBE Discontinued type; see chart at end of section for tabulated data.                            |
| 2EN5        | TWIN DIODE  Renewal type; see chart at end of of section for tabulated data.                                    |
| 2ER5        | SHARP-CUTOFF TRIODE  Miniature type identical with type 6ER5 except for heater ratings; refer to 6ER5 for data. |
| 2FH5        | SHARP-CUTOFF TRIODE  Miniature type identical with type 6FH5 except for heater ratings; refer to 6FH5 for data. |
| 2FS5        | BEAM HEXODE  Miniature type identical with type 6FS5 except for heater ratings; refer to 6FS5 for data.         |
| 2GK5        | HIGH-MU TRIODE  Miniature type identical with type 6GK5 except for heater ratings; refer to 6GK5 for data.      |
| 2GU5        | BEAM HEXODE  Miniature type identical with type 6GU5 except for heater ratings; refer to 6GU5 for data.         |
| 3A2         | HALF-WAVE VACUUM RECTIFIER Renewal type; see chart at end of of section for tabulated data.                     |
|             | HALF-WAVE VACUUM RECTIFIER  |



### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of

section for tabulated data.

Glass octal type used as rectifier of high-voltage pulses produced in the scanning systems of color television receivers. Outline 14E, Outlines section. Tube requires octal socket and may be mounted in any position.

3A3/ 3B2

**3A3** 

Socket terminals 1, 3, 4, 5, 6, and 8 may be connected to socket terminal 7. Socket terminals 4 and 6 may be used as tie points for components at or near heater potential. For high-voltage considerations, see type 1G3GT/1B3GT.

| Heater Voltage (ac)                           | 3.15°<br>0.22 | volts<br>ampere |
|---|---------------|-----------------|
| Plate to Heater, Cathode, and Internal Shield | 1.5           | pf              |

\* Under no circumstances should the heater voltage be less than 2.65 volts or greater than 3.65 volts.

### Pulsed Rectifier

| MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|--|-----------|-------|
| Peak Inverse Plate Voltage               | 30000 max | volts |
| Peak Plate Current                       | 88 max    | ma    |
| Average Plate Current                    | 1.7 max   | ma    |

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

3A8GT

### DIODE—TRIODE—PENTODE

Discontinued type; see chart at end of section for tabulated data.

3AF4A

### MEDIUM-MU TRIODE

Miniature type identical with type 6AF4A except for heater ratings; refer to 6AF4A for data.

**3AL5** 

### TWIN DIODE

Miniature type identical with type 6AL5 except for heater ratings; refer to 6AL5 for data.

HALF-WAVE VACUUM RECTIFIER

**3AT2** 

Duodecar type used to supply high voltage to the anode of picture tubes in television receivers. Outline 9B, outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. For high-



voltage and X-ray safety considerations, refer to type 1G3GT/1B3GT. Heater volts (ac/dc), 3.15; amperes 0.22.

### **Pulsed Rectifier**

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values):

Peak Inverse Plate Voltage\*

988 max max

Average Plate Current

1.7 max ma

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

**3AU6** 

### SHARP-CUTOFF PENTODE

Miniature type identical with type 6AU6A except for heater ratings; refer to 6AU6A for data.

### TWIN DIODE—HIGH-MU TRIODE

Miniature type identical with type 6AV6 except for heater ratings; refer to 6AV6 for data.

**3AV6** 



### HALF-WAVE VACUUM RECTIFIER

Glass octal type used as rectifier of high-voltage pulses produced in the scanning system of television receivers. Outline 14B, Outlines section. Tube requires octal socket and may be mounted in any position. Heater volts (ac/dc), 3.15; amperes, 0.22.

**3AW3** 

### **Pulsed Rectifier**

For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values):

Peak Inverse Plate Voltage\*
Peak Plate Current
Average Plate Current

30000 max 88 max 1.7 max

3B2

**3BA6** 

3BC5

volts

ma

ma

\* The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

REMOTE-CUTOFF PENTODE

Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.

SHARP-CUTOFF PENTODE

Miniature type identical with type 6BC5 except for heater ratings; refer to 6BC5 for data.

PENTAGRID CONVERTER

Miniature type identical with type 6BE6 except for heater ratings; refer to 6BE6 for data.

**3BE6** 

**MEDIUM-MU TRIODE** 

Discontinued type; see chart at end of section for tabulated data.

**3BN4** 

MEDIUM-MU TRIODE

Miniature type identical with type 6BN4A except for heater ratings; refer to 6BN4A for data.

3BN4A

**BEAM TUBE** 

Miniature type identical with type 6BN6 except for heater ratings; refer to 6BN6 for data.


**3BN6** 

| 3BU8  | SHARP-CUTOFF TWIN PENTODE  Miniature type identical with type 6BU8 except for heater ratings; refer to 6BU8 for data. |
|-------|---|
| 3BY6  | PENTAGRID AMPLIFIER  Miniature type identical with type 6BY6 except for heater ratings; refer to 6BY6 for data.       |
| 3BZ6  | SEMIREMOTE-CUTOFF PENTODE Miniature type identical with type 6BZ6 except for heater ratings; refer to 6BZ6 for data.  |
| 3CB6  | SHARP-CUTOFF PENTODE Miniature type identical with type 6CB6A except for heater ratings; refer to 6CB6A for data.     |
| 3CE5  | SHARP-CUTOFF PENTODE  Miniature type identical with type 6CE5 except for heater ratings; refer to 6CE5 for data.      |
| 3CF6  | SHARP-CUTOFF PENTODE  Miniature type identical with type 6CF6 except for heater ratings; refer to 6CF6 for data.      |
| 3C\$6 | PENTAGRID AMPLIFIER  Miniature type identical with type 6CS6 except for heater ratings; refer to 6CS6 for data.       |
| 3CY5  | SHARP-CUTOFF TETRODE  Miniature type identical with type 6CY5 except for heater ratings; refer to 6CY5 for data.      |

### **FULL-WAVE VACUUM RECTIFIER**

**3DG4** 

Glass octal type used as power supply in television receivers and other equipment having high de requirements. Outline 19E, Outlines section. Tube requires octal socket and may be operated in any position. It is espe-




cially important that this tube, like other power-handling tubes, be adequately ventilated. For discussion of Rating Chart, refer to Interpretation of Tube Data. Filament volts (ac/dc), 3.3; amperes, 3.8.

### Full-Wave Rectifier

| MAXIMUM RATINGS (Design-Maximum Values):          |          |         |
|---|----------|---------|
| Peak Inverse Plate Voltage                        | 1050 max |         |
| Peak Plate Current (Per Plate)                    | 1.2 max  | amperes |
| Hot-Switching Transient Plate Current (Per Plate) | 6.5 max  | amperes |





| TYPICAL OPERATION WITH CAPACITOR INPUT TO FILTER:  AC Plate-to-Plate Supply Voltage (rms)  Filter-Input Capacitor  Effective Plate-Supply Impedance per Plate  DC Output Voltage at Input to Filter (Approx.):  At full-load current of 350 ma |           | volts<br>µf<br>ohms<br>volts |
|--|-----------|------------------------------|
| CHARACTERISTICS: Tube Voltage Drop for plate current of 350 ma (per plate)   | 300<br>25 | volts                        |

Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for peak plate current,

### SHARP-CUTOFF PENTODE

Miniature type identical with type 6DK6 except for heater ratings; refer to 6DK6 for data.

### SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

### SHARP-CUTOFF PENTODE

Miniature type identical with type 6DT6A except for heater ratings; refer to 6DT6A for data.

### MEDIUM-MU TRIODE

Miniature type identical with type 6DZ4 except for heater ratings; refer to 6DZ4 for data.

### SHARP-CUTOFF PENTODE

Miniature type identical with type 6EA5 except for heater ratings; refer to 6EA5 for data.

3DT6A

**3DK6** 

**3DT6** 

3DZ4

**3EA5** 

| 3EH7   | SEMIREMOTE-CUTOFF PENTODE Miniature type identical with type 6EH7 except for heater ratings; refer to 6EH7 for data.  | <b>:</b>                          |                            |
|--|---|-----------------------------------|----------------------------|
| 3EJ7   | SHARP-CUTOFF PENTODE  Miniature type identical with type 6EJ7 except for heater ratings; refer to 6EJ7 for data.  |                                   |                            |
| 3ER5   | HIGH-MU TRIODE  Miniature type identical with type 6ER5 except for heater ratings; refer to 6ER5 for data.  |                                   |                            |
| 3FH5   | HIGH-MU TRIODE  Miniature type identical with type 6FH5 except for heater ratings; refer to 6FH5 for data.  |                                   |                            |
| 3 <b>G</b> K5  | HIGH-MU TRIODE  Miniature type identical with type 6GK5 except for heater ratings; refer to 6GK5 for data.  |                                   |                            |
|  | SHARP-CUTOFF TWIN PENTODE   | н_ ө                              | 63P2                       |
| 3GS8   | Miniature type used as combined sync separator, sync clipper, and agc amplifier tube in television receivers employing series-connected heater strings. Outline 6E, Outlines section. Tube requires miniature nine-contact mounted in any position. | PP23                              | G PPI                      |
| •  | • •   | 3.15                              | volts                      |
| Heater Current Heater Warm-Up Time Peak Heater-Cathode V   | · (Average)   | 0.6<br>11                         | ampere<br>seconds          |
| Heater negative with   | th respect to cathode   | 200 max<br>200°max                | volts<br>volts             |
| Grid No.3 to Plate Grid No.1 to All Grid No.1 to All Grid No.3 to All Plate to All Other Grid No.3 of Unit | apacitances: (Each Unit) Other Electrodes Other Electrodes (Each Unit) Electrodes (Each Unit) No.1 to Grid No.3 of Unit No.2  | 2<br>6<br>3.8<br>3.2<br>0.015 max | pf<br>pf<br>pf<br>pf<br>pf |
| The dc component m   | ust not exceed 100 volts.   |                                   |                            |
| MAXIMUM RATINGS Plate Voltage (Each U  | Class A <sub>1</sub> Amplifier (Design-Maximum Values): Unit)   | 300 max                           | volts                      |
| Peak positive value  | Unit)<br>Grid) Voltage (Each Unit):<br>Ie   | 50 max<br>-50 max                 | volts<br>volts             |
| DC positive value<br>Grid-No.2 (Screen-Grid  | ) Voltage   | 3 max<br>150 max                  | volts<br>volts             |
| Grid-No.1 (Control-Grid  | ) Voltage, Negative bias value  | -50 max<br>12 max                 | volts<br>ma                |
| Grid-No.2 Input  | Unit)   | 0.75 max<br>1.1 max               | watt<br>watts              |

| CHARACTERISTICS: With Both Units Operating Plate Voltage (Each Unit)  | 100<br>0<br>67.5<br>2<br>3.6<br>7.7<br>100<br>0<br>67.5<br>270<br>-2<br>-3.7<br>-2 | volts volts volts ma ma ma volts volts volts volts volts |
|---|--|--|
| MAXIMUM CIRCUIT VALUES: Grid-No.3-Circuit Resistance (Each Unit) Grid-No.1-Circuit Resistance                                 |  | megohm<br>megohm   |
| Adjusted to give a dc grid-No.1 current of 100 microamperes.  With plate and grid No.3 of the other unit connected to ground. | O.J IIIAX  | megonin  |
| SHARP-CUTOFF TWIN PENTODE Renewal type; see chart at end of section for tabulated data.                                       | 3GS8<br>3BU  | -  |
| HIGH-MU TRIODE  Miniature type identical with type 6HA5 except for heater ratings; refer to 6HA5 for data.                    | ЗНА  | 5  |
| HIGH-MU TRIODE  Miniature type identical with type 6HM5/6HA5 except for heater ratings; refer to 6HM5/6HA5 for data.          | 3HM5<br>3HA  | •  |
| SHARP-CUTOFF TWIN PENTODE  Miniature type identical with type 6HS8 except for heater ratings; refer to 6HS8 for data.         | 3HS  | 8  |
| SHARP-CUTOFF PENTODE  Miniature type identical with type 6JC6 except for heater ratings; refer to 6JC6 for data.              | 3JC  | 5  |
| SHARP-CUTOFF PENTODE  Miniature type identical with type 6JD6 except for heater ratings; refer to 6JD6 for data.              | 3JD(   | 5  |
| BEAM POWER TUBE Renewal type; see chart at end of section for tabulated data.   | 3LF4   | ı  |
| POWER PENTODE   | 204  | 1  |

Renewal type; see chart at end of section for tabulated data.

**BEAM POWER TUBE** 3Q5GT Renewal type; see chart at end of section for tabulated data. POWER PENTODE **3S4** Renewal type; see chart at end of section for tabulated data. **POWER PENTODE 3V4** Renewal type; see chart at end of section for tabulated data. SHARP-CUTOFF PENTODE Miniature type identical with type **4AU6** 6AU6A except for heater ratings; refer to 6AU6A for data. TWIN DIODE— HIGH-MU TRIODE **4AV6** Miniature type identical with type 6AV6 except for heater ratings; refer to 6AV6 for data SHARP-CUTOFF PENTODE 4BC5 Renewal type; see chart at end of section for tabulated data. MEDIUM-MU TWIN TRIODE Miniature type identical with type 4BC8 6BC8 except for heater ratings; refer to 6BC8 for data. MEDIUM-MU TRIODE SHARP-CUTOFF PENTODE **4BL8** Miniature type identical with type 6BL8 except for heater ratings; refer to 6BL8 for data. **BEAM TUBE** Miniature type identical with type **4BN6** 6BN6 except for heater ratings; refer to 6BN6 for data. MEDIUM-MU TWIN TRIODE Miniature type identical with type 4BQ7A 6BQ7A except for heater ratings; refer to 6BQ7A for data. MEDIUM-MU TWIN TRIODE

Miniature type identical with type

6BS8 except for heater ratings; refer to 6BS8 for data.

4BS8

|    | u .   |               |
|----|---|---------------|
|    | SHARP-CUTOFF TWIN PENTODE Miniature type identical with type 6BU8 except for heater ratings; refer to 6BU8 for data.  | 4BU8          |
|    | SEMIREMOTE-CUTOFF PENTODE  Miniature type identical with type 6BZ6 except for heater ratings; refer to 6BZ6 for data. | 4BZ6          |
| 4E | MEDIUM-MU TWIN TRIODE Miniature type identical with type 6BZ7 except for heater ratings; refer to 6BZ7 for data.      | 4B <b>Z</b> 7 |
| 40 | SHARP-CUTOFF PENTODE  Miniature type identical with type 6CB6A except for heater ratings; refer to 6CB6A for data.    | 4CB6          |
| 40 | PENTAGRID AMPLIFIER  Miniature type identical with type 6CS6 except for heater ratings; refer to 6CS6 for data.       | 4CS6          |
| 40 | SHARP-CUTOFF TETRODE  Miniature type identical with type 6CY5 except for heater ratings; refer to 6CY5 for data.      | 4CY5          |
| 40 | SHARP-CUTOFF PENTODE  Miniature type identical with type 6DE6 except for heater ratings; refer to 6DE6 for data.      | 4DE6          |
| 40 | SHARP-CUTOFF PENTODE Miniature type identical with type 6DK6 except for heater ratings; refer to 6DK6 for data.       | 4DK6          |
| 40 | SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.                               | 4DT6          |
| 4D | SHARP-CUTOFF PENTODE  Miniature type identical with type 6DT6A except for heater ratings; refer to 6DT6A for data.    | 4DT6A         |
|    | SEMIREMOTE-CUTOFF PENTODE  Miniature type identical with type 6EH7 except for heater ratings; refer to 6EH7 for data. | 4EH7          |
|    |   |               |

**4GS8** 

4**G**S8/

**4BU8** 

#### SHARP-CUTOFF PENTODE

Miniature type identical with type 6EJ7 except for heater ratings; refer to 6EJ7 for data.

#### **VARIABLE-MU TWIN TRIODE**

4ES8 Miniature type identical with type 6ES8 except for heater ratings; refer to 6ES8 for data.

#### SHARP-CUTOFF PENTODE

4EW6 Miniature type identical with type 6EW6 except for heater ratings; refer to 6EW6 for data.

#### HIGH-MU TRIODE

Miniature type identical with type 6GK5 except for heater ratings; refer to 6GK5 for data.

4GM6

SEMIREMOTE-CUTOFF PENTODE

Miniature type identical with type
6GM6 except for heater ratings; refer
to 6GM6 for data.

## SHARP-CUTOFF TWIN PENTODE

Renewal type; see chart at end of section for tabulated data.

SHARP-CUTOFF TWIN PENTODE
Renewal type; see chart at end of
of section for tabulated data.


#### POWER PENTODE

Miniature type identical with type 6GZ5 except for heater ratings; refer to 6GZ5 for data.

#### SHARP-CUTOFF PENTODE

AHM6

Miniature type with frame grid used in the if-amplifier stages of television receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be mounted



in any position. Heater volts (ac/dc), 4.2; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Class A<sub>1</sub> Amplifier

| MAXIMUM KATINGS (Design-Maximum values):              |                   |
|---|-------------------|
| Plate Voltage   | 250 max volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                | 250 max volts     |
| Grid-No.2 Voltage                                     | See curve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Negative-bias value | -50 max volts     |

| Cathode Current Plate Dissipation  | 25 max<br>2.5 max                 | ma<br>watts                            |
|--|-----------------------------------|--|
| Grid-No.2 Input:  For grid-No.2 voltages up to 125 volts  For grid-No.2 voltages between 125 and 250 volts   | 0.6 max<br>See curve              |  |
| CHARACTERISTICS: Plate Supply Voltage Grid No.3 (Suppressor Grid) Connected Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current | 125<br>56<br>0.156<br>15000<br>13 | volts<br>ohms<br>megohm<br>µmhos<br>ma |
| Grid-No.2 Current  | 3.2<br>—3                         | ma<br>volts                            |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circut Resistance: For fixed-bias operation For cathode-bias operation   | 0.25 max<br>1 max                 | megohm<br>megohm                       |

#### SHARP-CUTOFF TWIN PENTODE

Miniature type identical with type 6HS8 except for heater ratings; refer to 6HS8 for data.

**4HS8** 



#### SEMIREMOTE-CUTOFF PENTODE

Miniature type with frame grid used in the if-amplifier stages of television receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be mounted

**4HT6** 

in any position. Heater volts (ac/dc), 4.2; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage ..... 250 max volts Grid-No.2 (Screen-Grid) Supply Voltage ...... 250 max volts Grid-No.2 Voltage See curve page 75 Grid-No.1 (Control-Grid) Voltage, Negative-bias value ......... -50 max volts Cathode Current ..... 25 max ma 2.5 max Plate Dissipation watts Grid-No.2 Input: For grid-No.2 voltages up to 125 volts ...... 0.6 max For grid-No. 2 voltages between 125 and 250 volts ...... See curve page 75 CHARACTERISTICS: Grid-No.2 Supply Voltage ..... 125 volts Cathode-Bias Resistor ...... 56 ohms Plate Resistance (Approx.) ..... 0.143 megohm Transconductance ..... 14000 *u*mhos Plate Current ..... 15 ma Grid-No.2 Current ...... ma Grid-No.1 Voltage (Approx.) for transconductance of 100 µmhos .... volts

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

|     | nxed-bias operation    | 0.25 max | megohm |
|-----|------------------------|----------|--------|
| For | cathode-bias operation | 1 max    | megohm |

5AN8

#### SHARP-CUTOFF PENTODE

4JC6

Miniature type identical with type 6JC6 except for heater ratings; refer to 6JC6 for data.

#### SHARP-CUTOFF PENTODE

4JD6

Miniature type identical with type 6JD6 except for heater ratings; refer to 6JD6 for data.

#### DIODE—SHARP-CUTOFF PENTODE

5AM8

Miniature type identical with type 6AM8A except for heater ratings; refer to 6AM8A for data.

# MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE Miniature type identical with ty

Miniature type identical with type 6AN8A except for heater ratings; refer to 6AN8A for data.

#### **BEAM POWER TUBE**

Miniature type identical with type 6AQ5A except for heater ratings; refer to 6AQ5A for data.

5AS4

FULL-WAVE VACUUM RECTIFIER
Discontinued type; see chart at end
of section for tabulated data.

#### **FULL-WAVE VACUUM RECTIFIER**

Glass octal type used in power supply of television receivers having high do requirements. Outline 19D, Outlines section. This type may be supplied with pins 3, 5, and 7 omitted. Tube requires octal socket. Vertical mount-

PD2 NC NC 3 1 6 PD1 F2 7 NC NC F

ing is preferred, but horizontal mounting is permissible if pins 1 and 4 are in vertical plane. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater volts (ac), 5.0; amperes, 3.0. For maximum ratings, typical operation, and curves, refer to type 5U4GB.


#### DIODE—SHARP-CUTOFF PENTODE

Miniature type identical with type 6AS8 except for heater ratings; refer to 6AS8 for data.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6AT8A except for heater ratings; refer to 6AT8A for data.

#### **FULL-WAVE VACUUM RECTIFIER**



Glass octal type used as power supply in television receivers and other equipment having high dc requirements.


Outline 19G, Outlines section. Tube requires octal socket and must be used in vertical position; horizontal

**5AU4** 

operation is permissible only if pins 2 and 4 are in vertical plane. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Filament volts (ac/dc), 5; amperes, 3.75. For discussion of Rating Chart, refer to Interpretation of Tube Data.


#### **Full-Wave Rectifier**

| MAXIMUM RATINGS (Design-Center Values);  |           |         |
|--|-----------|---------|
| Peak Inverse Plate Voltage               | 1400 max  | volts   |
| Peak Plate Current (Per Plate)           | 1075 max  | ma      |
| Hot-Switching Transient Plate Current    |           |         |
| (Per Plate), maximum duration 0.2 second | 5.25 max  | amperes |
| AC Plate Supply Voltage (Per Plate, rms) | See Ratin | g Chart |
| DC Output Current (Per Plate)            | See Ratin |         |



#### TYPICAL OPERATION:

| TIFICAL OFERATION:                             |          |        |       |         |
|--|----------|--------|-------|---------|
| Filter Input                                   | Capa     | .citor | Choke |         |
| AC Plate-to-Plate Supply Voltage (rms)         | 600 `    | 800    | 1000  | volts   |
| Filter-Input Capacitor                         | 40       | 40     |       | μf      |
| Effective Plate Supply Impedance per Plate     | 30       | 50     | _     | ohms    |
| Filter-Input Choke                             | _        | _      | 10    | henries |
| DC Output Current                              | 350      | 325    | 325   | ma      |
| DC Output Voltage at Input to Filter (Approx.) | 275      | 395    | 395   | volts   |
| CHARACTERISTICS, Instantaneous Value:          |          |        |       |         |
| Tube Voltage Drop for plate current of 350 ma  | per plat | te)    | 50    | volts   |



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in a wide variety of applications in television receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

**5AV8** 

| Heater Voltage (ac/dc)                                  | <b>4.7</b><br>0.6 | volts<br>ampere |
|---|-------------------|-----------------|
| Heater Warm-Up Time (Average)                           | 11                | seconds         |
| Peak Heater-Cathode Voltage:                            |                   |                 |
| Heater negative with respect to cathode                 | 200 max           | volts           |
| Heater positive with respect to cathode                 | 200°max           | voits           |
| Direct Interelectrode Capacitances:                     |                   |                 |
| Triode Unit:  |                   |                 |
| Grid to Plate   | 1.5               | pf              |
| Grid to Cathode and Heater                              | 2                 | pf              |
| Plate to Cathode and Heater                             | 0.34              | pf              |
| Pentode Unit:   |                   | _               |
| Grid No.1 to Plate                                      | 0.04 max          | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and |                   | _               |
| Internal Shield   | 7                 | pf              |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and     |                   | •               |
| Internal Shield   | 3                 | pf              |
| Triode Grid to Pentode Plate                            | 0.005             | pf              |
| Pentode Grid No.1 to Triode Plate                       | 0.006             | pf              |
| Pentode Plate to Triode Plate                           | 0.045             | pf              |
|   |                   | P-              |

<sup>°</sup> The dc component must not exceed 100 volts.

#### Class A<sub>1</sub> Amplifier

| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Grid No.2 Supply Voltage | Triode Unit<br>300 max | Pentode Un<br>300 max<br>300 max | it<br>volts<br>volts |
|--|------------------------|----------------------------------|----------------------|
| Grid-No.2 (Screen-Grid) Voltage  | _                      |                                  | e page 75            |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value                          | 0 max                  | 0 max                            | volts                |
|  | 2.5 max                | 2 max                            | watts                |
| Plate Dissipation  | 2.5 max                | 2 Illax                          | watts                |
| Grid-No.2 Input:   |                        | 0.5                              |                      |
| For grid-No.2 voltages up to 150 volts   | _                      | 0.5 max                          | watt                 |
| For grid-No.2 voltages between 150 and 300 volts                               | _                      | See curv                         | e page 75            |
| CHARACTERISTICS:   |                        |                                  |                      |
| Plate Supply Voltage   | 200                    | 200                              | volts                |
| Grid-No.2 Supply Voltage   | _                      | 150                              | volts                |
| Grid-No.1 Voltage  | 6                      |                                  | volts                |
| Cathode-Bias Resistor  | _                      | 180                              | ohms                 |
| Amplification Factor   | 19                     | _                                | ohms                 |
| Plate Resistance (Approx.)   | 5750                   | 300000                           | ohms                 |
| Transconductance   | 3300                   | 6200                             | μmhos                |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu a$                    | -19                    | -8                               | volts                |
| Plate Current  | 13                     | 9.5                              | ma                   |
| Grid-No.2 Current  |                        | 2.8                              | ma                   |
| Grid-No.1-Circuit Resistance:*   |                        | 2.0                              |                      |
| For fixed-bias operation   | 0.5 max                | 0.25 max                         | megohm               |
| For cathode-bias operation   | 1.0 max                | 1.0 max                          |                      |
| For camoue-oras operation  | 1.0 Illax              | 1.0 Illax                        | megomm               |

<sup>\*</sup> If either unit is operating at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated values.

5AW4


#### **FULL-WAVE VACUUM RECTIFIER**

Discontinued type; see chart at end of section for tabulated data.

# 5AZ4

### **FULL-WAVE VACUUM RECTIFIER**

Renewal type; see chart at end of section for tabulated data.



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined vhf oscillator and mixer in television receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted

**5B8** 

in any position. Heater volts (ac/dc), 4.7; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Class A. Amplifier

| MAXIMUM RATINGS (Design-Center Values); Plate Voltage Grid No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid No.2 Input: | Triode Unit 300 max  0 max 2.5 max | 300 max<br>300 max  | volts<br>volts<br>ve page 75<br>volts                        |
|---|------------------------------------|---|--|
| For grid-No.2 voltages up to 150 volts  |                                    | 0.5 max   | watt   |
| For grid-No.2 voltages between 150 and 300 volts  |                                    |   | ve page 75   |
| CHARACTERISTICS: Plate Supply Voltage Grid-No.2 Supply Voltage Grid Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current      | 200<br>                            | 200<br>150<br>—<br>180<br>—<br>300000<br>6200<br>9.5<br>2.8 | volts<br>volts<br>volts<br>ohms<br>ohms<br>umhos<br>ma<br>ma |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ a   | -19                                | 8   | volts  |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance*:  | 0.5                                | 0.05  | ·  |
| For fixed-bias operation  | 0.5 max                            |   | megohm   |
| For cathode-bias operation  | 1.0 max                            | 1.0 max   | megohm   |

\* If either unit is operated at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated values.



#### **FULL-WAVE VACUUM RECTIFIER**

Novar types used in power supplies of radio equipment and television receivers having high dc requirements. Outlines 17C and 31C, respectively, Outlines section. Tubes require novar nine-contact socket. Vertical operation

5BC3 5BC3A


is preferred, but tubes may be operated in horizontal position if pins 2 and 7 are in vertical plane. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Filament volts (ac), 5; amperes, 3.

#### **Full-Wave Rectifier**

| MAXIMUM RATINGS (Design-Maximum Values):          |                  |
|---|------------------|
| Peak Inverse Plate Voltage                        | 1700 max volts   |
| Peak Plate Current (Per Plate)                    | 1 max ampere     |
| Hot-Switching Transient Plate Current (Per Plate) | 5 max amperes    |
| AC Plate-Supply Voltage (Per Plate, rms)          | See Rating Chart |
| DC Output Current (Per Plate)                     | See Rating Chart |

| TYPICAL OPERATION WITH CAPACITOR                |     |     |      |         |
|---|-----|-----|------|---------|
| INPUT TO FILTER:                                | 600 | 900 | 1100 | 14      |
| AC Plate-to-Plate Supply Voltage (rms)          |     |     | 1100 | volts   |
| Filter-Input Capacitor                          | 40  | 40  | 40   | μf      |
| Total Effective Plate-Supply Impedance per      |     |     |      |         |
| Plate   | 21  | 67  | 97   | ohms    |
| DC Output Voltage at Input to Filter            |     |     |      |         |
| (Approx.):                                      |     |     |      |         |
| At load current of: 300 ma                      | 290 |     |      | volts   |
| 275 ma  |     | 460 | _    | volts   |
| 162 ma  | _   | _   | 630  | volts   |
| 150 ma  | 335 |     |      | volts   |
| 137.5 ma  | 555 | 520 |      | volts   |
| 81 ma   | _   | 320 | 680  | volts   |
| 61 IIId   |     | _   | 000  | VOILS   |
| TYPICAL OPERATION WITH CHOKE INPUTO FILTER:     | T   |     |      |         |
| AC Plate-to-Plate Supply Voltage (rms)          |     | 900 | 1100 | volts   |
| Filter-Input Choke                              |     | 10  | 10   | henries |
| DC Output Voltage at Input to Filter (Approx.): |     |     |      |         |
| At load current of: 348 ma                      |     | 340 | _    | volts   |
| 275 ma  |     | 540 | 440  | volts   |
|   |     | 255 | 440  |         |
| 174 ma  |     | 355 |      | volts   |
| 137.5 ma  |     | _   | 455  | volts   |
|   |     |     |      |         |

<sup>•</sup> If hot switching is regularly required in operation, the use of choke-input circuits is recommended. Such circuits limit the hot-switching current to a value no higher than that of the peak plate current. When capacitor-input circuits are used, a maximum peak current value per plate of 5 amperes during the initial cycles of the hot-switching transient should not be exceeded.
• Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for peak plate current.



**5BE8** 

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

5BK7A

## MEDIUM-MU TWIN TRIODE

Miniature type identical with type 6BK7B except for heater ratings; refer to 6BK7B for data.

# 5BQ7A

#### MEDIUM-MU TWIN TRIODE Miniature type identical with type 6BQ7A except for heater ratings; refer

to 6BQ7A for data.

| MEDIUM-MU T  | RIODE   |
|--------------|---------|
| SHARP-CUTOFF | PENTODE |

Miniature type identical with type 6BR8A except for heater ratings; refer to 6BR8A for data.

5BR8

#### TWIN DIODE— SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

**5BT8** 

#### TWIN DIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6BW8 except for heater ratings; refer to 6BW8 for data.

**5BW8** 

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6CG8A except for heater ratings; refer to 6CG8A for data.

5CG8

#### MEDIUM-MU TRIODE— SHARP-CUTOFF TETRODE

Discontinued type; see chart at end of section for tabulated data.

5CL8

#### MEDIUM-MU TRIODE— SHARP-CUTOFF TETRODE

Miniature type identical with type 6CL8A except for heater ratings; refer to 6CL8A for data.

5CL8A

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6CM8 except for heater ratings; refer to 6CM8 for data.

**5CM8** 

#### MEDIUM-MU TRIODE— SHARP-CUTOFF TETRODE

Miniature type identical with type 6CQ8 except for heater ratings; refer to 6CQ8 for data.

5CQ8

#### **BEAM POWER TUBE**


Miniature type identical with type 6CZ5 except for heater ratings; refer to 6CZ5 for data.

**5CZ5** 

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

# **5DH8**

Miniature type used in television re- KT ceivers having series-connected heater G3P-IS 3 strings. Pentode used as video or audio if amplifier; triode used as sync amplifier, sync clipper, sync separator, or vertical oscillator. Out-



line 6B, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Heater volts (ac/dc), 5.2; amperes, 0.6; heater warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A | A, Am | nplifier |
|---------|-------|----------|
|---------|-------|----------|

| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation | Triode Unit 300 max 0 max 2.0 max | Pentode Un<br>300 max<br>300 max<br>See cur<br>0 max<br>2.2 max | volts<br>volts<br>ve page 75<br>volts |
|---|-----------------------------------|---|---------------------------------------|
| Grid-No.2 Input   |                                   | 0.55  | 44                                    |
| For grid-No.2 voltages up to 150 volts  | _                                 | 0.55 max  |                                       |
| For grid-No.2 voltages between 150 and 300 volts  | _                                 | See cur   | ve page 75                            |
| CHARACTERISTICS:  |                                   |   | •                                     |
| Plate Supply Voltage  | 250                               | 125   | volts                                 |
| Grid-No.2 Supply Voltage  | _                                 | 125   | volts                                 |
| Cathode-Bias Resistor   | 390                               | 56  | ohms                                  |
| Plate Current   | 7.3                               | 13.5  | ma                                    |
| Grid-No. 2 Current  |                                   | 3.8   | ma                                    |
| Amplification Factor  | 53                                | _   |                                       |
| Plate Resistance (Approx.)  | 0.012                             | 0.15  | megohm                                |
| Transconductance  | 4400                              | 8600  | μmhos                                 |
| For plate current of 10 µa  | -10                               |   | volts                                 |
| For plate current of 20 µa  | _                                 | 6   | volts                                 |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:   |                                   |   |                                       |
| For fixed-bias operation  | 0.5 max                           | 0.25 max  | megohm                                |
| For cathode-bias operation  | 1.0 max                           | 1.0 max   | megohm                                |
| Vartical Deflection Occi  | Hotor                             |   |                                       |

#### Vertical Deflection Oscillator

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): | Triode Unit |       |
|--|-------------|-------|
| DC Plate Voltage                         | 300 max     | volts |
| Peak Negative-Pulse Grid Voltage         | 400 max     | volts |
| Peak Cathode Current                     | 35 max      | ma    |
| Average Cathode Current                  | 12 max      | ma    |
| Plate Dissipation                        | 1 max       | watt  |

#### MAXIMUM CIRCUIT VALUES:

Grid Circuit Resistance:


For fixed-bias, cathode-bias, or grid-resistor-bias operation .....

2.2 max megohms

#### **FULL-WAVE VACUUM RECTIFIER**

**5DJ4** 


Glass octal type used in power supply of radio and television receivers having high dc requirements. Outline 19E, Outlines section. Tube requires octal socket; operation in vertical position is preferred, but horizontal oper-



ation is permissible if pins 2 and 4 are in vertical plane. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Filament volts (ac/dc), 5; amperes, 3.

#### Full-Wave Rectifier

| MAXIMUM RATINGS (Design-Maximum Values):               |          |           |
|--|----------|-----------|
| Peak Inverse Plate Voltage                             | 1700 max |           |
| Peak Plate Current (Per Plate)                         |          | ampere    |
| Hot-Switching Transient Plate Current (Per Plate)      |          | amperes   |
| AC Plate-Supply Voltage (Per Plate, rms, without load) |          | ing Chart |
| DC Output Current (Per Plate)                          | See Rat  | ing Chart |



#### TYPICAL OPERATION: Choke Capacitor Filter Input AC Plate-to-Plate Supply Voltage (rms, without 1100 volts 900 600 цf Filter-Input Capacitor\* 40 40 10 henries Filter-Input Choke Filter-Input Choke ...... Effective Plate-Supply Impedance per Plate ... 21 67 ohms 420 DC Output Voltage at Input to Filter (Approx.) 290 460 volts

• When capacitor values greater than 40 µf are used, the effective plate-supply impedance should be increased so that the maximum rating for peak plate current is not exceeded.

300

DC Output Current .....

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6EA8 except for heater ratings; refer to 6EA8 for data.

**5EA8** 

275

ma

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6EU8 except for heater ratings; refer to 6EU8 for data.

**5EU8** 

#### SHARP-CUTOFF PENTODE

Miniature type identical with type 6EW6 except for heater ratings; refer to 6EW6 for data.

**5EW6** 

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE **5FG7** Miniature type identical with type 6FG7 except for heater ratings; refer to 6FG7 for data. MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE **5FV8** Miniature type identical with type 6FV8 except for heater ratings; refer to 6FV8 for data. MEDIUM-MU TRIODE... SHARP-CUTOFF PENTODE **5GH8** Miniature type identical with type 6GH8A except for heater ratings; refer to 6GH8A for data, SEMIREMOTE-CUTOFF PENTODE Miniature type identical with type **5GM6** 6GM6 except for heater ratings; refer to 6GM6 for data. SHARP-CUTOFF PENTODE Miniature type identical with type **5GX6** 6GX6 except for heater ratings; refer to 6GX6 for data. MEDIUM-MU TWIN TRIODE Miniature type identical with type 5.16 6J6A except for heater ratings; refer to 6J6A for data. MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE 5KE8 Miniature type identical with type 6KE8 except for heater ratings; refer to 6KE8 for data. FULL-WAVE VACUUM RECTIFIER Renewal type; see chart at end of **5T4** section for tabulated data.

#### TRIPLE DIODE— HIGH-MU TRIODE

Miniature type identical with type 6T8A except for heater ratings; refer to 6T8A for data.

# 5U4G FULL-WAVE VACUUM RECTIFIER Renewal type; see chart at end of section for tabulated data.

**5T8** 

#### **FULL-WAVE VACUUM RECTIFIER**




Glass octal type used in power supplies of radio and television receivers having high dc requirements. Outline 19E, Outlines section. Tube requires octal socket. This type may be supplied with pins 3, 5, and 7 omitted.

# **5U4GB**

Vertical mounting is preferred but horizontal mounting is permissible if pins 1 and 4 are in vertical plane. The coated filament is designed to operate from the ac line through a step-down transformer. The voltage at the filament terminals should be 5.0 volts at an average line voltage of 117 volts. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. For discussion of Rating Chart and Operation Characteristics, refer to Interpretation of Tube Data. Filament volts (ac), 5; amperes, 3.

#### **Full-Wave Rectifier**

| Luit-Mase vectilies                               |          |          |
|---|----------|----------|
| MAXIMUM RATINGS (Design-Center Values):           |          |          |
| Peak Inverse Plate Voltage                        | 1550 max | volts    |
| Peak Plate Current (Per Plate)                    | 1.0 max  | ampere   |
| Hot-Switching Transient Plate Current (Per Plate) | #        | •        |
| AC Plate Supply Voltage (Per Plate, rms)          | See Rati | ng Chart |
| DC Output Current (Per Plate)                     | See Rati | ng Chart |



# TYPICAL OPERATION WITH CAPACITOR


| THUL TO PILLER:             |                         |     |     |      |       |
|-----------------------------|-------------------------|-----|-----|------|-------|
| AC Plate-to-Plate Supply    | Voltage (rms)           | 600 | 900 | 1100 | volts |
| Filter-Input Capacitor*     |                         | 40  | 40  | 40   | μf    |
| Total Effective Plate-Suppl | y Impedance per Plate   | 21  | 67  | 97   | ohms  |
| DC Output Voltage at Inp    | ut to Filter (Approx.); |     |     |      |       |
|                             | ( 150 ma                | 335 |     |      | volts |
| At half-load current of     | 137.5 ma                | _   | 520 | _    | volts |
|                             | ( 81 ma                 | _   | _   | 680  | volts |
|                             | ( 300 ma                | 290 |     | _    | volts |
| At full-load current of     | { 275 ma                | _   | 460 | _    | volts |
|                             | ( 162 ma                | _   | _   | 630  | volts |
| Voltage Regulation (Appr    |                         |     |     |      |       |
| Half-load to full-load      | current                 | 45  | 60  | 50   | volts |


<sup>#</sup> If hot switching is regularly required in operation, the use of choke-input circuits is recommended. Such circuits limit the hot-switching current to a value no higher than that of the peak plate current. When capacitor-input circuits are used, a maximum peak current value per plate of 4.6 amperes during the initial cycles of the hot-switching transient should not be exceeded.

<sup>\*</sup> Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for peak plate current.

### TYPICAL OPERATION WITH CHOKE INPUT

| AC Plate-to-Plate Supply Voltage (rms)                       | 900 | 1100 | volts          |
|--|-----|------|----------------|
|  | 10  | 10   | henries        |
| At half-load current of { 174 ma                             | 355 | 455  | volts<br>volts |
| At full-load current of { 348 ma                             | 340 | _    | volts          |
|  | —   | 440  | volts          |
| Voltage Regulation (Approx.): Half-load to full-load current | 15  | 15   | volts          |





**5U8** 

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6U8A except for heater ratings; refer to 6U8A for data.

#### **FULL-WAVE VACUUM RECTIFIER**


**5V3** 

Discontinued type; see chart at end of section for tabulated data.

#### **FULL-WAVE VACUUM RECTIFIER**

5V3A

Glass octal type used as power supply in color television receivers and other equipment having high dc requirements. Outline 19E, Outlines section. Tube requires octal socket. Vertical mounting is preferred, but horizontal



mounting is permissible if pins 2 and 4 are in vertical plane. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. For discussion of Rating Chart, refer to Interpretation of Tube Data. Filament volts (ac/dc), 5; amperes, 3.

#### Full-Wave Rectifier

| MAXIMUM RATINGS (Design-Maximum Values):               |          |         |
|--|----------|---------|
| Peak Inverse Plate Voltage                             | 1550 max | volts   |
| Peak Plate Current (Per Plate)                         | 1.4 max  | amperes |
| Hot-Switching Transient Plate Current (Per Plate)      | 6.6 max  |         |
| AC Plate-Supply Voltage (Per Plate, rms, without load) | 550 max  |         |
| DC Output Current (Per Plate)                          | 415°max  | ma      |

• With capacitor-input filter for ac plate-supply volts (rms, per plate, without load) = 470.


#### TYPICAL OPERATION:

| Filter Input                               | Capacitor | Choke |         |
|--|-----------|-------|---------|
| AC Plate-to-Plate Supply Voltage (rms)     | 850       | 1000  | volts   |
| Filter-Input Capacitor                     | 40        |       | μf      |
| Effective Plate-Supply Impedance per Plate | 50        | _     | ohms    |
| Minimum Filter-Input Choke                 | _         | 10    | henries |
| DC Output Current                          | 350       | 350   | ma      |
| DC Output at Input to Filter (Approx.)     | 440       | 390   | volts   |
|  |           |       |         |

#### CHARACTERISTICS:

Tube Voltage Drop for plate current of 350 ma (per plate) ....... 42 volts

■ When capacitor values greater than 40 µf are used, the effective plate-supply impedance should be increased so that the maximum rating for peak plate current is not exceeded.





#### **FULL-WAVE VACUUM RECTIFIER**

Glass octal types used in full-wave power supplies having high dc requirements. Outlines 25 and 19B, respectively, Outlines section. Tubes require octal socket and may be mounted in any position. The heater is designed

5V4G 5V4GA

volts

to operate from the ac line through a step-down transformer. The voltage at the heater terminals should be 5.0 volts under operating conditions at an average line voltage of 117 volts. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 5; amperes, 2.

#### Full-Wave Rectifier

AC Plate-Supply Voltage (Per Plate, rms):

DC Output Voltage at Input to Filter (Approx.) for dc output current of 175 ma ......


410

volts

410

| with capacitor-input inter                       |           | 3/3 max | voits   |
|--|-----------|---------|---------|
| With choke-input filter                          |           | 500 max | volts   |
| Peak Plate Current (Per Plate)                   |           | 525 max | ma      |
| DC Output Current                                |           | 175 max | ma      |
| TYPICAL OPERATION:                               |           |         |         |
| Filter Input                                     | Capacitor | Choke   |         |
| AC Plate-to-Plate Supply Voltage (rms)           | 750       | 1000    | volts   |
| Filter-Input Capacitor*                          | 10        | _       | μf      |
| Total Effective Plate-Supply Impedance per Plate | 100       | _       | ohms    |
| Filter-Input Choke                               | -         | 4       | henries |

<sup>\*</sup> Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for peak plate current.



#### **BEAM POWER TUBE**

5V6GT

Glass octal type identical with type 6V6GTA except for heater ratings; refer to 6V6GTA for data.

5W4 5W4GT

#### **FULL-WAVE VACUUM RECTIFIER**

Discontinued types; see chart at end of section for tabulated data.

**5X4G** 

#### **FULL-WAVE VACUUM RECTIFIER**

Renewal type; see chart at end of section for tabulated data.

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6X8 except for heater ratings; refer to 6X8 for data.

#### FULL-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

**5Y3G** 



#### **FULL-WAVE VACUUM RECTIFIER**


Glass octal type used in power supply of radio equipment having moderate dc requirements. Outline 13E, Outlines section. Tube requires octal socket. Vertical mounting is preferred, but horizontal mounting is permis-

**5Y3GT** 

sible if pins 2 and 8 are in horizontal plane. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. For discussion of Rating Chart and Operating Characteristics, refer to Interpretation of Tube Data. Filament volts (ac), 5; amperes, 2.

#### Full-Wave Rectifier

| MAXIMUM RATINGS (Design-Center Values):           |                  |
|---|------------------|
| Peak Inverse Plate Voltage                        | 1400 max volts   |
| Peak Plate Current (Per Plate)                    | 440 max ma       |
| Hot-Switching Transient Plate Current (Per Plate) | 2.5 max amperes  |
| AC Plate Supply Voltage (Per Plate, rms)          | See Rating Chart |
| DC Output Current (Per Plate)                     | See Rating Chart |



#### TYPICAL OPERATION WITH CAPACITOR INPUT TO FILTER:


| AC Plate-to-Plate Supply Voltage (rms)                      | 700 | 1000 | volts |
|---|-----|------|-------|
| Filter Input Capacitor*                                     | 20  | 10   | μf    |
| Effective Plate-Supply Impedance per Plate                  | 50  | 140  | ohms  |
| DC Output Voltage at Input to Filter (Approx.):             |     |      |       |
| At half-load current of \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | 390 | _    | volts |
| At nan-load current of { 42 ma                              | -   | 610  | volts |
| At full-load current of 125 ma                              | 360 | -    | volts |
| ( 04 IIIa   |     | 560  | volts |
| Voltage Regulation (Approx.):                               |     |      |       |
| Half-load to full-load current                              | 40  | 50   | volts |
| TYPICAL OPERATION WITH CHOKE                                |     |      |       |


| AC Plate-to-Plate Supply Voltage (rms) Filter Input Choke#                      | 700 | 1000 | volts          |
|---|-----|------|----------------|
|   | 10  | 10   | henries        |
| DC Output Voltage at Input to Filter (Approx.): At half-load current of { 75 ma | 270 | 405  | volts<br>volts |

| At full-load current of { 150 ma | 245<br>— | 380 | volts<br>volts |
|----------------------------------|----------|-----|----------------|
| current                          | 25       | 15  | volts          |

<sup>\*</sup> Higher values of capacitance than indicated may be used but the effective plate supply impedance may have to be increased to prevent exceeding the maximum rating for hot-switching transient plate current.

<sup>#</sup> This value is adequate to maintain optimum regulation in the region to the right of line L = 10H on curve OPERATION CHARACTERISTICS with Choke Input to Filter, provided the load currents are not less than 35 ma., and 50 ma., respectively, for Plate-to-Plate supply voltages of 700 and 1000 volts (rms).





#### FULL-WAVE VACUUM RECTIFIER


**5Y4G** 

Discontinued type; see chart at end of section for tabulated data.

#### FULL-WAVE VACUUM RECTIFIER

5Y4GA 5Y4GT

Glass octal types used in power supplies of radio equipment having moderate dc requirements. Outlines 19E and 13E, respectively, Outlines section. Tubes require octal socket. Type 5Y4GT is supplied with pins 4 and 6




missing. Vertical tube mounting is preferred, but horizontal mounting is permissible: if pins 1 and 4 are in vertical plane (5Y4GA); if pins 2 and 3 are in vertical plane (5Y4GT). It is especially important that these tubes, like other power handling tubes, be adequately ventilated. For discussion of Rating Chart, refer to Interpretation of Tube Data. Filament volts (ac/dc), 5: amperes, 2.

#### **Full-Wave Rectifier**

|           | 400<br>2.2          | max volts<br>max ma<br>max amperes               |
|-----------|---------------------|--|
|           |                     | Rating Chart<br>Rating Chart                     |
|           |                     |  |
| Capacitor | Choke               |  |
| 700       | 1000                | volts  |
| 10        | _                   | μf   |
|           | _                   | ohms   |
| _         | 10                  | henries  |
| 125       |                     | ma   |
|           |                     |  |
| 330       | 390                 | volts  |
|           |                     |  |
| e)        | 60                  | volts  |
|           | Capacitor 700 10 50 | Capacitor Choke 700 1000 10 - 10 125 125 350 390 |

Values of capacitance greater than 20 µf may be used, provided the plate-supply impedance is increased to prevent exceeding the maximum peak-plate-current rating.



#### **FULL-WAVE VACUUM RECTIFIER**

Renewal type; see chart at end of section for tabulated data.

5**Z**3



#### **FULL-WAVE VACUUM RECTIFIER**

Metal type used in power supply of radio equipment having moderate do requirements. Outline 2B, Outlines section. Tube requires octal socket and may be mounted in any position. Heater volts (ac), 5.0; amperes, 2.0.

**5Z4** 

Maximum ratings: peak inverse plate volts, 1400 max; peak plate ma. per plate, 375 max. Typical operation as full-wave rectifier with capacitor-input filter: ac plate-to-plate supply volts (rms), 700; total effective plate-supply impedance per plate, 50 ohms; dc output ma., 125. Typical operation with choke-input filter: ac plate-to-plate supply volts, 1000; minimum filter-input choke, 5 henries; dc output ma., 125.

6**A**3

**POWER TRIODE** 

Discontinued type; see chart at end of section for tabulated data.

**6A6** 

HIGH-MU TWIN POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

6Δ7

PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

**6A7S** 

PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

**6A**8

PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

6A8G 6A8GT PENTAGRID CONVERTER

Discontinued types; see chart at end of section for tabulated data.

#### HIGH-MU TRIODE

**6AB4** 

Miniature type used as cathode-drive amplifier, frequency converter, or oscillator at frequencies up to about 300 megacycles per second, particularly in television and FM receivers. Outline 5C, Outlines section. Tube re-



quires miniature seven-contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.15. For maximum ratings, characteristics, and curves, refer to type 12AT7.

**ELECTRON-RAY TUBE** 

6AB5/6N5 Renewal type; see chart at end of section for tabulated data.

**6AB7** 

SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6AC5GT

HIGH-MU POWER TRIODE

Renewal type; see chart at end of section for tabulated data.

6AC7

SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6AD6G

**ELECTRON-RAY TUBE** 

Discontinued type; see chart at end of section for tabulated data.

#### LOW-MU TRIODE— POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

6AD7G

#### LOW-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

6AE5GT

## TWIN-PLATE CONTROL TUBE

Discontinued type; see chart at end of section for tabulated data.

6AE6G

#### TWIN-INPUT TRIODE

Discontinued type; see chart at end of section for tabulated data.

6AE7GT



#### HALF-WAVE VACUUM RECTIFIER

Miniature type used as a damper tube in horizontal deflection circuits of television receivers. Outline 7C, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Socket ter-

6AF3
Related type: 12AF3

minals 1, 2, 3, 6, 7, and 8 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Type 12AF3 is identical with type 6AF3 except for heater ratings, as shown below.

| Heater Voltage (ac/dc) | 6AF3<br>6.3<br>1.2 | 12AF3<br>12,6<br>0.6<br>11 | volts<br>amperes<br>seconds |
|------------------------|--------------------|----------------------------|-----------------------------|
| Damper Service         |                    |                            |                             |

| Dampor Corrico                               |          |       |
|--|----------|-------|
| For operation in a 525-line, 30-frame system |          |       |
| MAXIMUM RATINGS (Design-Maximum Values):     |          |       |
| Peak Inverse Plate Voltage†                  | 4500 max | volts |
| Peak Plate Current                           | 750 max  | ma    |
| Average Plate Current                        | 185 max  | ma    |
| Bulb Temperature (At hottest point)          | 210 max  | *C    |
| Peak Heater-Cathode Voltage:                 |          |       |
| Heater negative with respect to cathode      | 4500 max | volts |
| Heater positive with respect to cathode      | 300₄max  | volts |

- † The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 1000 volts.
- A The dc component must not exceed 100 volts.



#### MEDIUM-MU TRIODE

Miniature types used as local oscillators in uhf television receivers covering the frequency range of 470 to 890 megacycles per second. Outlines 5C and 5B, respectively, **Outlines** section. Tubes require miniature seven-

6AF4 6AF4A

Related types: 2AF4B, 3AF4A

contact socket and may be mounted in any position. Types 2AF4B and 3AF4A

24544

6AF4

are identical with type 6AF4A except for heater and heater-cathode ratings, as shown below.

2 A E 4 D

|  | AF4B              | 3AF4A      | 6AF4A  |         |
|--|-------------------|------------|--------|---------|
| Heater Voltage (ac/dc)   | 2.35              | 3.15       | 6.3    | volts   |
| Heater Current   | 0.6               | 0.45       | 0.225  | ampere  |
| Heater Warm-up Time (Average)  | 11                | 11         | ~      | seconds |
| Peak Heater-Cathode Voltage:   |                   |            |        |         |
| Heater negative with respect to cathode  | 180               | 50         | 50 max | volts   |
| Heater positive with respect to cathode  | 180=              | 50≥        | 50△max | volts   |
| Direct Interelectrode Capacitances:  |                   |            |        |         |
| Grid to Plate  |                   |            | 1.9    | pf      |
| Grid to Cathode and Heater   |                   |            | 2.2    | pf      |
| Plate to Cathode and Heater  |                   |            | 1.4    | pf      |
| Heater to Cathode*   |                   |            | 2.2    | pf      |
| <ul> <li>The dc component must not exceed 100 volts.</li> <li>∆ The dc component must not exceed 25 volts.</li> <li>♦ With external shield connected to cathode, ex</li> <li>♦ With external shield connected to plate.</li> </ul> | cept as 1         | noted.     |        |         |
| Class A, A   | mplifie           | r          |        |         |
| CHARACTERISTICS:   | •                 |            |        |         |
| Plate Supply Voltage   | . <b></b> .       | . <b>.</b> | 80     | volts   |
| Cathode-Bias Resistor  | • • • • • • • • • |            | 150    | ohms    |
| Amplification Factor   |                   |            | 13.5   |         |
| Plate Resistance (Approx.)   | . <b></b>         |            | 2100   | ohms    |
| Transconductance   |                   |            | 6500   | μmhos   |
| Plate Current  | · • • • • • • •   |            | 17.5   | ma      |
| UHF Osc  | illator           |            |        |         |


|              |         | Uni             | . Oscillati |
|--------------|---------|-----------------|-------------|
| MAXIMUM      | RATINGS | (Design-Maximum | Values):    |
| Plate Voltag |         |                 |             |

| Plate Voltage                               | 150 max  | volts |
|---|----------|-------|
| Grid Voltage, Negative-bias value           | -50 max  | volts |
| C-11 Course                                 | -JO HIAX |       |
| Grid Current                                | 2 max    | ma    |
| Plate Dissipation                           | 2.5 max  | watts |
| DC Cathode Current                          | 24 max   | ma    |
| TYPICAL OPERATION AS OSCILLATOR AT 1000 MC: |          |       |
| Plate Supply Voltage                        |          | volts |
| Plate Resistor                              | 220      | ohms  |
| Grid Resistor                               | 10000    | ohms  |
| Plate Current                               | 17       | ma    |
| Grid Current (Approx.)                      | 750      | 49    |

#### MAXIMUM CIRCUIT VALUES:

Grid-Circuit Resistance:

For fixed-bias operation Not recommended For cathode-bias operation 0.5 max megohm




#### **ELECTRON-RAY TUBE**

Glass octal type used to indicate visually, by means of two shadows on the fluorescent target, the effects of changes in the controlling voltages. It is a twin-indicator type and is used as a convenient means of indicating

6AF6G

accurate radio-receiver tuning. This type may be supplied with pin No.1 omitted. Tube requires octal socket. Heater volts (ac/dc), 6.3; amperes, 0.15. Maximum ratings in indicator service; fluorescent-target volts, 250 max, 125 min; ray-controlelectrode supply volts, 250 max; peak heater-cathode volts, 90 max. Typical operation: fluorescent-target volts, 250; fluorescent-target ma., 3.75; ray-contact-electrode volts (approx. for 0° shadow angle), 155; ray-control-electrode volts (approx. for 100° shadow angle), 0.



of 100 μa ......

Heater Voltage (ac/dc) .....

#### **DUAL TRIODE**— SHARP-CUTOFF PENTODE

Duodecar type used in a variety of applications in television receivers. The high-mu triode unit is used for agc keyer service, the medium-mu triode unit for sync separator service, and the pentode unit for video am-

Related type: 15AF11

15AF11

14.7

volts

volts

plifier service. Outline 8C, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Type 15AF11 is identical with type 6AF11 except for heater ratings, as shown below.

6AF11

6.3

-6.5

-10

| Heater Voltage (ac/uc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode |                      | 1.05<br><br>200 max<br>200•max | 0.45<br>11<br>200 max<br>200•max | amperes<br>seconds<br>volts |
|--|----------------------|--------------------------------|----------------------------------|-----------------------------|
| • The dc component must not exceed 100 volts.  |                      |                                |                                  |                             |
| Class A <sub>1</sub>   | Amplifier            |                                |                                  |                             |
|  | Triode<br>Unit No. 1 | Triode<br>Unit No. 2           | Pentode<br>Unit                  |                             |
| Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-   | 330 max              | 330 max                        | 330 max<br>330 max<br>See curve  | volts<br>volts<br>page 75   |
| bias value Plate Dissipation Grid-No.2 Input:  | 0 max<br>1.1 max     |                                | 0 max<br>5 max                   | volts<br>watts              |
| For grid-No.2 voltages up to 165 volts<br>For grid-No.2 voltages between 165 and 330<br>volts  | -                    | _                              | 1.25 max<br>See curve            | watts<br>page 75            |
| CHARACTERISTICS: Plate Supply Voltage  | 200                  | 200                            | 250                              | volts                       |
| Grid-No.2 Supply Voltage Grid-No.1 Voltage   |                      | =                              | 150                              | volts                       |
| Cathode-Bias Resistor Amplification Factor   | <del>-</del>         | 220<br>41                      | 100                              | ohms                        |
| Plate Resistance (Approx.)  Transconductance   | 12400<br>5500        | 9400<br>4400                   | 68000<br>11000                   | ohms<br>µmhos               |
| Plate Current  | <del>7</del>         | 9.2                            | 24<br>4.8                        | ma<br>ma                    |
|  |                      |                                |                                  |                             |

MAXIMUM CIRCUIT VALUES:
Grid-No.1-Circuit Resistance:
For fixed-bias operation ......

For cathode-bias operation ......

Unit No.1 Unit No.2

0.5 max 0.5 max
1 max 1 max

Triode

Triode

Unit


0.25 max megohm
1 max megohm

Pentode

#### SHARP-CUTOFF PENTODE

**6AG5** 

Miniature type used in compact radio equipment as an rf or if amplifier up to 400 megacycles per second. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.



Except for slightly different characteristics, this type is similar electrically to miniature type 6BC5. Heater volts (ac/dc), 6.3; amperes, 0.3. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

#### POWER PENTODE

6AG7

Metal type used in output stage of video amplifier of television receivers. Outline 2B, Outlines section. Tube requires octal socket. Heater volts (ac/dc), 6.3; amperes, 0.65. Typical operation as class A<sub>1</sub> amplifier: plate



volts, 300 max; grid No.3 connected to cathode at socket; grid-No.2 volts, 150 (300 max); grid-No.1 volts, -3 (0 max); peak af grid-No.1 volts, 3; plate ma., 30 (zero signal), 30.5 (maximum signal); grid-No.2 ma., 7 (zero signal); 9 (maximum signal); plate resistance (approx.), 0.13 megohm; transconductance, 11000  $\mu$ mhos; load resistance, 10000 ohms; maximum-signal power output, 3 watts; plate dissipation, 9 max watts; grid-No.2 input, 1.5 max watts.

#### TWIN DIODE—TWIN TRIODE

**6AG11** 

MAXIMUM RATINGS (Design-Maximum Values):

Plate Current .....

Duodecar type containing two diodes and two high-mu triodes, used primarily in FM stereo multiplex service. Outline 8A, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any



5 max

position. Heater volts (ac/dc), 6.3; amperes, 0.75; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A. Amplifier (Each Triode Unit)                  |            |       |
|--|------------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):               |            |       |
| Plate Voltage  | 330 max    | volts |
| Plate Dissipation                                      | 2 max      | watts |
| CHARACTERISTICS:                                       |            |       |
| Plate Voltage  | 125        | volts |
| Grid Voltage   | -1         | volt  |
| Amplification Factor                                   | 66         |       |
| Plate Resistance (Approx.)                             | 8500       | ohms  |
| Transconductance                                       | 7800       | μmhos |
| Plate Current  | 7.5        | ma    |
| Grid Voltage (Approx.) for plate current of 30 $\mu$ a | <b>-</b> 5 | volts |
| Diode Units (Each Unit)                                |            |       |

CHARACTERISTICS. Instantaneous Value: Tube Voltage Drop for plate current of 18 ma .....

5

volts

#### LOW-MU TRIODE

Renewal type; see chart at end of 6AH4GT section for tabulated data.

#### SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

**6AH6** 

#### SHARP-CUTOFF PENTODE



Miniature type used as an rf or if amplifier especially in high-frequency wide-band applications. It is useful as an amplifier at frequencies up to 400 megacycles per second. Outline 5B, Outlines section. Tube requires min-

**6AK**5

iature seven-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc)                              | 6.3<br>0.175 | volts<br>ampere |
|---|--------------|-----------------|
| Heater negative with respect to cathode             | 90 max       | volts           |
| Heater positive with respect to cathode             | 90 max       | volts           |
| Direct Interelectrode Capacitances (Approx.):       |              |                 |
| Grid No.1 to Plate                                  | 0.02 max     | pf              |
| Internal Shield                                     | 4.0          | pf              |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and |              |                 |
| Internal Shield                                     | 2.8          | pf              |
| Internal Shield                                     | 2.8          | pf              |

With external shield connected to pins 2 or 7.

| Class A <sub>1</sub> Amplifier                  |      |           |         |
|---|------|-----------|---------|
| MAXIMUM RATINGS (Design-Center Values):         |      |           |         |
| Plate Voltage                                   |      | 180 max   | volts   |
| Grid-No.2 (Screen-Grid) Voltage                 |      |           | page 75 |
| Grid-No.2 Supply Voltage                        |      | 180 max   |         |
| Grid-No.1 Voltage, Positive-bias value          |      | 0 max     |         |
| Plate Dissipation                               |      | 1.7 max   |         |
| Grid-No.2 Input:                                |      | 217 21121 | ,, 4,10 |
| For grid-No.2 voltages up to 90 volts           |      | 0.5 max   | watt    |
| For grid-No.2 voltages between 90 and 180 volts |      | See curve |         |
| Cathode Current                                 |      | 18 max    | ma ma   |
| Cambao Cartelle                                 |      | 10 max    | 1114    |
| CHARACTERISTICS:                                |      |           |         |
| Plate Supply Voltage                            | 120  | 180       | volts   |
| Grid-No.2 Supply Voltage                        | 120  | 120       | volts   |
| Cathode-Bias Resistor                           | 180  | 180       | ohms    |
| Plate Resistance (Approx.)                      | 0.3  | 0.5       | megohm  |
|   | 5000 | 5100      | umhos   |
|   | -8.5 | -8.5      | volts   |
| Plate Current                                   | 7.5  | 7.7       | ma      |
| Grid-No.2 Current                               | 2.5  | 2.4       | ma      |



#### HALF-WAVE VACUUM RECTIFIER

Miniature type used as damper tube in horizontal-deflection circuits of television receivers. Outline 7D, Outlines section. Tube requires miniature ninecontact socket and may be mounted in any position. Socket terminals 1,

6AL3

2, 3, 6, 7, and 8 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 6.3; amperes, 1.55.

Damper Service


| For operation in 525-line, 30-frame system    |          |       |
|---|----------|-------|
| MAXIMUM RATINGS (Design-Center Values):       |          |       |
| Peak Inverse Plate Voltage (Absolute maximum) | 7500°max | volts |
| Peak Plate Current                            | 550 max  | ma    |
| DC Plate Current                              | 220 max  | ma    |
| Plate Dissipation                             | 5 max    | watts |
| Peak Heater-Cathode Voltage                   | 6600 max | volts |

Onder no circumstances should this absolute value be exceeded.

#### TWIN DIODE


6AL5
Related types: 3AL5, 12AL5

Miniature, high-perveance type used as detector in FM and television circuits. It is especially useful as a ratio detector in ac-operated FM receivers. Each diode section can be used independently of the other, or the two



sections can be combined in parallel or full-wave arrangement. Resonant frequency of each unit is approximately 700 megacycles per second. Outline 5B, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 3AL5 and 12AL5 are identical with type 6AL5 except for heater ratings, as shown below.

| Heater Voltage (ac/dc)   | 0.6                | 6AL5<br>6.3<br>0.3 | 12AL5<br>12.6<br>0.15 | volts<br>ampere<br>seconds |
|--|--------------------|--------------------|-----------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 330 max<br>330 max |                    | 330 max<br>330 max    | volts<br>volts             |



<sup>■</sup> The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

| 2.5<br>2.5<br>3.4<br>3.4 | pf<br>pf<br>pf<br>pf           |
|--------------------------|--------------------------------|
| 0.068 max                | pf                             |
|                          |                                |
|                          |                                |
| 330 max                  | volts                          |
| 54 max                   | ma                             |
| 9 max                    | ma                             |
| 445                      |                                |
|                          | volts                          |
|                          | ohms                           |
| 9                        | ma                             |
|                          | 2.5<br>3.4<br>3.4<br>0.068 max |

#### **ELECTRON-RAY TUBE**

Renewal type; see chart at end of 6AL7GT section for tabulated data.




Plate Resistance (Approx.)

Load Resistance ......
Total Harmonic Distortion

Transconductance

#### **BEAM POWER TUBE—** SHARP-CUTOFF PENTODE

Duodecar type used as FM detector and audio-frequency output amplifier <sup>62</sup>B in television receivers. Outline 8B, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Types

# **6AL11**

Related types: 10AL11, 12AL11

0.1

megohm

umhos.

ohms per cent

watts

10AL11 and 12AL11 are identical with type 6AL11 except for heater ratings,

| as shown below.  |  |  |  |
|--|--|--|--|
| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode   | 6AL11<br>6.3<br>0.9<br>—<br>200 max<br>200 max | 12AL11<br>12.6<br>0.45<br>11<br>200 max<br>200*max | volts<br>ampere<br>seconds<br>volts<br>volts       |
| • The dc component must not exceed 100 volts.  |  |  |  |
| Beam Power Unit as MAXIMUM RATINGS (Design-Maximum Value Plate Voltage Grid-No.2 (Screen-Grid) Voltage Plate Dissipation Grid-No.2 Input   | s):  | <br>275 max<br>275 max<br>10 max<br>2 max          | volts<br>volts<br>watts<br>watts                   |
| TYPICAL OPERATION: Plate Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage Peak AF Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current |  | 250<br>250<br>8<br>8<br>35<br>39<br>2.5            | volts<br>volts<br>volts<br>volts<br>ma<br>ma<br>ma |

Maximum-Signal Power Output .....

| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation | 0.25 max<br>0.5 max | megohm<br>megohm |
|---|---------------------|------------------|
| Pentode Unit as Class A, Amplifier  |                     |                  |
| CHARACTERISTICS:  |                     |                  |
| Plate Supply Voltage  | 150                 | volts            |
| Grid-No.3 (Suppressor-Grid) Voltage   | 0                   | volts            |
| Grid-No.2 (Screen-Grid) Supply Voltage  | 100                 | volts            |
| Cathode-Bias Resistor   | 560                 | ohms             |
| Plate Resistance (Approx.)  | 0.15                | megohm           |
| Transconductance, Grid No.1 to Plate  | 1000                | $\mu$ mhos       |
| Transconductance, Grid No.3 to Plate  | 400                 | $\mu$ mhos       |
| Plate Current   | 1.3                 | ma               |
| Grid-No.2 Current   | 2.1                 | ma               |
| Grid-No.1 Voltage (Approx.) for plate current of 30 μa  | -4.5                | volts            |
| Grid-No.3 Voltage (Approx.) for plate current of 50 μa  | -4.5                | volts            |
| Pentode Unit as FM Detector   |                     |                  |
| MAXIMUM RATINGS (Design-Maximum Values):  |                     |                  |
| Plate Voltage   | 330 max             | volts            |
| Grid-No.3 Voltage   | 28 max              | volts            |
| Grid-No.2 Supply Voltage  | 330 max             | volts            |
| Grid-No.2 Voltage   | See curve           |                  |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value   | 0 max               | volts            |
| Plate Dissipation   | 1.7 max             | watts            |
| For grid-No.2 voltages up to 165 volts  | 1.1 max             | watts *          |
| For grid-No.2 voltages between 165 and 330 volts  | See curve           | page 75          |

6AM4

# HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

6AM8


#### DIODE— SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

# DIODE—SHARP-CUTOFF PENTODE

6AM8A
Related type:
5AM8


Miniature type used in diversified applications in television receivers employing series-connected heater strings. The pentode unit is used as an if amplifier, video amplifier, or age amplifier. The high-perveance diode is




used as an audio detector, video detector, or dc restorer. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 5AM8 is identical with type 6AM8A except for heater ratings, as shown below.

|   | 5AM8    | 6AM8A   |         |
|---|---------|---------|---------|
| Heater Voltage (ac/dc)                  | 4.7     | 6.3     | volts   |
| Heater Current                          | 0.6     | 0.45    | ampere  |
| Heater Warm-up Time (Average)           | 11      | 11      | seconds |
| Peak Heater-Cathode Voltage:            |         |         |         |
| Heater negative with respect to cathode | 200 max | 200 max | volts   |
| Heater positive with respect to cathode | 200°max | 200°max | volts   |
| Direct Interelectrode Capacitances:     |         |         |         |
| Diode Unit:                             |         |         |         |
| Plate to Cathode and Heater             |         | 1.8     | pf      |
| Cathode to Plate and Heater             |         | 3       | pf      |

| 1 econical Data   |  | 15)   |
|---|--|---|
| Pentode Unit: Grid No.1 to Plate  | 0.015 max  | pf  |
| Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, and   | 6.5  | pf  |
| Internal Shield Pentode Grid No.1 to Diode Plate Pentode Plate to Diode Cathode Pentode Plate to Diode Plate  | 2.6<br>0.006 max<br>0.15 max<br>0.1 max                                | pf  |
| <sup>o</sup> The dc component must not exceed 100 volts.  |  |   |
| Pentode Unit as Class A, Amplifier  |  |   |
| MAXIMUM RATINGS (Design-Maximum Values):  Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts | 0 max<br>3.2 max<br>0.55 max   | volts<br>volts<br>ve page 75<br>volts<br>watts              |
| CHARACTERISTICS: Plate Supply Voltage Grid No.3 Connected Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Grid-No.1 Voltage (Approx.) for plate current of 20 \(\mu\)a Grid-No.1 Voltage (Approx.) for plate current of 2 ma and cathode- bias resistor of 0 ohms Plate Current Grid-No.2 Current          | 125<br>to cathode<br>125<br>56<br>0.3<br>7800<br>6<br>3<br>12.5<br>3.2 | volts at socket volts ohms megohm  µmhos volts  volts ma ma |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation   | 0.25 max<br>1.0 max  | megohm<br>megohm  |
| Diode Unit  |  |   |
| MAXIMUM RATINGS (Design-Maximum Values):  | 5 max  | ma  |





#### HIGH-MU TRIODE

# **6AN4**

Miniature type used as mixer or rf amplifier in cathode-drive circuits of uhf television tuners covering the frequency range of 470 to 890 megacycles per second. Outline 5B, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.



| •   |               |              |
|---|---------------|--------------|
| Heater Voltage (ac/dc)                            | 6.3           | volts        |
| Heater Current                                    | 0.225         | ampere       |
| Peak Heater-Cathode Voltage:                      |               |              |
| Heater negative with respect to cathode           | 200 max       | volts        |
| Heater positive with respect to cathode           | 200 max       | volts        |
| Direct Interelectrode Capacitances:               |               |              |
| Grid to Plate                                     | 1.7°          | pf           |
| Grid to Cathode and Heater                        | 3.3°          | pf           |
| Plate to Cathode and Heater                       | 1.8°          | pf           |
| Heater to Cathode                                 | 2.9▲          | pf           |
| Grid to Cathode                                   | 2.64          | pi<br>pf     |
|   | 2.8−<br>0.18▲ |              |
| Plate to Cathode                                  |               | pf           |
| Cathode to Grid and Heater                        | 5.7*          | pf           |
| Plate to Grid and Heater                          | 3.4*          | pf           |
| The dc component must not exceed 100 volts.       |               |              |
| With external shield connected to cathode.        |               |              |
| ▲ With external shield connected to ground.       |               |              |
| * With external shield connected to grid.         |               |              |
| Class A. Amplifier                                |               |              |
|   |               |              |
| MAXIMUM RATINGS (Design-Center Values):           |               | _            |
| Plate Voltage                                     | 300 max       | volts        |
| Plate Dissipation                                 | 4 max         | watts        |
| Cathode Current                                   | 30 max        | ma           |
| CHARACTERISTICS:                                  |               |              |
| Plate-Supply Voltage                              | 200           | volts        |
| Cathode-Bias Resistor                             | 100           | ohms         |
| Amplification Factor                              | 70            | OIIII.5      |
| Transconductance                                  | 10000         | μmhos        |
| Plate Current                                     | 13            | μημιοs<br>ma |
| Grid Voltage (Approx.) for plate current of 20 µa | <del></del> 7 | volts        |
| •           | /             | AOMS         |
| MAXIMUM CIRCUIT VALUES:                           |               |              |
| Grid-Circuit Resistance:                          |               |              |
| For fixed-bias operation                          | 0.1 max       | meghom       |
| For cathode-bias operation                        | 0.5 max       | megohm       |

# **6AN8**


#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

#### MEDIUM-MU TRIODE.... SHARP-CUTOFF PENTODE

**6AN8A** Related type: 5AN8

Miniature type used in a wide variety of applications in color television receivers employing series-connected heater strings. The pentode unit is used as an intermediate-frequency amplifier, a video amplifier, an agc




amplifier, or as a reactance tube. The triode unit is used in low-frequency oscillator, sync-separator, sync-clipper, and phase-splitter circuits. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 5AN8 is identical with type 6AN8A except for heater ratings, as shown below.

| Heater Voltage (ac/dc)                             | 5AN8<br>4.7 | 6AN8A<br>6.3 | volts   |
|--|-------------|--------------|---------|
| Heater Current                                     | 0.6         | 0.45         | ampere  |
| Heater Warm-Up Time (Average)                      | 11          | 11           | seconds |
| Peak Heater-Cathode Voltage:                       |             |              |         |
| Heater negative with respect to cathode            | 200 max     | 200 max      | volts   |
| Heater positive with respect to cathode            | 200° max    | 200° max     | volts   |
| Direct Interelectrode Capacitances:                |             |              |         |
| Triode Unit:                                       |             |              |         |
| Grid to Plate                                      |             | 1.5          | pf      |
| Grid to Cathode and Heater                         |             | 2.0          | pf      |
| Plate to Cathode and Heater                        |             | 0.26         | pf      |
| Pentode Unit:                                      |             |              | •       |
| Grid No.1 to Plate                                 |             | 0.04 max     | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid      |             |              | •       |
| Internal Shield                                    |             | 7            | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, as |             |              | _       |
| Shield   |             | 2.4          | pf      |
| Triode Grid to Pentode Plate                       |             | 0.02         | pf      |
| Pentode Grid No.1 to Triode Plate                  |             | 0.02         | pf      |
| Pentode Plate to Triode Plate                      |             | 0.15         | pf      |
|  |             |              | _       |

<sup>\*</sup> The dc component must not exceed 100 volts.


#### Class A. Amplifier

| Oldoo 11 11mpinioi                                     |             |              |         |
|--|-------------|--------------|---------|
| MAXIMUM RATINGS (Design-Maximum Values):               | Triode Unit | Pentode Unit |         |
| Plate Voltage  | 330 max     | 330 max      | volts   |
| Grid-No.2 Supply Voltage                               |             | 330 max      | volts   |
| Grid-No.2 (Screen-Grid) Voltage                        |             | See curve    | page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value. | 0 max       | 0 max        | volts   |
| Plate Dissipation Grid-No.2 Input:                     | 2.8 max     | 2.3 max      | watts   |
| For grid-No.2 voltages up to 165 volts                 |             | 0.55 max     | watt    |
| For grid-No.2 voltages between 165 and 330 volts       | -           | See curve    | page 75 |
| CHARACTERISTICS:                                       |             |              |         |
| Plate Supply Voltage                                   | 150         | 125          | volts   |
| Grid-No.2 Supply Voltage                               | -           | 125          | volts   |
| Grid-No.1 Voltage                                      | -3          | _            | volts   |
| Cathode-Bias Resistor                                  |             | 56           | ohms    |
| Amplification Factor                                   | 21          | _            |         |
| Plate Resistance (Approx.)                             | 4700        | 170000       | ohms    |
| Transconductance                                       | 4500        | 7800         | μmhos   |



| Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu$ a Grid-No.1 Voltage (Approx.) for plate current of 1.6 | Triode Unit17 | Pentode Uni<br>-6 | t<br>volts |
|--|---------------|-------------------|------------|
| ma and cathode-bias resistor of 0 ohms   | _             | <b>—3</b>         | volts      |
| Plate Current  | 15            | 12                | ma         |
| Grid-No.2 Current  | _             | 3.8               | ma         |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:*   |               |                   |            |
| For fixed-bias operation   | 0.5 max       | 0.25 max          |            |
| For cathode-bias operation   | 1.0 max       | 1.0 max           | megohm     |

\* If either unit is operating at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated values.




6AQ5

#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**


6AQ5A Related types: 5AQ5, 12AQ5 Miniature type used as output amplifier primarily in automobile receivers and in ac-operated receivers and, triode-connected, as a vertical deflection amplifier in television receivers employing series-connected heater



strings. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Within its maximum ratings, the performance of this type is equivalent to that of larger types 6V6 and 6V6GTA. Types 5AQ5 and 12AQ5 are identical with type 6AQ5A except for heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)  | 5AQ5<br>4.7<br>0.6<br>11 | 6AQ5A<br>6.3<br>0.45<br>11 | 12AQ5<br>12.6<br>0.225 | volts<br>ampere<br>seconds |
|--|--------------------------|----------------------------|------------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode.  Heater positive with respect to cathode. | 200 ma:                  | x 200 max                  | 200 max                | volts                      |
|  | 200=ma:                  | x 200•max                  | 200•max                | volts                      |


The dc component must not exceed 100 volts.



| Direct Interelectrode Capacitances (Approx.):  |        |              |
|--|--------|--------------|
| Grid No.1 to Plate   | 0.4    | pf           |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3                               | 8      | pf           |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3                                   | 8.5    | pf           |
| Amplification Factor*  | 9.5    | =            |
| Plate Resistance (Approx.)*  | 1970   | ohms         |
| Transconductance*  | 4800   | μmhos        |
| Grid-No.1 Voltage (Approx.) for plate current of 0.5 ma                              | -37    | volts        |
| * Grid No.2 connected to plate; plate and grid-No.2 volts, 250; grid-No.1 ma., 49.5. | volts, | -12.5; plate |

#### Class A. Amplifier

| MAXIMUM RATINGS (Design-Maximum Values): |         |       |
|--|---------|-------|
| Plate Voltage                            | 275 max | volts |
| Grid-No.2 (Screen-Grid) Voltage          | 275 max | volts |
| Plate Dissipation                        | 12 max  | watts |
| Grid-No.2 Input                          | 2 max   | watts |
| Bulb Temperature (At hottest point)      | 250 max | °C    |



#### TYPICAL OPERATION:

Same as for type 6V6GTA within the limitations of the maximum ratings.

#### **MAXIMUM CIRCUIT VALUES:**

| Grid-No.1-Circuit | Resistance: |
|-------------------|-------------|
| For fived bigs    | anaration   |

| For fixed-bias operation   | 0.1 max | megohm |
|----------------------------|---------|--------|
| For cathode-bias operation | 0.5 max | megohm |

#### Vertical Deflection Amplifier (Triode Connection)°

| For operation in a 525-line, 30-frame system         |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):             |          |       |
| DC Plate Voltage                                     | 275 max  | volts |
| Peak Positive-Pulse Plate Voltage†                   | 1100 max | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | 275 max  | volts |
| Peak Cathode Current                                 | 115 max  | ma    |
| Average Cathode Current                              | 40 max   | ma    |
| Plate Dissipation                                    | 10 max   | watts |
| Bulb Temperature (At hottest point)                  | 250 max  | °C    |

#### MAXIMUM CIRCUIT VALUE:

Grid-No.1-Circuit Resistance:

For cathode-bias operation ...

o Grid No.2 connected to plate.

2.2 max megohms

† The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

6AQ6

#### TWIN DIODE— HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

6AQ7GT


#### TWIN DIODE— HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

#### HIGH-MU TWIN TRIODE

6AQ8

Miniature type used as rf amplifier and self-oscillating mixer in FM/AM KT2(3) radio receivers. Outline 6B, Outlines section. Tube requires nine-contact socket and may be operated in any position.



| Heater Voltage (ac/dc)                        |           | 6.3       | volts      |
|---|-----------|-----------|------------|
| Heater Current                                |           | 0.435     | ampere     |
| Peak Heater-Cathode Voltage:                  |           |           |            |
| Heater negative with respect to cathode       |           | 90 max    | volts      |
| Heater positive with respect to cathode       |           | 90 max    | volts      |
| Direct Interelectrode Capacitances:           | Unit No.1 | Unit No.2 |            |
| Grid to Plate                                 | 1.5       | 1.5       | pf         |
| Cathode to Plate                              | 0.18      | 0.18      | pf         |
| Grid to Cathode, Heater, and Internal Shield  | 3         | 3         | pf         |
| Plate to Cathode, Heater, and Internal Shield | 1.2       | 1.2       | pf         |
| Plate to Grid of Other Unit                   | 0.008 max | 0.008 max | pf         |
| Plate to Cathode of Other Unit                | 0.008 max | 0.008 max | pf         |
| Grid to Cathode of Other Unit                 | 0.003 max | 0.003 max | pf         |
| Plate of Unit No.1 to Plate of Unit No.2      |           | 0.04 max  | pf         |
| Grid of Unit No.1 to Grid of Unit No.2        |           | 0.003 max | pf         |
| Amplification Factor*                         |           | 57        | •          |
| Plate Resistance (Approx.)*                   |           | 9700      | ohms       |
| Transconductance*                             |           | 5900      | $\mu$ mhos |
|   |           |           |            |

<sup>\*</sup> Each unit; with plate volts, 250; grid volts, -2.3; plate ma, 10.

| MAXIMUM RATINGS (Design-Center Values, Each I |                         |              |        |
|---|-------------------------|--------------|--------|
| Plate Supply Voltage                          |                         | 550 max      | volts  |
| Plate Voltage                                 |                         | 300 max      | volts  |
| Grid Voltage, Negative-bias value             | • • • • • • • • • • • • | —100 max     | volts  |
| For either plate                              |                         | 2.5 max      | watts  |
| For both plates with both units operating     |                         | 4.5 max      | watts  |
| Cathode Current                               |                         | 15 max       | ma     |
|   | RF                      |              |        |
| TYPICAL OPERATION (Each Unit):                | Amplifier               | Converter    |        |
| Plate Supply Voltage                          | 250                     | 250          | volts  |
| Plate Voltage                                 | 230                     | _            | volts  |
| Plate Resistor                                | 1800                    | 12000        | ohms   |
| Grid Resistor                                 | ~                       | 1            | megohm |
| Grid Voltage                                  | -2                      |              | volts  |
| RMS Oscillator Voltage                        |                         | 3            | volts  |
| Cathode-Bias Resistor                         | 200                     |              | ohms   |
| Plate Resistance (Approx.)                    | 9700                    | 22000        | ohms   |
| Transconductance                              | 6000                    |              | umhos  |
| Conversion Transconductance                   |                         | 2300         | μmhos  |
| Input Resistance at frequency of 100 Mc       | 6000                    | 15000        | ohms   |
| Plate Current                                 | 10                      | 5.2          | ma     |
| Equivalent Noise Resistance                   | 500                     | <del>-</del> | ohms   |
| MAXIMUM CIRCUIT VALUES (Each Unit):           |                         |              |        |
| Grid-Circuit Resistance                       |                         | 1 max        | megohm |
| Resistance between Cathode and Heater         |                         | 20000 max    | ohms   |

#### **POWER PENTODE**

Renewal type; see chart at end of section for tabulated data.

6AR5



#### SEMIREMOTE-CUTOFF TWIN PENTODE

Duodecar type used as if-amplifier tube in television receivers. Outline 8A, Outlines section. Tube requires duodecar twelve-contact-socket and may be mounted in any position. Type 11AR11 is identical with type 6AR11

6AR1 Related type: 11AR11

except for heater ratings, as show below.

|   | 6AR11     | 11AR11    |         |
|---|-----------|-----------|---------|
| Heater Voltage (ac/dc)                          | 6.3       | 11.2      | volts   |
| Heater Current                                  | 0.8       | 0.45      | ampere  |
| Heater Warm-up Time (Average)                   |           | 11        | seconds |
| Peak Heater-Cathode Voltage:                    |           |           |         |
| Heater negative with respect to cathode         | 200 max   | 200 max   | volts   |
| Heater positive with respect to cathode         | 200 max   | 200 max   | volts   |
| Direct Interelectrode Capacitances:             | Unit No.1 | Unit No.2 |         |
| Grid No.1 to Plate                              | 0.026     | 0.026     | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid   |           |           |         |
| No.3, and Internal Shield                       | 10        | 10        | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, |           |           | -       |
| and Internal Shield                             | 2.8       | 3         | pf      |
| Grid No.1 to Plate of Other Unit                | 0.002 max | 0.002 max | pf      |
| Plate of Unit No.1 to Plate of Unit No.2        |           | 0.02 max  | pf      |
| The do component must not exceed 100 volts      |           |           | -       |

The dc component must not exceed 100 volts.

| Class A <sub>1</sub> Amplifier                      |
|---|
| MAXIMUM RATINGS (Design-Maximum Values, Each Unit): |
| Plate Voltage                                       |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value |

330 max 0 max volts

volts


| Grid-No.2 (Screen-Grid) Supply Voltage                       | 330 max  | volts      |
|--|----------|------------|
| Grid-No.2 Voltage  | See cur  | ve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value        | 0 max    | volts      |
| Grid-No.2 Input:   |          |            |
| For grid-No.2 voltages up to 165 volts                       | 0.65 max | watt       |
| For grid-No.2 voltages between 165 and 330 volts             | See cur  | ve page 75 |
| Plate Dissipation  | 3.1 max  | watts      |
| CHARACTERISTICS (Each Unit):                                 |          |            |
| Plate Supply Voltage   | 125      | volts      |
| Grid No.3  |          |            |
| Grid-No.2 Supply Voltage                                     | 125      | volts      |
| Cathode-Bias Resistor  | 56       | ohms       |
| Plate Resistance (Approx.)                                   | 0.2      | megohm     |
| Transconductance   | 10500    | µmhos      |
| Plate Current  | 11       | ma         |
| Grid-No.2 Current  | 3.5      | ma         |
| Grid-No.1 Voltage (Approx.) for transconductance of 50 µmhos | 15       | volts      |
| - · · · · · · · · · · · · · · · · · · ·                      |          |            |

#### BEAM POWER TUBE

6AS5

MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:

Miniature type used as output amplifier primarily in automobile and in ac-operated receivers. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. For curves of average plate characteristics, refer to type 35C5.




0.1 max megohm

0.5 max megohm

Heater Voltage (ac/dc) ...... 6.3 volts Heater Current ..... 0.8ampere Peak Heater-Cathode Voltage: Heater negative with respect to cathode ...... 100 max volts Heater positive with respect to cathode ...... 100 max volts Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate ...... 0.6 рf 12 рf Plate to Cathode, Heater, Grid No.2, and Grid No.3 ........ 9.0 ρf Class A. Amplifier MAXIMUM RATINGS (Design-Center Values): 150 max Plate Voltage ..... volts Grid-No.2 (Screen-Grid) Voltage ..... 117 max volts Plate Dissipation ..... 5.5 max watts Grid-No.2 Input 1.0 max watt 250 max Bulb Temperature (At hottest point) ..... °C TYPICAL OPERATION: Plate Voltage ..... 150 volts Grid-No.2 Voltage ..... 110 volts Grid-No.1 (Control-Grid) Voltage ..... -8.5 volts Peak AF Grid-No.1 Voltage ..... 8.5 volts Zero-Signal Plate Current ..... 35 ma Maximum-Signal Plate Current
Zero-Signal Grid-No.2 Current (Approx.) 36 ma ma Maximum-Signal Grid-No.2 Current (Approx.) ..... 6.5 ma Transconductance ..... 5600 μmhos ..... 4500 Load Resistance ohms Total Harmonic Distortion ...... 10 per cent 2.2 watts Maximum-Signal Power Output ......

For fixed-bias operation ......

For cathode-bias operation .....



### DIODE— SHARP-CUTOFF PENTODE

Miniature type used in diversified applications in television and radio receivers. The pentode unit is used as an if amplifier, video amplifier, or age amplifier. The high-perveance diode is used as an audio detector, video de-

6AS8
Related type:


tector, or dc restorer. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be mounted in any position. For curve of average plate characteristics of pentode unit, see type 6AN8A. Type 5AS8 is identical with type 6AS8 except for heater ratings, as shown below.

| Heater Voltage (ac/dc)   | 5AS8<br>4.7                             | 6AS8<br>6.3           | volts             |
|--|---|-----------------------|-------------------|
| Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage:  | 0.6<br>11                               | 0.45<br>—             | ampere<br>seconds |
| Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances:  Diode Unit: | 200 max<br>200*max                      | 200 max<br>200 max    | volts<br>volts    |
| Plate to Cathode, Heater, Pentode Grid No.3, and   |   |                       |                   |
| Internal Shield  |   | 3.0                   | pf                |
| Grid No.1 to Plate   | 3. and                                  | 0.03 max              | pf                |
| Internal Shield  |   | 7                     | pf                |
| Internal Shield  |   | 2.4                   | pf                |
| Pentode Grid No.1 to Diode Plate   |   | 0.005 max<br>0.15 max | pf<br>pf          |
| Pentode Plate to Diode Plate   |   | 0.10 max              | pi                |
| The dc component must not exceed 100 volts.  |   | 0.10 11111            | ν.                |
| Pentode Unit As Class A.   | Amplifier                               |                       |                   |
| MAXIMUM RATINGS (Design-Center Values):  | ·                                       |                       |                   |
| Plate Voltage  |   | 300 max               | volts             |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value  |   | 0 max<br>300 max      | volts<br>volts    |
| Grid-No.2 Supply Voltage   |   | See curve             |                   |
| Grid-No.1 (Control-Grid) Voltage, Positive bias value  |   | 0 max                 | volts             |
| Plate Dissipation  | • | 2.5 max               | watts             |
| For grid-No.2 voltages up to 150 volts   |   | 0.5 max<br>See curve  | watt<br>page 75   |
| CHARACTERISTICS:   |   | 200 00270             | 2-0               |
| Plate Supply Voltage   |   | 200                   | volts             |
| Grid No.3  |   |                       |                   |
| Grid-No.2 Supply Voltage   |   | 150                   | volts             |
| Cathode-Bias Resistor  |   | 180                   | ohms              |
| Plate Resistance (Approx.)   |   | 300000                | ohms              |
| Transconductance Grid-No.1 Voltage (Approx.) for plate current of 10 μa.   |   | 6200<br>—8            | μmhos<br>volts    |
| Plate Current  |   | 9.5                   | ma                |
| Grid-No.2 Current  |   | 3                     | ma                |
| MAXIMUM CIRCUIT VALUES:  |   |                       |                   |
| Grid-No.1-Circuit Resistance:  |   |                       |                   |
| For fixed-bias operation   |   | 0.25 max              |                   |
| For cathode-bias operation   | • | 1.0 max               | megohm            |
| Diode Unit   |   |                       |                   |
| MAXIMUM RATINGS (Design-Center Values):  |   |                       | . •.              |
| Peak Inverse Plate Voltage   |   | 330 max<br>50 max     | volts<br>ma       |
| Peak Plate Current DC Plate Current  |   | 5 max                 | ma<br>ma          |
|  |   | ~ ~~~                 | *****             |

### DUAL TRIODE— SHARP-CUTOFF PENTODE

### **6AS11**

Duodecar type used in television receivers. High-mu triode is used in audio if-amplifier service; medium-mu triode is used in sync-separator service; pentode is used in video amplifier service. Outline 8B, Outlines




section. Tube requires 12-contact socket and may be mounted in any position. Heater voltage (ac/dc), 6.3; amperes, 1.05; peak heater-cathode volts, 200 max (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, Amplifier                     |          |          |          |               |  |
|--|----------|----------|----------|---------------|--|
|  |          | iode Uni | ts Pento | de            |  |
| MAXIMUM RATINGS                        | N        | o.1 No.  | 2 Unit   |               |  |
| (Design-Maximum Values):               |          |          |          |               |  |
| Plate Voltage                          | 330 л    | nax 330  |          | max volts     |  |
| Grid-No.2 (Screen-Grid) Supply Voltage | _        |          | •        | max volts     |  |
| Grid-No.2 Voltage                      | _        | _        | See      | curve page 75 |  |
| Grid-No.1 (Control-Grid) Voltage,      |          |          | _        |               |  |
| Positive-bias value                    | 0 г      | nax 0    | max 0    | max volts     |  |
| Grid-No.2 Input:                       |          |          |          |               |  |
| For grid-No.2 voltages up to 165 volts | _        | _        | 1.1      | max watts     |  |
| For grid-No.2 voltages between 165 and |          |          |          |               |  |
| 330 volts                              |          | _        |          | curve page 75 |  |
| Plate Dissipation                      | 1.5 r    | nax 2    | max 5    | max watts     |  |
| CHARACTERISTICS:                       |          |          |          |               |  |
|  | 200      | 200      | 200      | volts         |  |
| Plate Supply Voltage                   | 200      | 200      | 125      | volts         |  |
| Grid Voltage                           | _2       | _        | 127      | volts         |  |
| Cathode-Bias Resistor                  | -2       | 220      | 68       | ohms          |  |
| Amplification Factor                   | 68       | 41       | _        | OIIIII3       |  |
| Plate Resistance (Approx.)             |          | 9400     | 70000    | ohms          |  |
| Transconductance                       | 5500     | 4400     | 10500    | μmhos         |  |
| Plate Current                          | 7        | 9.2      | 24       | ma            |  |
| Grid-No.2 Current                      | <u> </u> |          | 5.2      | ma            |  |
| Grid-No.1 Voltage (Approx.):           |          |          | **-      |               |  |
| For plate current of 10 $\mu$ a        | 5.5      |          |          | volts         |  |
| For plate current of 100 µa            | -        | -6.5     | 8        | volts         |  |
| 2 of place cultone of 200 pa           |          |          |          |               |  |
| MAXIMUM CIRCUIT VALUES:                |          |          |          |               |  |
| Grid-No.1-Circuit Resistance:          |          |          |          |               |  |
| For fixed-bias operation               | 0.5 r    |          |          | max megohm    |  |
| For cathode-bias operation             | 1 n      | nax 1    | max 1    | max megohm    |  |

### TWIN DIODE— HIGH-MU TRIODE

6AT6
Related type: 12AT6

Miniature type used as a combined detector, amplifier, and avc tube in automobile and ac-operated radio receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any



position. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 12AT6 is identical with type 6AT6 except for heater ratings, as shown below.


|        |         |   | 6AT6 | 12AT6 |        |
|--------|---------|---|------|-------|--------|
| Heater | Voltage | (ac/dc)                                 | 6.3  | 12.6  | volts  |
| Heater | Current | *************************************** | 0.3  | 0.15  | ampere |

The two diode plates are placed around a cathode, the sleeve of which is common to the triode unit. Each diode plate has its own base pin. For diode operation curves, refer to type 6AV6.

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

6AT8



### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature types used as combined oscillator and mixer tubes in television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. This type has a controlled heater warm-up time for use in receiv-

6AT8A
Related type:
5AT8

6AT8A

ers employing series-connected heater strings. Outline 6B, Outlines section. Except for interelectrode capacitances and basing arrangement, this type is identical with miniature type 6X8. The basing arrangement is particularly suitable for connection to the coils of certain designs of turret tuners. Type 5AT8 is identical with type 6AT8A except for heater ratings, as shown below.

5AT8

| Heater Voltage (ac/dc)                      | 4.7                                     | 6.3       | volts   |
|---|---|-----------|---------|
| Heater Current                              | 0.6                                     | 0.45      | ampere  |
| Heater Warm-up Time (Average)               | 11                                      | 11        | seconds |
| ,   | Without                                 | With      |         |
| Direct Interelectrode Capacitances:         | External                                | External  |         |
| Triode Unit:                                | Shield                                  | Shield*   |         |
| Grid to Plate                               | 1.5                                     | 1.5       | pf      |
| Grid to Cathode and Heater                  | 2.0                                     | 2.4       | pf      |
| Plate to Cathode and Heater                 | 0.5                                     | 1.0       | pf      |
| Pentode Unit:                               | <b></b>                                 |           |         |
| Grid No.1 to Plate                          | 0.06 max                                | 0.03 max  | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2 and | *************************************** | V/ 211111 | -       |
| Grid No.3                                   | 4.6                                     | 4.8       | ρf      |
| Plate to Cathode, Heater, Grid No.2, and    | 7.0                                     | 7.0       | P-      |
| Grid No.3                                   | 0.9                                     | 1.6       | ρf      |
| GIR 110.5                                   | V.7                                     | 2.0       | P.      |
|   |   |           |         |

| Pentode Grid No.1 to Triode Plate | 0.05 max | 0.04 max  | pf |
|-----------------------------------|----------|-----------|----|
| Pentode Plate to Triode Plate     | 0.05 max | 0.008 max | pf |
| Heater to Cathode                 | 6.0      | 6.0†      | pf |

<sup>\*</sup> With external shield connected to cathode except as noted.

### **6AU4GT**

### HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

### HALF-WAVE VACUUM RECTIFIER

Glass octal type used as damper tube in horizontal-deflection circuits of color television receivers and of tele-6AU4GTA vision receivers utilizing picture tubes having wide-angle deflection. Outline 13G. Outlines section. This type re-



quires octal socket and may be mounted in any position. Type may be supplied with pin No.1 omitted. Socket terminals 1, 2, 4, and 6 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated.

| Heater Voltage (ac/dc)  | 6.3  | volts   |
|---|------|---------|
| Heater Current  | 1.8  | amperes |
| Direct Interelectrode Capacitances (Approx.): Plate to Heater and Cathode | 8.5  | pf      |
| Cathode to Heater and Plate   | 11.5 | pf      |
| Heater to Cathode   | 4.0  | pf      |

#### Damper Service

| For operation in a 323-tine, 30-frame system |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |          |       |
| Peak Inverse Plate Voltage†                  | 4500 max | volts |
| Peak Plate Current                           | 1300 max | ma    |
| DC Plate Current                             | 210 max  | ma    |
| Plate Dissipation                            | 6.5 max  | watts |
| Peak Heater-Cathode Voltage:                 |          |       |
| Heater negative with respect to cathode      | 4500*max | volts |
| Uester positive with respect to cothode      | 300#may  | volte |

<sup>†</sup> The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

### **BEAM POWER TUBE**

### 6AU5GT

Glass octal type used as horizontal deflection amplifier in low-cost, highefficiency deflection circuits of television receivers employing either transformer coupling or direct coupling to the deflecting voke. Outline



13D, Outlines section. Tube requires octal socket and may be mounted in any position.

<sup>†</sup> With external shield connected to plate.

<sup>\*</sup> The dc component must not exceed 900 volts.

<sup>#</sup> The dc component must not exceed 100 volts.

| Heater Voltage (ac/dc)   | 6.3       | volts   |
|--|-----------|---------|
| Heater Current   | 1.25      | amperes |
| Peak Heater-Cathode Voltage:   |           |         |
| Heater negative with respect to cathode  | 200 max   | volts   |
| Heater positive with respect to cathode  | 200 max   | volts   |
| Direct Interelectrode Capacitances (Approx.):  |           |         |
| Grid No.1 to Plate   | 0.5       | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3   | 11.3      | pf      |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3   | 7.0       | pf      |
| Transconductance#  | 5600      | μmhos   |
| Mu-Factor, Grid No.2 to Grid No.1†   | 5.9       |         |
| • The dc component must not exceed 100 volts.  |           |         |
| # For plate volts, 115; grid-No.2 volts, 175; grid-No.1 volts, -20.  |           |         |
| † For plate volts, 100; grid-No.2 volts, 100; grid-No.1 volts, -4.5.   |           |         |
|  |           |         |
| Horizontal Deflection Amplifier For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Center Values): |           |         |
| DC Plate Voltage   | 550 max   | volts   |
| Peak Positive-Pulse Plate Voltage* (Absolute Maximum)  | 5500°max  | volts   |
| Peak Negative-Pulse Plate Voltage  | -1250 max | volts   |
| DC Grid-No.2 (Screen-Grid) Voltage*  | 200 max   | volts   |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage   | 300 max   | volts   |
| Peak Cathode Current   | 400 max   | ma      |
| Average Cathode Current  | 110 max   | ma      |
| Grid-No.2. Input   | 25 max    | watte   |

Bulb Temperature (At hottest point) ..... 210 max MAXIMUM CIRCUIT VALUE: Grid-No.1-Circuit Resistance 0.47 max megohm

- \* The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- Ounder no circumstances should this absolute value be exceeded.
- \* Obtained through a series dropping resistor of sufficient magnitude to limit the grid-No.2 input to the rated maximum value.
- †† An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

### SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

6AU6

10 max

watte



Plate Dissipation†† .....

### SHARP-CUTOFF PENTODE

Miniature type used in compact radio equipment as rf amplifier especially in high-frequency, wide-band applications; also used as limiter tube in FM equipment. Type 6AU6A has a 3AU6, 4AU6, 12AU6 controlled heater warm-up time for

6ΔU6Δ

Related types:

use in applications employing series-connected heater strings. Outline 5C, Outlines section. Type requires miniature seven-contact socket and may be operated in any position. For a discussion of limiters, refer to Electron Tube Applications section. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Types 3AU6, 4AU6, and 12AU6 are identical with type 6AU6A except for heater ratings, as shown below.

| 3AU6                             | 4AU6 | 6AU6A | 12AU6 |         |
|----------------------------------|------|-------|-------|---------|
| Heater Voltage (ac/dc)3.15       | 4.2  | 6.3   | 12.6  | volts   |
| Heater Current 0.6               | 0.45 | 0.3   | 0.15  | ampere  |
| Heater Warm-up Time (Average) 11 | 11   | 11    | _     | seconds |

4.3

ma


| Death Wester Claffer to Western                                  |            |       |
|--|------------|-------|
| Peak Heater-Cathode Voltage:                                     |            | _     |
| Heater negative with respect to cathode                          | 200 max    | volts |
| Heater positive with respect to cathode                          | 200₄max    | volts |
| Direct Interelectrode Capacitances:                              |            |       |
| Pentode Connection:  |            |       |
| Grid No.1 to Plate   | 0.0035 max | pf    |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal | orogon man | P     |
| Shield   | 5.5        | pf    |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal     | 5.5        | Pι    |
| Shield   | 5.0        |       |
| Triode Connection:†  | 3.0        | pf    |
|  |            | _     |
| Grid No.1 to Plate, Grid No.2, Grid No.3, and Internal Shield    | 2.6        | pf    |
| Grid No.1 to Cathode and Heater                                  | 3.2        | pf    |
| Plate, Grid No.2, Grid No.3, and Internal Shield to Cathode and  |            | _     |
| Heater   | 1.2•       | pf    |
| 4 The dc component must not exceed 100 volts.                    |            |       |

a the dc component must not exceed 100 volts.

† Grid No.2, grid No.3, and internal shield connected to plate.

• Value is 8.5 pf with external shield connected to cathode.

| Class .                                      | A. Amplif   | ier            |              |         |
|--|-------------|----------------|--------------|---------|
|  | •           | Triode†        | Pentode      |         |
| MAXIMUM RATINGS (Design-Maximum              |             | Connection     | Connection   | ı       |
| Plate Voltage                                |             | 275 max        | 330 max      | volts   |
| Grid-No.3 (Suppressor-Grid) Voltage, Positiv | ve value    | _              | 0 max        | volts   |
| Grid-No.2 (Screen-Grid) Voltage              |             | _              | See curve    | page 75 |
| Grid-No.2 Supply Voltage                     |             |                | 330 max      | volts   |
| Plate Dissipation                            |             | 3.5 max        | 3.5 max      | watts   |
| Grid-No.2 Input:                             |             |                |              |         |
| For grid-No.2 voltages up to 165 volts       |             | _              | 0.75 max     | watt    |
| For grid-No.2 voltages between 165 asd       | 330 volts . | _              | See curve    | page 75 |
| Grid-No.1 (Control-Grid) Voltage:            |             |                |              | • •     |
| Positive-bias value                          |             | 0 max          | 0 max        | volts   |
| Tri  | ode†        |                |              |         |
| CHARACTERISTICS: Con                         | nection     | Pentode Connec | tion         |         |
| Plate Supply Voltage 2                       | 50 100      | 250            | 250          | volts   |
| Grid No.3                                    | - Con       | ected to catho | de at socket |         |
| Grid-No.2 Supply Voltage                     | - 100       | 125            | 150          | volts   |
|  | 30 150      | 100            | 68           | ohms    |
|  | 36          |                | _            |         |
| Plate Resistance (Approx.)                   | - 0.5       | 1.5            | 1.0          | megohms |
|  | 00 3900     | 4500           | 5200         | μmhos   |
| Grid-No.1 Voltage for plate current          |             |                |              | F       |
| of 10 μa                                     | 4.2         | -5.5           | -6.5         | volts   |
| Plate Current                                | 2.2 5.0     | 7.6            | 10.6         | ma      |



MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.


**6AU7** 

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6AU8

Discontinued type; see chart at end of section for tabulated data.

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE



Miniature type used in television receiver applications. This type has controlled heater warm-up time for use in series-heater strings. Pentode unit is used as video amplifier, if amplifier, age amplifier. Triode unit is used in

6AU8A
Related type:

sync-amplifier, sync-separator, sync-clipper, and phase-inverter circuits. Outline 6E, Outlines section. This type requires nine-contact socket and may be mounted in any position. Type 8AU8 is identical with type 6AU8A except for heater ratings, as shown below.

|  | DAUBA   | 8AU8      |            |
|--|---------|-----------|------------|
| Heater Voltage (ac/dc)                                 | 6.3     | 8.4       | volts      |
| Heater Current   | 0.6     | 0.45      | ampere     |
| Heater Warm-up Time (Average)                          | 11      | _         | seconds    |
| Peak Heater-Cathode Voltage:                           |         |           |            |
| Heater negative with respect to cathode                | 200 max | 200 max   | volts      |
| Heater positive with respect to cathode                | 200 max | 200 max   | volts      |
| Direct Interelectrode Capacitances:                    |         |           |            |
| Triode Unit:   |         |           |            |
| Grid to Plate  |         | 2.2       | p <b>f</b> |
| Grid to Cathode and Heater                             |         | 2.6       | pf         |
| Plate to Cathode and Heater                            |         | 0.34      | pf         |
| Pentode Unit:  |         |           | -          |
| Grid No.1 to Plate                                     |         | 0.06      | pf         |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, as |         |           | -          |
| Shield   |         | 7.5       | pf         |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, an     |         |           | -          |
| Shield   |         | 3.4       | pf         |
| Triode Grid to Pentode Plate                           |         | 0.022 max | pf         |
| Pentode Grid No.1 to Triode Plate                      |         | 0.006 max | pf         |
| Pentode Plate to Triode Plate                          |         | 0.12 max  | pf         |
| The dc component must not exceed 100 volts.            |         |           |            |

The dc component must not exceed 100 volts.

| The dy component made not entered too voice.          |             |              |                 |
|---|-------------|--------------|-----------------|
| MAXIMUM RATINGS (Design-Maximum Values):              | Triode Unit | Pentode Unit |                 |
| Plate Voltage   | 330 max     | 330 max      | volts           |
| Grid-No.2 (Screen-Grid) Supply Voltage                |             | 330 max      | volts           |
| Grid-No.2 Voltage                                     | _           | See curve    | page 75         |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max       | 0 max        | volts           |
| Plate Dissipation                                     | 2.8 max     | 3.3 max      | watts           |
| Grid-No.2 Input:                                      |             |              |                 |
| For grid-No.2 voltages up to 165 volts                | _           | 1 max        | watt            |
| For grid-No.2 voltages between 165 and 330 volts      |             | See curve p  | pag <b>e 75</b> |
| CHARACTERISTICS:                                      |             |              |                 |
| Plate Supply Voltage                                  | 150         | 200          | volts           |

| CHARACTERISTICS:         |     |     |       |
|--------------------------|-----|-----|-------|
| Plate Supply Voltage     | 150 | 200 | volts |
| Grid-No.2 Supply Voltage | _   | 125 | volts |
| Cathode-Bias Resistor    | 150 | 82  | ohms  |
| Amplification Factor     | 43  | _   |       |
|                          |     |     |       |

Pentode Unit

Triode Unit

| Plate Resistance (Approx.)  Transconductance Grid-No.1 Voltage (Approx.) for plate current of 100 µa Plate Current Grid-No.2 Current | 8100<br>5300<br>6.5<br>9.5 | 100000<br>8000<br>7.5<br>17<br>3.4 | ohms<br>μmhos<br>volts<br>ma<br>ma |
|--|----------------------------|------------------------------------|------------------------------------|
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation                            | 0.5 max                    | 0.25 max                           | megohm                             |
|  | 1.0 max                    | 1.0 max                            | megohm                             |

### **BEAM POWER TUBE**

6AV5GA
Related types:
12AV5GA, 25AV5GA

Glass octal type used as horizontal deflection amplifier in television receivers employing either transformer coupling or direct coupling to the deflecting yoke. Outline 19C, **Outlines** section. This type requires octal socket



and may be mounted in any position. Types 12AV5GA and 25AV5GA are identical with type 6AV5GA except for heater ratings, as shown below.

| Heater Voltage (ac/dc)  | 6.3       | 12AV5GA<br>12.6<br>0.6 | 25AV5GA<br>25<br>0.3 | volts<br>amperes |
|---|-----------|------------------------|----------------------|------------------|
| Heater Warm-up Time (Average)   |           | 11                     | _                    | seconds          |
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode | 200 max   | 200 max                | 200 max              | volts            |
| Heater positive with respect to cathode                               | 200 • max |                        | 200=max              | volts            |
| Transconductance* Mu Factor, Grid No.2 to Grid No.1**                 |           |                        | 5900<br>4.3          | μmhos            |

- The dc component must not exceed 100 volts.
- \* Plate volts, 250; grid-No.2 volts, 150; grid-No.1 volts, -22.5.
- \*\* Triode connected; plate and grid-No.2 volts, 150; grid-No.1 volts, -22.5.

### Horizontal Deflection Amplifier

For operation in a 525-line, 30-frame system


| MAXIMUM RATINGS (Design-Center Values):               |           |       |
|---|-----------|-------|
| DC Plate Voltage                                      | 550 max   | volts |
| Peak Positive-Pulse Plate Voltage† (Absolute Maximum) | 5500°max  | volts |
| Peak Negative-Pulse Plate Voltage                     | -1250 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage                    | 175 max   | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage  | -300 max  | volts |
| Peak Cathode Current                                  | 400 max   | ma    |
| Average Cathode Current                               | 110 max   | ma    |
| Grid-No.2 Input                                       | 2.5 max   | watts |
| Plate Dissipation††                                   | 11 max    | watts |
| Bulb Temperature (at hottest point)                   | 210 max   | °C    |

#### MAXIMUM CIRCUIT VALUE:

- † The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- Ounder no circumstances should this absolute value be exceeded.
- †† An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

### **BEAM POWER TUBE**

Discontinued type; see chart at end 6AV5GT of section for tabulated data.



### TWIN DIODE-HIGH-MU TRIODE

Miniature type used as combined detector, amplifier, and ave tube in automobile and ac-operated radio receivers. The 6AV6 may be substituted directly for the 6AT6 in 3AV6, 4AV6, 12AV6 applications where the higher ampli-

**6AV6** 

Related types:

330 max

0 max

volts

volts

fication of the 6AV6 is advantageous. Types 3AV6, 4AV6, and 12AV6 are identical with type 6AV6 except for heater ratings, as shown below.

| Heater Voltage (ac/dc)  | 3AV6<br>3.15<br>0.6<br>11 | 4AV6<br>4.2<br>0.45<br>11 | 6AV6<br>6.3<br>0.3                    | 12AV6<br>12.6<br>0.15         | volts<br>ampere<br>seconds |
|---|---------------------------|---------------------------|---------------------------------------|-------------------------------|----------------------------|
| Heater negative with respect to cath Heater positive with respect to cath Direct Interelectrode Capacitances:                       | ode                       |                           |                                       | 200 max<br>2004max            | volts<br>volts             |
| Triode Grid to Triode Plate Triode Grid to Cathode and Heater Triode Plate to Cathode and Heater Plate of Diode Unit No.2 to Triode |                           |                           | · · · · · · · · · · · · · · · · · · · | 2.0<br>2.2<br>0.8<br>0.04 max | pf<br>pf<br>pf<br>pf       |


- 4 The dc component must not exceed 100 volts.
- This value is 1.2 pf with external shield connected to cathode.

### Triode Unit As Class A, Amplifier MAXIMUM RATING (Design-Maximum Value): Plate Voltage .....

Grid Voltage, Positive-bias value .....

| Plate Dissipation    | • • • • • • • • • | 0.55 max  | watt  |
|----------------------|-------------------|-----------|-------|
| CHARACTERISTICS:     |                   |           |       |
| Plate Voltage        | 100               | 250       | volts |
| Grid Voltage         | -1                | <b></b> 2 | volts |
| Amplification Factor | 100               | 100       |       |

### AVERAGE PLATE CHARACTERISTICS



| Plate Resistance Transconductance Plate Current | 80000 | 62500 | ohms  |
|---|-------|-------|-------|
|   | 1250  | 1600  | µmhos |
|   | 0.50  | 1.2   | ma    |

### **Diode Units**

MAXIMUM RATING (Design-Maximum Value):


### Installation and Application

Type 6AV6 requires miniature seven-contact socket and may be mounted in any position. Outline 5C, Outlines section.

The triode unit of the 6AV6 is recommended for use only in resistance-coupled circuits. Refer to the Resistance-Coupled Amplifier section for typical operating conditions.

Grid bias for the triode unit of the 6AV6 may be obtained from a fixed source, such as a fixed-voltage tap on the dc power supply, or from a cathode-bias resistor. It should not be obtained by the diode-biasing method because of the probability of plate-current cutoff, even with relatively small signal voltages applied to the diode circuit.

### AVERAGE DIODE CHARACTERISTICS HALF-WAVE RECTIFICATION-SINGLE DIODE UNIT



6AW8


### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

6AW8A
Related type:
8AW8A

Miniature type used in a wide variety of applications in television receivers. This type has a controlled heater warm-up time for use in receivers employing series-connected heater strings. The pentode unit is used as an if am-



plifier, video amplifier, age amplifier, or reactance tube. The triode unit is used in low-frequency oscillator, sync-separator, sync-clipper, and phase-splitter circuits. Outline 6E, Outlines section. This type requires miniature nine-contact socket and may be mounted in any position. Type 8AW8A is identical with type 6AW8A except for heater ratings, as shown below.

|                               | 6AW8A | 8AW8A |         |
|-------------------------------|-------|-------|---------|
| Heater Voltage (ac/dc)        | 6.3   | 8.4   | volts   |
| Heater Current                | 0.6   | 0.45  | ampere  |
| Heater Warm-up Time (Average) | 11    | 11    | seconds |
|                               |       |       | 2000000 |


| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances:  Triode Unit: | Without<br>External<br>Shield | 200 max<br>200°max<br>With<br>External<br>Shield• | volts<br>volts |
|---|-------------------------------|---|----------------|
| Grid to Plate   | 2.2                           | 2.2   | pf             |
| Grid to Cathode, Pentode Cathode, Pentode Grid No.3, Internal Shield, and Heater Grid to Cathode, Pentode Cathode, Pentode  | 3.2                           | 3.4   | pf             |
| Grid No.3. Internal Shield, and Heater  | 1.8                           | 3.0   | pf             |
| Pentode Unit:   |                               |   | -              |
| Grid No.1 to Plate  | 0.06 max                      | 0.05 max  | pf             |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield Plate to Cathode, Heater, Grid No.2, Grid   | 10                            | 10  | pf             |
| No.3, and Internal Shield   | 3.6                           | 4.5   | pf             |
| Pentode Grid No.1 to Triode Plate   | 0.008 max                     | 0.005 max   | pf             |
| Pentode Plate to Triode Plate  The dc component must not exceed 100 volts.  | 0.15 max                      | 0.025 max   | pf             |

AVERAGE CHARACTERISTICS
TRIODE UNIT

• With external shield connected to pins 4 and 5.

Plate Current .....

Grid-No.2 Current .....



Class A<sub>1</sub> Amplifier Pentode Unit MAXIMUM RATINGS (Design-Maximum Values): Triode Unit 330 max volts 330 max Plate Voltage ..... 330 max Grid-No.2 (Screen-Grid) Supply Voltage ..... volts See curve page 75 Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: 0 max 0 max volts Positive bias value ..... Plate Dissipation ..... 1.1 max 3.75 max watts Grid-No.2 Input: 1.1 max For grid-No.2 voltages up to 165 volts watts For grid-No.2 voltages between 165 and 330 volts. See curve page 75 CHARACTERISTICS: 200 150 volts Plate Supply Voltage ..... Grid-No.2 Supply Voltage ..... volts 150 volts Grid-No.1 Voltage 150 ohms Cathode-Bias Resistor ..... Amplification Factor ..... 70 Plate Resistance (Approx.) 0.2 megohm 4000 9500 μmhos. Transconductance ...... Grid-No.1 Voltage (Approx.) for plate current of volts 20 μa ............


15

3.5

ma


ma

# MAXIMUM CIRCUIT VALUES: Triode Unit Pentode Unit Grid-No.1-Circuit Resistance: For fixed-bias operation ... 0.5 max 0.25 max megohm For cathode-bias operation ... 1.0 max megohm



### HALF-WAVE VACUUM RECTIFIER

6AX3 Related types: 12AX3, 17AX3 Duodecar type used as damper tube in horizontal-deflection circuits of television receivers. Outline 8C, Outlines section. Tube requires 12-contact socket and may be mounted in any position. Socket terminals 5, 6, 8, and



17AX3

9 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Types 12AX3 and 17AX3 are identical with type 6AX3 except for heater ratings, as shown below.

12AX3

| Heater Voltage (ac/dc)   | 6.3<br>1.2 | 12.6<br>0.6  | 16.8<br>0.45 | volts<br>amperes |
|--|------------|--------------|--------------|------------------|
| Heater Warm-up Time (Average)  | _          | 11           | 11           | seconds          |
| Damper:<br>For operation in a 525-   |            | frame system |              |                  |
| MAXIMUM RATINGS (Design-Maximum Valu   | ies):      |              |              |                  |
| Peak Inverse Plate Voltage°  |            |              | 5000 max     | volts            |
| Peak Plate Current   |            |              | 1000 max     | ma               |
| DC Plate Current   |            |              | 165 max      | ma               |
| Plate Dissipation  |            |              | 5.3 max      | watts            |
| Heater negative with respect to cathode  |            |              | 5000*max     | volts            |
| Heater positive with respect to cathode  |            |              | 300°max      | volts            |
| CHARACTERISTICS, Instantaneous Value:<br>Tube Voltage Drop for plate current of 250 ma | a          |              | 32           | volts            |
|  |            |              |              |                  |

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 900 volts.
- The dc component must not exceed 100 volts.

### HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

### **6AX4GT**



### HALF-WAVE VACUUM RECTIFIER

Glass octal type used as damper tube in horizontal deflection circuits of television receivers. Outline 13D, Outlines section. May be supplied with Related types: pin No.1 omitted. This type requires 12AX4GTB, 17AX4GTA, octal socket and may be operated in

25AX4GT

25AX4GT

any position. Socket terminals 1, 2, 4, and 6 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Types 12AX4GTB, 17AX4GTA, and 25AX4GT are identical with type 6AX4GTB except for heater ratings, as shown below.

6AX4- 12AX4-

17 A X4.

|   | GTB     | GTB               | GTA                                     | 23AA401   |         |
|---|---------|-------------------|---|-----------|---------|
| Heater Voltage (ac/dc)  | 6.3     | 12.6              | 16.8                                    | 25        | 14      |
|   | 1.2     | 0.6               |   |           | volts   |
| Heater Current  |         |                   | 0.45                                    | 0.3       | amperes |
| Heater Warm-up Time (Average)   | `—      | 11                | 11                                      | _         | seconds |
| Direct Interelectrode Capacitances (Appro                                     |         |                   |   |           |         |
| Cathode to Plate and Heater   |         |                   |   | 8.5       | pf      |
| Plate to Cathode and Heater   |         |                   |   | 5         | pf      |
| Heater to Cathode   |         |                   |   | 4         | pf      |
| For operation in  MAXIMUM RATINGS (Design-Maximum Pack Inverse Plate Voltages | m Value | s):               |   | \$000 may |         |
| Peak Inverse Plate Voltage  |         |                   |   | 5000 max  | volts   |
| Peak Plate Current  |         |                   |   | 1000 max  | ma      |
| DC Plate Current  |         |                   |   | 165 max   | ma      |
| Plate Dissipation Peak Heater-Cathode Voltage:                                |         |                   |   | 5.3 max   | watts   |
| Heater negative with respect to cath  | ode     | <b></b>           |   | 5000*max  | volts   |
| Heater positive with respect to cath  | ode     | • • • • • • • • • | • | 300¤max   | volts   |
| CHARACTERISTICS, Instantaneous Te   | st Cond | ition:            |   |           |         |
| Tube Voltage Drop for plate current of  |         |                   |   | 32        | volts   |

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 900 volts.
- The dc component must not exceed 100 volts.



### FULL-WAVE VACUUM RECTIFIER

Glass octal type used in power supply of radio equipment having moderate dc requirements. Outline 13D, Outlines section. This type may be supplied with pin No.1 omitted. Tube requires octal socket and may be

6AX5GT


mounted in any position. It is especially important that this tube, like other powerhandling tubes, be adequately ventilated. Heater volts (ac), 6.3; amperes, 1.2.

#### **Full-Wave Rectifier**

| MAXIMUM RATINGS (Design-Center Values):  |                   |             |                  |
|--|-------------------|-------------|------------------|
| Peak Inverse Plate Voltage   |                   | 1250 max    | volts            |
| Peak Plate Current (Per Plate)   |                   | 375 max     | ma               |
| Hot-Switching Transient Plate Current:   |                   |             |                  |
| For duration of 0.2 second maximum   |                   |             | amperes          |
| AC Plate Supply Voltage (Per Plate, rms)   |                   |             | ing Chart        |
| DC Output Current (Per Plate, rms) Peak Heater-Cathode Voltage:                                      | • • • • • • • • • | See Rati    | ng Chart         |
| Heater negative with respect to cathode  |                   | 450 max     | volts            |
| Heater positive with respect to cathode  | • • • • • • • • • | 450 max     | volts            |
|  |                   | 450 1144    | 10163            |
| TYPICAL OPERATION WITH CAPACITOR   |                   |             |                  |
| INPUT TO FILTER:   |                   |             |                  |
| AC Plate-to-Plate Supply Voltage (rms)   | 700               | 900         | volts            |
| Filter Input Capacitor*  | 10                | 10          | μf               |
| Effective Plate-Supply Impedance Per Plate   | 50                | 105         | ohms             |
| DC Output Voltage at Input to Filter (Approx.):  | 205               |             |                  |
| At half-load current of $\begin{cases} 62.5 \text{ ma} & \dots \\ 40 \text{ ma} & \dots \end{cases}$ | 395               | 540         | volts<br>volts   |
| } 10-  | 350               | 340         | volts            |
| At full-load current of 80 ma  | -                 | 490         | volts            |
| Voltage Regulation (Approx.):  |                   | .,,         | , 0100           |
| Half-load to full-load current   | 45                | 50          | volts            |
|  |                   |             |                  |
| TYPICAL OPERATION WITH CHOKE INPUT<br>TO FILTER:   |                   |             |                  |
|  |                   |             |                  |
| AC Plate-to-Plate Supply Voltage (rms)   | 700<br>10#        | 900<br>10## | volts<br>henries |
| DC Output Voltage at Input to Filter (Approx.):  | 10#               | 10##        | nemies           |
| ( 75 ma  | 270               |             | volts            |
| At half-load current of 62.5 ma  |                   | 365         | volts            |
| At full-load current of 150 ma   | 250               |             | volts            |
| ( 125 ma   | _                 | 350         | volts            |
| Voltage Regulation (Approx.):  |                   |             |                  |
| Half-load to full-load current   | 20                | 15          | volts            |


<sup>\*</sup> Higher values of capacitance than indicated may be used but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for hotswitching transient plate current.

<sup>##</sup> This value is adequate to maintain optimum regulation provided the load current is not less than 35 ma. For load currents less than 35 ma, a larger value of inductance is required for optimum regulation.



<sup>#</sup>This value is adequate to maintain optimum regulation provided the load current is not less than 30 ma. For load currents less than 30 ma, a larger value of inductance is required for optimum regulation.

### MEDIUM-MU TRIODE— SEMIREMOTE-CUTOFF PENTODE



Miniature type used in television-receiver applications; the pentode unit is used as a video amplifier; the triode unit is used as a sync separator. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

6AX8

| Heater Voltage (ac/dc)                                  | 6.3              | volts  |
|---|------------------|--------|
| Heater Current Peak Heater-Cathode Voltage:             | 0.45             | ampere |
| Heater negative with respect to cathode                 | 90 max           | volts  |
| Heater positive with respect to cathode                 | 90 max           | volts  |
| Direct Interelectrode Capacitances:                     | >0 max           | 10113  |
| Triode Unit:  |                  |        |
| Grid to Plate   | 1.8              | pf     |
| Grid to Cathode and Heater                              | 2.5              | pf     |
| Plate to Cathode and Heater                             | 1                | pf     |
| Pentode Unit:   |                  |        |
| Grid No.1 to Plate                                      | 0.006 max        | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and |                  | _      |
| Internal Shield   | 5                | pf     |
|   |                  |        |
|   | 3.5              | pf     |
| Heater to Cathode (Each Unit)                           | 3.5•             | pf     |
| Internal Shield   | 5<br>3.5<br>3.5• | pf     |

- With external shield connected to cathode of unit under test except as noted.
- With external shield connected to ground.

For cathode-bias operation .....

| Class A, Amplifier                                    |               |            |           |
|---|---------------|------------|-----------|
| MAXIMUM RATINGS (Design-Center Values):               | Triode Unit   | Pentode Un | it        |
| Plate Voltage   | 300 max       | 300 max    | volts     |
| Grid-No.2 Supply Voltage                              | -             | 300 max    | volts     |
| Grid-No.2 (screen-grid) Voltage                       | _             | See curv   | e page 75 |
| Grid-No.1 (control-grid) Voltage                      | 0 max         | 0 max      | volts     |
| Plate Dissipation                                     | 2.7 max       | 2.8 max    | watts     |
| Grid-No.2 Input                                       |               |            |           |
| For grid-No.2 voltages up to 150 volts                | _             | 0.5 max    | watt      |
| For grid-No.2 voltages between 150 and 300 volts      | _             | See curv   | e page 75 |
| CHARACTERISTICS:                                      |               |            |           |
|   | 150           | 250        | 14-       |
| Plate Supply Voltage                                  | 150           | 250        | volts     |
| Grid-No.2 Supply Voltage Cathode-Bias Resistor        | <u></u><br>56 | 110        | volts     |
|   | 40            | 120        | ohms      |
| Amplification Factor                                  |               | 0.4        |           |
| Plate Resistance (Approx.)                            | 0.005<br>8500 |            | megohm    |
| Transconductance                                      |               | 4800       | μmhos     |
| Grid-No.1 Voltage (Approx.) for plate current of 10µa | -12           | -12        | volts     |
| Plate Current   | 18            | 10         | ma        |
| Grid-No.2 Current                                     | _             | 3.5        | ma        |
| MAXIMUM CIRCUIT VALUES:                               |               |            |           |
| Grid-No.1 Circuit Resistance:                         |               |            |           |
| For fixed-bias operation                              | 0.1 max       | 0.1 max    | megohm    |
| V4  |               |            |           |

### HALF-WAVE VACUUM RECTIFIER



Novar types used as damper tubes in horizontal deflection circuits of black-and-white television receivers. Outlines 11D and 30B, respectively, **Outlines** section. Tubes require novar socket and may be operated in any position.

6AY3 6AY3B

0.5 max megohm

0.5 max

Related types: 12AY3, 12AY3A 17AY3, 17AY3A Socket terminals 1, 3, 6, and 8 should not be used as tie points. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Types 12AY3 and 12AY3A and types 17AY3 and 17AY3A are identical with types 6AY3 and 6AY3B except for heater ratings, as shown below.

|   | UMIJ               | 12M I 3 | 1/AI3      |         |
|---|--------------------|---------|------------|---------|
|   | 6AY3B              | 12AY3A  | 17AY3A     |         |
| Heater Voltage (ac/dc)  | 6.3                | 12.6    | 16.8       | volts   |
| Heater Current  | 1.2                | 0.6     | 0.45       | amperes |
| Heater Warm-up Time (Average)                                 | _                  | 11      | 11         | seconds |
| Direct Interelectrode Capacitances (Approx.):                 |                    | ••      | ••         | seconds |
| Plate to Cathode and Heater                                   |                    |         | 6.5        | pf      |
| Cothodo to Dista and Heater                                   |                    |         |            |         |
| Cathode to Plate and Heater                                   |                    |         | 9.0        | pf      |
| Heater to Cathode   |                    |         | 2.8        | pf      |
| For operation in a 525 MAXIMUM RATINGS (Design-Maximum Value) | -line, 30-<br>es): | •       |            |         |
| Peak Inverse Plate Voltage                                    |                    |         | 5000 max   | volts   |
| Peak Plate Current  |                    |         | 1100 max   | ma      |
| DC Plate Current  |                    |         | 175 max    | ma      |
| Plate Dissipation   |                    |         | 6.5 max    | watts   |
| Peak Heater-Cathode Voltage:                                  |                    |         |            |         |
| Heater negative with respect to cathode                       |                    |         | 5000 max   | volts   |
| Heater positive with respect to cathode                       |                    |         | 300¤max    | volts   |
|   |                    |         | 230-111411 |         |

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 900 volts.
- The dc component must not exceed 100 volts.


CHARACTERISTICS, Instantaneous Value:

Tube Voltage Drop for plate current of 18 ma .....

### TWIN DIODE— HIGH-MU TWIN TRIODE

**6AY11** 


Duodecar type used as combined FM detector and af voltage amplifier in Po<sub>2</sub>(3 radio and television receivers. Outline 8A, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position.



volts

Heater volts (ac/dc), 6.3; amperes, 0.69; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A <sub>1</sub> Amplifier (Each Triode Unit) MAXIMUM RATINGS (Design-Maximum Values): |              |       |
|--|--------------|-------|
| Plate Voltage  | 330 max      | volts |
| Grid Voltage: Positive-bias value  | 0 max        | volts |
| Negative-bias value  | -50 max      | volts |
| Plate Dissipation  | 1 max        | watt  |
| CHARACTERISTICS:   |              |       |
| Plate Voltage  | 250          | volts |
| Grid Voltage   | -2           | volts |
| Amplification Factor Plate Resistance (Approx.)  | 100<br>52700 | ohms  |
| Transconductance   | 1900         | umhos |
| Plate Current  | 1.2          | ma    |
| Diode Units (Each Unit) MAXIMUM RATINGS (Design-Maximum Values):                           |              |       |
| Plate Current  | 5 max        | ma    |



### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in a wide variety of applications in television receivers. The pentode unit is used as an if amplifier, video amplifier, age amplifier, or reactance tube. The triode unit is used in low-frequency oscillator, sync-

6AZ8

separator, sync-clipper, and phase-splitter circuits. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc)  | 6.3<br>0.45        | volts<br>ampere |
|---|--------------------|-----------------|
| Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances:                 | 200 max<br>200 max | volts<br>volts  |
| Triode Unit:  |                    |                 |
| Grid to Plate   | 1.7                | pf              |
| Grid to Cathode, Heater, Pentode Grid No.3, and Internal Shield   | 2                  | pf              |
| Plate to Cathode, Heater, Pentode Grid No.3, and Internal Shield  | 1.7                | pf              |
| Pentode Unit:   |                    |                 |
| Grid No.1 to Plate  | 0.02 max           | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield  Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal | 6.5                | pf              |
| Shield  | 2.2                | pf              |
| Triode Grid to Pentode Plate  | 0.027 max          | pf              |
| Pentode Grid No.1 to Triode Plate   | 0.020 max          | pf              |
| Pentode Plate to Triode Plate   | 0.045 max          | pf              |
| remode Plate to Thode Plate   | Valit Cho.o.       | pı              |

The heater-cathode voltage of the pentode unit should not exceed the value of the operating cathode bias. If the heater-cathode voltage exceeds the operating cathode bias value, grid No.3 will be made negative with respect to cathode, and thus possibly cause a change in tube characteristics.

The dc component must not exceed 100 volts.

| Class A. Amplifier  |             |            |            |
|---|-------------|------------|------------|
| MAXIMUM RATINGS (Design-Center Values):                     | Triode Unit | Pentode Ur |            |
| Plate Voltage   | 300 max     | 300 max    |            |
| Grid-No.2 (Screen-Grid) Supply Voltage                      | -           | 300 max    | volts      |
| Grid-No.2 Voltage   |             | See cur    | ve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value.      | 0 max       | 0 max      | volts      |
| Plate Dissipation   | 2.6 max     | 2 max      | watts      |
| Grid-No.2 Input:  |             |            |            |
| For grid-No.2 voltages up to 150 volts                      |             | 0.5 max    | watt       |
| For grid-No.2 voltages between 150 and 300 volts            | _           | See cur    | ve page 75 |
| CHARACTERISTICS:  |             |            |            |
| Plate Supply Voltage  | 200         | 200        | volts      |
| Grid-No.2 Voltage   |             | 150        | volts      |
| Grid-No.1 Voltage   | -6          | _          | volts      |
| Cathode-Bias Resistor                                       | Ľ           | 180        | ohms       |
| Amplification Factor  | 19          |            | 011110     |
| Plate Resistance (Approx.)                                  | 5750        | 300000     | ohms       |
| Transconductance  | 3300        | 6000       | μmhos      |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ a | -19         | -          | volts      |
| Grid-No.1 Voltage (Approx.) for transconductance of         |             |            | 1010       |
| 100 µmhos   |             | -12.5      | volts      |
| Plate Current   | 13          | 9.5        | ma         |
| Grid-No.2 Current   | 13          | 3          | ma         |
| Ghd-No.2 Cuttent  | _           | 3          | ma         |
| MAXIMUM CIRCUIT VALUES:                                     |             |            |            |
| Grid-No.1-Circuit Resistance:*                              |             |            |            |
| For fixed-bias operation                                    | 0.5 max     | 0.25 max   | megohm     |
| For cathode-bias operation                                  | 1.0 max     |            | meghom     |

<sup>\*</sup> If either unit is operating at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated values.

**6B5** 

### **POWER TRIODE**

6B4G Discontinued type; see chart at end of section for tabulated data.

### DIRECT-COUPLED POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

### TWIN DIODE ... HIGH-MU TRIODE

6B6G Discontinued type; see chart at end of section for tabulated data.

### TWIN DIODE-**6B7** REMOTE-CUTOFF PENTODE **6B7S**

Discontinued types; see chart at end of section for tabulated data.

### TWIN DIODE-SEMIREMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

### TWIN DIODE-SEMIREMOTE-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.


### TWIN DIODE-MEDIUM-MU TWIN TRIODE

6B10 Related type: 8R10

**6B8** 

6B8G

Duodecar type used in television receivers; diode units are used in horizontal-phase-detector circuits, triode units are used in horizontaloscillator circuits. Outline 8A, Outlines section. Tube requires duodecar



-20

volts

twelve-contact socket and may be mounted in any position. Type 8B10 is identical with type 6B10 except for heater ratings, as shown below.

|  | 6B10      | 8B10    |         |
|--|-----------|---------|---------|
| Heater Voltage (ac/dc)                                   | 6.3       | 8.5     | volts   |
| Heater Current   | 0.6       | 0.45    | ampere  |
| Heater Warm-up Time (Average)                            | 11        | 11      | seconds |
| Peak Heater-Cathode Voltage:                             |           |         |         |
| Heater negative with respect to cathode                  | 200 max   | 200 max | volts   |
| Heater positive with respect to cathode                  | 200°max   | 200°max | volts   |
| <sup>o</sup> The dc component must not exceed 100 volts. |           |         |         |
| Class A Amplifier (Each Tri                              | ode Unit) |         |         |

### MAXIMUM RATINGS (Design-Maximum Value):

Grid Voltage (Approx.) for plate current of 50 µa ......

| Plate Voltage              | 330 max | volts |
|----------------------------|---------|-------|
| DC Cathode Current         |         | ma    |
| Plate Dissipation          | 3 max   | watts |
| CHARACTERISTICS:           |         |       |
| Plate Voltage              | 250     | volts |
| Grid Voltage               |         | volts |
| Amplification Factor       | 18      |       |
| Plate Resistance (Approx.) | 7200    | ohms  |
| Transconductance           | 2500    | μmhos |
| Plate Current              | 10      | ma    |

| MAXIMUM | CIRCUIT | VALUES: |
|---------|---------|---------|


| **** |        |      | CIICOII     |  |
|------|--------|------|-------------|--|
| Gri  | id-Ciı | cuit | Resistance: |  |
|      |        |      |             |  |

|                            | 0.25 max |        |
|----------------------------|----------|--------|
| For cathode-bias operation | 1 max    | megohm |

### Diode Units (Each Unit)

| Divide Office (Each Office)            |       |    |
|--|-------|----|
| MAXIMUM RATING (Design-Maximum Value): |       |    |
| Plate Current                          | 5 max | ma |

CHARACTERISTICS, Instantaneous Value:



### HALF-WAVE VACUUM RECTIFIER

Novar type used as damper tube in horizontal-deflection circuits of television receivers. Outline 11B or 30C, Outlines section. Tube requires novar nine-contact socket and may be mounted in any position. Socket termi-

6BA3

nals 1, 3, 6, and 8 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated.

| Heater Voltage (ac/dc)  | 6,3 | volts    |
|---|-----|----------|
| Heater Current  Direct Interelectrode Capacitances, (Approx.):                        | 1.2 | amperes  |
| Plate to Cathode and Heater  Cathode to Plate and Heater                              | 4.4 | pf       |
| Heater to Cathode   | 1.8 | pf<br>pf |
| Damper Service  |     |          |
| For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values): |     |          |
| MAXIMUM KATINGS (Design-Maximum Values):  |     |          |

| MAAIMUM KAIINGS (Design-Maximum Values); |          |       |
|--|----------|-------|
| Peak Inverse Plate Voltage               | 5000 max | volts |
| Peak Plate Current                       | 1000 max | ma    |
| DC Plate Current                         | 165 max  | ma    |
| Plate Dissipation                        | 5.3 max  | watts |
| Peak Heater-Cathode Voltage:             | 0.0      |       |
| Heater negative with respect to cathode  | 5000 max | volts |
| Heater positive with respect to cathode  | 300□max  | volts |

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 900 volts.
- The dc component must not exceed 100 volts.



### **REMOTE-CUTOFF PENTODE**

Miniature type used as rf amplifier in standard broadcast and FM receivers, as well as in wide-band, highfrequency applications. The low value of grid-No.1-to-plate capacitance minimizes regenerative effects, while the


6BA6 Related types: 3BA6, 12BA6

high transconductance makes possible high signal-to-noise ratio. Types 3BA6 and 12BA6 are identical with type 6BA6 except for heater ratings, as shown below.

|   | 3BA6    | 6BA6    | 12BA6   |         |
|---|---------|---------|---------|---------|
| Heater Voltage (ac/dc)                  | 3.15    | 6.3     | 12.6    | volts   |
| Heater Current                          | 0.6     | 0.3     | 0.15    | ampere  |
| Heater Warm-up Time (Average)           | 11      |         | _       | seconds |
| Peak Heater-Cathode Voltage:            |         |         |         |         |
| Heater negative with respect to cathode | 200 max | 200 max | 200 max | volts   |
| Heater positive with respect to cathode | 200₄max | 200₄max | 200₄max | volts   |

| Direct Interelectrode Capacitances:                                     |            |    |
|---|------------|----|
| Grid No.1 to Plate  | 0.0035 max | pf |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield | 5.5        |    |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal            | 3.3        | pf |
| Shield  | 5●         | pf |

| △ The dc component must not exceed 100 volts.  This value is 5.5 pf with external shield connected to cathode. |              |            |
|--|--------------|------------|
| Class A <sub>1</sub> Amplifier MAXIMUM RATINGS (Design-Maximum Values):  |              |            |
| Plate Voltage  | 330 max      | volts      |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value  | 0 max        | volts      |
| Grid-No.2 (Screen-Grid) Voltage  | See cur      | ve page 75 |
| Grid-No.2 Supply Voltage   | 330 max      |            |
| Plate Dissipation  | 3.4 max      | watts      |
| Grid-No.2 Input:   |              |            |
| For grid-No.2 voltages up to 165 volts   | 0.7 max      | watt       |
| For grid-No.2 voltages between 165 and 330 volts   | See cur      | ve page 75 |
| Grid-No.1 (Control-Grid) Voltage:  |              |            |
| Negative bias value  | -55 max      | volts      |
| Positive bias value  | 0 max        | volts      |
| CHARACTERISTICS:   |              |            |
| Plate Supply Voltage 100   | 250          | volts      |
|  | d to cathode |            |
| Grid-No. 2 Supply Voltage  | 100          | volts      |
| Cathode-Bias Resistor 68   | 68           | ohms       |
| Plate Resistance (Approx.) 0.25  | 1.0          | megohm     |
| Transconductance   | 4400         | μmhos      |
| Grid-No.1 Voltage (Approx.) for transconductance   | · · · · · ·  | F00        |
| of 40 μmhos  | -20          | volts      |
| Plate Current 10.8   | 11           | ma         |
| Grid-No.2 Current  | 4.2          | ma         |



### Installation and Application

Type 6BA6 requires miniature seven-contact socket and may be mounted in any position. Outline 5C, Outlines section.

Control-grid bias variation will be found effective in changing the volume of the receiver. In order to obtain adequate volume control, an available grid-No.1-bias voltage of approximately 50 volts will be required. The exact value will depend upon the circuit design and operating conditions. This voltage may be obtained, depending on the receiver requirements, from a potentiometer across a

fixed supply voltage, from a variable cathode-bias resistor, from the avc system, or from a combination of these methods.

The grid-No.2 (screen-grid) voltage may be obtained from a potentiometer or bleeder circuit across the B-supply source, or through a dropping resistor from the plate supply. The use of series resistors for obtaining satisfactory control of grid-No.2 voltage in the case of four-electrode tubes is usually impossible because of secondary-emission phenomena. In the 6BA6, however, because grid No.3 practically removes these effects, it is practical to obtain grid-No.2 voltage through a series-dropping resistor from the plate supply or from some high intermediate voltage, provided the source does not exceed the plate-supply voltage. With this method, the grid-No.2-to-cathode voltage will fall off very little from minimum to maximum value of the resistor controlling cathode bias. In some cases, it may actually rise. This rise of grid-No.2-to-cathode voltage above the normal maximum value is allowable because both the grid-No.2 current and the plate current are reduced simultaneously by a sufficient amount to prevent damage to the tube. It should be recognized that, in general, the series-resistor method of obtaining grid-No.2 voltage from a higher voltage supply necessitates the use of the variable cathode-resistor method of controlling volume in order to prevent too high a voltage on grid No.2. When grid-No.2 and control-grid voltage are obtained in this manner, the remote "cutoff" advantage of the 6BA6 can be fully realized. However, it should be noted that the use of a resistor in the grid-No.2 circuit will have an effect on the change in plate resistance with variation in grid-No.3 (suppressorgrid) voltage in case grid No.3 is utilized for control purposes.

Grid No.3 (suppressor grid) may be connected directly to the cathode or it may be made negative with respect to the cathode. For the latter condition, the grid-No.3 voltage may be obtained from a potentiometer or bleeder circuit, or

from the avc system.



### PENTAGRID CONVERTER

Miniature type used as converter in superheterodyne circuits especially those for the FM broadcast band. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

6BA7

Heater volts (ac/dc), 6.3; amperes, 0.3; peak heater-cathode volts, 90.

**Converter Service** 

| Onitalite: Selaice                        |          |       |
|---|----------|-------|
| MAXIMUM RATINGS (Design-Center Values):   |          |       |
| Plate Voltage                             | 300 max  | volts |
| Grid-No.5-and-Internal-Shield Voltage4    | 0 max    | volts |
| Grids-No.2-and-No.4 (Screen-Grid) Voltage | 100 max  | volts |
| GridsNo.2-and-No.4 Supply Voltage         | 300 max  | volts |
| Plate Dissipation                         | 2.0 max  | watts |
| Grids-No.2-and-No.4 Input                 | 1.5 max  | watts |
| Total Cathode Current                     |          | ma    |
| Grid-No.3 Voltage:                        | 111000   | ***** |
| Negative bias value                       | -100 max | volts |
| Positive bias value                       |          | volts |
| **************************************    | Jillan   | 10103 |
| CHARACTERISTICS (Separate Excitation):*   |          |       |

| Grid No.5 and Internal Shield Grids-No.2-and-No.4 (Screen-Grid) Voltage Grid-No.3 (Control-Grid) Voltage Grid-No.1 (Oscillator-Grid) Resistor Plate Resistance (Approx.) Conversion Transconductance | 100<br>-1.0<br>20000<br>0.5<br>900 | 100<br>-1.0<br>20000<br>1.0<br>950 | volts to ground volts volt ohms megohm  µmhos |
|--|------------------------------------|------------------------------------|---|
| Conversion Transconductance (Approx.)**  | 900                                | 950                                | μmhos   |
|  | 3.5                                | 3.5                                | μmhos   |

| Plate Current               | 3.6  | 3.8  | ma |
|-----------------------------|------|------|----|
| Grids-No.2-and-No.4 Current | 10.2 | 10   | ma |
| Grid-No.1 Current           | 0.35 | 0.35 | ma |
| Total Cathode Current       | 14.2 | 14.2 | ma |

NOTE: The transconductance between grid No.1 and grids No.2 and No.4 connected to plate (not oscillating) is approximately  $8000~\mu$ mhos under the following conditions: signal applied to grid No.1 at zero bias; grids No.2 and No.4 and plate at 100 volts; grid No.3 grounded. Under the same conditions, the plate current is 32 milliamperes, and the amplification factor is 16.5.

\* The characteristics shown with separate excitation correspond very closely with those obtained in a self-excited oscillator circuit operating with zero bias.


\*\* With grid-No.3 bias of -20 volts.

A Internal Shield (pins No.6 and No.8) connected directly to ground.

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6BA8A
Related type:
8BA8A

Miniature type used in a wide variety of applications in color and blackand-white television receivers. This type has a controlled heater warm-up time for use in receivers employing series-connected heater strings. The



SDASA

Pentode

pentode unit is used as a video amplifier, an age amplifier, or a reactance tube. The triode unit is used in low-frequency oscillator and phase-splitter circuits. Outline 6E, **Outlines** section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8BA8A is identical with type 6BA8A except for the heater ratings, as shown below.

CD A O A

Triode

|   | ODAOA    | OBAGA    |         |
|---|----------|----------|---------|
| Heater Voltage (ac/dc)                        | 6.3      | 8.4      | volts   |
| Heater Current                                | 0.3      | 0.45     | ampere  |
| Heater Warm-up Time (Average)                 | 11       | _        | seconds |
| Peak Heater-Cathode Voltage:                  |          |          |         |
| Heater negative with respect to cathode       | 200 max  | 200 max  | volts   |
| Heater positive with respect to cathode       | 200° max | 200° max | volts   |
|   | Without  | With     |         |
| Direct Interelectrode Capacitances (Approx.): | External | External |         |
| Triode Unit:                                  | Shield   | Shield=  |         |
| Grid to Plate                                 | 2.2      | 2.2      | pf      |
| Grid to Cathode and Heater                    | 2.5      | 2.7      | pf      |
| Plate to Cathode and Heater                   | 0.4      | 1.9      | pf      |
| Pentode Unit:                                 |          |          | • -     |
| Grid No.1 to Plate                            | 0.06     | 0.05     | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid | -        |          | -       |
| No.3, and Internal Shield                     | 10       | 10       | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid     |          |          | •-      |
| No.3, and Internal Shield                     | 3.6      | 4.5      | pf      |
| Triode Grid to Pentode Plate                  | 0.016    | 0.006    | pf      |
| Pentode Grid No.1 to Triode Plate             | 0.006    | 0.003    | pf      |
| Pentode Plate to Triode Plate                 | 0.15     | 0.023    | pf      |
|   |          |          | • -     |


The dc component must not exceed 100 volts.

Class A<sub>1</sub> Amplifier

| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: | Unit<br>300 max<br>— | Unit<br>300 max<br>300 max<br>See curve | volts          |
|--|----------------------|---|----------------|
| Negative bias value Positive bias value  | _                    | -50 max<br>0 max                        | volts<br>volts |
| Plate Dissipation  | 2 max                | 3.25 max                                | watts          |

With external shield connected to cathode of unit under test.

| Grid-No.2 Input:  For grid-No.2 voltages up to 150 volts  For grid-No.2 voltages between 150 and 300 volts . | Triode Unit | Pentode Uni<br>1 max<br>See curve | watt       |
|--|-------------|-----------------------------------|------------|
| CHARACTERISTICS:   | 200         | 200                               | volts      |
| Plate-Supply Voltage   |             |                                   |            |
| Grid-No.2 Supply Voltage   | _           | 150                               | volts      |
| Grid-No.1 Voltage  | 8           |                                   | volts      |
| Cathode-Bias Resistor  | -           | 180                               | ohms       |
| Amplification Factor   | 18          |                                   | _          |
| Plate Resistance (Approx.)   | 6700        | 400000                            | ohms       |
| Transconductance   | 2700        | 9000                              | $\mu$ mhos |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ a  | -16         | 10                                | volts      |
| Plate Current  | 8           | 13                                | ma         |
| Grid-No.2 Current  | -           | 3.5                               | ma         |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:  |             |                                   |            |
| For fixed-bias operation   | 0.5 max     | 0.25 max                          | megohm     |
| For cathode-bias operation   | 1.0 max     | 1.0 max                           | megohm     |
|  |             |                                   |            |



### TRIODE—TWIN PENTODE

Duodecar type used as vertical deflection oscillator and for combined sync-age applications in television receivers employing series-connected heater strings. Outline 8B, Outlines section. Tube requires duodecar

6BA11

twelve-contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode). For ratings and characteristics of pentode units, refer to type 6HS8.

Triode Unit As Class A<sub>1</sub> Amplifier

| MAINON RAINOS (Design-Center Values).              |          |        |
|--|----------|--------|
| Plate Voltage                                      | 300 max  | volts  |
| Average Cathode Current                            | 20 max   | ma     |
|  | 1.5 max  | watts  |
| Plate Dissipation                                  | 1.5 max  | waits  |
| CHARACTERISTICS:                                   |          |        |
| Plate Voltage                                      | 250      | volts  |
| Grid Voltage                                       | -11      | volts  |
|  |          | VOILS  |
| Amplification Factor                               | 18       |        |
| Transconductance                                   | 1800     | μmhos  |
| Plate Current                                      | 5        | ma     |
| Grid Voltage (Approx.) for plate current of 100 μa | -18      | volts  |
| MAXIMUM CIRCUIT VALUES:                            |          |        |
| Grid-Circuit Resistance:                           |          |        |
| VIII   | 0.25 max |        |
| For fixed-bias operation                           | U.23 max | meroum |



### MEDIUM-MU TRIODE

Miniature type used as an rf amplifier in the cathode-drive circuits of uhf television tuners covering the frequency range of 470 to 890 megacycles per second. Outline 6A, Outlines section. Tube requires miniature nine-

**6BC4** 

1 max megohm

contact socket and may be mounted in any position.

For cathode-bias operation .....


| volts  | 6.3   | age (ac/dc) | Voltage ( | Heater |
|--------|-------|-------------|-----------|--------|
| ampere | 0.225 | rent        | Current . | Heater |

| Peak Heater-Cathode Voltage:                           |       |       |           |
|--|-------|-------|-----------|
| Heater negative with respect to cathode                | 75    | max   | volts     |
| Heater positive with respect to cathode                | 75    | max   | volts     |
| Direct Interelectrode Capacitances (Approx.);          | ,     |       |           |
| Grid to Plate  | 1.6   |       | pf        |
| Grid to Heater and Cathode                             | 2.9   |       | pf        |
| Plate to Heater and Cathode                            | 0.26  |       | pf        |
| Heater to Cathode                                      | 2.7   |       | pf        |
| Heater to Camoue                                       | 2.1   |       | Pι        |
| Class A. Amplifier                                     |       |       |           |
| MAXIMUM RATINGS (Design-Center Values):                |       |       |           |
|  | 250   |       | volts     |
| Plate Voltage  |       | max   |           |
| Plate Dissipation                                      |       | max   | watts     |
| Cathode Current  | 25    | max   | ma        |
| CHARACTERISTICS:                                       |       |       |           |
| Plate Supply Voltage                                   | 150   |       | voits     |
| Cathode-Bias Resistor                                  | 100   |       | ohms      |
| Amplification Factor                                   | 48    |       | Omms      |
| Plate Resistance (Approx.)                             | 4800  |       | ohms      |
|  | 10000 |       |           |
|  |       |       | μmhos     |
| Grid Voltage (Approx.) for plate current of 10 $\mu$ a | -10   |       | volts     |
| Plate Current  | 14.5  |       | ma        |
| MAXIMUM CIRCUIT VALUES:                                |       |       |           |
| Grid-Circuit Resistance:                               |       |       |           |
| For fixed-bias operation                               | Not   | recom | mended    |
| For cathode-bias operation                             |       |       | negohm    |
| TOI Camoue-Dias Operation                              | 0.5   | maa l | TICKOUIII |

### SHARP-CUTOFF PENTODE

Related type: 3BC5

Miniature type used in compact radio equipment as an rf or if amplifier at frequencies up to 400 megacycles per second. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any



position. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 3BC5 is identical with type 6BC5 except for heater ratings, as shown below.

|  | 3BC5             | 6BC5      |         |
|--|------------------|-----------|---------|
| Heater Voltage (ac/dc)                               | 3.15             | 6.3       | volts   |
| Heater Current                                       | 0.6              | 0.3       | ampere  |
| Heater Warm-up Time (Average)                        | 11               | _         | seconds |
| Peak Heater-Cathode Voltage:                         |                  |           |         |
| Heater negative with respect to cathode              | 200 max          | 90 max    | volts   |
| Heater positive with respect to cathode              | 200 <b>•</b> max | 90 max    | volts   |
| Direct Interelectrode Capacitances:                  |                  |           |         |
| Pentode Connection:                                  |                  |           |         |
| Grid No.1 to Plate                                   |                  | 0.030 max | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3   | 3, and           |           |         |
| Internal Shield                                      | 6.5              | pf        |         |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and  |                  |           |         |
| Internal Shield                                      |                  | 1.8       | pf      |
| Triode Connection:*                                  |                  |           |         |
| Grid No.1 to Plate and Grid No.2                     |                  | 2.5       | pf      |
| Grid No.1 to Cathode, Heater, Grid No.3, and Interna |                  | 3.9       | pf      |
| Plate and Grid No.2 to Cathode, Heater, Grid No.3,   | and              |           |         |
| Internal Shield                                      |                  | 3.0       | pf      |
| The dc component must not exceed 100 volts.          |                  |           |         |
| * Grid No.2 connected to plate.                      |                  |           |         |

| Class A: Amplifier                                    |                        |                       |       |
|---|------------------------|-----------------------|-------|
| Oldos At Ampillier                                    | Triode                 | Pentode               |       |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage | Connection*<br>300 max | Connection<br>300 max | volts |
| Grid-No.2 (Screen-Grid) Supply Voltage                | _                      | 300 max               | volts |

| Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation                  | 0 max<br>2.5 max | See curve page 75<br>0 max volts<br>2 max watts |
|--|------------------|---|
| Grid-No.2 Input:  For grid-No.2 voltages up to 150 volts  For grid-No.2 voltages between 150 and 300 volts | _                | 0.5 max watt<br>See curve page 75               |

| CHARACTERISTICS:                                 |        | ode<br>ection* |      | Pentod<br>onnecti | -    |        |
|--|--------|----------------|------|-------------------|------|--------|
| Plate Supply Voltage                             | 180    | 250            | 100  | 125               | 250  | volts  |
| Grid-No.2 Supply Voltage                         | . –    |                | 100  | 125               | 150  | volts  |
| Cathode-Bias Resistor                            |        | 820            | 180  | 100               | 180  | ohms   |
| Amplification Factor                             | . 42   | 40             | _    | _                 |      |        |
| Plate Resistance (Approx.)                       | .0.006 | 0.009          | 0.6  | 0.5               | 0.8  | megohm |
| Transconductance                                 | 6000   | 4400           | 4900 | 6100              | 5700 | μmhos  |
| Grid-No.1 Voltage (Approx.) for plate current of |        |                |      |                   |      | •      |
| 10 μα  |        |                | 5    | -6                | 8    | volts  |
| Plate Current                                    | . 8    | 6              | 4.7  | 8                 | 7.5  | ma     |
| Grid-No.2 Current                                | . –    | _              | 1.4  | 2.4               | 2.1  | ma     |

<sup>\*</sup> Grid No.2 connected to plate.



### TRIPLE DIODE


Miniature type containing three highperveance diode units in one envelope; used in dc restorer circuits of color television receivers. Also used in AM/FM radio receivers as a combination FM discriminator and AM

**6BC7** 

detector tube. Outline 6B, Outlines section. Tube requires nine-contact miniature socket and may be mounted in any position.

| Heater Voltage (ac/dc)  | 6.3<br>0.450                | volts<br>ampere   |
|---|-----------------------------|-------------------|
| Heater negative with respect to cathode   | 200 max                     | volts             |
| Heater positive with respect to cathode  Direct Interelectrode Capacitances (Approx.):                                    | 200 max                     | volts             |
| Diode-No.1 Plate to Diode-No.1 Cathode, Heater, and Internal Shield   | 3.5                         | pf                |
| Diode-No.2 Plate to Diode-No.2 Cathode, Heater, and Internal Shield   | 5.5                         | pf                |
| Diode-No.3 Plate to Diode-No.3 Cathode, Heater, and Internal Shield   | 3.5                         | pf                |
| MAXIMUM RATINGS (Design-Center Values, Each Diode Unit): Peak Inverse Plate Voltage Peak Plate Current* DC Output Current | 330 max<br>54 max<br>12 max | volts<br>ma<br>ma |

<sup>\*</sup> In rectifier service, the minimum total effective plate-supply impedance per plate is 560 ohms.



### MEDIUM-MU TWIN TRIODE

Miniature type used in direct-coupled cathode-drive rf amplifier circuits of whf television tuners. In such circuits, one triode unit is used as the direct-coupled grounded-cathode driver for the other unit. This type is also used

6BC8
Related type:
4BC8

in push-pull cathode-drive rf amplifiers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 4BC8 is identical with type 6BC8 except for heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 4BC8<br>4.2<br>0.6<br>11 | 6BC8<br>6.3<br>0.4 | volts<br>ampere<br>seconds |
|--|--------------------------|--------------------|----------------------------|
| Heater negative with respect to cathode  | 200-max                  | 200₄max            | volts                      |
| Heater positive with respect to cathode  | 200 max                  | 200 max            | volts                      |
| Direct Interelectrode Capacitances*:   | Unit No.1                | Unit No.2          |                            |
| Grid to Plate  | 1.2                      | 1.2                | pf                         |
| Grid to Cathode, Heater, and Internal Shield   | 2.6                      | _                  | pf                         |
| Cathode to Grid, Heater, and Internal Shield   |                          | 5.5                | pf                         |
| Plate to Cathode, Heater, and Internal Shield  | 1.3                      | _                  | pf                         |
| Plate to Grid, Heater, and Internal Shield   | _                        | 2.4                | pf                         |
| Plate to Cathode   | _                        | 0.12               | pf                         |
| Heater to Cathode  | 2.8                      | 2.8                | pf                         |
| Plate of Unit No.1 to Plate of Unit No.2   | 0.02                     | max                | pf                         |
| Plate of Unit No.2 to Plate and Grid of Unit No.1  | 0.04                     | max                | pf                         |

- $\dot{\Delta}$  This rating may be as high as 300 volts under cutoff conditions, when the tube is used as a cascode amplifier and the two units are connected in series.
- The dc component must not exceed 100 volts.
- \* With external shield connected to internal shield.

Class A. Amplifier (Each Unit)

| MAXIMUM RATINGS (Design-Maximum Values):                     |         |            |
|--|---------|------------|
| Plate Voltage  | 250≟max | volts      |
| Plate Dissipation  | 2.2 max | watts      |
| Cathode Current  | 22 max  | ma         |
| CHARACTERISTICS:   |         |            |
| Plate Supply Voltage   | 150     | volts      |
| Cathode-Bias Resistor  | 220     | ohms       |
| Plate Resistance (Approx.)                                   | 5300    | ohms       |
| Amplification Factor   | 35      |            |
| Transconductance   | 6200    | $\mu$ mhos |
| Grid Voltage (Approx.) for transconductance of 50 $\mu$ mhos | 13      | volts      |
| Plate Current  | 10      | ma         |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-Circuit Resistance .....

0.5 max megohm

Δ This rating may be as high as 300 volts under cutoff conditions, when the tube is used as a cascode amplifier and the two units are connected in series.

6BD4 6BD4A

### SHARP-CUTOFF BEAM TRIODE

Discontinued types; see chart at end of section for tabulated data.


6BD6

### REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

### DUAL TRIODE— SHARP-CUTOFF PENTODE


6BD11 Related type: 15BD11 Duodecar type used in a variety of applications in television receivers. The high-mu triode unit No.1 is used in general-purpose applications, the medium-mu triode unit No.2 in syncseparator circuits, and the pentode



unit as a video amplifier. Outline 8B, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Type 15BD11 is identical with type 6BD11 except for heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode |                              | 6.3<br>1.05<br>—<br>200 max<br>200•max | 15BD11<br>14.7<br>0.45<br>11<br>200 max<br>200•max |                      |
|--|------------------------------|--|--|----------------------|
| • The dc component must not exceed 100 volts.  |                              |  |  |                      |
| Class A, A   | mplifier                     |  |  |                      |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage   | Triode<br>Unit No<br>330 mas | .1 Unit No.2                           | Pentode<br>Unit<br>330 ma<br>330 ma                | x volts              |
| Grid-No.2 Voltage  | _                            |  | See cui  | rve page 75          |
| value Plate Dissipation Grid-No.2 Input:   | 0 max<br>1.5 max             |  | 0 ma<br>4 ma                                       |                      |
| For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts  | _                            | _                                      | 1.1 ma   | x watts              |
| CHARACTERISTICS:   |                              |  | Pentode Ur   |                      |
| Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage  | 200<br>—2                    | 200<br>                                | 35 135<br>135 135<br>0 (                           | volts<br>volts       |
| Cathode-Bias Resistor  | -                            | 220                                    | 100  | ohms o               |
| Amplification Factor   | 68                           | 41                                     | - 45000  |                      |
| Plate Resistance (Approx.) Transconductance  | 12400<br>5500                | 9400<br>4400                           | - 45000<br>- 10400                                 | μmhos                |
| Plate Current  | 7                            | 9.2                                    | 34• 17<br>13• 4                                    |                      |
| Grid-No.1 Voltage (Approx.) for plate current of 100 µa  | -5.5                         | 6.5                                    | 6  |                      |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:  | 0.5                          |  | _  |                      |
| For fixed-bias operation  For cathode-bias operation   | 0.5 max                      |  |  | x megohm<br>x megohm |

• This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.



### HALF-WAVE VACUUM RECTIFIER

Duodecar type used as damper tube in horizontal-deflection circuits of television receivers. Outline 8D, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Types

12BE3

ODE3
Related types:

17BE3

12BE3, 17BE3

12BE3 and 17BE3 are identical with type 6BE3 except for the heater ratings, as shown below.

|           | 16.8         | voits  |
|-----------|--------------|--|
| 0.6       | 0.45         | ampere   |
| 11        | 11           | seconds  |
|           |              |  |
| ne system |              |  |
|           |              |  |
|           | 5000 max     | volts  |
|           | 1200 max     | ma   |
|           | 200 max      | ma   |
|           | 6.5 max      | watts  |
|           |              |  |
|           | 5000=max     | volts  |
|           | 300□max      | volts  |
|           | 11 ne system | 0.6 0.45<br>11 11 11 ne system 5000 max 200 max 6.5 max 5000 max |

CHARACTERISTICS. Instantaneous Value: Tube Voltage Drop for dc plate current of 350 ma ..... 25 volts #The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning

cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

- The dc component must not exceed 900 volts.
- □ The dc component must not exceed 100 volts.

### PENTAGRID CONVERTER

6BE6 Related types: 3BE6, 12BE6

Miniature type used as converter in superheterodyne circuits in both the standard broadcast and FM bands. The 6BE6 is similar in performance to metal type 6SA7. For general



discussion of pentagrid types, see

Frequency Conversion in Electron Tube Application section. Types 3BE6 and 12BE6 are identical with type 6BE6 except for the heater ratings, as shown below.

|   | 3BE6     | 6BE6     | 12BE6    |         |
|---|----------|----------|----------|---------|
| Heater Voltage (ac/dc)                        | 3.15     | 6.3      | 12.6     | volts   |
| Heater Current                                | 0.6      | 0.3      | 0.15     | ampere  |
| Heater Warm-up time (Average)                 | 11       | _        |          | seconds |
| Peak Heater-Cathode Voltage:                  |          |          |          |         |
| Heater negative with respect to cathode       | 200 max  | 200 max  | 200 max  | volts   |
| Heater positive with respect to cathode       | 200-max  | 200≟max  | 200∴max  | volts   |
| •   |          | Without  | With     |         |
|   |          | External | External |         |
| Direct Interelectrode Capacitances:           |          | Shield   | Shield.  |         |
| Grid No.3 to Plate                            | <b>.</b> | 0.30 max | 0.25 max | pf      |
| Grid No.3 to Grid No.1                        |          | 0.15 max | 0.15 max | pf      |
| Grid No.1 to Plate                            |          | 0.10 max | 0.05 max | pf      |
| Grid No.3 to All Other Electrodes             |          | 7.0      | 7.0      | pf      |
| Grid No.1 to All Other Electrodes             |          | 5.5      | 5.5      | pf      |
| Plate to All Other Electrodes                 |          | 8.0      | 13.0     | pf      |
| Grid No.1 to Cathode and Grid No.5            |          | 3.0      | 3.0      | pf      |
| Cathode and Grid No.5 to All Other Electro    | odes     |          |          | • -     |
| except Grid No.1                              |          | 15.0     | 20.0     | pf      |
| A The dc component must not exceed 100 volts. |          |          |          |         |

Plate Current .....

| △ The dc component must not exceed 100 volts.  ■ With external shield connected to cathode and grid No.5. |                         |          |        |
|---|-------------------------|----------|--------|
| Converter   |                         |          |        |
| MAXIMUM RATINGS (Design-Maximum Values):  |                         | 330 max  | volts  |
| Plate Voltage Grids-No.2-and-No.4 (Screen-Grid) Voltage   |                         |          |        |
|   |                         | 110 max  | volts  |
| Grids-No.2-and-No.4 Supply Voltage  |                         | 330 max  | volts  |
| Plate Dissipation   | · · · · · · · · · · · · | 1.1 max  | watts  |
| Grids-No.2-and-No.4 Input   |                         | 1.1 max  | watts  |
| Cathode Current   |                         | 15.5 max | ma     |
| Grid-No.3 Voltage:  |                         |          |        |
| Negative bias value   |                         | —55 max  | volts  |
| Positive bias value   |                         | 0 max    | volts  |
| Peak Heater-Cathode Voltage:  |                         |          |        |
| Heater negative with respect to cathode   |                         | 200 max  | volts  |
| Heater positive with respect to cathode   |                         | 200≟max  | volts  |
| TYPICAL OPERATION (Separate Excitation):*   |                         |          |        |
| Plate Voltage   | 100                     | 250      | volts  |
| Grids-No.2-and-No.4 (Screen-Grid) Voltage   | 100                     | 100      | volts  |
| Grid-No.1 (Oscillator-Grid) Voltage (rms)   | 10                      | 10       | volts  |
| Grid-No.3 (Control-Grid) Voltage  | -1.5                    | -1.5     | volts  |
| Grid-No.1 (Oscillator-Grid) Resistor  | 20000                   | 20000    | ohms   |
| Plate Resistance (Approx.)  | 0.4                     | 1.0      | megohm |
| Conversion Transconductance   | 455                     | 475      | μmhos  |
| Grid-No.3 Voltage for conversion transconductance of  |                         |          | -      |
|   |                         |          |        |

-30

2.6

volts

ma

| Grids-No.2-and-No.4 Current                                    | 7.0          | 6.8                  | ma      |
|--|--------------|----------------------|---------|
| Grid-No.1 Current  | 0.5          | 0.5                  | ma      |
| Cathode Current  | 10.1         | 10.2                 | ma      |
| NOTE: The transconductance between grid No.1 and grid          | s No.2 and   | No.4 connected to    | plate   |
| (not oscillating) is approximately 7250 $\mu$ mhos under the f | following co | onditions: grids No. | 1 and   |
| No.3 at 0 volts; grids No.2 and No.4 and plate at 100 vo       | olts. Under  | the same condition   | s, the  |
| cathode current is 25 ma., and the amplification factor is     | 20. Grid-N   | o.1 voltage (Approx  | r.) for |
| plate current of 10 $\mu a$ is -11 volts.                      |              | - · ••               |         |

\* The characteristics shown with separate excitation correspond very closely with those obtained in a self-excited oscillator circuit operating with zero bias.


### Installation and Application


Type 6BE6 requires miniature seven-contact socket and may be mounted in any position. Outline 5C, Outlines section.

Because of the special structural arrangement of the 6BE6, a change in signal-grid voltage produces little change in cathode current. Consequently, an rf voltage on the signal grid produces little modulation of the electron current flowing in the cathode circuit. This feature is important because it is desirable that the impedance in the cathode circuit should produce little degeneration or regeneration of the signal-frequency input and intermediate-frequency output. Another important feature is that, because signal-grid voltage has very little effect on the space charge near the cathode, changes in ave bias produce little change in oscillator transconductance and in the input capacitance of grid No.1. There is, therefore, little detuning of the oscillator by ave bias.

A typical self-excited oscillator circuit employing the 6BE6 is given in the Circuit section.

In the 6BE6 operation characteristics curves with self-excitation,  $E_{\mathbf{x}}$  is the voltage across the oscillator-coil section between cathode and ground;  $E_{\mathbf{g}}$  is the oscillator voltage between cathode and grid.





### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

6BF5

## **6BF6**

### TWIN DIODE— MEDIUM-MU TRIODE

Renewal type; see chart at end of section for tabulated data.


### BEAM POWER TUBE— SHARP-CUTOFF PENTODE

## 6BF11 Related type:

Plate Supply Voltage

Plate Resistance (Approx.)

Duodecar type used as combined detector and amplifier tube in television  $\epsilon_{ip}$  (some ceeivers. The dual-control, sharp-cutoff pentode unit is used as an FM detector and the beam power unit as an af output amplifier. Outline 8B,



........

150

100

560

0.15

1000

400

0

volts

volts

volts

ohms

megohm

μmhos

μmhos

Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Type 17BF11 is identical with type 6BF11 except for heater ratings, as shown below.

|   | 6BF11                                   | 17BF11   |   |
|---|---|----------|---|
| Heater Voltage (ac/dc)                                      | 6.3                                     | 16.8     | volts                                   |
| Heater Current  | 1.2                                     | 0.45     | amperes                                 |
| Heater Warm-up Time (Average)  Peak Heater-Cathode Voltage: |   | 11       | seconds                                 |
| Heater negative with respect to cathode                     | 200 max                                 | 200 max  | volts                                   |
| Heater positive with respect to cathode                     | 200•max                                 | 200 max  | volts                                   |
| • The dc component must not exceed 100 volts.               |   |          |   |
| Beam Power Unit as Class A                                  | , Amplifier                             |          |   |
| MAXIMUM RATINGS (Design-Maximum Values):                    |   |          |   |
| Plate Voltage   |   | 165 max  | volts                                   |
| Grid-No.2 (Screen-Grid) Voltage                             |   | 150 max  | volts                                   |
| Plate Dissipation   |   | 6.5 max  | watts                                   |
| Grid-No.2 Input   |   | 1.8 max  | watts                                   |
| Average Cathode Current                                     |   | 65 max   | ma                                      |
| TYPICAL OPERATION:  |   |          |   |
| Plate Voltage   |   | 145      | volts                                   |
| Grid-No.2 Voltage   |   | 110      | volts                                   |
| Grid-No.1 (Control-Grid) Voltage                            |   | 6        | volts                                   |
| Peak AF Grid-No.1 Voltage                                   |   | 6        | volts                                   |
| Zero-Signal Plate Current                                   |   | 36       | ma                                      |
| Maximum-Signal Plate Current                                |   | 40       | ma                                      |
| Zero-Signal Grid No.2 Current                               |   | 3<br>9   | ma                                      |
| Maximum-Signal Grid-No.2 Current                            |   | 0.03     | ma<br>megohm                            |
| Plate Resistance (Approx.)                                  |   | 8600     | umhos                                   |
| Load Resistance   |   | 3000     | ohms                                    |
| Total Harmonic Distortion                                   |   | 10       | per cent                                |
| Maximum-Signal Power Output                                 |   | 2.4      | watts                                   |
| Waxingin Dignar Tower Output                                |   | 2.4      | *************************************** |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:       |   |          |   |
| For fixed-bias operation                                    |   | 0.25 max |   |
| For cathode-bias operation                                  | • | 0.5 max  | megohm                                  |
| Pentode Unit as Class A, A                                  | Amplifier                               |          |   |
| CHARACTERISTICS:  |   |          |   |

Grid-No.3 (Suppressor-Grid) Voltage ......

Grid-No.2 (Screen-Grid) Supply Voltage ......

Cathode-Bias Resistor .....

Transconductance, Grid No.1 to Plate ......

Transconductance, Grid No.3 to Plate .....

| Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 30 μa Grid-No.3 Voltage (Approx.) for plate current of 50 μa | 1.3<br>2<br>4.5<br>4.5 | ma<br>ma<br>volts<br>volts |
|---|------------------------|----------------------------|
| Pentode Unit as FM Detector   |                        |                            |
| MAXIMUM RATINGS (Design-Maximum Values):  |                        |                            |
| Plate Voltage   | 330 max                | volts                      |
| Grid-No.3 Voltage   | 28 max                 | volts                      |
| Grid No.2 Supply Voltage  | 330 max                | volts                      |
| Grid-No.2 Voltage   | See curve              | page 75                    |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value   | 0 max                  | volts                      |
| Plate Dissipation   | 1.7 max                | watts                      |
| Grid-No.2 Input:  |                        |                            |
| For grid-No.2 voltages up to 165 volts  | 1.1 max                | watts                      |
| For grid-No.2 voltages between 165 and 330 volts  | See curve              | page 75                    |

### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

6BG6G



### **BEAM POWER TUBE**

Glass octal type used as output amplifier in horizontal-deflection circuits of television equipment and other applications where high pulse voltages occur during short duty cycles. Outline 21B, Outlines section. This tube

6BG6GA

requires octal socket and may be supplied with pins 4 and 6 or with pins 1, 4, and 6 omitted. Vertical tube mounting is preferred but horizontal operation is permissible if pins No.2 and 7 are in vertical plane.

| Heater Voltage (ac/dc) Heater Current                  | 6.3<br>0.9 | volts<br>ampere |
|--|------------|-----------------|
| Peak Heater-Cathode Voltage:                           | 0.5        | ampere          |
| Heater negative with respect to cathode                | 200 max    | volts           |
| Heater positive with respect to cathode                | 200 max    | volts           |
| Direct Interelectrode Capacitances:                    |            |                 |
| Grid No.1 to Plate                                     | 0.8        | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 11         | pf              |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 6          | pf              |
| Transconductance°                                      | 6000       | μmhos           |
| Mu-Factor, Grid No.2 to Grid No.1°                     | 8.0        |                 |

- ° For plate and grid-No.2 volts, 250; grid-No.1 volts, -15.
- \* The dc component must not exceed 100 volts.

#### Horizontal Deflection Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage 700 max volts Peak Positive-Pulse Plate Voltage\* (Absolute Maximum) ...... 6600<sub>4</sub>max volts Peak Negative-Pulse Plate Voltage ..... -1500 max volts DC Grid-No.2 (Screen-Grid) Voltage ..... 350 max volts Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage ...... -300 max volts Peak Cathode Current ..... 400 max ma Average Cathode Current ..... 110 max ma Plate Dissipation†† ..... 20 max watts Grid-No.2 Input ...... 3.2 max watts Bulb Temperature (At hottest point) ..... 210 max °C

#### MAXIMUM CIRCUIT VALUE:

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- A Under no circumstances should this absolute value be exceeded.
- †† An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

### HALF-WAVE VACUUM RECTIFIER

### 6BH3 6BH3A

Related types: 17BH3, 17BH3A, 22BH3, 22BH3A Novar types used as damper tubes in horizontal deflection circuits of black-and-white television receivers. Outlines 11D and 30B, respectively, **Outlines** section. Tubes require novar socket and may be operated in any position.



Socket terminals 1, 3, 6, and 8 should not be used as tie points. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Types 17BH3 and 17BH3A and types 22BH3 and 22BH3A are identical with types 6BH3 and 6BH3A except for the heater ratings, as shown below.

|   | 6BH3<br>6BH3A | 17BH3<br>17BH3A   | 22BH3<br>22BH3A |         |
|---|---------------|-------------------|-----------------|---------|
| Heater Voltage (ac/dc)                        | 6.3           | 17                | 22.4            | volts   |
| Heater Current                                | 1.6           | 0.6               | 0.45            | amperes |
| Heater Warm-up Time (Average)                 |               | 11                | 11              | seconds |
| Direct Interelectrode Capacitances (Approx.): |               |                   |                 |         |
| Plate to Cathode and Heater                   |               |                   | 6.5             | pf      |
| Cathode to Plate and Heater                   |               |                   | 9.0             | pf      |
| Heater to Cathode                             | <b></b> .     | • • • • • • • • • | 2.8             | pf      |

#### Damper Service

| For operation in a 525-line, 30-frame system |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |          |       |
| Peak Inverse Plate Voltage                   | 5500 max | volts |
| Peak Plate Current                           | 1100 max | ma    |
| DC Plate Current                             | 180 max  | ma    |
| Plate Dissipation                            | 6.5 max  | watts |
| Peak Heater-Cathode Voltage:                 |          |       |
| Heater negative with respect to cathode      | 5500°max | volts |
| Heater positive with respect to cathode      | 300□max  | volts |

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 900 volts.
- The dc component must not exceed 100 volts.

### SHARP-CUTOFF PENTODE

6BH6


Miniature type used as rf amplifier particularly in ac/dc receivers and in mobile equipment where low heater-current drain is important. It is particularly useful in high-frequency, wide-band applications. Outline 5C,



Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc) Heater Current  | 6.3<br>0.15      | volts<br>ampere        |
|--|------------------|------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 90 max<br>90 max | volts<br>volt <b>s</b> |

| Direct Interelectrode Capacitances:  Grid No.1 to Plate  Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, an Internal Shield  Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield  Without external shield, or with external shield connected to | d 5.4 pf 4.4 pf               |
|---|-------------------------------|
| Class A, Amplifier  |                               |
| MAXIMUM RATINGS (Design-Center Values):   |                               |
| Plate Voltage Grid-No.2 (Screen-Grid) Voltage   |                               |
| Grid-No.2 Supply Voltage  |                               |
| Plate Dissipation   | 3 max watts                   |
| Grid-No.2 Input:  For grid-No.2 voltages up to 150 volts  | 0.5 max watt                  |
| For grid-No.2 voltages between 150 and 300 volts  |                               |
| Grid-No.1 (Control-Grid) Voltage:   | Bee curve page 15             |
| Negative-bias value   |                               |
| Positive-bias value   | 0 max volts                   |
| CHARACTERISTICS:  |                               |
| Plate Voltage   | 00 250 volts                  |
|   | onnected to cathode at socket |
|   | 00 150 volts                  |
|   | -1 -1 volt<br>0.7 1.4 megohms |
| Plate Resistance (Approx.)  | 0.7 1.4 megohms               |



Transconductance .....

Plate Current .....

Grid-No.2 Current .....

Grid-No.1 Voltage (Approx.) for plate current of

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

3400

Miniature type used in a wide variety of applications in television receivers. This type has a controlled heater warm-up time for use in receivers employing series-connected heater strings. The pentode unit is used as

6BH8
Related type:

1600

*u*mhos

volts

ma

ma

Related type 8BH8

91119

an if amplifier, a video amplifier, or an agc amplifier. The triode unit is used in low-frequency oscillator circuits. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8BH8 is identical with type 6BH8 except for the heater ratings, as shown below.

| оддо    | ODIIO     |   |
|---------|-----------|---|
| 8.4     | 6.3       | Heater Voltage (ac/dc)  |
| 0.45    | 0.6       | Heater Current  |
|         | 11        | Heater Warm-up Time (Average)   |
|         |           | Peak Heater-Cathode Voltage:  |
| 200 max | 200 max   | Heater negative with respect to cathode   |
| 200=max | 200 = max | Heater positive with respect to cathode   |
|         |           | Direct Interelectrode Capacitances (Approx.):   |
|         |           | Triode Unit:  |
| 2.4     |           | Grid to Plate   |
| 2.6     |           | Grid to Cathode and Heater  |
| 0.38    |           | Plate to Cathode and Heater   |
|         |           | Pentode Unit:   |
| 0.046   |           | Grid No.1 to Plate  |
|         |           | Grid No.1 to Cathode, Heater, Grid No.2, Grid   |
| 7       |           | Internal Shield   |
| -       |           | Plate to Cathode, Heater, Grid No.2, Grid No.3, as  |
| 2.4     |           | Shield  |
|         | 0.45<br>  | 0.6 0.45 11 — 200 max 200 m 200 max 200 max 200 m 200 |

Triode Grid to Pentode Plate

0.016

| rnode Grid to Pentode Plate                             |             | 0.016      | pı        |
|---|-------------|------------|-----------|
| Pentode Grid No.1 to Triode Plate                       |             | 0.004      | pf        |
| Pentode Plate to Triode Plate                           |             | 0.095      | pf        |
| • The dc component must not exceed 100 volts.           |             |            |           |
| Class A, Amplifier                                      |             |            |           |
| MAXIMUM RATINGS (Design-Center Values):                 | Triode Unit | Pentode Ur | nit       |
| Plate Voltage   | 300 max     | 300 max    | volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                  |             | 300 max    | volts     |
| Grid-No.2 Voltage                                       |             |            | e page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value   | 0 max       | 0 max      | volts     |
| Plate Dissipation                                       | 2.5 max     | 3 max      | watts     |
| Grid-No.2 Input:  |             |            |           |
| For grid-No.2 voltages up to 150 volts                  | _           | 1 max      | watt      |
| For grid-No.2 voltages between 150 and 300 volts        | -           | See curv   | e page 75 |
| CHARACTERISTICS:  |             |            |           |
| Plate Supply Voltage                                    | 150         | 200        | volts     |
| Grid-No.2 Supply Voltage                                | -           | 125        | volts     |
| Grid-No.1 Voltage                                       | <b>—</b> 5  | _          | volts     |
| Cathode-Bias Resistor                                   |             | 82         | ohms      |
| Amplification Factor                                    | 17          | _          |           |
| Plate Resistance (Approx.)                              | 5150        | 150000     | ohms      |
| Transconductance  | 3300        | 7000       | μmhos     |
| Grid-No.1 Voltage (Approx.) for plate current of 100 μa | <b>—14</b>  | 8          | volts     |
| Plate Current   | 9.5         | 15         | ma        |
| Grid-No.2 Current                                       |             | 3.4        | ma        |
| MAXIMUM CIRCUIT VALUES:                                 |             |            |           |
| Grid-No.1-Circuit Resistance:                           |             |            |           |
| For fixed-bias operation                                | 0.5 max     | 0.25 max   | megohm    |
| For cathode-bias operation                              | 1.0 max     | 1.0 max    | megohm    |

### HALF-WAVE VACUUM RECTIFIER

6BJ3

Duodecar type used as damper tube in horizontal-deflection circuits of television receivers. Outline 8C, **Outlines** section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Socket ter-




minals 5, 6, 8, and 9 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 6.3; amperes, 1.2.

#### **Damper Service**

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values): Peak Inverse Plate Voltage# ..... 3300 max volts Peak Plate Current ..... 840 max ma DC Plate Current ..... 140 max ma Plate Dissipation .... 4 max watts Peak Heater-Cathode Volts: Heater negative with respect to cathode ..... 33004max volts Heater positive with respect to cathode ..... 300+max volts CHARACTERISTICS, Instantaneous Value: Tube Voltage Drop for plate current of 250 ma ..... 21 volts

- #The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- ▲ The dc component must not exceed 600 volts.
- The dc component must not exceed 100 volts.



### REMOTE-CUTOFF PENTODE

Miniature type used as rf amplifier in high-frequency and wide-band applications. Features high transconductance and low grid-to-plate capacitance. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.


**6BJ6** 

| volts  | 6.3        | Heater Voltage (ac/dc)                                       |
|--------|------------|--|
| ampere | 0.15       | Heater Current   |
| =      |            | Peak Heater-Cathode Voltage:                                 |
| volts  | 90 max     | Heater negative with respect to cathode                      |
| volts  | 90 max     | Heater positive with respect to cathode                      |
|        |            | Direct Interelectrode Capacitances:                          |
| pf     | 0.0035 max | Grid No.1 to Plate   |
| _      |            | Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and      |
| pf     | 4.5        | Internal Shield  |
| _      |            | Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal |
| pf     | 5.5        | Shield   |

• Without external shield, or with external shield connected to cathode.

| MAXIMUM RATINGS (Design-Center Values):          | 200         | volts   |
|--|-------------|---------|
| Plate Voltage                                    | 300 max     |         |
| Grid-No.2 (Screen-Grid) Voltage                  | See curve p |         |
| Grid-No.2 Supply Voltage                         | 300 max     | volts   |
| Plate Dissipation                                | 3 max       | watts   |
| Grid-No.2 Input:                                 |             |         |
| For grid-No.2 voltages up to 150 volts           | 0.6 max     | watt    |
| For grid-No.2 voltages between 150 and 300 volts | See curve p | page 75 |
| Grid-No.1 (Control-Grid) Voltage:                |             |         |
| Negative bias value                              | -50 max     | volts   |
| Positive bias value                              | 0 max       | volts   |

| Plate Voltage                                       | 100                            | 250  | volts   |  |
|---|--------------------------------|------|---------|--|
| Grid No.3   | Connected to cathode at socket |      |         |  |
| Grid-No.2 Voltage                                   | 100                            | 100  | volts   |  |
| Grid-No.1 Voltage                                   | -1.0                           | -1.0 | volt    |  |
| Plate Resistance (Approx.)                          | 0.25                           | 1.3  | megohms |  |
| Transconductance                                    | 3650                           | 3600 | μmhos   |  |
| Grid-No.1 Voltage (Approx.) for transconductance of |                                |      |         |  |
| 10 μmhos  | -20                            | 20   | volts   |  |
| Plate Current                                       | 9.0                            | 9.2  | ma      |  |
| Grid-No.2 Current                                   | 3.5                            | 3.3  | ma      |  |



### TRIPLE DIODE

Miniature type used as a dc-restorer tube in each of the three signal channels of color-television receivers. Each diode has a separate cathode. Outline 6B, Outlines section. Tube re-

**6BJ7** 

<sup>KD3</sup> <sup>KD0</sup> quires miniature nine-contact socket and may be mounted in any position. Heater volts, 6.3; amperes, 0.45.

DC Restorer Service


| MAXIMUM RATINGS (Design-Center Values, Each Diode Unit): |         |       |
|--|---------|-------|
| Peak Inverse Plate Voltage                               | 330 max | volts |
| Peak Plate Current                                       | 10 max  | ma    |
| DC Output Current  | 1 max   | ma    |

Peak Heater-Cathode Voltage: Heater negative with respect to cathode ..... 330 max volts Heater positive with respect to cathode ..... 100 max volts

### TWIN DIODE-MEDIUM-MU TRIODE

**6BJ8** 

Miniature type used in a wide variety of applications in black-and-white and color television receivers. The diode units are used in phase-detector, phase-comparator, ratio-detector or discriminator, and horizontal afc dis-



criminator circuits. The triode unit is used in phase-splitter, audio-frequency amplifier, and low-frequency oscillator applications; it may also be used as a vertical-deflection amplifier in compact portable television receivers. This type has a controlled heater warm-up time for use in receivers employing series-connected heater strings. Each of the three units has its own cathode with individual base-pin terminal to provide for flexibility of circuit connections. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Volts (ac/dc)                                 | 6.3      | volts   |
|--|----------|---------|
| Heater Current                                       | 0.6      | ampere  |
| Heater Warm-up Time (Average)                        | 11       | seconds |
| Peak Heater-Cathode Voltage:                         |          |         |
| Heater negative with respect to cathode              | 200 max  | volts   |
| Heater positive with respect to cathode              | 200=max  | volts   |
| Direct Interelectrode Capacitances:                  |          |         |
| Triode Unit:   |          |         |
| Grid to Plate  | 2.6      | pf      |
| Grid to Cathode and Heater                           | 2.8      | pf      |
| Plate to Cathode and Heater                          | 0.31     | pf      |
| Diode Units:   |          | -       |
| Plate to Cathode and Heater (Each Unit)              | 1.9      | pf      |
| Cathode to Plate and Heater (Each Unit)              | 4.6      | pf      |
| Plate of Unit No.1 to Plate of Unit No.2             | 0.06 max | pf      |
| Plate of Diode Unit No.1 to Triode Grid              | 0.07 max | pf      |
| Plate of Diode Unit No.2 to Triode Grid              | 0.11 max | pf      |
| Plate of Either Diode Unit to All Other Electrodes   | 3.0      | pf      |
| Cathode of Either Diode Unit to All Other Electrodes | 4.8      | pf      |
| ■ The dc component must not exceed 100 volts,        |          |         |

|                 | Triode Unit As Class A. Amplifier |
|-----------------|-----------------------------------|
| MAXIMUM RATINGS | (Design-Maximum Values):          |
| Plate Voltage   |                                   |

330 max volts Grid Voltage, Positive-bias value ..... 0 max volts Average Cathode Current ..... 22 max ma Plate Dissipation ..... 4 max watts CHADACTEDISTICS.

|       |     |      | <br>- | - | • | - | • | • |
|-------|-----|------|-------|---|---|---|---|---|
| Plate | Vol | tage |       |   |   |   |   |   |

| Plate Voltage  | 90   | 250      | volts |
|--|------|----------|-------|
| Grid Voltage   | 0    | <b>9</b> | volts |
| Amplification Factor                                   | 22   | 20       |       |
| Plate Resistance (Approx.)                             | 4700 | 7150     | ohms  |
| Transconductance                                       | 4700 | 2800     | μmhos |
| Grid Voltage (Approx.) for plate current of 10 $\mu$ a | 7    | 18       | volts |
| Plate Current  | 13.5 | 8        | ma    |
| Plate Current for grid voltage of -12.5 volts          | _    | 1.7      | ma    |

### MAXIMUM CIRCUIT VALUE:

Grid-Circuit Resistance ..... 1 max megohm

#### Triode Unit As Vertical Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values):

DC Plate Voltage 330 max

Peak Positive Pulse Plate Voltaget 1200 may

| DC Plate Voltage                   | 330 max  | volts |
|------------------------------------|----------|-------|
| Peak Positive-Pulse Plate Voltage† | 1200 max | volts |
| Peak Negative-Pulse Grid Voltage   | -275 max | volts |
| Peak Cathode Current               | 77 max   | ma    |
| Average Cathode Current            | 22 max   | ma    |
| Plate Dissipation                  | 4 max    | watts |

#### MAXIMUM CIRCUIT VALUE:

Grid-Circuit Resistance:

For cathode-bias operation .....

2.2 max megohms

† The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.


#### Diode Units

MAXIMUM RATINGS (Design-Maximum Values):

Plate Current (Each Unit):

 Peak
 54 max
 ma

 Average
 9 max
 ma





Hantor Maltaga (ag/da)

#### SHARP-CUTOFF BEAM TRIODE

Glass octal types used for the voltage regulation of high-voltage, low-current dc power supplies in color television receivers. Outline 21B, **Outlines** section. Tubes require octal socket and may be mounted in any position.

# 6BK4 6BK4A

| Heater voltage (ac/dc)                        | 6.3      | VOITS   |
|---|----------|---------|
| Heater Current                                | 0.2      | ampere  |
| Peak Heater-Cathode Voltage:                  |          | •       |
| Heater negative with respect to cathode       | 200 max  | volts   |
| Heater positive with respect to cathode       | Not reco | mmended |
| Direct Interelectrode Capacitances (Approx.): |          |         |
| Grid to Plate                                 | 0.03     | pf      |
| Grid to Cathode and Heater                    | 2.6      | pf      |
| Plate to Cathode and Heater                   | 1        | pf      |
| Amplification Factor (Approx.)                | 2000     | F-      |
|   |          |         |

#### **Voltage-Control Service**

| MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|--|-----------|-------|
| DC Plate Voltage                         | 27000 max | volts |
| Unregulated DC Supply Voltage            | 60000 max | volts |
| DC Grid Voltage                          | —135 max  | volts |
| Peak Grid Voltage                        | —440 max  | volts |
| DC Plate Current                         |           | ma    |
| Plate Dissipation (6BK4)                 | 25 max    | watts |
| Plate Dissipation (6BK4A)                | 30 max    | watts |


#### MAXIMUM CIRCUIT VALUE:

Grid-Circuit Resistance:

For use with "Flyback Transformer" high-voltage supply ......

3 max megohms

For interval of 20 seconds maximum duration during equipment warm-up period.



**6BK5** 

#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

**6BK7A** 


#### MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.

#### MEDIUM-MU TWIN TRIODE

6BK7B
Related type:
5BK7A

Miniature type used in direct-coupled cathode-drive rf amplifier circuits of vhf television tuners. In such circuits, one triode unit is used as the direct-coupled grounded-cathode driver for the other unit. This type is also used



in push-pull cathode-drive rf amplifiers. It has a controlled heater warm-up time

for use in receivers employing series-connected heater strings. Outline 6B, Outlines section. Type requires miniature nine-contact socket and may be mounted in any position. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 5BK7A is identical with type 6BK7B except for the heater ratings, as shown below.

|   | 5BK7A      | 6BK7B      |         |
|---|------------|------------|---------|
| Heater Voltage (ac/dc)                        | 4.7        | 6.3        | volts   |
| Heater Current                                | 0.6        | 0.45       | ampere  |
| Heater Warm-up Time (Average)                 | 11         | 11         | seconds |
| Peak Heater-Cathode Voltage:                  |            |            |         |
| Heater negative with respect to cathode       | 200*       | 200*       | volts   |
| Heater positive with respect to cathode       | 200=       | 200=       | volts   |
| Direct Interelectrode Capacitances:           | Unit No. 1 | Unit No. 2 |         |
| Grid to Plate                                 | 1.8        | 1.8        | pf      |
| Grid to Cathode, Heater, and Internal Shield  | 3          | 3          | pf      |
| Plate to Cathode, Heater, and Internal Shield | 1          | 0.9        | pf      |
| Cathode to Grid, Heater, and Internal Shield  | 6          | 6          | pf      |
| Plate to Grid, Heater, and Internal Shield    | 2.4        | 2.4        | pf      |
| Plate to Cathode                              | 0.22       | 0.22       | pf      |
| Heater to Cathode                             | 2.8        | 3          | pf      |
| Grid of Unit No.1 to Grid of Unit No.2        |            | 0.004 max  | pf      |
| Plate of Unit No.1 to Plate of Unit No.2      |            | 0.075 max  | pf      |

<sup>\*</sup> In cathode-drive circuits with direct-coupled drive, it is permissible for this voltage to be as high as 300 volts under cutoff conditions.

# Class A, Amplifier (Each Unit) MAXIMUM RATINGS (Design Center Values):

| Plate Voltage  | 300 max | volts |
|--|---------|-------|
| Grid Voltage, Negative-bias value                      |         | volts |
| Plate Dissipation                                      | 2.7 max | watts |
| CHARACTERISTICS:                                       |         |       |
| Plate Supply Voltage                                   | 150     | volts |
| Cathode-Bias Resistor                                  | 56      | ohms  |
| Amplification Factor                                   | 43      |       |
| Plate Resistance (Approx.)                             | 4600    | ohms  |
| Transconductance                                       | 9300    | μmhos |
| Plate Current  | 18      | ma    |
| Grid Voltage (Approx.) for plate current of 10 $\mu$ a | -11     | volts |

#### HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

6BL4

#### MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.

6BL7GT

#### MEDIUM-MU TWIN TRIODE



Glass octal type used as combined vertical deflection amplifier and vertical deflection oscillator in television receivers. When so operated, it is recommended that unit No.1 (pins 4, 5, and 6) be used as the oscillator.

6BL7GTA

Outline 13D, Outlines section. This type requires octal socket and may be mounted in any position.

The dc component must not exceed 100 volts.

| Heater Voltage (ac/dc) Heater Current                    | 6.3<br>1.5 | volts<br>amperes |
|--|------------|------------------|
| Peak Heater-Cathode Voltage:                             |            |                  |
| Heater negative with respect to cathode                  | 200 max    | volts            |
| Heater positive with respect to cathode                  | 200 ■ max  | volts            |
| Direct Interelectrode Capacitances (Approx.): Unit No. 1 | Unit No. 2 |                  |
| Grid to Plate 6  | 6          | p <b>f</b>       |
| Grid to Cathode and Heater 4.2                           | 4.6        | pf               |
| Plate to Cathode and Heater 0.9                          | 0.9        | pf               |
| Amplification Factor*                                    | 15         | -                |
| Plate Resistance (Approx.)*                              | 2150       | ohms             |
| Transconductance*  | 7000       | μmhos            |

- The dc component must not exceed 100 volts.
- \* Each unit; for plate volts, 250; grid volts, -9; plate ma., 40.


| Vertical Deflection Oscillator ( For operation in a 525-line, 30-fr |            |           |        |
|---|------------|-----------|--------|
| MAXIMUM RATINGS (Design-Center Values):                             | Oscillator | Amplifier |        |
| DC Plate Voltage  | 500 max    | 500 max   | volts  |
| Peak Positive-Pulse Plate Voltage† (Absolute Maximum)               |            | 2000≟max  | volts  |
| Peak Negative-Pulse Grid Voltage                                    | -400 max   | -250 max  | volts  |
| Peak Cathode Current  | 210 max    | 210 max   | ma     |
| Average Cathode Current   | 60 max     | 60 max    | ma     |
| Plate Dissipation:  |            | ••••••    |        |
| For either plate  | 10 max     | 10 max    | watts  |
| For both plates with both units operating                           | 12 max     | 12 max    | watts  |
| MAXIMUM CIRCUIT VALUES:   |            |           |        |
| Grid-Circuit Resistance   | 4.7 max    | 4.7#max m | egohms |

- Unless otherwise specified, values are for each unit.
- † The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.
- △ Under no circumstances should this absolute value be exceeded.
- # For cathode-bias operation.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6BL8
Related type:
4BL8

Miniature type used in frequencychanger service in television receivers. Outline 6B, **Outlines** section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 4BL8 is identical with type



175 max

200 max

14 max

volts

volts

ma

6BL8 except for the heater ratings, as shown below.


With cathode current of 14 ma .......

Cathode Current ......

With cathode current less than 10 ma ......

| Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage: | 4BL8<br>4.6<br>0.6 | 6BL8<br>6.3<br>0.45 | volts<br>ampere |
|--|--------------------|---------------------|-----------------|
| Heater negative with respect to cathode                            | 100 max            | 100 max             | volts           |
| Heater positive with respect to cathode                            | 100 max            | 100 max             | volts           |
| Class A <sub>1</sub> Amplifier                                     |                    |                     |                 |
| MAXIMUM RATINGS (Design-Center Values):                            | Triode Unit        | Pentode Unit        |                 |
| Plate Supply Voltage   | 550 max            | 550 max             | volts           |
| Plate Voltage  | 250 max            | 250 max             | volts           |
| Grid-No.2 (Screen-Grid) Supply Voltage                             |                    | 550 max             | volts           |
| Grid-No.2 Voltage:   |                    | 550 max             | 10113           |

| Grid-No.2 Input:  With plate dissipation greater than 1.2 watts  With plate dissipation less than 1.2 watts  Plate Dissipation | Triode Unit  — 1.5 max | Pentode Un<br>0.5 max<br>0.75 max<br>1.7 max | it<br>watt<br>watt<br>watts |
|--|------------------------|--|-----------------------------|
| CHARACTERISTICS:   |                        |  |                             |
| Plate Voltage  | 100                    | 170  | volts                       |
| Grid-No.2 Voltage  | _                      | 170  | volts                       |
| Grid-No.1 Voltage  | -2                     | -2   | volts                       |
| Amplification Factor   | 20                     | _  |                             |
| Mu-Factor, Grid No.2 to Grid No.1  | _                      | 47   |                             |
| Plate Resistance (Approx.)   | _                      | 0.4  | megohm                      |
| Transconductance   | 5000                   | 6200   | μmhos                       |
| Plate Current  | 14                     | 10   | ma                          |
| Grid-No.2 Current  |                        | 2.8  | ma                          |
| Input Resistance at frequency of 50 Mc   | _                      | 0.01   | megohm                      |
| Equivalent Noise Resistance  | -                      | 1500   | ohms                        |
| MAXIMUM CIRCUIT VALUES:  |                        |  |                             |
| Grid-No.1-Circuit Resistance:  |                        |  |                             |
| For fixed-bias operation   | 0.5 max                | 0.5 max                                      | megohm                      |
| For cathode-bias operation   | 0.5 max                |  | megohm                      |



#### HIGH-MU TRIODE— POWER PENTODE

<sup>3</sup>C<sup>2</sup>P Miniature type used in television receivers. The pentode unit is used as an κ<sub>τ</sub> audio output tube, and the triode unit as an oscillator and af voltage amplifier. Outline 6G, **Outlines** section. Tube requires miniature nine-contact

# 6BM8/ ECL82

socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.78; peak heater-cathode volts, 100.

#### Class A, Amplifier

| Viass A <sub>1</sub> Amplific           | •           |            |         |
|---|-------------|------------|---------|
| MAXIMUM RATINGS (Design-Center Values): | Triode Unit | Pentode Un | -•      |
| Plate Supply Voltage                    | 550 max     | 900 max    | volts   |
| Plate Voltage                           | 300 max     | 600 max    | volts   |
| Grid-No.2 Supply Voltage                | _           | 550 max    | volts   |
| Grid-No.2 Voltage                       | _           | 300 max    | volts   |
| Cathode Current                         | 15 max      | 50 max     | ma      |
| Plate Dissipation                       | 1 max       | 7 max      | watts   |
| Grid-No.2 Input                         | -           | 1.8 max    | watts   |
| CHARACTERISTICS:                        |             |            |         |
| Plate Voltage                           | 100         | 200        | volts   |
| Grid-No.2 Voltage                       |             | 200        | volts   |
| Grid-No.1 Voltage                       | 0           | <b>—16</b> | volts   |
| Amplification Factor                    | 70          | 9.5*       |         |
| Plate Resistance (Approx.)              | _           | 0.02       | megohm  |
| Transconductance                        | 2500        | 6400       | μmhos   |
| Plate Current                           | 3.5         | 35         | ma      |
| Grid-No.2 Current                       | -           | 7          | ma      |
| MAXIMUM CIRCUIT VALUES:                 |             |            |         |
| Grid-No.1-Circuit Resistance:           |             |            |         |
| For fixed-bias operation                | 1 max       | 1 max      | megohm  |
| For cathode-bias operation              | 2 max       |            | negohms |

<sup>\*</sup> Grid No.2 to Grid No.1.

#### MEDIUM-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

**6BN4** 

#### MEDIUM-MU TRIODE

Related types: 2BN4A. 3BN4A

Miniature type used as rf amplifier tube in grid-drive circuits of vhf television tuners. The double base-pin connections for both cathode and grid reduce effective lead inductance and lead resistance with consequent reduc-



tion in input conductance. In addition, the basing arrangement facilitates isolation of input and output circuits and permits short, direct connections to base-pin terminals. Outline 5C, Outlines section. This type requires miniature seven-contact socket and may be mounted in any position. Types 2BN4A and 3BN4A are identical with type 6BN4A except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode Direct Interelectrode Capacitances (Approx.):* Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater |                  | x 100 max | 6BN4A<br>6.3<br>0.2<br>—<br>100 max<br>100 max<br>1.2<br>3.2<br>1.4 |   |
|--|------------------|-----------|---|---|
| * With external shield connected to cathode.   |                  |           |   |   |
| Class A. A MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation Cathode Current  | :                |           | 275 max<br>0 max<br>2.2 max<br>22 max                               | volts<br>watts                                |
| CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 Plate Current   | <br><br><br>) μa |           | 150<br>220<br>43<br>5400<br>7700<br>—6                              | volts<br>ohms<br>ohms<br>µmhos<br>volts<br>ma |
| MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance   |                  |           | 0.5 ma  | megohm  |

#### **BEAM TUBE**

Related types: 3BN6, 4BN6

Miniature type used as combined limiter, discriminator, and audio-voltage amplifier in intercarrier television and FM receivers. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be




mounted in any position. Types 3BN6 and 4BN6 are identical with type 6BN6 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-Up Time (Average)  | 3BN6<br>3.15<br>0.6<br>11 | 4BN6<br>4.2<br>0.45<br>11 | 6BN6<br>6.3<br>0.3 | volts<br>ampere<br>seconds |
|--|---------------------------|---------------------------|--------------------|----------------------------|
| Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode | 200 max<br>200°max        |                           | 200 max<br>200°max | volts<br>volts             |

<sup>\*</sup> The dc component must not exceed 100 volts.

| Limiter  | Δnd   | Discriminator   | Service |
|----------|-------|-----------------|---------|
| Fillifel | Ali u | Discillilliator | SELLICE |

| MAXIMUM RATINGS (Design-Maximum Values): |         |       |
|--|---------|-------|
| Plate-Supply Voltage                     | 330 max | volts |
| Grid-No.2 Voltage                        | 110 max | volts |
| Grid-No.1 Voltage, Positive peak value   | 60 max  | volts |
| Cathode Current                          | 13 max  | ma    |



#### TWIN DIODE— HIGH-MU TRIODE

Miniature type used in a wide variety of applications in color and blackand-white television receivers. This type has a controlled heater warm-up time for use in receivers employing series-connected heater strings. The

6BN8
Related type: 8BN8

330 max

volts

triode unit is used in burst-amplifier, af amplifier, and low-frequency oscillator applications. The diode units are used in phase-detector, ratio-detector or discriminator, and horizontal afc discriminator circuits. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8BN8 is identical with type 6BN8 except for the heater ratings, as shown below.

|  | 6BN8     | 8BN8     |         |
|--|----------|----------|---------|
| Heater Voltage (ac/dc)                               | 6.3      | 8.4      | volts   |
| Heater Current                                       | 0.6      | 0.45     | ampere  |
| Heater Warm-up Time (Average)                        | 11       | 11       | seconds |
| Peak Heater-Cathode Voltage:                         |          |          |         |
| Heater negative with respect to cathode              | 200 max  | 200 max  | volts   |
| Heater positive with respect to cathode              | 200=max  | 200 max  | volts   |
| Direct Interelectrode Capacitances:                  |          |          |         |
| Triode Grid to Triode Plate                          |          | 2.5      | pf      |
| Triode Grid to Cathode and Heater                    |          | 3.6      | pf      |
| Triode Plate to Cathode and Heater                   |          | 0.25     | pf      |
| Plate of Diode Unit No.1 to Triode Grid              |          | 0.06 max | pf      |
| Plate of Diode Unit No.2 to Triode Grid              |          | 0.1 max  | pf      |
| Plate of Diode Unit No.1 to Plate of Diode Unit No.2 |          | 0.07 max | pf      |
| Diode Cathode to All Other Electrodes (Each Diode I  | Jnit)    | 5        | pf      |
| Diode Plate to Diode Cathode and Heater (Each Diod   | le Unit) | 1.9      | pf      |
| Diode Cathode to Diode Plate and Heater (Each Diod   | e Unit)  | 4.8      | pf      |
| Diode Plate to All Other Electrodes (Each Diode Unit | ·)       | 3        | pf      |
| The do component must not exceed 100 volts           |          |          |         |

<sup>•</sup> The dc component must not exceed 100 volts.

MAXIMUM RATINGS (Design-Maximum Values):
Plate Voltage

#### Triode Unit as Class A, Amplifier


| Grid Voltage, Positive bias value                 |       | 0 max<br>1.7 max | volts<br>watts |
|---|-------|------------------|----------------|
| CHARACTERISTICS:                                  |       |                  |                |
| Plate Voltage                                     | 100   | 250              | volts          |
| Grid Voltage                                      | -1    | -3               | volts          |
| Amplification Factor                              | 75    | 70               |                |
| Plate Resistance (Approx.)                        | 21000 | 28000            | ohms           |
| Transconductance                                  | 3500  | 2500             | μmhos          |
| Grid Voltage (Approx.) for plate current of 10 µa | 2.5   | -5.5             | volts          |
| Plate Current                                     | 1.5   | 1.6              | ma             |

#### MAXIMUM CIRCUIT VALUE:

#### **Diode Units**

MAXIMUM RATINGS (Design-Maximum Values): Plate Current (Each Unit):

| ac Current (Lach Ollie). |        |    |
|--------------------------|--------|----|
| Peak                     | 54 max | ma |
| Average                  | 9 max  | ma |



#### POWER PENTODE

6BQ5
Related type:
8BQ5

Miniature type used in the output stage of audio-frequency amplifiers. Outline 6G, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8BQ5 is identical with type 6BQ5



volts

voits

50.6

ma

ma

except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage:                      | 6BQ5<br>6.3<br>0.76<br>— | 8BQ5<br>8<br>0.6<br>11             | volts<br>ampere<br>seconds |
|---|--------------------------|------------------------------------|----------------------------|
| Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances: | 100 max<br>100△max       | 100 max<br>100△max                 | volts<br>volts             |
| Grid No.1 to Plate  | No.3                     | 0.5 max<br>10.8<br>6.5<br>0.25 max | pf<br>pf<br>pf<br>pf       |

The dc component must not exceed 100 volts.

#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Center Values):               |         |       |
|---|---------|-------|
| Plate Voltage   | 300 max | volts |
| Grid-No.2 (Screen-Grid) Voltage                       | 300 max | volts |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max   | volts |
| Grid-No.2 Input                                       | 2 max   | watts |
| Plate Dissipation                                     | 12 max  | watts |
| Cathode Current                                       | 65 max  | ma    |
| TYPICAL OPERATION:                                    |         |       |
| Plate Voltage   | 250     | volts |
| Grid-No.2 Voltage                                     | 250     | volts |

Grid-No.1 (Control-Grid) Voltage .....

Zero-Signal Plate Current .....

Maximum-Signal Plate Current .....


Peak AF Grid-No.1 Voltage .....

| Zero-Signal Grid-No.2 Current  |                           | 5.5     | ma                                      |
|--|---------------------------|---------|---|
| Maximum-Signal Grid-No.2 Current   |                           | 10      | ma                                      |
| Plate Resistance (Approx.)   |                           | 38000   | ohms                                    |
| Transconductance   |                           | 11300   | umhos                                   |
| Load Resistance  |                           | 4500    | ohms                                    |
| Total Harmonic Distortion  |                           | 10      | per cent                                |
| Maximum-Signal Power Output  |                           | 5.7     | watts                                   |
| Transmitted to the Company of the Co |                           | •       | *************************************** |
| MAXIMUM CIRCUIT VALUES:  |                           |         |   |
| Grid-No.1-Circuit Resistance:  |                           |         |   |
| For fixed-bias operation   |                           | 0.3 max | megohm                                  |
| For cathode-bias operation   |                           | 1.0 max | megohm                                  |
| Doort Bull Olean AD Ame  |                           |         |   |
| Push-Pull Class AB, Am   | pliner                    |         |   |
| MAXIMUM RATINGS: (Same as for Single-Tube Class A  | A <sub>1</sub> Amplifier) |         |   |
| TYPICAL OPERATION (Values are for two tubes):  |                           |         |   |
| Plate Supply Voltage   | 250                       | 300     | volts                                   |
| Grid-No.2 Supply Voltage   | 250                       | 300     | volts                                   |
| Cathode-Bias Resistor  | 130                       | 130     | ohms                                    |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage   | 22.6                      | 28.3    | volts                                   |
| Zero-Signal Plate Current  | 62                        | 72      | ma                                      |
| Maximum-Signal Plate Current   | 75                        | 92      | ma                                      |
| Zero-Signal Grid-No.2 Current  | 7                         | 8       | ma                                      |
| Maximum-Signal Grid-No.2 Current   | 15                        | 22      | ma                                      |
| Effective Load Resistance (Plate-to-plate)   | 8000                      | 8000    | ohms                                    |
| Total Harmonic Distortion  | 3                         | 4       | per cent                                |
| Maximum-Signal Power Output  | 11                        | 17      | watts                                   |
| MAXIMUM CIRCUIT VALUES:  |                           |         |   |
|  |                           |         |   |
| Grid-No.1-Circuit Resistance:  |                           | 0.2     |   |
| For fixed-bias operation   |                           |         | megohm                                  |
| For cathode-bias operation   |                           | 1.U max | megohm                                  |

#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

6BQ6GT



#### **BEAM POWER TUBE**

Glass octal type used as horizontal deflection amplifier in television receivers. Outline 14D, Outlines section. Tube requires octal socket and may Related types: be mounted in any position. This type 12BQ6GTB/12CU6, 17BQ-may be supplied with pin No.1

# 6BQ6GTB **/6CU6**

omitted. Types 12BQ6GTB/12CU6, 17BQ6GTB, and 25BQ6GTB/25CU6 are identical with type 6BQ6GTB/6CU6 except for the heater ratings, as shown below.

|                                       | 6BQ6GTB/    | 12BQ6G-    | 17BQ6-  | 25BQ6GTB/ |            |
|---------------------------------------|-------------|------------|---------|-----------|------------|
|                                       | 6CU6        | TB/12CU6   | GTB     | 25CU6     |            |
| Heater Voltage (ac/dc)                | 6.3         | 12.6       | 16.8    | 25        | volts      |
| Heater Current                        | 1.2         | 0.6        | 0.45    | 0.3       | ampere     |
| Heater Warm-up Time (Average)         | _           | 11         | 11      | -         | seconds    |
| Peak Heater-Cathode Voltage:          |             |            |         |           |            |
| Heater negative with respect to       |             |            |         |           |            |
| cathode                               | 200 max     | 200 max    | 200 max | 200 max   | volts      |
| Heater positive with respect to       |             |            |         |           |            |
| cathode                               |             | 200 max    | 200≠max | 200=max   | volts      |
| Direct Interelectrode Capacitances (A |             |            |         |           |            |
| Grid No.1 to Plate                    |             |            |         | 0.6       | pf         |
| Grid No.1 to Cathode, Heater, C       |             |            |         | 15        | pf         |
| Plate to Cathode, Heater, Grid 1      | No.2, and G | rid No.3 . |         | 7         | pf         |
| Transconductance*                     |             |            |         | 5900      | $\mu$ mhos |
| Mu-Factor, Grid No.2 to Grid No.1     | ••          |            |         | 4.3       |            |

- The dc component must not exceed 100 volts.
- \* For plate volts, 250; grid-No.2 volts, 150; grid-No.1 volts, -22.5; plate ma., 57; grid-No.2 ma., 2.1.
- \*\* For plate and grid-No.2 volts, 150; grid-No.1 volts, -22.5.

#### Horizontal Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Center Values):              |           |       |
|--|-----------|-------|
| DC Plate Voltage                                     | 600 max   | volts |
| Peak Positive-Pulse Plate Voltage (Absolute Maximum) | 6000†max  | volts |
| Peak Negative-Pulse Plate Voltage                    | -1250 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage                   | 200 max   | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | -300 max  | volts |
| Peak Cathode Current                                 | 400 max   | ma    |
| Average Cathode Current                              | 110 max   | ma    |
| Grid-No.2 Input                                      | 2.5 max   | watts |
| Plate Dissipation#                                   | 11 max    | watts |
| Bulb Temperature (At hottest point)                  | 220 max   | °C    |
|  |           |       |

#### MAXIMUM CIRCUIT VALUE:

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- † Under no circumstances should this absolute value be exceeded.
- #An adequate bias resistor or other means is required to protect the tube in the absence of excitation.


**6BQ7** 

#### MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.

#### MEDIUM-MU TWIN TRIODE

6BQ7A Related types: 4BQ7A, 5BQ7A Miniature type used in direct-coupled cathode-drive rf amplifier circuits of vhf television tuners. In such circuits, one triode unit is used as the direct-coupled grounded-cathode driver for the other unit. This type is also used in



6RO7A

push-pull cathode-drive rf amplifiers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Types 4BQ7A and 5BQ7A are identical with type 6BQ7A except for the heater ratings, as shown below.

ARO7A

SRO7A

|  | 4DQ/A   | JEQIA     | ODQIA     |         |
|--|---------|-----------|-----------|---------|
| Heater Voltage (ac/dc)                       | 4.2     | 5.6       | 6.3       | volts   |
| Heater Current                               | 0.6     | 0.45      | 0.4       | ampere  |
| Heater Warm-up Time (Average)                | 11      | 11        |           | seconds |
| Peak Heater-Cathode Voltage:                 |         |           |           |         |
| Heater negative with respect to cathode      | 200*max | 200*max   | 200*max   | volts   |
| Heater positive with respect to cathode      | 200=max | 200 max   | 200 max   | volts   |
| Direct Interelectrode Capacitances:°         |         | Unit No.1 | Unit No.2 |         |
| Grid to Plate                                |         | 1.2       | 1.2       | pf      |
| Grid to Cathode, Heater, and Internal Shield |         | 2.6       | _         | pf      |
| Cathode to Grid, Heater, and Internal Shield | i       |           | 5.0       | pf      |
| Plate to Cathode, Heater, and Internal Shie  |         | 1.2       |           | pf      |
| Plate to Grid, Heater, and Internal Shield   |         | _         | 2.2       | pf      |
| Plate to Cathode                             |         | 0.12      | 0.12      | pf      |
| Heater to Cathode                            |         | 2.6       | 2.6       | pf      |
| Plate of Unit No.1 to Plate of Unit No.2     |         | 0.010     | ) max     | pf      |
| Plate of Unit No.2 to Plate and Grid of Unit |         |           | max       | pf      |

- With external shield connected to internal shield.
- \* In cathode-drive circuits with direct-coupled drive, it is permissible for this voltage to be as high as 300 volts.
- \* The dc component must not exceed 100 volts.


#### Class A, Amplifier (Each Unit)

| Tidoo M Mach Child                      |            |       |
|---|------------|-------|
| MAXIMUM RATINGS (Design-Center Values): |            |       |
| Plate Supply Voltage                    | 250*max    | volts |
| Plate Dissipation                       | 2 max      | watts |
| Cathode Current                         | 20 max     | ma    |
| CHARACTERISTICS:                        |            |       |
|   | 150        | volts |
| Plate Supply Voltage                    |            |       |
| Cathode-Bias Resistor                   | 220        | ohms  |
| Amplification Factor                    | 38         |       |
| Plate Resistance (Approx.)              | 5900       | ohms  |
| Transconductance                        | 6400       | μmhos |
| Plate Current                           | 9          | ma    |
| Grid Voltage (Approx.):                 |            |       |
| For plate current of 100 $\mu a$        | <b>6.5</b> | volts |
| For plate current of 10 $\mu$ a         | _          | volts |
| MAXIMUM CIRCUIT VALUE.                  |            |       |

# 

0.5 max megohm


\* In cathode-drive circuits with direct-coupled drive, it is permissible for this voltage to be as high as 300 volts.



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

6BR8



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in a wide variety of applications in color and blackand-white television receivers. Especially useful as combined triode oscillator and pentode mixer in vhf television tuners. Tube has a con-

6BR8A
Related type:
5BR8

trolled heater warm-up time for use in receivers employing series-connected heater

strings. Outline 6B, Outlines section. Except for basing arrangement and grid-No.1-to-plate capacitance of pentode unit, this type is identical with type 6U8A.

#### HALF-WAVE VACUUM RECTIFIER

# 6BS3 6BS3A

Related types: 12BS3, 12BS3A, 17BS3, 17BS3A Novar types used as damper tubes in horizontal-deflection circuits of black-and-white television receivers. Outlines 11D and 30B, respectively, **Outlines** section. Tubes require novar nine-contact socket and may be mounted in



17BS3

any position. Socket terminals 1, 3, 6, and 8 should not be used as tie points; it is recommended that socket clips for these pins be removed to reduce the possibility of arc-over and to minimize leakage. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Types 12BS3 and 12BS3A and types 17BS3 and 17BS3A are identical with types 6BS3 and 6BS3A, respectively, except for the heater ratings, as shown below.

6BS3

12RS3

|   | ODSS        | 11100       | 1,000    |         |
|---|-------------|-------------|----------|---------|
|   | 6BS3A       | 12BS3A      | 17BS3A   |         |
| Heater Voltage (ac/dc)                        | 6.3         | 12.6        | 16.8     | volts   |
| Heater Current                                | 1.2         | 0.6         | 0.45     | ampere  |
| Heater Warm-up Time (Average)                 | _           | 11          | 11       | seconds |
| Direct Interelectrode Capacitances (Approx.): |             |             |          |         |
| Plate to Cathode and Heater                   |             |             | 6.5      | pf      |
| Cathode to Plate and Heater                   |             |             | 9        | pf      |
| Heater to Cathode                             |             |             | 2.8      | pf      |
|   |             |             |          | -       |
| Damper  | Sarvica     |             |          |         |
| •   |             |             |          |         |
| For operation in a 525                        | -line, 30-f | rame system |          |         |
| MAXIMUM RATINGS (Design-Maximum Valu          | es):        |             |          |         |
| Peak Inverse Plate Voltage                    |             |             | 5000 max | volts   |
| Peak Plate Current                            |             |             | 1100 max | ma      |
| DC Plate Current                              |             |             | 200 max  | ma      |
| Plate Dissipation                             |             |             | 6 max    | watts   |
| Peak Heater-Cathode Voltage:                  |             |             |          |         |
| Heater negative with respect to cathode       |             |             | 5000 max | volts   |

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

Heater positive with respect to cathode ......

Tube Voltage Drop for plate current of 140 ma ......

• The dc component must not exceed 900 volts.

CHARACTERISTICS. Instantaneous Value:

The dc component must not exceed 100 volts.

#### MEDIUM-MU TWIN TRIODE

6BS8
Related type:
4BS8

Miniature type used in direct-coupled cathode-drive rf amplifier circuits of vhf television tuners. In such circuits, one triode unit is used as the direct-coupled grounded-cathode driver for the other unit. This type is also used



300□max


12


volts

volts

in push-pull cathode-drive rf amplifiers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 4BS8 is identical with type 6BS8 except for the heater ratings, as shown below.

|  | 4BS8    | 6BS8  |   |
|--|---------|---|---|
| Heater Voltage (ac/dc)   | 4.5     | 6.3   | volts   |
| Heater Current   | 0.6     | 0.4   | ampere  |
| Heater Warm-up Time (Average)  | 11      |   | seconds                                       |
| Peak Heater-Cathode Voltage:   |         |   |   |
| Heater negative with respect to cathode  | 200 max | 200 max   | volts   |
| Heater positive with respect to cathode  | 200 max | 200 max   | volts   |
| Direct Interelectrode Capacitances:  |         |   |   |
| Grid to Plate (Each Unit)  |         | 1.15  | pf  |
| Grid to Cathode, Heater, and Internal Shield (Unit N   | No.1)   | 2.6   | pf  |
| Plate to Cathode, Heater, and Internal Shield (Unit N  | No.1)   | 1.2   | pf  |
| Plate to Cathode (Each Unit)   |         | 0.15 max  | pf  |
| Heater to Cathode (Each Unit)  |         | 2.6   | pf  |
| Cathode to Grid, Heater, and Internal Shield (Unit N   | No.2)   | 5   | pf  |
| Plate to Grid, Heater, and Internal Shield (Unit No  |         | 2.2   | pf  |
| Plate of Unit No.1 to Plate of Unit No.2   |         | 0.010 max   | pf  |
| Plate of Unit No.2 to Plate and Grid of Unit No.1  |         | 0.024 max   | pf  |
|  |         |   | •   |
|  |         |   |   |
| Class A, Amplifier (Each   | h Unit) |   |   |
| Class A, Amplifier (Each MAXIMUM RATINGS (Design-Center Values):   | h Unit) |   |   |
| MAXIMUM RATINGS (Design-Center Values):  | •       | 150 max   | volts   |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage  |         | 150 max<br>2 max  | volts<br>watts                                |
| MAXIMUM RATINGS (Design-Center Values):  |         |   |   |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current  |         | 2 max   | watts   |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS:   | ••••••  | 2 max<br>20 max   | watts<br>ma                                   |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage  |         | 2 max<br>20 max   | watts<br>ma<br>volts                          |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor  |         | 2 max<br>20 max<br>150<br>220                                   | watts<br>ma                                   |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor   |         | 2 max<br>20 max<br>150<br>220<br>36                             | watts<br>ma<br>volts<br>ohms                  |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.)  |         | 2 max<br>20 max<br>150<br>220<br>36<br>5000                     | watts<br>ma<br>volts<br>ohms                  |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance   |         | 2 max<br>20 max<br>150<br>220<br>36<br>5000<br>7200             | watts<br>ma<br>volts<br>ohms<br>ohms<br>μmhos |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current   |         | 2 max<br>20 max<br>150<br>220<br>36<br>5000<br>7200<br>10       | volts<br>ohms<br>ohms<br>umhos<br>ma          |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance   |         | 2 max<br>20 max<br>150<br>220<br>36<br>5000<br>7200             | watts<br>ma<br>volts<br>ohms<br>ohms<br>μmhos |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.) for plate current of 10 µa*                          |         | 2 max<br>20 max<br>150<br>220<br>36<br>5000<br>7200<br>10       | volts<br>ohms<br>ohms<br>umhos<br>ma          |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current  CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.) for plate current of 10 μa*  MAXIMUM CIRCUIT VALUE: |         | 2 max<br>20 max<br>150<br>220<br>36<br>5000<br>7200<br>10<br>-7 | volts<br>ohms<br>ohms<br>µmhos<br>ma<br>volts |
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Plate Dissipation Cathode Current CHARACTERISTICS: Plate-Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.) for plate current of 10 µa*                          |         | 2 max<br>20 max<br>150<br>220<br>36<br>5000<br>7200<br>10       | volts<br>ohms<br>ohms<br>µmhos<br>ma<br>volts |





#### SHARP-CUTOFF TWIN PENTODE

Miniature type used as combined sync separator, sync clipper, and age amplifier tube in television receivers.

Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

6BU8
Related types:
3BU8, 4BU8

CDT TO

Types 3BU8 and 4BU8 are identical with type 6BU8 except for the heater ratings, as shown below.

20110

ADTTO

|   | 3000      | 4 <b>D</b> U0 | ODCO      |         |
|---|-----------|---------------|-----------|---------|
| Heater Voltage (ac/dc)                    | . 3.15    | 4.2           | 6.3       | volts   |
| Heater Current                            |           | 0.45          | 0.3       | ampere  |
| Heater Warm-up Time (Average)             |           | 11            | _         | seconds |
| Peak Heater-Cathode Voltage:              |           |               |           |         |
| Heater negative with respect to cathode.  | . 200 max | 200 max       | 200 max   | volts   |
| Heater positive with respect to cathode.  |           | 200 max       | 200 max   | volts   |
| Direct Interelectrode Capacitances:       |           |               |           |         |
| Grid No.3 to Plate (Each Unit)            |           |               | 1.9       | pf      |
| Grid No.1 to All Other Electrodes         |           |               | 6         | pf      |
| Grid No.3 to All Other Electrodes (Each   | Unit)     |               | 3.6       | pf      |
| Plate to All Other Electrodes (Each Unit) |           |               | 3         | pf      |
| Grid No.3 of Unit No.1 to Grid No.3 of    |           |               | 0.015 max | pf      |
|   |           |               |           | -       |

<sup>•</sup> The dc component must not exceed 100 volts.

Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values):


| Grid-No.3 (Suppressor-Grid) Voltage (Each Unit):                 |                           |          |        |
|--|---------------------------|----------|--------|
| Peak positive value  |                           | 50 max   | volts  |
| DC negative value  |                           | —50 max  | volts  |
| DC positive value  |                           | 3 max    | volts  |
| Grid-No.2 (Screen-Grid) Voltage                                  |                           | 150 max  | volts  |
| Grid-No.1 (Control-Grid) Voltage, Negative bias value.           |                           | -50 max  | volts  |
| Cathode Current  |                           | 12 max   | ma     |
| Grid-No.2 Input  |                           | 0.75 max | watt   |
| Plate Dissipation (Each Unit)                                    | · · · · · · · · · · · · · | 1,1 max  | watts  |
| CHARACTERISTICS: With Both Units Operating                       |                           |          |        |
| Plate Voltage (Each Unit)  | 100                       | 100      | volts  |
| Grid-No.3 Voltage (Each Unit)                                    | -10                       | 0        | volts  |
| Grid-No.2 Voltage  | 67.5                      | 67.5     | volts  |
| Grid-No.1 Voltage  | *                         | *        | volts  |
| Plate Current (Each Unit)  | _                         | 2.2      | ma     |
| Grid-No.2 Current  | 6.5                       | 3.3      | ma     |
| Cathode Current  | 6.6                       | 7.8      | ma     |
| With One Unit Operating  |                           |          |        |
| Plate Voltage  | 100                       | 100      | volts  |
| Grid-No.3 Voltage  | 0                         | 100      | volts  |
| Grid-No.2 Voltage  | 67.5                      | 67.5     | volts  |
| Grid-No.1 Voltage  | 07.5                      | *        | volts  |
| Grid-No.3 Transconductance                                       |                           | 180      | umhos  |
| Grid-No.1 Transconductance                                       | 1500                      |          | umhos  |
| Plate Current  | -                         | 2.2      | ma     |
| Grid-No.3 Voltage (Approx.) for plate current of                 |                           |          |        |
| 100 μα   |                           | 4.5      | volts  |
| Grid-No.1 Voltage (Approx.) for plate current of                 |                           | ****     | ,0113  |
| 100 μα   | _                         | -2.3     | volts  |
| MAXIMUM CIRCUIT VALUES: Grid-No.3-Circuit Resistance (Each Unit) |                           | 0.5 max  | megohm |

Grid-No.3-Circuit Resistance (Each Unit)

O.5 max megohm


Grid-No.1-Circuit Resistance


0.5 max megohm



<sup>\*</sup> Adjusted to give a dc grid-No.1 current of 100 microamperes.

<sup>†</sup> With plate and grid No.3 of the other unit connected to ground.





#### TWIN DIODE— MEDIUM-MU TRIODE

Miniature type used as combined synchronous detector and chrominance amplifier in color television receivers; also used as combined FM detector and af voltage amplifier. Tube has controlled warm-up time for use in

6BV8

series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Heater volts (ac/dc), 6.3; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to cathode).

#### Triode Unit as Class A, Amplifier


| mode one as olass A <sub>1</sub> A                      | ubimei            |         |        |
|---|-------------------|---------|--------|
| MAXIMUM RATINGS (Design-Maximum Values):                |                   |         |        |
| Plate Voltage   |                   | 330 max | volts  |
| Grid Voltage, Positive-bias value                       |                   | 0 max   | volts  |
| Plate Dissipation                                       | • • • • • • • • • | 2.7 max | watts  |
| CHARACTERISTICS:  |                   |         |        |
| Plate Voltage   | 75                | 200     | volts  |
| Grid Voltage  | 0                 | _       | volts  |
| Cathode Resistor  | -                 | 330     | ohms   |
| Amplification Factor                                    | _                 | 33      |        |
| Plate Resistance (Approx.)                              | -                 | 5900    | ohms   |
| Transconductance  | _                 | 5600    | μmhos  |
| Plate Current   | 14                | 11      | ma     |
| Grid Voltage (Approx.) for plate current of 100 $\mu a$ | -                 | -11     | volts  |
| MAXIMUM CIRCUIT VALUES:                                 |                   |         |        |
| Grid-Circuit Resistance:                                |                   |         |        |
| For fixed-bias operation                                |                   | 0.1 max | megohm |
| For cathode-bias operation                              |                   |         | megohm |
|   |                   |         |        |

#### Diode Units (Each Unit)

#### **FULL-WAVE VACUUM RECTIFIER**

6BW4
Related type:

Miniature type used in full-wave power supplies having high dc output current requirements. Outline 6E, Outlines section. Type 6BW4 requires miniature nine-contact socket and may be mounted in any position. It is




especially important that this tube, like other power-handling tubes, be adequately ventilated. Type 12BW4 is identical with type 6BW4 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current                              | 6BW4<br>6.3<br>0.9 | 12BW4<br>12.6<br>0.45 | volts<br>ampere |
|--|--------------------|-----------------------|-----------------|
| Full-Wave Rectifi  | er                 |                       |                 |
| MAXIMUM RATINGS (Design-Center Values):                            |                    |                       |                 |
| Peak Inverse Plate Voltage   |                    | 1275 max              | volts           |
| AC Plate Supply Voltage (Per Plate, rms)                           |                    | 450 max               | volts           |
| Steady-State Peak Plate Current (Per Plate)                        |                    | 350 max               | ma              |
| DC Output Current  |                    | 62.5 max              | ma              |
| Transient Peak Plate Current (Per Plate)                           |                    | 2 max                 | amperes         |
| DC Heater-Cathode Voltage: Heater negative with respect to cathode |                    | 450 max               | volts           |
| TYPICAL OPERATION: Filter Input                                    | Capacitor          | Choke                 |                 |
| AC Plate-To-Plate Supply Voltage (rms)                             | 650                | 900                   | volts           |
| Filter Input Capacitor   | 40                 |                       | μf              |
| Total Effective Plate Supply Resistance per Plate                  | 82                 | _                     | ohms            |
| Filter Input Choke   | _                  | 10                    | henries         |
| DC Output Current  | 100                | 100                   | ma              |
| DC Output Voltage at Input to Filter (Approx.)                     | 330                | 360                   | volts           |
|  |                    |                       |                 |

#### TWIN DIODE— SHARP-CUTOFF PENTODE

6BW8
Related type:
5BW8

Miniature type used in television receivers; diodes are used as horizontal phase detectors; pentode is used as a sound if amplifier, sound limiter, and age keyer. Outline 6B, Outlines section. Tube requires miniature nine-




contact socket and may be operated in any position. Type 5BW8 is identical with type 6BW8 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)  | 5BW8<br>4.7<br>0.6<br>11 | 6BW8<br>6.3<br>0.45 | volts<br>ampere<br>seconds |
|--|--------------------------|---------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max                  | 200 max             | volts                      |
|  | 200°max                  | 200°max             | volts                      |

The dc component must not exceed 100 volts.

AC plate supply voltage is measured without load.

| Direct Interelectrode Capacitances: Pentode Unit:                                      |                       |                |
|--|-----------------------|----------------|
| Grid No.1 to Plate   | 0.02 max              | pf             |
| Internal Shield  | 4.8                   | pf             |
| Internal Shield  | 2.6                   | pf             |
| Plate of Diode Unit No.1 to Cathode and Heater   | 1.3                   | pf             |
| Plate of Diode Unit No.2 to Cathode and Heater Pentode Grid No.1 to Either Diode Plate | 1.2<br>0.006 max      | pf<br>pf       |
|  | 0.000 max             | pı             |
| Pentode Unit as Class A, Amplifier   |                       |                |
| MAXIMUM RATINGS (Design-Maximum Values):   |                       |                |
| Plate Voltage  | 330 max<br>330 max    | volts<br>volts |
| Grid-No.2 (Screen-Grid) Supply Voltage   | See curve             |                |
| Grid-No.1 (Control-Grid) Voltage:  | Sec curve             | page 15        |
| Positive-bias value  | 0 max                 | volts          |
| Negative-bias value  | —55 max               | volts          |
| Grid-No.2 Input:   | 0.55                  | 44             |
| For grid-No.2 voltages up to 165 volts   | 0.55 max<br>See curve | watt           |
| Plate Dissipation  | 3 max                 | watts          |
| •  |                       | ,, 4,,,,       |
| CHARACTERISTICS:   |                       | 4.             |
| Plate Voltage  | 250                   | volts          |
| Grid-No.2 Voltage Cathode-Bias Resistor  | 110<br>68             | volts<br>ohms  |
| Plate Resistance (Approx.)   | 0.25                  | megohm         |
| Transconductance   | 5200                  | μmhos          |
| Grid-No.1 Voltage (Approx.) for plate current of 10 μa                                 | -10                   | volts          |
| Plate Current  | 10                    | ma             |
| Grid-No.2 Current  | 3. <b>5</b>           | ma             |
| MAXIMUM CIRCUIT VALUES: Grid-No.1 Circuit Resistance:                                  |                       |                |
| For fixed-bias operation   | 0.1 max               |                |
| For cathode-bias operation   | 0.5 max               | megohm         |
| Diode Units (Each Unit)  |                       |                |
| MAXIMUM RATINGS (Design-Maximum Value):  |                       |                |



#### MEDIUM-MU TWIN TRIODE

Glass octal type used as combined vertical deflection amplifier and vertical deflection oscillator in television receivers. When so operated, it is recommended that unit No.1 (pins 4, 5, and 6) be used as the oscillator. Out-

6BX7GT

5 max

ma

line 13D, Outlines section. Tube requires octal socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 1.5; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode). Characteristics as class  $A_1$  amplifier with plate volts = 50, cathode-bias resistor = 390 ohms, and plate ma = 42: amplification factor, 10; plate resistance (approx.), 1300 ohms; transconductance, 7600  $\mu$ mhos.

#### Vertical Deflection Oscillator or Amplifier (Each Unit)

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage | Oscillator<br>500 max | Amplifier<br>500 max  | volts |
|--|-----------------------|-----------------------|-------|
| Peak Positive-Pulse Plate Voltage                        |                       |                       |       |
| (Absolute Maximum)#                                      | _                     | 2000 <sub>4</sub> max | volts |

Amnlifier

Occillator

| Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: | -400 max<br>180 max<br>60 max | -250 max<br>180 max<br>60 max | volts<br>ma<br>ma |
|--|-------------------------------|-------------------------------|-------------------|
| For either plate   | 10 max                        | 10 max                        | watts             |
| For both plates with both units operating  | 12 max                        | 12 max                        | watts             |
| MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance   | 2.2 max                       | 2.2 • max m                   | egohms            |

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds. A Under no circumstances should this absolute value be exceeded.

# 6BY5GA Renewal type;

#### **FULL-WAVE VACUUM RECTIFIER**

Renewal type; see chart at end of section for tabulated data.

#### PENTAGRID AMPLIFIER

6BY6
Related type: 3BY6

CHARACTERISTICS:

Miniature type used as a gated amplifier in color television receivers. In such service, it may be used as a combined sync separator and sync clipper. Outline 5C, Outlines section. Tube requires miniature seven-contact sock-



et and may be mounted in any position. Type 3BY6 is identical with type 6BY6 except for the heater ratings, as shown below.

|   | 3BY6    | 6BY6     |         |
|---|---------|----------|---------|
| Heater Voltage (ac/dc)                  | 3.15    | 6.3      | volts   |
| Heater Current                          | 0.6     | 0.3      | ampere  |
| Heater Warm-up Time (Average)           | 11      | _        | seconds |
| Peak Heater-Cathode Voltage:            |         |          |         |
| Heater negative with respect to cathode | 200 max | 200 max  | volts   |
| Heater positive with respect to cathode | 200°max | 200°max  | volts   |
| Direct Interelectrode Capacitances:     |         |          |         |
| Grid No.1 to Plate                      |         | 0.08 max | pf      |
| Grid No.3 to Plate                      |         | 0.35 max | pf      |
| Grid No.1 to Grid No.3                  |         | 0.22 max | pf      |
| Grid No.1 to All Other Electrodes       |         | 5.4      | pf      |
| Grid No.3 to All Other Electrodes       |         | 6.9      | pf      |
| Plate to All Other Electrodes           |         | 7.6      | pf      |
|   |         |          |         |

<sup>\*</sup> The dc component must not exceed 100 volts.

#### Class A, Amplifier


| CIMICIC I EMB 12CD.   |      |       |
|---|------|-------|
| Plate Voltage   | 250  | volts |
| Grids-No.2-and-No.4 Voltage                                   | 100  | volts |
| Grid-No.3 Voltage   | -2.5 | volts |
| Grid-No.1 Voltage   | 2.5  | volts |
| Grid-No.3-to-Plate Transconductance                           | 500  | μmhos |
| Grid-No.1-to-Plate Transconductance                           | 1900 | umhos |
| Plate Current   | 6.5  | ma    |
| Grids-No.2-and-No.4 Current                                   | 9    | ma    |
| Grid-No.3 Volts (Approx.) for plate current of 35 $\mu$ a and |      |       |
| grid-No.1 volts $=$ -4  | 15   | volts |
| Grid-No.1 Volts (Approx.) for plate current of 35 µa and      |      |       |
| grid-No.3  volts = 0  | -12  | volts |
|   |      |       |


#### **Gated Amplifier**

| MAXIMUM RATINGS (Design-maximum values): |           |         |
|--|-----------|---------|
| Plate Voltage                            | 330 max   | volts   |
| Grids-No.2-and-No.4 Voltage              | See curve | page 75 |
| Grids-No.2-and-No.4 Supply Voltage       | 330 max   | volts   |

<sup>•</sup> For cathode-bias operation.

| Grid-No.3 Voltage:   |       |       |         |
|--|-------|-------|---------|
| Negative bias value  | 55    | max   | volts   |
| Positive bias value  | 0 :   | max   | volts   |
| Positive peak value  | 27    | max   | volts   |
| Grid-No.1 Voltage, Negative bias value   | 110   | max   | volts   |
| Plate Dissipation  | 2.3   | max   | watts   |
| Grid-No.3 Input  | 0.1   | max   | watt    |
| Grids-No.2-and-No.4 Input:   |       |       |         |
| For grids-No.2-and-No.4 voltages up to 165 volts   | 1.1   | max   | watts   |
| For grids-No.2-and-No.4 voltages between 165 and 330 volts   | See   | curve | page 75 |
| Grid-No.1 Input  | 0.1   | max   | watt    |
| CITADA CENTRACIA A CARRAGA CAR |       |       |         |
| CHARACTERISTICS AS SYNC SEPARATOR AND SYNC CLIPPER:  |       |       |         |
| Plate Voltage  | 10    |       | volts   |
| Grid-No.3 Voltage  | 0     |       | volts   |
| Grids-No.2-and-No.4 Voltage  | 25    |       | volts   |
| Grid-No.1 Voltage  | 0     |       | volts   |
| Plate Current  | 1.4   |       | ma      |
| Grids-No.2-and-No.4 Current  | 3.5   |       | ma      |
| Grid-No.3 Volts (Approx.) for plate voltage of 25 volts, grids-No.2-   |       |       |         |
| and-No.4 voltage of 25 volts, grid-No.1 voltage of 0 volts, and  |       |       |         |
| plate current of 50 μa   | 2.5   |       | volts   |
| Grid-No.1 Volts (Approx.) for plate voltage of 25 volts, grids-No.2-   |       |       |         |
| and-No.4 voltage of 25 volts, grid-No.3 voltage of 0 volts, and  |       |       |         |
| plate current of 50 $\mu$ a  | 2.3   |       | volts   |
| MAXIMUM CIRCUIT VALUES:  |       |       |         |
| Grid-No.1 or Grid-No.3-Circuit Resistance:   |       |       |         |
|  |       |       |         |
| For fixed-bias operation   |       |       | negohm  |
| For cathode-bias operation   | 1.0 1 | max n | negohm  |





#### DIODE— SHARP-CUTOFF PENTODE

Miniature type used in diversified applications in television receivers. The pentode unit is used as an rf amplifier and the high-perveance diode as a limiter or detector. This type has a controlled heater warm-up time for

**6BY8** 

use in receivers employing series-connected heater strings. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

|  | •                |                                     |
|--|------------------|-------------------------------------|
| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)  | 0.6              | volts<br>ampere<br>seconds          |
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances:  Pentode Unit: |                  |                                     |
| Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and   |                  | max pf                              |
| Internal Shield  |                  | pf                                  |
| Internal Shield Diode Plate to All Other Electrodes  | 5<br>4.8*        | pf<br>pf                            |
| △ The dc component must not exceed 100 volts.  * With external shield connected to cathode of pentode unit (pin  With external shield connected to ground.         | 9), except as no | ted.                                |
| Pentode Unit as Class A, Ampli   | ifier            |                                     |
| MAXIMUM RATINGS (Design-Center Values):  |                  |                                     |
| Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Screen Grid) Supply Voltage Grid-No.2 Voltage   | 0 r              | nax volts                           |
| Grid-No.1 (Control-Grid) Voltage: Negative bias value Positive bias value Plate Dissipation Grid-No.2 Input:   | 0 r              | nax volts<br>nax volts<br>nax watts |
| For grid-No.2 voltages up to 150 volts   |                  | nax watt<br>urve page 75            |
| CHARACTERISTICS: Plate Supply Voltage  | 250              | volts                               |

| CHIL  |     |      | WISTICS. |  |
|-------|-----|------|----------|--|
| Plate | Sur | oply | Voltage  |  |

| Plate Supply Voltage  | 100  | 250                | volts     |
|---|------|--------------------|-----------|
| Grid No.3   |      | Connect to cathode | at socket |
| Grid-No.2 Supply Voltage                                    | 100  | 150                | volts     |
| Cathode-Bias Resistor                                       | 150  | 68                 | ohms      |
| Plate Resistance (Approx.)                                  | 0.5  | 1                  | megohm    |
| Transconductance  | 3900 | 5200               | μmhos     |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ a | -4.2 | <b>6.5</b>         | volts     |
| Plate Current   | 5    | 10.6               | ma        |
| Grid-No.2 Current   | 2.1  | 4.3                | ma        |
| MAVIMIM CIRCLIP VALUES.                                     |      |                    |           |

### MAXIMUM CIRCUIT VALUES:

| iu-No. | 1-Circuit 1 | kesistance: |
|--------|-------------|-------------|
| For    | fixed-bias  | operation   |

| For fixed-bias operation   | 0.25 max | megohm |
|----------------------------|----------|--------|
| For cathode-bias operation | 1.0 max  | megohm |

#### **Diode Unit**


| MAXIMUM      | RATING   | S (Design-Center | Values): |
|--------------|----------|------------------|----------|
| Dook Inverse | Diota Va | ltono            |          |

| Peak Inverse Plate Voltage | 430 max | volts |
|----------------------------|---------|-------|
| Peak Plate Current         | 180 max | ma    |
| DC Plate Current           | 45 max  | ma    |

#### SEMIREMOTE-CUTOFF PENTODE

**6BZ6** 

Related types: 3BZ6, 4BZ6, 12BZ6 Miniature type used in gain-controlled video if stages of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 3BZ6, 4BZ6, and 12BZ6 are



identical with type 6BZ6 except for the heater ratings, as shown below.

| 3B2                           | Z6 41 | 3 <b>Z</b> 6 61 | 3Z6 12B2 | <b>Z</b> 6 |
|-------------------------------|-------|-----------------|----------|------------|
| Heater Voltage (ac/dc) 3.3    | 15 4  | .2 6.           | 3 12.6   | volts      |
| Heater Current (              |       | <b>45</b> 0.    | 3 0.15   | ampere     |
| Heater Warm-up Time (Average) | 11    | 11 -            |          | seconds    |

8000

-4.5

14

3.6

μmhos.

volts

volts

ma

ma

| Peak Heater-Cathode Voltage: Heater negative with respect   | 3 <b>BZ6</b>         | 4BZ6                  | 6BZ6               | 12BZ6              |                |
|---|----------------------|-----------------------|--------------------|--------------------|----------------|
| to cathode  | 200 max              | 200 max               | 200 max            | 200 max            | volts          |
| Heater positive with respect to cathode   | 200•max              | 1                     | Without            | 200 max<br>With    | volts          |
| Direct Interelectrode Capacitances:   |                      |                       | External<br>Shield | External<br>Shield |                |
| Grid No.1 to Plate  |                      |                       | 0.025 max          | 0.015 max          | pf             |
| Grid No.1 to Cathode, Heater, Grid<br>No.3, and Internal Shield<br>Plate to Cathode, Heater, Grid No.2  |                      |                       | 7                  | 7                  | pf             |
| and Internal Shield   |                      |                       | 2                  | 3                  | pf             |
| The dc component must not exceed 10<br>Δ With external shield connected to catho  |                      |                       |                    |                    |                |
| Class MAXIMUM RATINGS (Design-Maximu)   | ss A, An<br>m Values |                       |                    |                    |                |
| Plate Voltage   |                      |                       |                    | 330 max            | volts          |
| Grid No.3 (Suppressor-Grid) Voltage, Po<br>Grid-No.2 (Screen-Grid) Supply Voltage   |                      |                       |                    | 0 max<br>330 max   | volts<br>volts |
| Grid-No.2 Voltage   |                      |                       |                    | See curve          |                |
| Grid-No.1 (Control-Grid) Voltage, Positiv   | e bias va            | lue                   |                    | 0 max              | volts          |
| Plate Dissipation   | • • • • • • • • •    |                       | • • • • • • •      | 2.3 max            | watts          |
| For grid-No.2 voltages up to 165 vo<br>For grid-No.2 voltages between 165 a   |                      |                       |                    | 0.55 max           | watt           |
| - · · · · ·   | ina 330 vi           | ms                    |                    | See curve          | page /5        |
| CHARACTERISTICS: Plate Supply Voltage   |                      |                       |                    | 125                | volts          |
| Grid No.3   |                      |                       | Connected          | to cathode a       | t socket       |
| Grid-No.2 Supply Voltage  |                      |                       |                    | 125                | volts          |
| Cathode-Bias Resistor   |                      |                       |                    | 56<br>0.26         | ohms<br>megohm |
| Towns and the design of the control | · · · · · · · · · ·  | · · · · · · · · · · · |                    | 0.20               | megomin        |

#### 

Grid-No.1-Circuit Resistance:


For fixed-bias operation 0.25 max megohm
For cathode-bias operation 1.0 max megohm

Transconductance .....

Grid-No.1 Voltage (Approx.) for transconductance of 50 µmhos ....

Plate Current .....


Grid No.1 Voltage (Approx.) for transconductance of 700 μmhos and cathode resistor of 0 ohms



#### MEDIUM-MU TWIN TRIODE

6BZ7
Related type:
4BZ7

Miniature type used in direct-coupled cathode-drive rf amplifier circuits of vhf television tuners. In such circuits, one triode unit is used as the direct-coupled grounded-cathode driver for the other unit. This type is also used




in push-pull cathode-drive rf amplifiers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 4BZ7 is identical with type 6BZ7 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 4BZ7<br>4.2<br>0.6<br>11 | 6BZ7<br>6.3<br>0.4 | volts<br>ampere<br>seconds |
|--|--------------------------|--------------------|----------------------------|
| Heater negative with respect to cathode  | 200*max                  | 200*max            | volts                      |
| Heater positive with respect to cathode  | 200•max                  | 200=max            | volts                      |
| Direct Interelectrode Capacitances:  |                          |                    |                            |
| Grid to Plate (Each Unit)  |                          | 1.2                | pf                         |
| Grid to Cathode, Heater, and Internal Shield (Unit   | No.1)                    | 2.6                | pf                         |
| Plate to Cathode, Heater, and Internal Shield (Unit  | No.1)                    | 1.2                | pf                         |
| Plate to Cathode (Each Unit)   |                          | 0.12               | pf                         |
| Heater to Cathode (Each Unit)  |                          | 2.6                | pf                         |
| Cathode to Grid, Heater, and Internal Shield (Unit   |                          |                    | pf                         |
| Plate to Grid, Heater, and Internal Shield (Unit No.:  | 7)                       | 2.2                | pf                         |
| Plate of Unit No.1 to Plate of Unit No.2   | ٠                        | 0.010 max          |                            |
| Plate of Unit No.2 to Plate and Grid of Unit No.1  |                          |                    | pf                         |
| rate of Ome 140.2 to Flate and Orid of Unit No.1   |                          | 0.024 max          | pf                         |

<sup>•</sup> In cathode-drive circuits with direct-coupled drive, it is permissible for this voltage to be as high as 300 volts under cutoff conditions.

#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Center Values): |         |       |
|---|---------|-------|
| Plate Voltage                           | 250*max | volts |
| Plate Dissipation                       | 2.0 max | watts |
| Cathode Current                         | 20 max  | ma    |



<sup>•</sup> The dc component must not exceed 100 volts.

| CHARACTERISTICS:  |            |       |
|---|------------|-------|
| Plate Supply Voltage                                    | 150        | volts |
| Cathode-Bias Resistor                                   | 220        | ohms  |
| Amplification Factor                                    | 36         |       |
| Plate Resistance (Approx.)                              | 5300       | ohms  |
| Transconductance  | 6800       | μmhos |
| Plate Current   | 10         | ma    |
| Grid Voltage (Approx.) for plate current of 100 $\mu$ a | <b>—</b> 7 | volts |
| MAXIMUM CIRCUIT VALUE:                                  |            |       |

#### MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

**6BZ8** 



#### **POWER TRIODE**

Miniature type used in compact radio equipment as a local oscillator in FM and other high-frequency circuits. It may also be used as a class C rf amplifier. In such service, it delivers a power output of 5.5 watts at moder-

**6C4** 

ate frequencies, and 2.5 watts at 150 megacycles per second. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. For additional curve of plate characteristics, refer to type 12AU7A.

| Heater Voltage (ac/dc)                        |          | 6.3                 | volts  |
|---|----------|---------------------|--------|
| Heater Current                                |          | 0.15                | ampere |
| Peak Heater-Cathode Voltage:                  |          |                     |        |
| Heater negative with respect to cathode       |          | 200 max             | volts  |
| Heater positive with respect to cathode       |          | 200 • max           | volts  |
| · ·   | Without  | With                |        |
|   | External | External            |        |
| Direct Interelectrode Capacitances (Approx.): | Shield   | Shield <sub>4</sub> |        |
| Grid to Plate                                 | 1.6      | 1.4                 | pf     |
| Grid to Cathode and Heater                    | 1.8      | 1.8                 | pf     |
| Plate to Cathode and Heater                   | 1.3      | 2.5                 | pf     |
| The dc component must not exceed 100 volts    |          |                     |        |

- The dc component must not exceed 100 volts.
- △ With external shield connected to cathode.

## Class A Amplifier

| Plate Voltage Plate Dissipation                   |      | 300 max<br>3.5 max | volts<br>watts |
|---|------|--------------------|----------------|
| CHARACTERISTICS:                                  | 100  | 250                | volts          |
| Plate Voltage                                     |      |                    |                |
| Grid Voltage*                                     | 0    | 8.5                | volts          |
| Amplification Factor                              | 19.5 | 17                 |                |
| Plate Resistance (Approx.)                        | 6250 | 7700               | ohms           |
| Transconductance                                  | 3100 | 2200               | μmhos          |
| Plate Current                                     | 11.8 | 10.5               | ma             |
| Grid Voltage (Approx.) for plate current of 10 μa | -10  | -25                | volts          |
| MAYIMIM CIDCUIT VALUES.                           |      |                    |                |

#### MAXIMUM CIRCUIT VALUES:

Grid-Circuit Resistance:


For fixed bias operation 0.25 max megohm
For cathode-bias operation 1.0 max megohm

\*Transformer- or impedance-type input coupling devices are recommended to minimize resistance in the grid circuit.

#### RF Power Amplifier and Oscillator—Class C Telegraphy

| MAXIMUM RATINGS (Design-Center Values):       |         |       |
|---|---------|-------|
| Plate Voltage                                 | 300 max | volts |
| Grid Voltage                                  | 50 max  | volts |
| Plate Current                                 | 25 max  | ma    |
| Grid Current                                  | 8 max   | ma    |
| Plate Dissipation                             |         | watts |
| TYPICAL OPERATION at frequencies up to 50 Mc: |         |       |
| Plate Voltage                                 | 300     | volts |
| Grid Voltage                                  | 27      | volts |
| Plate Current                                 | 25      | ma    |
| Grid Current (Approx.)                        | 7       | ma    |
| Driving Power (Approx.)                       | 0.35    | watt  |
| Power Output (Approx.).                       | 5.5     | watts |

Approximately 2.5 watts power output can be obtained when the 6C4 is used at 150 megacycles as an oscillator with grid resistor of 10,000 ohms and with maximum rated input.



6C5

#### MEDIUM-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

6C5GT

#### **MEDIUM-MU TRIODE**

Discontinued type; see chart at end of section for tabulated data.

6**C**6

#### SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6**C**7


#### TWIN DIODE— MEDIUM-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

#### MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

6CG8




Miniature type used as vhf rf-amplifier and autodyne mixer tube. Outline 6B, Outlines section, except center pin is added to base. Tube requires miniature ten-contact socket and may be mounted in any position. Type 17C9

Related type: 17C9

is identical with type 6C9 except for the heater ratings, as shown below.

|  | 0 ,       |           |        |
|--|-----------|-----------|--------|
|  | 6C9       | 17C9      |        |
| Heater Voltage (ac/dc)                           | 6.3       | 16.8      | volts  |
| Heater Current                                   | 0.4       | 0.15      | ampere |
| Peak Heater-Cathode Voltage:                     |           |           | •      |
| Heater negative with respect to cathode          | 100 max   | 100 max   | volts  |
| Heater positive with respect to cathode          | 100 max   | 100 max   | volts  |
| Direct Interelectrode Capacitances:              | Unit No.1 | Unit No.2 |        |
| Grid No.1 to Plate                               | 0.055 max | 0.06 max  | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and     |           |           | -      |
| Internal Shield                                  | 4.4       | 4.2       | pf     |
| Plate to Cathode, Heater, Grid No.2, and         |           |           | •      |
| Internal Shield                                  | 2.2       | 2.2       | pf     |
| Heater to Cathode                                | 4.2       | 4.8       | pf     |
| Plate of Unit No.1 to Plate of Unit No.2         |           | 0.003 max | pf     |
| Grid No.1 of Unit No.1 to Grid No.1 of Unit No.2 |           | 0.001 max | pf     |
| Grid No.1 of Unit No.1 to Plate of Unit No.2     |           | 0.001 max | pf     |
| Grid No.1 of Unit No.2 to Plate of Unit No.1     |           | 0.032 max | pf     |
| Class A, Amplifier (Each                         | ı Unit)   |           |        |
| MAXIMUM RATINGS (Design-Maximum Values):         |           |           |        |
| Plate Voltage                                    |           | 250 max   | volts  |
| Grid-No.2 (Screen-Grid) Supply Voltage           |           | 180 max   | volts  |
| Grid-No.2 Voltage                                |           | See curve |        |
| Cathode Current                                  |           | 20 max    | ma     |
| Plate Dissipation:                               |           |           |        |
| Fither plate                                     |           | 15 may    | watte  |

|   | 0.002    | p.         |
|---|----------|------------|
| Class A, Amplifier (Each Unit)                  |          |            |
| MAXIMUM RATINGS (Design-Maximum Values):        |          |            |
| Plate Voltage                                   | 250 ma:  | x volts    |
| Grid-No.2 (Screen-Grid) Supply Voltage          | 180 ma   | x volts    |
| Grid-No.2 Voltage                               | See cur  | ve page 75 |
| Cathode Current                                 | 20 ma:   | x ma       |
| Plate Dissipation:                              |          |            |
| Either plate                                    | 1.5 ma   | x watts    |
| Both plates (both units operating)              | 2.5 ma   | x watts    |
| Grid-No.2 Input;                                |          |            |
| For grid-No.2 voltages up to 90 volts           | 0.5 ma   | x watt     |
| For grid-No.2 voltages between 90 and 180 volts | See curv | e page 75  |
| CHARACTERISTICS:                                |          |            |
| Plate Voltage                                   | 125      | volts      |
| Grid-No.2 Voltage                               | 80       | volts      |
| Grid-No.1 Voltage                               | —1       | volt       |
| Plate Resistance (Approx.)                      | 0.1      | megohm     |
| Transconductance                                | 8000     | $\mu$ mhos |
| Plate Current                                   | 10       | ma         |
| Grid-No.2 Current                               | 1.5      | ma         |



#### **FULL-WAVE VACUUM RECTIFIER**

Grid-No.1 Voltage (Approx.) for plate current of 20 µa ......

Miniature type used in power-supply of compact, audio equipment having moderate de requirements. Outline 6G, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. It is

6CA4


volts

especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 6.3; amperes, 1.

#### **Full-Wave Rectifier**

| MAXIMUM RATINGS (Design-Center Values):           |          |                     |          |       |
|---|----------|---------------------|----------|-------|
| Peak Inverse Plate Voltage                        |          |                     | 1000 max | volts |
| Peak Plate Current (Per Plate)                    |          |                     | 450 max  | ma    |
| AC Plate Supply Voltage (Per Plate, rms) with C   | apacitor | Input               | 100 mun  | 1114  |
| to Filter   |          |                     | 350 max  | volts |
| DC Output Current                                 |          |                     | 150 max  | ma    |
| Hot Switching Transient Plate Current (Per Plate  | e)       |                     | #        | ma    |
| Peak Heater-Cathode Voltage:                      | •,       | • • • • • • • • • • | #        |       |
| Heater negative with respect to cathode           |          |                     | 500 max  | volts |
| tioner ingenie with respect to camode             |          |                     | Joo max  | VOILS |
| TYPICAL OPERATION with Capacitor Input to Filter: |          |                     |          |       |
| AC Plate-to-Plate Supply Voltage (rms)            | 500      | 600                 | 700      | volts |
| Filter-Input Capacitor                            | 50       | 50                  | 50       | μf    |
| Total Effective Plate Supply Impedance            | -        | -                   | 50       | μι    |
| per Plate   | 150      | 200                 | 240      | ohms  |
| DC Output Voltage at Input to Filter (Approx.)    | 150      | 200                 | 240      | Onnis |
| For dc output current of 150 ma                   | 245      | 293                 | 347      |       |
| to de output cuitent of 150 ma                    | 243      | 293                 | 347      | volts |
|   |          |                     |          |       |

# When capacitor-input circuits are used, a maximum peak current value per plate of 1 ampere during the initial cycles of the hot-switching transient should not be exceeded.



#### **BEAM POWER TUBE**

6CA5
Related types: 12CA5, 25CA5

Miniature type used in af power output stage of radio and television receivers. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be operated in any position. Types 12CA5 and 25CA5



are identical with type 6CA5 except for the heater ratings, as shown below.

|                               | 6CA5 | 12CA5 | 25CA5 |         |
|-------------------------------|------|-------|-------|---------|
| Heater Voltage (ac/dc)        | 6.3  | 12.6  | 25    | volts   |
| Heater Current                | 1.2  | 0.6   | 0.3   | ampere  |
| Heater Warm-up Time (Average) | -    | 11    | _     | seconds |

25CA5

3.8

|   | 6CA5                                 | 12CA5                                | 25CA5              | )                                       |
|---|--------------------------------------|--------------------------------------|--------------------|---|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode    | 200 max<br>200°max                   | 300=max<br>200°max                   | 200 ma<br>200°ma   |   |
| • The dc component must not exceed 200 volts.   |                                      |                                      |                    |   |
| The dc component must not exceed 100 volts.   |                                      |                                      |                    |   |
| Class A, At   | mplifier                             |                                      |                    |   |
| MAXIMUM RATINGS (Design-Center Values):   |                                      |                                      |                    |   |
| Plate Voltage   |                                      | • • • • • •                          | 130 max            | volts                                   |
| Grid-No.2 (Screen-Grid) Voltage   |                                      | • • • • • • •                        | 130 max<br>0 max   | volts<br>volts                          |
| Plate Dissipation   |                                      |                                      | 5 max              | watts                                   |
| Grid-No.2 Input   |                                      | · · · · · · ·                        | 1.4 max            | watts                                   |
| Bulb Temperature (At hottest point)   |                                      | • • • • • •                          | 180 max            | °C                                      |
| TYPICAL OPERATION:  |                                      |                                      |                    |   |
| Plate Voltage   |                                      | 110                                  | 125                | volts                                   |
| Grid-No.2 Voltage   | • • • • •                            | 110<br>4                             | 125<br><b>4.</b> 5 | volts<br>volts                          |
| Peak AF Grid-No.1 Voltage   |                                      | 4                                    | 4.5                | volts                                   |
| Zero-Signal Plate Current   |                                      | 32                                   | 37                 | ma                                      |
| Maximum-Signal Plate Current  |                                      | 31                                   | 36                 | ma                                      |
| Zero-Signal Grid-No.2 Current (Approx.) Maximum-Signal Grid-No.2 Current (Approx.)                                |                                      | 3.5<br>7.5                           | 4<br>11            | ma<br>ma                                |
| Plate Resistance (Approx.)  |                                      | 000                                  | 15000              | ohms                                    |
| Transconductance  |                                      | 100                                  | 9200               | $\mu$ mhos                              |
| Load Resistance   | 3                                    | 500<br>5                             | 4500<br>6          | ohms                                    |
| Total Harmonic Distortion   |                                      | 1.1                                  | 1.5                | per cent<br>watts                       |
| ·   | • • • • •                            | ***                                  | 1.5                | *************************************** |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation         |                                      |                                      | 0.1 max<br>0.5 max |   |
| BEAM POWI<br>Discontinued type; s<br>of section for ta  | see chart                            | at end                               | 6CB                | 5                                       |
| GI(4) P (SIG) BEAM POW  | ER TUBE                              | E                                    |                    |   |
| Glass octal type us deflection amplifier sion receivers. Outline section. This tube received and may be mountion. | in color<br>ne 21B, O<br>quires octa | televi-<br><b>utlines</b><br>l sock- | 6CB5               | A                                       |
| Heater Voltage (ac/dc)  |                                      | • • • • • •                          | 6.3<br>2.5         | volts<br>amperes                        |
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode   |                                      |                                      | 200 max            | volts                                   |
| Heater positive with respect to cathode   |                                      |                                      | 200#max            | volts                                   |
| Direct Interelectrode Capacitances (Approx.):   |                                      |                                      | 0.4                | £                                       |
| Grid No.1 to Plate  | nd Grid No                           | .3                                   | 22                 | pf<br>pf                                |
| Plate to Cathode, Heater, Grid No.2 and Gr  | id No.3                              |                                      | 10                 | pf                                      |
| Transconductance*   |                                      |                                      | 8800               | #mhos                                   |

6CA5

12CA5

Mu-Factor, Grid No.2 to Grid No.1\* .....

Transconductance\*

<sup>#</sup>The dc component must not exceed 100 volts.

<sup>\*</sup> For plate and grid-No.2 volts, 175; grid-No.1 volts, -30; plate ma., 90; grid-No.2 ma., 6.

#### Horizontal Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|--|-----------|-------|
| DC Plate Voltage                         | 880 max   | volts |
| Peak Positive-Pulse Plate Voltage#       | 6800 max  | volts |
| Peak Negative-Pulse Plate Voltage        | -1650 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage       | 220 max   | volts |
| DC Grid-No.1 (Control-Grid) Voltage      | 55 max    | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -220 max  | volts |
| Peak Cathode Current                     | 850 max   | ma    |
| Average Cathode Current                  | 240 max   | ma    |
| Grid-No.2 Input                          | 4 max     | watts |
| Plate Dissipation†                       | 26 max    | watts |
| Bulb Temperature (At hottest point)      | 220 max   | °C    |

#### MAXIMUM CIRCUIT VALUE:

Grid-No.1-Circuit Resistance .....

0.47 max megohm

#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.


† An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

# 6CB6

Related types: 3CB6, 4CB6

#### SHARP-CUTOFF PENTODE

Miniature types used in television receivers as intermediate-frequency amplifier at frequencies up to about 45 megacycles per second and as rf amplifier in vhf television tuners. Tubes feature very high transconductance



combined with low interelectrode capacitance values, and are provided with separate base pins for grid No.3 and the cathode to permit the use of an unbypassed cathode resistor to minimize the effects of regeneration. Type 6CB6A has a controlled heater warm-up time for use in television receivers employing seriesconnected heater strings. Outline 5C, Outlines section. Tubes require miniature seven-contact socket and may be mounted in any position. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Types 3CB6, 4CB6, and 6CB6 are identical with type 6CB6A except for the heater ratings, as shown below.


|  | 3CB6                     | 4CB6              | 6CB6                            | 6CB6A                            |          |
|--|--------------------------|-------------------|---------------------------------|----------------------------------|----------|
| Heater Voltage (ac/dc)                                     | 3.15                     | 4.2               | 6.3                             | 6.3                              | volts    |
| Heater Current   | 0.6                      | 0.45              | 0.3                             | 0.3                              | ampere   |
| Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 11                       | 11                | _                               | 11                               | seconds  |
| Heater negative with respect to                            |                          |                   |                                 |                                  |          |
| cathode  | 300 max                  | 300•max           | 200 max                         | 200 max                          | volts    |
| cathode  | 200°max                  | 200°max           | 200°max                         | 200°max                          | volts    |
|  |                          |                   | Without                         | With                             |          |
| Direct Interelectrode Capacitances:                        |                          |                   | External<br>Shield              | External<br>Shield               |          |
| Direct Interelectrode Capacitances: Grid No.1 to Plate     |                          |                   | External                        | External                         | pf       |
| Grid No.1 to Plate   | Grid No.2,               | Grid              | External<br>Shield<br>0.025 max | External<br>Shielda<br>0.015 max |          |
| Grid No.1 to Plate   | Grid No.2,               | Grid<br>          | External<br>Shield              | External Shielda                 | pf<br>pf |
| Grid No.1 to Plate   | Grid No.2,<br>No.2, Grid | Grid<br><br>No.3, | External<br>Shield<br>0.025 max | External<br>Shielda<br>0.015 max |          |

- The dc component must not exceed 200 volts.
- \* The dc component must not exceed 100 volts.
- △ With external shield connected to cathode.

#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):   |  |  |
|--|--|--|
| Plate Voltage  | 330 max  | volts  |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value  | 0 max  | volts  |
| Grid-No.2 (Screen-Grid) Voltage  | See curv   | e page 75  |
| Grid-No.2 Supply Voltage   | 330 max  | volts  |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  | 0 max  | volts  |
| Plate Dissipation  | 2.3 max  | watts  |
| Grid-No.2 Input:   |  |  |
| For grid-No.2 voltages up to 165 volts   | 0.55 max   | watt   |
| For grid-No.2 voltages between 165 and 330 volts   | See curv   | e page 75  |
| CHARACTERISTICS:   |  |  |
|  |  |  |
|  | 105  | 14-  |
| Plate Supply Voltage   | 125  | volts  |
| Grid No.3 Conne  | cted to cathode                                      | at socket  |
| Grid No.3  | cted to cathode<br>125                               | at socket<br>volts                                     |
| Grid No.3 Conne Grid-No.2 Supply Voltage Cathode-Bias Resistor   | cted to cathode<br>125<br>56                         | at socket<br>volts<br>ohms                             |
| Grid No.3  | cted to cathode<br>125<br>56<br>0.28                 | at socket<br>volts<br>ohms<br>megohm                   |
| Grid No.3 Conne Grid-No.2 Supply Voltage Cathode-Bias Resistor   | cted to cathode<br>125<br>56                         | at socket<br>volts<br>ohms                             |
| Grid No.3 Conne Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.)  | cted to cathode<br>125<br>56<br>0.28                 | at socket<br>volts<br>ohms<br>megohm                   |
| Grid No.3 Conne Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance   | cted to cathode<br>125<br>56<br>0.28<br>8000         | at socket<br>volts<br>ohms<br>megohm<br>µmhos          |
| Grid No.3 Conne Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu$ a | cted to cathode<br>125<br>56<br>0.28<br>8000         | at socket<br>volts<br>ohms<br>megohm<br>µmhos          |
| Grid No.3  | cted to cathode<br>125<br>56<br>0.28<br>8000<br>—6.5 | at socket<br>volts<br>ohms<br>megohm<br>µmhos<br>volts |






#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

6CD6G



#### **BEAM POWER TUBE**

Glass octal type used as horizontal deflection amplifier in high-efficiency deflection circuits of television receivers employing either transformer coupling or direct coupling to the deflection yoke. Outline 21B, Outlines

6CD6GA
Related type:
25CD6GB

section. Tube requires octal socket. This type may be supplied with pins 1, 4, and 6 omitted. Vertical tube mounting is preferred but horizontal operation is permis-

sible if pins No.2 and 7 are in vertical plane. Type 25CD6GB is identical with type 6CD6GA except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)                              | 6CD6GA<br>6.3 | 25CD6GB<br>25 | volts      |
|---|---------------|---------------|------------|
| Heater Current                                      | 2.5           | 0.6           | ampere     |
| Heater Warm-up Time (Average)                       | _             | 11            | seconds    |
| Peak Heater-Cathode Voltage:                        |               |               |            |
| Heater negative with respect to cathode             | 200 max       | 200 max       | volts      |
| Heater positive with respect to cathode             | 200≟max       | 200₄max       | volts      |
| Direct Interelectrode Capacitances (Approx.):       |               |               |            |
| Grid No.1 to Plate                                  |               | 1.1           | pf         |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid N |               | 22            | pf         |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3  |               | 8.5           | pf         |
| Transconductance°                                   |               | 7700          | $\mu$ mhos |
| Plate Resistance (Approx.)°                         |               | 7200          | ohms       |
| Mu-Factor, Grid No.2 to Grid No.1                   |               | 3.9           |            |

- A The dc component must not exceed 100 volts.
- \* For plate and grid-No.2 volts, 175; grid-No.1 volts, -30; plate ma., 75; grid-No.2 ma., 5.5.

#### **Horizontal Deflection Amplifier**


For operation in a 525-line, 30-frame system


| MAXIMUM RATINGS (Design-Center Values):               |           |       |
|---|-----------|-------|
| DC Plate Voltage                                      | 700 max   | volts |
| Peak Positive-Pulse Plate Voltage* (Absolute Maximum) | 7000 max  | volts |
| Peak Negative-Pulse Plate Voltage                     | -1500 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage                    | 175 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage                 | -200 max  | volts |
| Peak Cathode Current                                  | 700 max   | ma    |
| Average Cathode Current                               | 200 max   | ma    |
| Plate Dissipation†                                    | 20 max    | watts |
| Grid-No.2 Input                                       | 3 max     | watts |
| Bulb Temperature (At hottest point)                   | 225 max   | °C    |

#### MAXIMUM CIRCUIT VALUE:

Grid-No.1-Circuit Resistance: For grid-resistor-bias operation 0.47 max megohm

- \* The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 micro-
- Under no circumstances should this absolute value be exceeded.
- † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.





# H3 0°2

Plate Current

Grid-No.2 Current .....

#### SHARP-CUTOFF PENTODE

Miniature type used as rf and if amplifier in whf television receivers employing series-connected heater strings. Outline 5C, Outlines section.

Tube requires miniature seven-contest cooket and many heaters in

6CE5
Related type:
3CE5

ma

ma

6CE5

tact socket and may be operated in any position. Type 3CE5 is identical with type 6CE5 except for the heater ratings, as shown below.

3CE5

|  | JCLJ                                    | رشونان     |         |
|--|---|------------|---------|
| Heater Voltage (ac/dc)                                 | 3.15                                    | 6.3        | volts   |
| Heater Current   | 0.6                                     | 0.3        | ampere  |
| Heater Warm-up Time (Average)                          | 11                                      | 11         | seconds |
| Peak Heater-Cathode Voltage:                           |   |            |         |
| Heater negative with respect to cathode                | 200 max                                 | 200 max    | volts   |
| Heater positive with respect to cathode                | 200=max                                 | 200 max    | volts   |
| Direct Interelectrode Capacitances:                    | 200 milli                               | 200-11167  | 1016    |
| Grid No.1 to Plate                                     |   | 0.03 max   | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3     | • • • • • • • • • • • • • • • • • • •   | 0.05 Illax | pι      |
| and Internal Shield                                    | ·,                                      | 6.5        |         |
| Plate to Cathode, Heater, Grid No.2, Grid No.3.        |   | 0.5        | pf      |
| and Internal Shield                                    |   | 4.0        |         |
| and internal Sincing                                   |   | 1.9        | pf      |
| The dc component must not exceed 100 volts.            |   |            |         |
| •  |   |            |         |
| Class A, Amplifier                                     |   |            |         |
| MAXIMUM RATINGS (Design-Center Values):                |   |            |         |
| Plate Voltage  |   | 300 max    | volts   |
| Grid-No.2 (Screen-Grid) Voltage                        |   | 150 max    | volts   |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  |   | 0 max      | volts   |
| Grid-No.2 Input  | • | 0.5 max    |         |
| Plate Dissipation                                      |   |            | watt    |
| Tiate Dissipation                                      | • | 2 max      | watts   |
| CHARACTERISTICS:                                       |   |            |         |
| Plate Voltage  |   | 125        | volts   |
| Grid-No.2 Voltage                                      |   | 125        | voits   |
| Grid-No.1 Supply Voltage                               |   | -1         |         |
| Grid-No.1 Resistor (Bypassed)                          |   | 1          | volt    |
| Ploto Desistance (Approx)                              | •••••                                   | -          | megohm  |
| Plate Resistance (Approx.)                             |   | 0.3        | megohm  |
| Transconductance                                       | • • • • • • • • •                       | 7600       | µmhos   |
| Grid-No.1 Voltage (Approx.) for plate current of 35 μa |   | -5         | volts   |

3CF6

3.15

0.6

11

#### SHARP-CUTOFF PENTODE


6CF6
Related type:

Heater Current

Heater Voltage (ac/dc) .....

Heater Warm-up Time (Average) .....

Miniature type used in television receivers as an intermediate-frequency amplifier at frequencies up to about 45 megacycles per second and as an rf amplifier in vhf television tuners. Because of its plate-current cutoff



6CF6

6.3

0.3

volts

ma

ampere

seconds

characteristic, this type is used in gain-controlled stages of video if amplifiers. This type is electrically similar to miniature type 6CB6. Outline 5C, Outlines section. Type 3CF6 is identical with type 6CF6 except for the heater ratings, as shown below.


| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode | 300 max | 200 max          | volts     |
|---|---------|------------------|-----------|
| Heater positive with respect to cathode                               | 200 max | 200 <b>=</b> max | volts     |
| ■ The dc component must not exceed 100 volts.                         |         |                  |           |
| CHARACTERISTICS:  |         |                  |           |
| Plate Supply Voltage  |         | 125              | volts     |
| Grid No.3   | Connect | ed to cathode    | at socket |
| Grid-No.2 Supply Voltage  |         | 125              | volts     |
| Cathode-Bias Resistor   |         | 56               | ohms      |
| Plate Resistance (Approx.)  |         | 0.3              | megohm    |
| Transconductance  |         | 7800             | μmhos     |
| Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu a$           |         | 6                | volts     |
| Grid-No.1 Voltage (Approx.) for plate current of 2.2 ma a             | and     |                  |           |
| cathode-bias resistor of 0 ohms                                       |         | 3                | volts     |
| Plate Current   |         | 12.5             | ma        |

#### MEDIUM-MU TWIN TRIODE

6CG7
Related type:

Grid No.2 Current ......

Miniature type used as combined vertical deflection and horizontal deflection oscillator in television receivers. Also used as phase inverter, sync separator and amplifier, and resistance-coupled amplifier in radio receivers.




3.7

This type has a controlled heater warm-up time for use in receivers employing series-connected heater strings. Except for the common heater, each triode unit is independent of the other. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 6CG7 is identical with type 8CG7 except for the heater ratings, as shown below.

|  | 6CG7           | 8CG7    |         |
|--|----------------|---------|---------|
| Heater Voltage (ac/dc)                                   | 6.3            | 8.4     | volts   |
| Heater Current   | 0.6            | 0.45    | ampere  |
| Heater Warm-up Time (Average)                            | 11             | 11      | seconds |
| Peak Heater-Cathode Voltage:                             |                |         |         |
| Heater negative with respect to cathode                  | 200 max        | 200 max | volts   |
| Heater positive with respect to cathode                  | 200 <b>max</b> | 200 max | volts   |
| Direct Interelectrode Capacitances (Each Unit, Approx.): |                |         |         |
| Grid to Plate  |                | 4.0     | pf      |
| Grid to Cathode, Heater, and Internal Shield             |                | 2.3     | pf      |
| Plate to Cathode, Heater, and Internal Shield            |                | 2.2     | pf      |

The dc component must not exceed 100 volts.

| Class A, Amplifier (Eac  | h Unit)       |            |            |
|--|---------------|------------|------------|
| MAXIMUM RATINGS (Design-Maximum Values):                                 |               |            |            |
| Plate Voltage  |               | 330 max    | volts      |
| Grid Voltage, Positive-bias value  |               | 0 max      | volts      |
| For either plate   |               | 4 max      | watts      |
| For both plates with both units operating                                |               | 5.7 max    | watts      |
| Cathode Current  |               | 22 max     | ma         |
| CHARACTERISTICS:   |               |            |            |
| Plate Voltage  | 90            | 250        | volts      |
| Grid Voltage   | 0             | 8          | voits      |
| Amplification Factor   | 20            | 20         |            |
| Plate Resistance (Approx.)   | 6700          | 7700       | ohms       |
| Transconductance   | 3000          | 2600       | $\mu$ mhos |
| Grid Voltage (Approx.) for plate current of 10 µa                        | <del></del> 7 | -18        | volts      |
| Plate Current for grid voltage of -12.5 volts                            | _             | 1.3        | ma         |
| Plate Current  | 10            | 9          | ma         |
| MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance: For fixed-bias operation |               | 1.0 max    | megohm     |
| -  |               |            |            |
| Oscillator   |               |            |            |
| For operation in a 525-line, 30-f  | Vertical      | Horizontal | i          |
| MAXIMUM RATINGS (Design-Maximum Values,                                  | Deflection    | Deflection |            |
| Each Unit):  | Oscillator    | Oscillator |            |
| DC Plate Voltage   | 330 max       | 330 max    | volts      |
| Peak Negative-Pulse Grid Voltage   | -440 max      | 660 max    | volts      |
| Peak Cathode Current   | 77 max        | 330 max    | ma         |
| Average Cathode Current  | 22 max        | 22 max     | ma.        |
| Plate Dissipation:   | 22 max        | 22 max     | ma         |
| For either plate   | 4 max         | 4 max      | watts      |
| For both plates with both units operating                                | 5.7 max       | 5.7 max    | watts      |
| MAXIMUM CIRCUIT VALUE:   |               |            |            |
|  |               |            |            |



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE


Discontinued type; see chart at end of section for tabulated data.

**6CG8** 

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6CG8A

Miniature type used as combined oscillator and mixer tube in television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. When used in an AM/FM receiver, the triode unit is used as an



oscillator for both sections. In the AM section, the pentode unit is used as a highgain pentode mixer; in the FM section, the pentode unit is used either as a pentode mixer or as a triode-connected mixer depending on signal-to-noise considerations. This type has a controlled heater warm-up time for use in television receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 5CG8 is identical with type 6CG8A except for the heater ratings. These types are electrically identical with miniature type 6X8 except for interelectrode capacitances.


| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 5CG8<br>4.7<br>0.6<br>11 | 6CG8A<br>6.3<br>0.45<br>11 | volts<br>ampere<br>seconds |
|--|--------------------------|----------------------------|----------------------------|
| Heater negative with respect to cathode  | 200 max                  | 200 max                    | volts                      |
| Heater positive with respect to cathode  | 200=max<br>Without       | 200=max<br>With            | volts                      |
| Direct Interelectrode Capacitances:  | External                 | External                   |                            |
| Triode Unit:   | Shield                   | Shield°                    |                            |
| Grid to Plate  | 1.5                      | 1.5                        | pf                         |
| Grid to Cathode, Heater, and Pentode Grid No.3   | 2                        | 2.4                        | pf                         |
| Plate to Cathode, Heater, and Pentode Grid No.3  | 0.5                      | 1                          | pf                         |
| Pentode Unit: Grid No.1 to Plate   | 0.04 max                 | 0.02 max                   | pf                         |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3   | 4.6                      | 4.8                        | pf                         |
| Plate to Cathode, Heater, Grid No.2, and Grid  | 0.9                      | 1.6                        | pf                         |
| No.3  Pentode Grid No.1 to Triode Plate  | 0.05 max                 | 0.04 max                   | pf                         |
|  | 0.05 max                 | 0.008 max                  |                            |
| Pentode Plate to Triode Plate  Heater to Cathode   | 6.5                      | 6.5 •                      | pf<br>pf                   |

- The dc component must not exceed 100 volts.
- With external shield connected to cathode, except as noted.
- With external shield connected to plate.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**6CH8** 

Miniature type used in a wide variety of applications in television receivers. The pentode unit is used as an if amplifier, video amplifier, age amplifier, or reactance tube. The triode unit is used in low-frequency oscillator, sync-



separator, sync-clipper, and phase-splitter circuits. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. The pentode-unit curve for the 6AN8A applies for this type except that grid No.3, heater, and internal shield (pin 5) are connected to ground.

| Heater Voltage (ac/dc)  | 6.3<br>0.45        | volts<br>ampere |
|---|--------------------|-----------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances: | 200△max<br>200°max | volts<br>volts  |
| Triode Unit:  |                    | _               |
| Grid to Plate   | 1.6                | pf              |
| Grid to Cathode, Heater, Pentode Grid No.3, and Internal Shield   | 1.9                | pf              |
| Plate to Cathode, Heater, Pentode Grid No.3, and Internal Shield  | 1.6                | pf              |
| Pentode Unit:   |                    |                 |
| Grid No.1 to Plate  | 0.025              | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,   |                    | •               |
| and Internal Shield   | 7                  | pf              |
| Plate to Cathode, Heater, Grid No.2, Grid No.3,   |                    | _               |
| and Internal Shield   | 2.25               | pf              |
| Triode Grid to Pentode Plate  | 0.005              | pf              |
| Pentode Grid No.1 to Triode Plate   | 0.02               | pf              |
|   | 0.02               | pf              |
| Pentode Plate to Triode Plate   | 0.04               | Pι              |

A The heater-cathode voltage of the pentode unit should not exceed the value of the operating cathode bias because the voltage between the heater and cathode is also applied between the cathode and grid No.3. The net result is to make grid No.3 negative with respect to cathode with possible change in tube characteristics.

| Class A <sub>1</sub> Amplifier   |   |  |  |
|--|---|--|--|
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:              | Triode Unit<br>300 max<br>—<br>—<br>—<br>0 max<br>2.6 max | Pentode Uni<br>300 max<br>0 max<br>300 max<br>See curv<br>0 max<br>2 max | volts volts volts volts e page 75 volts watts            |
| For grid-No.2 voltages up to 150 volts   | =   | 0.5 max<br>See curv  | watt<br>e page 75  |
| CHARACTERISTICS: Plate Supply Voltage Grid No.3 Grid-No.2 Supply Voltage Grid Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ a Plate Current Grid-No.2 Current | 200 — Connect ————————————————————————————————————        | 200 cted to ground 150 180 300000 6200 8 9.5 2.8                         | volts at socket volts volts ohms ohms  µmhos volts ma ma |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:* For fixed-bias operation For cathode bias operation   | 0.5 max<br>1.0 max  | 0.25 max<br>1.0 max  | megohm<br>megohm   |

• If either unit is operating at maximum rated conditions, grid No.1-circuit resistance for both units should not exceed the stated values.

#### LOW-MU TRIODE

Renewal type; see chart at end of section for tabulated data.



<sup>\*</sup> The dc component must not exceed 100 volts.

#### **POWER PENTODE**

6CL6

Miniature type used in output stage of video amplifier of television receivers and as wide-band amplifier tube in industrial and laboratory equipment. Outline 6E, Outlines section. Tube requires miniature nine-




0.1 max megohm 0.5 max megohm

contact socket and may be mounted in any position.

| contact socket and may be mounted in any position.                                    |             |                 |
|---|-------------|-----------------|
| Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage:                    | 6.3<br>0.65 | volts<br>ampere |
| Heater negative with respect to cathode   | 100 max     | volts           |
| Heater positive with respect to cathode Direct Interelectrode Capacitances (Approx.): | 100 max     |                 |
| Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,                | 0.12        | pf              |
| and Internal Shield   | 11          | pf              |
| and Internal Shield   | 5.5         | pf              |
| Class A, Amplifier  |             |                 |
| MAXIMUM RATINGS (Design-Center Values):   |             |                 |
| Plate Voltage   | 300 max     | volts           |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive Value                                   | 0 max       | volts           |
| Grid-No.2 (Screen-Grid) Supply Voltage  | 300 max     | volts           |
| Grid-No.2 Voltage   | 150 max     | volts           |
| Grid-No.1 (Control-Grid) Voltage:   | 100 IIIan   | , , , ,         |
| Negative-bias value   | -50 max     | volts           |
| Positive-bias value   | 0 max       | volts           |
| Plate Dissipation   | 7.5 max     |                 |
|   |             |                 |
| Grid-No.2 Input   | 1.7 max     |                 |
| Bulb Temperature (At hottest point)   | 200 max     | °C              |
| TYPICAL OPERATION:  |             |                 |
| Plate Voltage   | 250         | volts           |
| Grid No.3 Connected   |             |                 |
|   |             | volts           |
| Grid-No.2 Voltage   | 150         |                 |
| Grid-No.1 Voltage   | -3          | volts           |
| Peak AF Grid-No.1 Voltage   | 3           | volts           |
| Zero-Signal Plate Current   | 30          | ma              |
| Maximum-Signal Plate Current  | 31          | ma              |
| Zero-Signal Grid-No.2 Current   | 7           | ma              |
| Maximum-Signal Grid-No.2 Current  | 7.2         | ma              |
| Plate Resistance (Approx.)  | 0.09        | megohm          |
| Transconductance  | 11000       | μmhos           |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ a                           | -14         | volts           |
| Load Resistance   | 7500        | ohms            |
| Total Harmonic Distortion   | 8           | per cent        |
| Maximum-Signal Power Output   | 2.8         | watts           |
|   | 2.0         | Watts           |
| TYPICAL OPERATION IN 4-MC-BANDWITH VIDEO AMPLIFIER:                                   |             |                 |
| Plate Supply Voltage  | 300         | volts           |
| Grid No.3 Connected   |             |                 |
| Grid-No.2 Supply Voltage  | 300         | volts           |
| Grid-No.1 Bias Voltage  | -2          | volts           |
| Grid-No.1 Signal Voltage (Peak to Peak)   | 3           | volts           |
| Grid-No.2 Resistor  | 24000       | ohms            |
| Grid-No.1 Resistor  | 0.1         |                 |
|   |             | megohm          |
| Load Resistor   | 3900        | ohms            |
| Zero-Signal Plate Current   | 30          | ma              |
| Zero-Signal Grid-No.2 Current   | 7.0         | ma              |
| Voltage Output (Peak to Peak)   | 132         | volts           |
| MAXIMUM CIRCUIT VALUES:   |             |                 |
| Grid-No.1 Circuit Resistance:   |             |                 |
| Gild-110.1 Circuit Medistance.  |             |                 |

For fixed-bias operation ......


For cathode-bias operation ......



## MEDIUM-MU TRIODE— SHARP-CUTOFF TETRODE

Discontinued type; see chart at end of section for tabulated data.

6CL8



# MEDIUM-MU TRIODE— SHARP-CUTOFF TETRODE

Miniature type used as combined vhf oscillator and mixer in television receivers employing series-connected heater strings. Outline 6B, Outlines section. This tube requires miniature nine-contact socket and may be

6CL8A
Related types:
5CL8A, 19CL8A

0.25 max megohm 1 max megohm

mounted in any position. For maximum ratings as class  $A_1$  amplifier, see type 6U8A. Types 5CL8A and 19CL8A are identical with type 6CL8A except for the heater ratings, as shown below.

|   | 5CL8A | 6CL8A | 19CL8A |         |
|---|-------|-------|--------|---------|
| Heater Voltage (ac/dc)                        | 4.7   | 6.3   | 18.9   | volts   |
| Heater Current                                | 0.6   | 0.45  | 0.15   | ampere  |
| Heater Warm-up Time (Average)                 | 11    | 11    | 11     | seconds |
| Heater negative with respect to cathode.      | 200   | 200   | 200    | volts   |
| Heater positive with respect to cathode.      | 200=  | 200=  | 200=   | volts   |
| • The dc component must not exceed 100 volts. |       |       |        |         |
|   |       |       |        |         |

| Class A, Amplifie                                      | r           |              |        |
|--|-------------|--------------|--------|
| CHARACTERISTICS:                                       | Triode Unit | Tetrode Unit |        |
| Plate Supply Voltage                                   | 125         | 125          | volts  |
| Grid-No.2 (Screen-Grid) Voltage                        | _           | 125          | volts  |
| Grid-No.1 Voltage                                      | -1          | -1           | volt   |
| Amplification Factor                                   | 40          | -            |        |
| Plate Resistance (Approx.)                             | 0.005       | 0.2          | megohm |
| Transconductance                                       | 8000        | 6500         | μmhos  |
| Grid-No.1 Voltage (Approx.) for plate current of 20 µa | -9          | -9           | volts  |
| Plate Current  | 14          | 12           | ma     |
| Grid-No.2 Current                                      | -           | 4            | ma     |
| MAXIMUM CIRCUIT VALUES:                                |             |              |        |
| Grid-No.1-Circuit Resistance:                          |             |              |        |

0.5 max

1 max


For fixed-bias operation .....

For cathode-bias operation ......

## **BEAM POWER TUBE**

6CM6

Miniature type used as vertical deflection amplifier in television receivers and as audio power amplifier in radio and television receivers. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and



may be mounted in any position. For typical operation and maximum circuit values as class  $A_1$  amplifier, refer to type 6V6GTA. For curves of average plate characteristics, refer to type 6AQ5A.

| Heater Voltage (ac/dc) Heater Current   | 6.3<br>0.45 | volts<br>ampere |
|---|-------------|-----------------|
| Peak Heater-Cathode Voltage:            |             |                 |
| Heater negative with respect to cathode | 200 max     | volts           |
| Heater positive with respect to cathode | 200=max     | volts           |
| Amplification Factor*                   | 9.8         |                 |
| Plate Resistance (Approx.)*             | 1960        | ohms            |
| Transconductance*                       | 5000        | μmhos           |
|   |             |                 |

- The dc component must not exceed 100 volts.
- \* Grid No.2 connected to plate; plate and grid-No.2 volts, 250; grid-No.1 volts, -12.5; plate and grid-No.2 ma., 49.5.

#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Center Values): |         |       |
|---|---------|-------|
| Plate Voltage                           | 315 max | volts |
| Grid-No.2 (Screen-Grid) Voltage         | 285 max | volts |
| Grid-No.2 Input                         | 2 max   | watts |
| Plate Dissipation                       | 12 max  | watts |

# Vertical Deflection Amplifier For operation in a 525-line, 30-frame system

|  | Triode                  | Pentode    |       |
|--|-------------------------|------------|-------|
| MAXIMUM RATINGS (Design-Center Values):              | Connection <sup>o</sup> | Connection |       |
| DC Plate Voltage                                     | 315 max                 | 315 max    | volts |
| Peak Positive-Pulse Plate Voltage† (Absolute         |                         |            |       |
| Maximum)   | 2000±max                | 2000≟max   | volts |
| DC Grid-No.2 (Screen-Grid) Voltage                   |                         | 285 max    | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | -250 max                | -250 max   | volts |
| Peak Cathode Current                                 | 120 max                 | 120 max    | ma    |
| Average Cathode Current                              | 40 max                  | 40 max     | ma    |
| Plate Dissipation                                    | 9 max                   | 8 max      | watts |
| Grid-No.2 Input                                      | -                       | 1.75 max   | watts |

# MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:

For cathode-bias operation

° Grid No.2 connected to plate.
† The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle.

2.2 max


In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

- Under no circumstances should this absolute value be exceeded.

#### MEDIUM-MU DUAL TRIODE

6CM7
Related type: 8CM7

Miniature type used as combined vertical deflection oscillator and vertical deflection amplifier in television receivers employing series-connected heater strings. Unit No.1 is used as a conventional blocking oscillator in



2.2 max megohms

vertical deflection circuits, and unit No.2 as a vertical deflection amplifier. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be

Grid-Circuit Resistance: For fixed-bias operation

For cathode-bias operation

mounted in any position. Type 8CM7 is identical with type 6CM7 except for the heater ratings, as shown below.

CON 17

2.2 max

2.2 max

1.0 max megohms

2.5 max megohms

00147


|  | 6CM7       | 8CM7      |          |
|--|------------|-----------|----------|
| Heater Voltage (ac/dc)   | 6.3        | 8.4       | volts    |
| Heater Current   | 0.6        | 0.45      | ampere   |
| Heater Warm-up Time (Average)  | 11         | 11        | seconds  |
| Heater negative with respect to cathode  | 200 max    | 200 max   | volts    |
| Heater positive with respect to cathode  | 200△max    | 200△max   | volts    |
| Direct Interelectrode Capacitances (Approx.):  | Unit No.1  | Unit No.2 |          |
| Grid to Plate  | 3.8        | 3         | pf       |
| Grid to Cathode and Heater   | 2          | 3.5       | pf       |
| Plate to Cathode and Heater  | 0.5        | 0.4       | pf       |
| a The dc component must not exceed 100 volts.  |            |           | _        |
| Class A, Amplific  | er         |           |          |
| CHARACTERISTICS:   | Unit No.1  | Unit No.2 |          |
| Plate Voltage  | 200        | 250       | volts    |
| Grid Voltage   | <b>-7</b>  | 8         | volts    |
| Amplification Factor   | 21         | 18        |          |
| Plate Resistance (Approx.)   | 10500      | 4100      | ohms     |
| Transconductance   | 2000       | 4400      | μmhos    |
| Grid Voltage (Approx.) for plate current of 10 μa  | -14        |           | volts    |
| Plate Current  | 5          | 20        | ma       |
| Plate Current for grid voltage of -10 volts  | 1          | _         | ma       |
| Vertical Deflection Oscillator   |            | er        |          |
| For operation in a 525-line, 30-   | Unit No.1  | Unit No.2 |          |
| MAXIMUM RATINGS (Design-Maximum Values):   | Oscillator | Amplifier |          |
| and the second of the second o | 550 max    | 550 max   | volts    |
| DC Plate Voltage Peak Positive-Pulse Plate Voltage#  | 330 max    | 2200 max  | volts    |
| Peak Negative-Pulse Grid Voltage   | -220 max   | -220 max  | volts    |
| Peak Cathode Current   | 77 max     | 77 max    | ma       |
| Average Cathode Current  | 17 max     | 22 max    | ma<br>ma |
| Plate Dissipation  | 1.45 max   | 6 max     | watts    |
| •  | I,4J IIIAX | O HIAX    | walls    |
| MAXIMUM CIRCUIT VALUES:  |            |           |          |


For grid-resistor-bias operation

2.2 max — megohms

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle.

In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.






## MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6CM8
Related type:
5CM8

Miniature type used in variety of applications in television receivers. The sap 3 pentode unit is used as an intermediate-frequency amplifier, a video amplifier, an age amplifier, or as a reactance tube. The triode unit is used in



volts

sweep-oscillator, sync-separator, sync-clipper, and phase-splitter circuits. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 5CM8 is identical with type 6CM8 except for the heater ratings, as shown below.


|   | 5CM8      | 6CM8      |         |
|---|-----------|-----------|---------|
| Heater Voltage (ac/dc)                              | 4.7       | 6.3       | volts   |
| Heater Current                                      | 0.6       | 0.45      | ampere  |
| Heater Warm-up Time (Average)                       | _         | 11        | seconds |
| Peak Heater-Cathode Voltage:                        |           |           |         |
| Heater negative with respect to cathode             | 200 max   | 200 max   | volts   |
| Heater positive with respect to cathode             | 200 • max | 200 ■ max | volts   |
| Direct Interelectrode Capacitances:                 |           |           |         |
| Triode Unit:  |           |           |         |
| Grid to Plate                                       |           | 1.9       | pf      |
| Grid to Cathode and Heater                          |           | 1.6       | pf      |
| Plate to Cathode and Heater                         |           | 0.22      | pf      |
| Pentode Unit:                                       |           |           | • -     |
| Grid No.1 to Plate                                  |           | 0.04 max  | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3  | 3, and    |           |         |
| Internal Shield                                     |           | 6         | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and |           |           | •       |
| Internal Shield                                     |           | 2.6       | pf      |
| Triode Grid to Pentode Plate                        |           | 0.01 max  | pf      |
| Pentode Grid No.1 to Triode Plate                   |           | 0.15 max  | pf      |
| Pentode Plate to Triode Plate                       |           | 0.1 max   | pf      |
| The de commonwel much make an all 100 makes         |           |           | _       |

The dc component must not exceed 100 volts.

# Class A, Amplifier

MAXIMUM RATINGS (Design-Center Values):Triode UnitPentode UnitPlate Voltage300 max300 max

| Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts                                   | Triode Unit  O max 1 max  —              | 0 max<br>2 max<br>0.5 max                       | volts<br>ve page 75<br>volts<br>watts                                   |
|---|--|---|---|
| CHARACTERISTICS: Plate Supply Voltage Grid-No.2 Supply Voltage Grid Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid-No.1 Voltage (Approx.) for plate current of 10 µa Plate Current Grid-No.2 Current | 250<br>—2<br>100<br>0.05<br>2000<br>—1.8 | 250<br>150<br>————————————————————————————————— | volts<br>volts<br>volts<br>ohms<br>megohm<br>µmhos<br>volts<br>ma<br>ma |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation   | 0.25 max<br>1 max                        | 0.25 max<br>1 max                               | megohm<br>megohm  |



# TWIN DIODE— HIGH-MU TRIODE

Miniature type used as combined horizontal phase detector and reactance tube in television receivers employing series-connected heater strings. The triode unit is used in sync-separator, sync-amplifier, or au-

6CN7
Related type:
8CN7

dio amplifier circuits. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For typical operation of triode unit as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 8CN7 is identical with type 6CN7 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc):   | 6CN7                     | 8CN7  |                                 |
|---|--------------------------|---|---------------------------------|
| Series  | 6.3                      | 8.4   | voits                           |
| Parallel  | 3.15                     | 4.2   | volts                           |
| Heater Current:   |                          |   |                                 |
| Series  | 0.3                      | 0.225                                       | ampere                          |
| Parallel  | 0.6                      | 0.45  | ampere                          |
| Heater Warm-up Time (Average)   | 11                       | 11  | seconds                         |
| Peak Heater-Cathode Voltage:  |                          |   |                                 |
| Heater negative with respect to cathode   | 200 max                  | 200 max                                     | volts                           |
| Heater positive with respect to cathode   | 200*max                  | 200 max                                     | volts                           |
| • The dc component must not exceed 100 volts.   |                          |   |                                 |
|   |                          |   |                                 |
| Triode Unit as Class A, A  MAXIMUM RATINGS (Design-Maximum Values):   | Amplifier                |   |                                 |
| MAXIMUM RATINGS (Design-Maximum Values):  | •                        | 330 max                                     | volts                           |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage  |                          | 330 max<br>0 max                            | volts<br>volts                  |
| MAXIMUM RATINGS (Design-Maximum Values):  |                          |   |                                 |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation  |                          | 0 max                                       | volts                           |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage  |                          | 0 max<br>1.1 max                            | volts<br>watt                   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation  CHARACTERISTICS: Plate Voltage  | 100                      | 0 max<br>1.1 max                            | volts<br>watt                   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation  CHARACTERISTICS: Plate Voltage Grid Voltage   | 100 —1                   | 0 max<br>1.1 max<br>250                     | volts<br>watt                   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation  CHARACTERISTICS: Plate Voltage Grid Voltage Amplification Factor                            | 100<br>1<br>70           | 0 max<br>1.1 max<br>250<br>3<br>70          | volts<br>watt                   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation  CHARACTERISTICS: Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) | 100<br>—1<br>70<br>54000 | 0 max<br>1.1 max<br>250<br>3<br>70<br>58000 | volts<br>watt<br>volts<br>volts |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation  CHARACTERISTICS: Plate Voltage Grid Voltage Amplification Factor                            | 100<br>1<br>70           | 0 max<br>1.1 max<br>250<br>3<br>70          | volts<br>watt                   |


#### **Diode Units**

| MAXIMUM RATING      | GS (Design-Maximum Values): |         |    |
|---------------------|-----------------------------|---------|----|
| Plate Current (Each | Unit)                       | 5.5 max | ma |

# HALF-WAVE VACUUM RECTIFIER

**6CQ4** 

Octal type used as damper tube in horizontal-deflection circuits of television receivers. Outline 13G. Outlines section. Tube requires octal socket and may be mounted in any position. Socket terminals 1, 2, 4, and 6 should



not be used as tie points. It is especially important that this tube, like other powerhandling tubes, be adequately ventilated. Heater volts (ac/dc), 6.3; amperes, 1.6.

#### Damper Service

| For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values): |          |       |
|---|----------|-------|
| Peak Inverse Plate Current  | 5500 max | volts |
| Peak Plate Current  | 1200 max | ma    |
| DC Plate Current  | 190 max  | ma    |
| Plate Dissipation   | 6.5 max  | watts |
| Peak Heater-Cathode Voltage:  |          |       |
| Heater negative with respect to cathode   | 5500 max | volts |
| Heater positive with respect to cathode   | 300□max  | volts |
| CHARACTERISTICS, Instantaneous Value: Tube Voltage Drop for plate current of 250 ma   | 25       | volts |

The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.


• The dc component must not exceed 900 volts.

□ The dc component must not exceed 100 volts.

# MEDIUM-MU TRIODE.... SHARP-CUTOFF TETRODE

Related type:

Miniature type used in a wide variety GZTR(3 of applications in color and blackand-white television receivers employing series-connected heater strings. Especially useful as combined vhf oscillator and mixer in tuners of



television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. The tetrode unit is used as a mixer, video if amplifier, or sound if amplifier tube. The triode unit is used in vhf oscillator, phase-splitter, syncclipper, sync-separator, and rf amplifier circuits. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 5CQ8 is identical with type 6CQ8 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 5CQ8<br>4.7<br>0.6<br>11 | 6CQ8<br>6.3<br>0.45<br>11 | volts<br>ampere<br>seconds |
|--|--------------------------|---------------------------|----------------------------|
| Heater negative with respect to cathode Heater positive with respect to cathode                  | 200 max                  | 200 max                   | volts                      |
|  | 200△max                  | 200△max                   | volts                      |


A The dc component must not exceed 100 volts.

|   | Without<br>External | With<br>External |    |
|---|---------------------|------------------|----|
| Direct Interelectrode Capacitances:     | Shield              | Shield=          |    |
| Triode Unit:                            |                     |                  | _  |
| Grid to Plate                           | 1.8                 | 1.8              | pf |
| Grid to Cathode and Heater              | 2.7                 | 2.7              | pf |
| Plate to Cathode and Heater             | 0.4                 | 1.2              | pf |
| Tetrode Unit:                           |                     |                  |    |
| Grid No.1 to Plate                      | 0.019 max           | 0.015 max        | pf |
| Grid No.1 to Cathode, Heater, Grid No.2 |                     |                  |    |
| and Internal Shield                     | 5.0                 | 5.0              | pf |
| Plate to Cathode, Heater, Grid No.2,    |                     |                  |    |
| and Internal Shield                     | 2.5                 | 3.3              | pf |
| Tetrode Plate to Triode Plate           | 0.07 max            | 0.01 max         | pf |
| Heater to Cathode (Each Unit)           | 3.0                 | 3.0†             | pf |

- \* With external shield connected to cathode of unit under test.
- † With external shield connected to ground.

### Class A, Amplifier

| Class A <sub>1</sub> Ampliner   |                                     |   |   |
|---|-------------------------------------|---|---|
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:  | Triode Unit 330 max - 0 max 3.1 max | 0 max<br>3.2 max  | volts<br>volts<br>ve page 75<br>volts<br>watts                  |
| For grid-No.2 voltages up to 165 volts  | -                                   | 0.7 max   |   |
| For grid-No.2 voltages between 165 and 330 volts.   |                                     | See cur   | ve page 75  |
| Grid Input  | 0.55 max                            |   | watt  |
| CHARACTERISTICS: Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid-No.1 Voltage (Approx.) for plate current of 100 µa Plate Current Grid-No.2 Current | 125<br>                             | 125<br>125<br>-1<br>-<br>-<br>140000<br>5800<br>-7<br>12<br>4.2 | volts<br>volts<br>volts<br>ohms<br>ohms<br>µmhos<br>volts<br>ma |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation   | 0.5 max<br>1.0 max                  |   | megohm<br>megohm  |



# DIODE---REMOTE-CUTOFF PENTODE

Goap Miniature type used as combined detector and audio amplifier in automobile and ac-operated radio receivers. The diode unit is used as an AM detector, and the pentode unit as an automatic-volume-controlled audio

6CR6
Related type: 12CR6

amplifier. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 12CR6 is identical with type 6CR6 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Rock Matter Cathoda Voltage  | 6CR6<br>6.3<br>0.3 | 12CR6<br>12.6<br>0.15 | volts<br>ampere |
|--|--------------------|-----------------------|-----------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 100 max            | 100 max               | volts           |
|  | 100 max            | 100 max               | volts           |

MAXIMUM RATINGS (Design-Center Values):

| Plate Voltage   | 300 max        | olts |
|---|----------------|------|
| Grid-No.2 (Screen-Grid) Voltage                                   | See curve page |      |
| Grid-No.2 Supply Voltage  |                | olts |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value             | •              | olts |
| Plate Dissipation   |                | atts |
| Grid-No.2 Input:  | 2.5 Inda       | utto |
| For grid-No.2 voltages up to 150 volts                            | 0.3 max        | watt |
| For grid-No.2 voltages between 150 and 300 volts                  | See curve page | 75   |
| CHARACTERISTICS:  |                |      |
| Plate Voltage   | 250            | olts |
| Grid-No.2 Voltage   |                | olts |
| Grid-No.1 Voltage   | -2 v           | olts |
| Plate Resistance (Approx.)  | 0.8 meg        | ohm  |
| Transconductance  | 2200 μn        | ihos |
| Plate Current   | 9.6            | ma   |
| Grid-No.2 Current   | 2.6            | ma   |
| Grid-No.1 Voltage (Approx.) for transconductance of 10 $\mu$ mhos | -32 v          | olts |
| MAXIMUM CIRCUIT VALUES:   |                |      |
| Grid-No.1-Circuit Resistance:                                     |                |      |
| For fixed-bias operation  | 0.25 max mege  | ohm  |
| For cathode-bias operation  | 1.0 max meg    | ohm  |
| Diode Unit  |                |      |
| MAXIMUM RATING (Design-Center Value):                             |                |      |

# PENTAGRID AMPLIFIER

6CS6
Related types: 3CS6, 4CS6

Heater Voltage (ac/dc) .....

MAXIMUM RATINGS (Design-Center Values): Plate Voltage

Miniature type used as a gated amplifier in television receivers. In such service, it may be used as a combined sync separator and sync clipper. Outline 5C, Outlines section. Tube requires miniature seven-contact socket



6CS6

300 max

1 max

ma

volts

volts

and may be mounted in any position. Types 3CS6 and 4CS6 are identical with type 6CS6 except for the heater ratings, as shown below.


3CS6

4CS6

| Heater Voltage (ac/dc)                           | 3.13       | 4.2     | 0.3     | voits      |
|--|------------|---------|---------|------------|
| Heater Current                                   | 0.6        | 0.45    | 0.3     | ampere     |
| Heater Warm-up Time (Average)                    | 11         | 11      |         | seconds    |
| Peak Heater-Cathode Voltage:                     |            |         |         | 5444       |
| Heater negative with respect to cathode          | 200 max    | 200 max | 200 max | volts      |
| Heater positive with respect to cathode          | 200 max    | 200 max | 200 max |            |
| ricater positive with respect to cathode         | 200-max    | 200•max | 200•max | volts      |
| The dc component must not exceed 100 volts.      |            |         |         |            |
| Class A, A                                       | mplifier   |         |         |            |
| CHARACTERISTICS:                                 |            |         |         |            |
| Plate Voltage                                    |            | 100     | 100     | volts      |
| Grids-No.2-and-No.4 Voltage                      |            | 30      | 30      | võlts      |
| Grid-No.3 Voltage                                |            | -1      | 0       | volt       |
| Grid-No.1 Voltage                                |            | 0       | -1      | volt       |
| Plate Resistance (Approx.)                       |            | 0.7     | 1       | megohm     |
| Grid-No.3-to-Plate Transconductance              |            | 1500    |         | $\mu$ mhos |
| Grid-No.1-to-Plate Transconductance              |            | -       | 1100    | $\mu$ mhos |
| Plate Current                                    |            | 0.8     | 1.0     | ma         |
| Grids-No.2-and-No4 Current                       |            | 5.5     | 1.3     | ma         |
| Grid-No.3 Voltage (Approx.) for plate current of | 50 μa      | -2.2    | _       | volts      |
| Grid-No.1 Voltage (Approx.) for plate current of | 50 μa      |         | 2.5     | volts      |
| Gated Amplifi                                    | ier Servic | e       |         |            |

| Grids-No.2-and-No.4 Supply Voltage                         | 300 max volts     |
|--|-------------------|
| Grids-No.2-and-No.4 Voltage                                | See curve page 75 |
| Plate Dissipation  | 1 max watt        |
| Grids-No.2-and-No.4 Input:                                 |                   |
| For grids-No.2-and-No.4 voltages up to 150 volts           | 1 max watt        |
| For grids-No.2-and-No.4 voltages between 150 and 300 volts | See curve page 75 |
| Cathode Current  | 14 max ma         |

| MAXIMUM CIRCUIT VAI |                                       |                                    |
|---------------------|---------------------------------------|------------------------------------|
|                     | · · · · · · · · · · · · · · · · · · · | 0.47 max megohm<br>2.2 max megohms |



# MEDIUM-MU DUAL TRIODE

Miniature type used as combined vertical deflection oscillator and vertical deflection amplifier in television receivers employing series-connected heater strings. Unit No.1 is used as a conventional blocking oscillator in

vertical deflection circuits, and unit No.2 as a vertical deflection amplifier. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8CS7 is identical with type 6CS7 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)  | 6CS7<br>6.3<br>0.6<br>11 | 8CS7<br>8.4<br>0.45<br>11 | volts<br>ampere<br>seconds |
|--|--------------------------|---------------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max                  | 200 max                   | volts                      |
|  | 200=max                  | 200•max                   | volts                      |

<sup>•</sup> The dc component must not exceed 100 volts.

# Class A. Amplifier

| CHARACTERISTICS:                                       | Unit No.1   | Unit No.2 |            |
|--|-------------|-----------|------------|
| Plate Voltage  | 250         | 250       | volts      |
| Grid Voltage   | <b>—8.5</b> | -10.5     | volts      |
| Amplification Factor                                   | 17          | 15.5      |            |
| Plate Resistance (Approx.)                             | 7700        | 3450      | ohms       |
| Transconductance                                       | 2200        | 4500      | $\mu$ mhos |
| Grid Voltage (Approx.) for plate current of 10 $\mu a$ | -24         | _         | volts      |
| Grid Voltage (Approx.) for plate current of 50 $\mu a$ | -           | -22       | volts      |
| Plate Current  | 10.5        | 19        | ma         |
| Plate Current for grid voltage of -16 volts            | _           | 3         | ma         |

# Vertical Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

|   | Unit No.1  | Unit No.2 |       |
|---|------------|-----------|-------|
| MAXIMUM RATINGS (Design-Center Values):               | Oscillator | Amplifier |       |
| DC Plate Voltage                                      | 500 max    | 500 max   | volts |
| Peak Positive-Pulse Plate Voltage† (Absolute Maximum) | -          | 2200△max  | volts |
| Peak Negative-Pulse Grid Voltage                      | -400 max   | -250 max  | volts |
| Peak Cathode Current                                  | 70 max     | 105 max   | ma    |
| Average Cathode Current                               | 20 max     | 30 max    | ma    |
| Plate Dissipation                                     | 1.25 max   | 6.5 max   | watts |

MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance ...... 2.2 max 2.2 max megohms

<sup>†</sup> The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.


<sup>△</sup> Under no circumstances should this absolute value be exceeded.

#### **BEAM POWER TUBE**

# 6CU5

Related types: 12CU5/12C5, 17CU5

Miniature type used in the audio output stage of television receivers. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 12CU5/12C5 and 17CU5 are



identical with type 6CU5 except for the heater ratings, as shown below.

|   |                       | 12CU5/                                |           |                |
|---|-----------------------|---------------------------------------|-----------|----------------|
|   | 6CU5                  | 12C5                                  | 17CU5     |                |
| Heater Voltage (ac/dc)                          | 6.3                   | 12.6                                  | 16.8      | volts          |
| Heater Current                                  | 1.2                   | 0.6                                   | 0.45      | ampere         |
| Heater Warm-up Time (Average)                   | _                     | 11                                    | 11        | seconds        |
| Peak Heater-Cathode Voltage:                    |                       |                                       |           |                |
| Heater negative with respect to cathode         | 200 max               |                                       | 200 max   | volts          |
| Heater positive with respect to cathode .       | 200•max               | 200 • max                             | 200 • max | volts          |
| Direct Interelectrode Capacitances (Approx.):   |                       |                                       |           |                |
| Grid No.1 to Plate                              |                       |                                       | 0.6       | pf             |
| Grid No.1 to Cathode, Heater, Grid No.2,        | and Grid              | No.3                                  | 13        | pf             |
| Plate to Cathode, Heater, Grid No.2, and (      | Grid No.3             | · · · · · · · · · ·                   | 8.5       | pf             |
| • The dc component must not exceed 100 volts.   |                       |                                       |           |                |
| Class A. A                                      | Amplifier             |                                       |           |                |
| MAXIMUM RATINGS (Design-Maximum Valu            | •                     |                                       |           |                |
| Plate Voltage                                   |                       |                                       | 150 max   | volts          |
| Grid-No.2 (Screen-Grid) Voltage                 |                       |                                       | 130 max   | volts          |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias |                       |                                       | 0 max     | volts          |
| Plate Dissipation                               |                       |                                       | 7 max     | watts          |
| Grid-No.2 Input                                 |                       |                                       | 1.4 max   | watts          |
| Bulb Temperature (At hottest point)             |                       |                                       | 220 max   | °C             |
|   |                       |                                       |           |                |
| TYPICAL OPERATION:                              |                       |                                       | 400       | •.             |
| Plate Voltage                                   |                       |                                       | 120       | volts          |
| Grid-No.2 Voltage                               |                       |                                       | 110       | volts          |
| Grid-No.1 Voltage                               |                       |                                       | 8<br>8    | volts<br>volts |
| Zero-Signal Plate Current                       |                       |                                       | 49        | ma             |
| Maximum-Signal Plate Current                    | • • • • • • • • • •   |                                       | 50        | ma             |
| Zero-Signal Grid-No.2 Current                   |                       |                                       | 4         | ma             |
| Maximum-Signal Grid-No.2 Current                |                       |                                       | 8.5       | ma             |
| Plate Resistance (Approx.)                      |                       |                                       | 10000     | ohms           |
| Transconductance                                |                       |                                       | 7500      | umhos          |
| Load Resistance                                 |                       |                                       | 2500      | ohms           |
| Total Harmonic Distortion                       |                       |                                       | 10        | per cent       |
| Maximum-Signal Power Output                     |                       |                                       | 2.3       | watts          |
| REAVISEINE CONCUENT MATTIMO.                    |                       |                                       |           |                |
| MAXIMUM CIRCUIT VALUES:                         |                       |                                       |           |                |
| Grid-No.1-Circuit Resistance:                   |                       |                                       | 0.1       |                |
| For fixed-bias operation                        |                       |                                       |           | megohm         |
| For cathode-bias operation                      | · · · · · · · · · · · | • • • • • • • • • • • • • • • • • • • | v.5 max   | megohm         |


**6CU6** 

Refer to type 6BQ6GTB/6CU6

# MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**6CU8** 

Miniature type used in a wide variety of applications in color and black-and-white television receivers employing series-connected heater strings. The pentode unit is used as an if amplifier, a video amplifier, an age am-



plifier, and a reactance tube. The triode unit is used in low-frequency oscillator, sync-separator, sync-clipper, and phase-splitter circuits. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc)                                       |                | volts   |
|--|----------------|---------|
| Heater Current   | 0.45           | ampere  |
| Peak Heater-Cathode Voltage:                                 |                |         |
| Heater negative with respect to cathode                      |                |         |
| Heater positive with respect to cathode                      | 200 ma         | c volts |
| Direct Interelectrode Capacitances:                          |                |         |
| Triode Unit:   |                |         |
| Grid to Plate  | 1.6            | pf      |
| Grid to Cathode, Heater, Pentode Grid No.3, and Internal Shi | eld 1.9        | pf      |
| Plate to Cathode, Heater, Pentode Grid No.3 and Internal Shi |                | pf      |
| Pentode Unit:  |                | •       |
| Grid No.1 to Plate   | 0.025 ma       | x pf    |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, Triode   |                | -       |
| Cathode, and Internal Shield                                 | 7              | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, Triode       |                | •       |
| Cathode, and Internal Shield                                 | 2.4            | pf      |
| Pentode Grid No.1 to Triode Plate                            |                |         |
| Pentode Plate to Triode Plate                                |                |         |
|  | 0.07 1114.     | t pr    |
| • The dc component must not exceed 100 volts.                |                |         |
| Class A, Amplifier   |                |         |
| MAXIMUM RATINGS (Design-Maximum Values): Triode              | Unit Pentode I | Jnit    |

| Class M mmpfills                                       |             |           |            |
|--|-------------|-----------|------------|
| MAXIMUM RATINGS (Design-Maximum Values):               | Triode Unit | Pentode U | Jnit       |
| Plate Voltage  | 330 max     | 330 ma    | x volts    |
| Grid-No.2 Supply Voltage                               |             | 330 ma    | x volts    |
| Grid-No.2 (Screen-Grid) Voltage                        |             |           | e page 75  |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value. | 0 max       | 0 max     |            |
|  |             |           |            |
| Plate Dissipation                                      | 2.8 max     | 2.3 ma    | x watts    |
| Grid-No.2 Input:                                       |             |           |            |
| For grid-No.2 voltages up to 165 volts                 | _           | 0.55 ma   | x watt     |
| For grid-No.2 voltages between 165 and 330 volts.      | -           | See cur   | ve page 75 |
| CHARACTERISTICS:                                       |             |           |            |
| Plate Supply Voltage                                   | 125         | 125       | volts      |
| Grid-No.2 Supply Voltage                               |             | 125       | volts      |
| Grid-No.1 Voltage                                      | -1          | -         | volts      |
| Cathode-Bias Resistor                                  | _           | 56        | ohms       |
| Amplification Factor                                   | 24          |           |            |
| Plate Resistance (Approx.)                             | 4100        | 170000    | ohms       |
| Transconductance                                       | 5800        | 7800      | μmhos      |
| Grid-No.1 Voltage (Approx.) for plate current of 20 μa | 19          | —8        | volts      |
| Plate Current  | 17          | 12        | ma         |
| Plate Current for grid-No.1 voltage of -3 volts and    |             |           |            |
| cathode-bias resistor of 0 ohms                        |             | -1.6      | ma         |
| Grid-No.2 Current                                      | _           | 3.2       | m 9        |



# HIGH-MU TRIODE

Nuvistor type used as a groundedcathode, neutralized rf amplifier in vhf tuners of television and FM receivers. Outline 1, **Outlines** section. Tube requires nuvistor socket and may be operated in any position.

Related types: 2CW4, 13CW4

Types 2CW4 and 13CW4 are identical with type 6CW4 except for the heater ratings, as shown below.

|                               | ZCW4 | 6CW4  | 13CW4 |         |
|-------------------------------|------|-------|-------|---------|
| Heater Voltage (ac/dc)        | 2.1  | 6.3   | 13.5  | volts   |
| Heater Current                | 0.45 | 0.135 | 0.06  | ampere  |
| Heater Warm-up Time (Average) | 8    | _     | _     | seconds |

Peak Heater-Cathode Voltage:

13CW4

6CW4

| Heater negative with respect to cathode 100 max<br>Heater positive with respect to cathode 100 max |   | 100 max<br>100 max | volts<br>volts |
|--|---|--------------------|----------------|
| Direct Interelectrode Capacitances (Approx.)   |   |                    |                |
| Grid to Plate  |   | 0.92               | pf             |
| Grid to Cathode, Heater, and Shell   |   | 4.3                | pf             |
| Plate to Cathode, Heater, and Shell  |   | 1.8                | pf             |
| Plate to Cathode   |   | 81.0               | pf             |
| Heater to Cathode  | • | 1.6                | pf             |
| Class A, Amplifier   |   |                    |                |
| MAXIMUM RATINGS (Design-Maximum Values):   |   |                    |                |
| Plate Supply Voltage   |   | 300°max            | volts          |
| Plate Voltage  |   | 135 max            | volts          |
| Grid Voltage:  |   |                    |                |
| Negative-bias value  |   | 55 max             | volts          |
| Peak positive value  |   | 0 max              | volts          |
| Plate Dissipation  |   | 1.5 max            | watt           |
| Cathode Current  | • • • • • • • • • •                     | 15 max             | ma             |
| CHARACTERISTICS AND TYPICAL OPERATION:   |   |                    |                |
| Plate Supply Voltage   | 110                                     | 70                 | voits          |
| Grid Supply Voltage  | ő                                       | Õ                  | volts          |
| Cathode-Bias Resistor  | 130                                     |                    | ohms           |
| Grid Resistor  |   | 47000              | ohms           |
| Amplification Factor   | 65                                      | 68                 |                |
| Plate Resistance (Approx.)   | 6600                                    | 5440               | ohms           |
| Transconductance   | 9800                                    | 12500              | $\mu$ mhos     |
| Grid Voltage (Approx.) for plate current of 10 μa  | -4                                      | _                  | volts          |
| Plate Current  | 7                                       | 7.2                | ma             |
|  |   |                    |                |


2CW4

#### **MAXIMUM CIRCUIT VALUES:**


Grid-Circuit Resistance:

For fixed-bias operation 0.5 max megohm
For cathode-bias operation 2.2 max megohms

<sup>•</sup> For operation at metal-shell temperatures up to 135° C.



<sup>°</sup> A plate supply voltage of 300 volts may be used provided that a sufficiently large resistor is used in the plate circuit to limit the plate dissipation to 1.5 watts under any condition of operation.



# MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in television re-ceiver applications. Pentode unit is used as video amplifier; triode unit is used in sound intermediate-frequency amplifier, sweep-oscillator, sync-separator, sync-amplifier, and sync-clip-

per circuits. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8CX8 is identical with type 6CX8 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)  | 6CX8<br>6.3<br>0.75 | 8CX8<br>8<br>0.6<br>11 | volts<br>ampere<br>volts |
|--|---------------------|------------------------|--------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max             | 200 max                | volts                    |
|  | 200 max             | 200 max                | volts                    |

<sup>•</sup> The dc component must not exceed 100 volts.

For fixed-bias operation .....

For cathode-bias operation .....

| Triode Unit<br>330 max | Pentode Uni<br>330 max | t<br>volts  |
|------------------------|------------------------|---|
| _                      | 330 max                | volts   |
| _                      | See curve              | page 75   |
| 0 max                  | 0 max                  | volts   |
| 2 max                  | 5 max                  | watts   |
| _                      | 1.1 max                | watts   |
|                        | See curve              | page 75   |
|                        |                        |   |
| 150                    | 200                    | volts   |
| _                      | 125                    | volts   |
| 150                    | 68                     | ohms  |
| 40                     |                        |   |
| 8700                   | 70000                  | ohms  |
| 4600                   | 10000                  | $\mu$ mhos  |
| 5                      | <b>—8.5</b>            | volts   |
| 9.2                    | 24                     | ma  |
| _                      | 52                     | ma  |
|                        |                        |   |
|                        |                        | _   |
|                        | 330 max                | 330 max 330 max 330 max 330 max See curve 0 max 5 max 5 max - 1.1 max See curve 150 200 125 150 68 40 - 8700 70000 4600 10000 -5 -8.5 |



# SHARP-CUTOFF TETRODE

Miniature type used as rf amplifier in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 2CY5, 3CY5, and 4CY5 are

0.25 max megohm

1 max megohm

0.5 max


1 max

Related types: 2CY5, 3CY5, 4CY5

identical with type 6CY5 except for the heater ratings, as shown below.

| 2CY5                             | 3CY5 | 4CY5 | 6CY5 |         |
|----------------------------------|------|------|------|---------|
| Heater Voltage (ac/dc)           | 2.9  | 4.5  | 6.3  | volts   |
| Heater Current 0.6               | 0.45 | 0.3  | 0.2  | ampere  |
| Heater Warm-up Time (Average) 11 | 11   | 11   | _    | seconds |

| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode Heater positive with respect to cathode Direct Interelectrode Capacitances (Approx.)°: Grid-No.1 to Plate Grid-No.1 to Cathode, Heater, Grid No.2, and Internal Shield Plate to Cathode, Heater, Grid No.2, and Internal Shield | 100 max<br>100 max<br>0.03<br>4.5<br>3            | volts<br>volts<br>pf<br>pf<br>pf                               |
|---|---|--|
| ° With external shield connected to cathode.  |   |  |
| Class A, Amplifier  MAXIMUM RATINGS (Design-Maximum Values):  |   |  |
| Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Cathode Current Grid-No.2 Input:   | 180 max<br>180 max<br>See curv<br>0 max<br>20 max | volts<br>volts<br>e page 75<br>volts<br>ma                     |
| For grid-No.2 voltages up to 90 volts  For grid-No.2 voltages between 90 and 180 volts  Plate Dissipation   | 0.5 max<br>See curv<br>2 max                      | watt<br>e page 75<br>watts                                     |
| CHARACTERISTICS: Plate Voltage Grid-No.1 Voltage Grid-No.1 Voltage Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu$ a  | 125<br>80<br>-1<br>0.1<br>8000<br>10<br>1.5<br>-6 | voits<br>volts<br>volt<br>megohm<br>µmhos<br>ma<br>ma<br>volts |




# **DUAL TRIODE**

6CY7
Related type:

MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance .....

Miniature type used as combined vertical oscillator and vertical deflection amplifier in television receivers. Unit No.1 is a high-mu triode unit used as a blocking oscillator in vertical deflection circuits, and unit No.2 is a



0.5 max megohm

low-mu triode unit used as a vertical deflection amplifier. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 11CY7 is identical with type 6CY7 except for the heater ratings, as shown below.


| Heater Voltage (ac/dc)                        | 6CY7<br>6.3 | 11CY7<br>11 | volts   |
|---|-------------|-------------|---------|
|   |             |             |         |
| Heater Current                                | 0.75        | 0.45        | ampere  |
| Heater Warm-up Time (Average)                 | _           | 11          | seconds |
| Peak Heater-Cathode Voltage:                  |             |             |         |
| Heater negative with respect to cathode       | 200 max     | 200 max     | volts   |
| Heater positive with respect to cathode       | 200=max     | 200 max     | volts   |
| ■ The dc component must not exceed 100 volts. |             |             |         |

Class A. Amplifier CHARACTERISTICS: Unit No.1 Unit No.2 150 volts Plate Supply Voltage ...... 250 -3 volts Grid Voltage .......... Cathode-Bias Resistor ..... 620 ohms Amplification Factor ..... 68 52000 920 ohms Plate Resistance (Approx.) ..... Transconductance ..... 1300 5400 μmhos Grid Voltage (Approx.) for plate current of 10  $\mu a \dots$ 5.5 volts Grid Voltage (Approx.) for plate current of 200 µa ... **.**4∩ volts 30 ma Plate Current . Plate Current for grid voltage of -30 volts ...... 3.5 ma

# Vertical Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

| <u>-</u>                                 | Unit No.1  | Unit No.2 |       |
|--|------------|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator | Amplifier |       |
| DC Plate Voltage                         | 350 max    | 350 max   | volts |
| Peak Positive-Pulse Plate Voltage#       |            | 1800 max  | volts |
| Peak Negative-Pulse Grid Voltage         | -400 max   | -250 max  | volts |
| Peak Cathode Current                     | _          | 120 max   | ma    |
| Average Cathode Current                  |            | 35 max    | ma    |
| Plate Dissipation                        | 1 max      | 5.5 max   | watts |
| •  |            |           |       |

† For cathode-bias operation.



## **BEAM POWER TUBE**

Miniature type used as a vertical deflection amplifier in high-efficiency deflection circuits of television receivers utilizing picture tubes having diagonal deflection angles of 110 degrees and operating at ultor voltages up to

6CZ5
Related type:
5CZ5

18 kilovolts. Also used in the audio output stage of television and radio receivers. This type has a controlled heater warm-up time for use in receivers employing series-connected heater strings. Outline 6G, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 5CZ5 is identical with type 6CZ5 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)   | 4.7<br>0.6<br>11 | 6.25<br>6.3<br>0.45<br>11 | volts<br>ampere<br>seconds |
|--|------------------|---------------------------|----------------------------|
| Heater pegative with respect to cathode  Heater positive with respect to cathode | 200 max          | 200 max                   | volts                      |
|  | 2004max          | 2004max                   | volts                      |

Direct Interelectrode Conscitances

| Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 0.4 max       | pf<br>pf        |
|---|---------------|-----------------|
| Plate to Cathode, Heater, Grid No.2, and Grid No.3                        | 6             | pf              |
| Plate Resistance (Approx.)*  Transconductance*                            | 0.073<br>4800 | megohm<br>umhos |
| Transconductance  | 4800          | $\mu$ mmos      |

<sup>\*</sup> Plate and grid-No.2 volts, 250; grid-No.1 volts, -14; plate ma., 46; grid-No.2 ma., 4.6.

Vertical Deflection Amplifica

| VELUCAL DEHECTION AMPLINE                            |          |       |
|--|----------|-------|
| For operation in a 525-line, 30-frame system         |          |       |
| MAXIMUM RATINGS (Design-Maximum Values):             |          |       |
| DC Plate Voltage                                     | 350 max  | volts |
| Peak Positive-Pulse Plate Voltage#                   | 2200 max | volts |
| Grid-No.2 (Screen-Grid) Voltage                      | 315 max  | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | —275 max | volts |
| Peak Cathode Current                                 | 155 max  | ma    |
| Average Cathode Current                              | 45 max   | ma    |
| Plate Dissipation                                    | 10 max   | watts |
| Grid-No.2 Input                                      | 2.2 max  | watts |
| Bulb Temperature (At hottest point)                  | 250 max  | •c    |
| MAXIMUM CIRCUIT VALUES:                              |          |       |
| Grid-No.1-Circuit Resistance:                        |          |       |

For fixed-bias operation ..... 0.5 max megohm For cathode-bias operation ..... 1.0 max megohm

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

▲ The dc component must not exceed 100 volts.

6**D**6

#### REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6**D**7

# SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

6D8G

# PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

# HALF-WAVE VACUUM RECTIFIER

6DA4 Related type: 17D4

Glass octal type used as damper tube in horizontal-deflection circuits of television receivers. Outline 13D. Outlines section. Tube requires octal socket and may be mounted in any



position. May be supplied with pin

No.1 omitted. Socket terminals 1, 2, 4, and 6 should not be used as tie points. It is important that this tube, like other power-handling tubes, be adequately ventilated. Type 17D4 is identical with type 6DA4 except for the heater ratings, as shown below.

|                               | 6DA4 | 17D4 |         |
|-------------------------------|------|------|---------|
| Heater Voltage (ac/dc)        | 6.3  | 16.8 | volts   |
| Heater Current                | 1.2  | 0.45 | атреге  |
| Heater Warm-up Time (Average) | _    | 11   | seconds |

Damper Service

| For operation in a 525-line, 30-frame system |            |       |
|--|------------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |            |       |
| Peak Inverse Plate Current                   | 4400 max   | volts |
| Peak Plate Current                           | 900 max    | ma    |
| DC Plate Current                             | 155 max    | ma    |
| Plate Dissipation                            | 5.5 max    | watts |
| Peak Heater-Cathode Voltage:                 |            |       |
| Heater negative with respect to cathode      | 4400 = max | volts |
| Heater positive with respect to cathode      | 300*max    | volts |
|  |            | _     |

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 900 volts.
- A The dc component must not exceed 100 volts.

For cathode-bias operation ...

DC Grid-No.2 (Screen-Grid) Voltage

DC Plate Voltage .....

MAXIMUM RATINGS (Design-Center Values):

Peak Positive-Pulse Plate Voltage (Absolute Maximum) ......

Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage .....



# **BEAM POWER TUBE**

Miniature type used as vertical-deflection-amplifier tube in television receivers. Outline 6F, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Type 12DB5 is identical

6DB5

6DB5
Related type: 12DB5

2.2 max megohms

volts

volts

volts

volts

300 max

150 max

-250 max

2000 max

12DB5

with type 6DB5 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode   | 6.3<br>1.2<br>—<br>200 max<br>200•max | 12.6<br>0.6<br>11<br>200 max<br>200•max  | volts<br>ampere<br>seconds<br>volts<br>volts |
|--|---------------------------------------|--|--|
| • The dc component must not exceed 100 volts.  |                                       |  |  |
| Class A, Amplifier MAXIMUM RATINGS (Design-Center Values):   |                                       |  |  |
| Plate Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.2 Input Plate Dissipation  |                                       | 300 max<br>150 max<br>1.25 max<br>10 max   | volts<br>volts<br>watts<br>watts             |
| TYPICAL OPERATION: Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Plate Resistance (Approx.) Transconductance Load Resistance Total Harmonic Distortion Maximum-Signal Power Output  MAXIMUM CIRCUIT VALUES: |                                       | 200<br>125<br>180<br>8.5<br>46<br>47<br>2.2<br>8.5<br>28000<br>8000<br>4000<br>10<br>3.8 | volts volts ohms volts ma ma ma ma ohms      |
| Grid-No.1 Circuit Resistance: For fixed-bias operation   |                                       | 0.1 max  | megohm                                       |

Vertical-Deflection Amplifier
For operation in a 525-line, 30-frame system

| Peak Cathode Current Average Cathode Current Grid-No.2 Input Plate Dissipation | 55<br>1.25 | max | ma<br>ma<br>watts<br>watts |
|--|------------|-----|----------------------------|
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:                          |            |     |                            |
| For fixed-bias operation   | 0.1        | max | megohm                     |


a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

Under no circumstances should this absolute maximum value be exceeded.

# SHARP-CUTOFF PENTODE

# 6DC6

Miniature type used in the gain-controlled picture if stages of color television receivers. It is also used as a radio-frequency amplifier in the tuners of such receivers. Outline 5C, Outlines section. Tube requires seven-




contact miniature socket and may be mounted in any position.


| Heater Voltage (ac/dc)                                  | 6.3       | volts  |
|---|-----------|--------|
| Heater Current  | 0.3       | ampere |
| Peak Heater-Cathode Voltage:                            |           |        |
| Heater negative with respect to cathode                 | 200 max   | volts  |
| Heater positive with respect to cathode                 | 200 • max | volts  |
| Direct Interelectrode Capacitances:                     |           |        |
| Grid No.1 to Plate                                      | 0.02 max  | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and |           |        |
| Internal Shield   | 6.5       | pf     |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and     |           |        |
| Internal Shield   | 2         | pf     |
| The dc component must not exceed 100 volts.             |           | _      |

### Class A, Amplifier

| MAXIMUM RATINGS (Design-Center Values):             |             |         |
|---|-------------|---------|
| Plate Voltage                                       | 300 max     | volts   |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value | 0 max       | volts   |
| Grid-No.2 Supply Voltage                            | 300 max     | volts   |
| Grid-No.2 (Screen-Grid) Voltage                     | See curve p | page 75 |



| Grid-No.1 (Control-Grid) Voltage, Positive-bias value        | 0 max<br>2 max |            |
|--|----------------|------------|
| For grid-No.2 voltages up to 150 volts                       | 0.5 max        | watt       |
| For grid-No.2 voltages between 150 and 300 volts             | See curve      | page 75    |
| CHARACTERISTICS:   |                |            |
| Plate Supply Voltage   | 200            | volts      |
| Grid No.3 Connected  | to cathode     | at socket  |
| Grid-No.2 Supply Voltage                                     | 150            | volts      |
| Cathode-Bias Resistor  | 180            | ohms       |
| Plate Resistance (Approx.)                                   | 0.5            | megohm     |
| Transconductance   | 5500           | $\mu$ mhos |
| Grid-No.1 Voltage (Approx.) for transconductance of 50 μmhos | -12.5          | volts      |
| Plate Current  | 9              | ma         |
| Grid-No.2 Current  | 3              | ma         |
| MAXIMUM CIRCUIT VALUES:                                      |                |            |
| Grid-No.1-Circuit Resistance:                                |                |            |
| For fixed-bias operation                                     |                | megohm     |
| For cathode-bias operation                                   | 1.0 max        | megohm     |
|  |                |            |



Miniature type used as rf- and if-amplifier tube in radio and television receivers. Outline 6E, Outlines section. Tube requires nine-contact socket and may be mounted in any

TWIN DIODE-

6DC8

250

200

| G <sub>2</sub> P | G <sub>3p</sub> | position.                          |        |     |        |
|------------------|-----------------|------------------------------------|--------|-----|--------|
| Heater Volt      | age (ac/dc)     |                                    | 6.3    |     | volts  |
|                  |                 |                                    | 0.3    |     | ampere |
| Peak Heate       | r-Cathode \     | /oltage:                           |        |     |        |
| Heater           | negative with   | h respect to cathode               | 100    | max | volts  |
|                  |                 | respect to cathode                 | 100    | max | volts  |
|                  | electrode Ca    |                                    |        |     |        |
| Pentode U        | Jnit:           | •                                  |        |     |        |
| Grid No          | o.1 to Plate    | .,,                                | 0.0025 | max | pf     |
| Grid No          | o.1 to All C    | Other Electrodes Except Plate      | 5      |     | pf     |
| Plate to         | All Other E     | Electrodes Except Grid No.1        | 5.2    |     | pf     |
| Grid No          | o.1 to Heat     | er                                 | 0.05   | max | pf     |
| Plate of I       | Each Diode      | Unit to All Other Electrodes       | 2.5    |     | pf     |
| Plate of I       | Diode Unit l    | No.1 to Plate of Diode Unit No.2   | 0.25   | max | pf     |
| Plate of I       | Diode Unit l    | No.1 to Heater                     | 0.015  | max | pf     |
| Plate of I       | Diode Unit I    | No.2 to Heater                     | 0.003  |     | pf     |
| Plate of I       | Diode Unit 1    | No.1 to Pentode Grid No.1          | 0.0008 |     | pf     |
|                  |                 | No.2 to Pentode Grid No.1          | 0.001  |     | pf     |
| Plate of I       | Diode Unit N    | No.1 to Pentode Plate              | 0.15   |     | pf     |
| Plate of I       | Diode Unit N    | No.2 to Pentode Plate              | 0.025  | max | pf     |
|                  |                 | Pentode Unit as Class A, Amplifier |        |     |        |
|                  |                 | (Design-Center Values):            |        |     | 14-    |
|                  |                 |                                    |        | max | volts  |
|                  |                 |                                    | 300    | max | volts  |
| Grid-No.2 V      |                 |                                    |        |     | • • -  |
| With pl          | ate current     | greater than 8 ma                  | 125    | max | volts  |

| Grid-No.2 Voltage:                   |          |       |
|--------------------------------------|----------|-------|
| With plate current greater than 8 ma | 125 max  | volts |
| With plate current less than 4 ma    | 300 max  | volts |
| Cathode Current                      | 16.5 max | ma    |
| Grid-No.2 Input                      | 0.45 max | watts |
| Plate Dissipation                    | 2.25 max | watts |
| CHADACTEDICTICS.                     |          |       |

#### CHARACTERISTICS: Plate Voltage .....

| Grid No.3                         | Connected to cathode at sock |      |            |
|-----------------------------------|------------------------------|------|------------|
| Grid-No.2 Voltage                 | 100                          | 100  | volts      |
| Grid-No.1 Voltage                 | -1.5                         | -2   | volts      |
| Mu Factor, Grid No.2 to Grid No.1 | 20                           | 20   |            |
| Plate Resistance (Approx.)        | 0.6                          | 1    | megohm     |
| Transconductance                  | 4500                         | 3800 | $\mu$ mhos |

| Plate Current                                       | 11  | 9   | ma          |
|---|-----|-----|-------------|
| Grid-No.2 Current                                   | 3.3 | 2.7 | ma          |
| Transconductance, at grid-No.1 voltage of -20 volts | 120 | 200 | μmhos       |
| MAXIMUM CIRCUIT VALUES:                             |     |     |             |
| Grid-No.1-Circuit Resistance                        |     | 3   | max megohms |
| Diode Units (Each Un                                | it) |     |             |
| MAXIMUM RATINGS (Design-Center Values):             |     |     |             |
| Peak Inverse Plate Voltage                          |     | 200 | max volts   |
| Peak Plate Current                                  |     | 5   | max ma      |
| Average Plate Current                               |     | 0.8 | max ma      |

# HALF-WAVE VACUUM RECTIFIER

6DE4

Related types: 17DE4, 22DE4 Glass octal type used as damper tube in horizontal-deflection circuits of television receivers. Outline 13G, Outlines section. Tube requires octal socket and may be operated in any position. Socket terminals 1, 2, 4, and



6 should not be used as tie points. It is important that this tube, like other power-handling tubes, be adequately ventilated. Types 17DE4 and 22DE4 are identical with type 6DE4 except for the heater ratings, as shown below.

|   | 6DE4      | 17DE4       | 22DE4    |         |
|---|-----------|-------------|----------|---------|
| Heater Voltage (ac/dc)                          | 6.3       | 17          | 22.4     | volts   |
| Heater Current                                  | 1.6       | 0.6         | 0.45     | ampere  |
| Heater Warm-up Time (Average)                   |           | 11          | 11       | seconds |
| Direct Interelectrode Capacitances (Approx.):   |           |             |          |         |
| Plate to Cathode and Heater                     |           |             | 8.5      | pf      |
| Cathode to Plate and Heater                     |           |             | 11.5     | pf      |
| Heater to Cathode                               |           |             | 4        | pf      |
| Damper  | Service   |             |          |         |
| For operation in a 525                          |           | rame system |          |         |
| MAXIMUM RATINGS (Design-Maximum Valu            |           |             |          |         |
| Peak Inverse Plate Voltage#                     |           |             | 5500 max | volts   |
| Peak Plate Current                              |           |             | 1100 max | ma      |
| DC Plate Current                                |           |             | 180 max  | ma      |
| Plate Dissipation                               |           |             | 6.5 max  | watts   |
| Peak Heater-Cathode Voltage:                    |           |             |          |         |
| Heater negative with respect to cathode         |           |             | 5500 max | volts   |
| Heater positive with respect to cathode         |           |             | 300 max  | volts   |
| CHARACTERISTICS, Instantaneous Value:           |           |             |          |         |
| Tube Voltage Drop for plate current of 350 ma   |           |             | 34       | volts   |
| # The direction of the voltage mules much mat a | wassal 15 |             |          |         |

#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

- The dc component must not exceed 900 volts.
- The dc component must not exceed 100 volts.

### SHARP-CUTOFF PENTODE

6DE6
Related type:
4DE6

Miniature type used in the gain-controlled picture if stages of television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. Also used as an rf amplifier in vhf television tuners. This




tube features very high transconductance combined with low interelectrode capacitance values, and is provided with separate base pins for grid No.3 and cathode to permit the use of an unbypassed cathode resistor to minimize the effects of

CDEC

regeneration. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 4DE6 is identical with type 6DE6 except for the heater ratings, as shown below.


|  | 4DE6             | 6DE6       |                |
|--|------------------|------------|----------------|
| Heater Voltage (ac/dc)                                 | 4.2              | 6.3        | volts          |
| Heater Current   | 0.45             | 0.3        | ampere         |
| Heater Warm-up Time (Average)                          | 11               |            | seconds        |
| Peak Heater-Cathode Voltage:                           |                  |            |                |
| Heater negative with respect to cathode                | 200 max          | 200 max    | volts          |
| Heater positive with respect to cathode                | 200 <b>=</b> max | 200≢max    | volts          |
|  | Without          | With       |                |
|  | External         | External   |                |
| Direct Interelectrode Capacitances:                    | Shield           | Shield*    |                |
| Grid No.1 to Plate                                     | 0.025 max        | 0.015 max  | pf             |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid          |                  |            |                |
| No.3, and Internal Shield                              | 6.5              | 6.5        | pf             |
| Plate to Cathode, Heater, Grid No.2, Grid No.3,        |                  |            |                |
| and Internal Shield                                    | 2                | 3          | pf             |
| • The dc component must not exceed 100 volts.          |                  |            |                |
| ▲ With external shield connected to cathode.           |                  |            |                |
| Class A, Amplifier                                     |                  |            |                |
| MAXIMUM RATINGS (Design-Maximum Values):               |                  |            |                |
| Plate Voltage  |                  | 330 max    | volts          |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value    |                  | 0 max      | volts          |
| Grid-No.2 (Screen-Grid) Supply Voltage                 |                  | 330 max    | volts          |
| Grid-No.2 Voltage                                      |                  | See curve  |                |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  |                  | 0 max      | volts          |
| Plate Dissipation                                      |                  | 2.3 max    | watts          |
| Grid-No.2 Input:                                       |                  | 2.0 1.12.1 |                |
| For grid-No.2 voltages up to 165 volts                 |                  | 0.55 max   | watt           |
| For grid-No.2 voltages between 165 and 330 volts       |                  | See curve  |                |
| CHARACTERISTICS:                                       |                  |            | F-8            |
| Plate Supply Voltage                                   |                  | 125        | walta          |
| Grid No.3  |                  |            | volts          |
| Grid-No.2 Supply Voltage                               |                  | 125        | volts          |
|  |                  | 56         |                |
| Cathode-Bias Resistor                                  |                  | 0.25       | ohms           |
| Plate Resistance (Approx.)                             |                  | 8000       | megohm         |
| Transconductance for grid-No.1 volts of -5.5 and catho |                  | 8000       | $\mu$ mhos     |
|  |                  | 700        |                |
| of 0 ohms  |                  | -9         | μmhos<br>volts |
| Plate Current  |                  | 15.5       |                |
| Grid-No.2 Current                                      |                  | 4.2        | ma             |
| Grid-No.2 Current                                      |                  | 4.2        | ma             |



### **DUAL TRIODE**

Related types: 10DE7. 13DE7

Miniature type used as combined vertical oscillator and vertical-deflection 672(3 amplifier in television receivers. Unit No.1 is a medium-mu triode unit used or as a blocking oscillator in vertical-deflection circuits, and unit No.2 is a



13DE7

volts

92CM-9988T

low-mu triode unit used as a vertical-deflection amplifier. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For curve of average plate characteristics, Unit No.2, refer to type 6DR7. Types 10DE7 and 13DE7 are identical with type 6DE7 except for the heater ratings, as shown below.

6DE7


10DE7

| Heater Voltage (ac/dc)                   | 6.3             | 9.7       | 13        | volts   |
|--|-----------------|-----------|-----------|---------|
| Heater Current                           | 0.9             | 0.6       | 0.45      | ampere  |
| Heater Warm-up Time (Average)            |                 | 11        | 11        | seconds |
| Peak Heater-Cathode Voltage:             |                 | ••        |           | Seconds |
| Heater negative with respect to cathe    |                 | 200 max   | 200 max   | volts   |
| Heater positive with respect to cathe    | ode 200∙max     | 200=max   | 200 max   | volts   |
| Direct Interelectrode Capacitances (Appr | ox.): I         | Jnit No.1 | Unit No.2 |         |
| Grid to Plate                            |                 | 4         | 8.5       | pf      |
| Grid to Cathode and Heater               |                 | 2.2       | 5.5       | pf      |
| Plate to Cathode and Heater              |                 | 0.52      | 1         | pf      |
| * The dc component must not exceed 100   |                 | 0.52      | •         | P       |
|  |                 |           |           |         |
|  | ss A, Amplifier |           |           |         |
| CHARACTERISTICS:                         |                 | Jnit No.1 | Unit No.2 |         |
| Plate Voltage                            |                 | 250       | 150       | volts   |
| Grid Voltage                             |                 | 11        | -17.5     | volts   |
| Amplification Factor                     |                 | 17.5      | 6         |         |
| Plate Resistance (Approx.)               |                 | 8750      | 925       | ohms    |
| Transconductance                         |                 | 2000      | 6500      | μmhos   |
| Plate Current                            |                 | 5.5       | 35        | ma      |
| Plate Current for grid voltage of -24 vo |                 |           | 10        | ma      |
| Grid Voltage (Approx.) for plate current |                 | -20       |           | volts   |
| Grid Voltage (Approx.) for plate current |                 |           | 44        | volts   |
| Old voltage (Approx.) for plate current  | οι 50 μα        |           |           | 40172   |

# Vertical-Deflection Oscillator and Amplifier


For operation in a 525-line, 30-frame system

Unit No.2 Unit No.1 MAXIMUM RATINGS (Design-Maximum Values): Oscillator Amplifier DC Plate Voltage ..... 330 max 275 max



|                                    | Unit No.1  | Unit No.2 |       |
|------------------------------------|------------|-----------|-------|
|                                    | Oscillator | Amplifier |       |
| Peak Positive-Pulse Plate Voltage# | -          | 1500 max  | volts |
| Peak Negative-Pulse Grid Voltage   | -400 max   | -250 max  | volts |
| Peak Cathode Current               | 77 max     | 175 max   | ma    |
| Average Cathode Current            | 22 max     | 50 max    | ma    |
| Plate Dissipation                  | 1.5 max    | 7 max     | watts |
| MAXIMUM CIRCUIT VALUES:            |            |           |       |
| Grid-Circuit Resistance            |            |           |       |

For grid-resistor bias or cathode-bias operation ..... 2.2 max 2.2 max megohms # The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.



#### **BEAM POWER TUBE**


Glass octal type used as output tube in audio-amplifier applications. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any position. This type may be supplied with pin 1 omitted.

# 6DG6GT

volts

6.3

| Heater Current                                     |            | 1.2      | amperes    |
|--|------------|----------|------------|
| Peak Heater-Cathode Voltage:                       |            |          | unip 41 00 |
| Heater negative with respect to cathode            |            | 200 max  | volts      |
| Heater positive with respect to cathode            |            | 200 max  | volts      |
| Direct Interelectrode Capacitances (Approx.):      |            |          |            |
| Grid No.1 to Plate                                 |            | 0.6      | pf         |
| Grid No.1 to Cathode, Heater, Grid No.2 and Grid N | To.3       | 15       | pf         |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3 |            | 10       | pf         |
| The dc component must not exceed 100 volts.        |            |          | •          |
| Class A, Audio-Frequency Power                     | Amplifier  |          |            |
| MAXIMUM RATINGS (Design-Center Values):            |            |          |            |
| Plate Voltage                                      |            | 200 max  | volts      |
| Grid-No.2 (Screen-Grid) Voltage                    |            | 125 max  | volts      |
| Plate Dissipation                                  |            | 10 max   | watts      |
| Grid-No.2 Input                                    |            | 1.25 max | watts      |
| TYPICAL OPERATION:                                 |            |          |            |
| Plate Supply Voltage                               | 110        | 200      | volts      |
| Grid-No.2 Supply Voltage                           | 110        | 125      | volts      |
|  | <b>7.5</b> | _        | volts      |
| Peak AF Grid-No.1 Voltage                          | 7.5        | 8.5      | volts      |
| Cathode-Bias Resistor                              | _          | 180      | ohms       |
| Zero-Signal Plate Current                          | 49         | 46       | ma         |
| Maximum-Signal Plate Current                       | 50         | 47       | ma         |
| Zero-Signal Grid-No.2 Current                      | 4          | 2.2      | ma         |
| Maximum-Signal Grid-No.2 Current                   | 10         | 8.5      | ma         |
| Plate Resistance (Approx.) 1                       | 3000       | 28000    | ohms       |
|  | 8000       | 8000     | μmhos      |
|  | 2000       | 4000     | ohms       |
| Total Harmonic Distortion                          | 10         | 10       | per cent   |
| Maximum-Signal Power Output                        | 2.1        | 3.8      | watts      |
| MAXIMUM CIRCUIT VALUES:                            |            |          |            |



Grid-No.1-Circuit Resistance: For fixed-bias operation

For cathode-bias operation

# SHARP-CUTOFF PENTODE

Miniature type used as intermediatefrequency amplifier tube in television receivers. This tube features high transconductance at low plate and grid-No.2 voltages, combined with 3DK6, 4DK6, 12DK6 low interelectrode capacitances. Out-

0.1 max megohm

0.5 max megohm

Related types:

CHARACTERISTICS:

12DK6

12

3.8

ma

ma

6DK6

line 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 3DK6, 4DK6, and 12DK6 are identical with type 6DK6 except for the heater ratings, as shown below.


4DK6

3DK6

|  | JUNO            | JUNU                                    | סטעט              | 12DA0       |         |
|--|-----------------|---|-------------------|-------------|---------|
| Heater Voltage (ac/dc)                     |                 | 4.2                                     | 6.3               | 12.6        | volts   |
| Heater Current                             | 0.6             | 0.45                                    | 0.3               | 0.15        | ampere  |
| Heater Warm-up Time (Average)              | 11              | 11                                      | _                 | -           | seconds |
| Peak Heater-Cathode Voltage:               |                 |   |                   |             | Decomes |
| Heater negative with respect               |                 |   |                   |             |         |
| to cathode                                 | 300 n           | nax 200 max                             | 200 max           | 200 max     | volts   |
| Heater postive with respect                |                 |   |                   | 200 max     | VOILS   |
| to cathode                                 | 200 en          | nax 200°max                             | 200 max           | 200 max     | volts   |
| Direct Interelectrode Capacitances:        |                 | ilan 200 Inter                          | 200 IIIux         | 200-Illax   | VOIIS   |
| Grid No.1 to Plate                         |                 |   |                   | 0.025 max   |         |
| Grid No.1 to Cathode, Heater, Gri          | d No 2          | Grid No 3                               | and               | U.UZJ IIIAA | pf      |
| Internal Shield                            |                 |   |                   | 6.3         |         |
| Plate to Cathode, Heater, Grid No.2        | Grid 1          | Jo 3 and                                |                   | 0.3         | pf      |
| Internal Shield                            | , Ond 1         | 10.5, апц                               |                   | 1.9         |         |
|  |                 | • • • • • • • • • • •                   | • • • • • • •     | 1.7         | pf      |
| The dc component must not exceed 100       | volts.          |   |                   |             |         |
| Cla  | ss A. A         | mplifier                                |                   |             |         |
| MAXIMUM RATINGS (Design-Maxim              | •               |   |                   |             |         |
| Plate Voltage                              | unt van         | 168):                                   |                   | 222         | ••      |
| Grid-No.3 (Suppressor-Grid) Voltage, P     |                 |   | • • • • • •       | 330 max     | volts   |
| Grid No. 2 (Screen Grid) Supply Voltage, P | OSTUVE A        | alue                                    |                   | 0 max       | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage     |                 | • • • • • • • • • • •                   |                   | 330 max     | volts   |
| Grid-No.2 Voltage                          |                 | · • • • • • • • • • • • • • • • • • • • | • • • • • • •     | See curve   |         |
| Grid-No.1 (Control-Grid) Voltage, Positi   | ve-bias         | value                                   | · · · · · · · · · | 0 max       | volts   |
| Plate Dissipation                          | • • • • • • • • |   |                   | 2.3 max     | watts   |
| Grid-No.2 Input:                           |                 |   |                   |             |         |
| For grid-No.2 voltages up to 165 vo        | Its             |   |                   | 0.55 max    | watt    |
| For grid-No.2 voltages between 165         | and 330         | volts                                   |                   | See curve   | page 75 |
|  |                 |   |                   |             |         |

#### 125 volts ......Connected to cathode at socket Grid-No.2 Supply Voltage ..... 125 volts Cathode-Bias Resistor ..... 56 ohms Plate Resistance (Approx.) 0.35 megohm Transconductance ..... 9800 *u*mhos Grid-No.1 Voltage (Approx.) for plate current of 20 μa ..... -6.5 volts Plate Current .....

Grid-No.2 Current .....



#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

**6DM4** 



## HALF-WAVE VACUUM RECTIFIER

Glass octal type used as damper tube in horizontal-deflection circuits of television receivers. Outline 13G, Outlines section. Tube requires octal socket and may be operated in any position. Socket terminals 1, 2, 4, and

6DM4A

Related types: 12DM4A, 17DM4A

17DM4A

6 should not be used as tie points. It is important that this tube, like other power-handling tubes, be adequately ventilated. Types 12DM4A and 17DM4A are identical with type 6DM4A except for the heater ratings, as shown below.

12DM4A

| Heater Voltage (ac/dc)                        | 6.3           | 12.6                            | 16.8       | volts   |
|---|---------------|---------------------------------|------------|---------|
| Heater Current                                | 1.2           | 0.6                             | 0.45       | ampere  |
| Heater Warm-up Time (Average)                 |               | 11                              | 11         | seconds |
| Direct Interelectrode Capacitances (Approx.): |               |                                 |            | 200220  |
| Plate to Cathode and Heater                   |               |                                 | 8.5        | pf      |
| Cathode to Plate and Heater                   |               |                                 | 11.5       |         |
|   |               |                                 | 11.5       | pi      |
| Heater to Cathode                             | • • • • • • • | · · · · · · · · · · · · · · · · | 4          | pf      |
| Damper So                                     | ervice        |                                 |            |         |
| For operation in a 525-1                      | ine, 30-f     | rame system                     |            |         |
| MAXIMUM RATINGS (Design-Maximum Value         | s):           |                                 |            |         |
| Peak Inverse Plate Voltage <sup>o</sup>       |               |                                 | 5000 max   | volts   |
| Peak Plate Current                            |               |                                 | 1200 max   | ma      |
| DC Plate Current                              |               |                                 | 200 max    | ma      |
| Plate Dissipation                             |               |                                 | 6.5 max    | watts   |
| Peak Heater-Cathode Voltage:                  |               |                                 | U.J IIIAX  | ** 4113 |
| Heater negative with respect to cathode       |               |                                 | 5000 = max | volts   |
| ricate herative with respect to carnode       |               |                                 | צממושואאר  | VOIIS   |

- <sup>o</sup> The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 900 volts.

Heater positive with respect to cathode ...


• The dc component must not exceed 100 volts.

#### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

6DN6

300 max



# MEDIUM-MU DUAL TRIODE

Glass octal type used as combined vertical-deflection-oscillator and vertical-deflection-amplifier tube in television receivers. Outline 13B, Outlines section. Tube requires octal socket and may be mounted in any position.

**6DN7** 

Heater volts (ac/dc), 6.3; amperes, 0.9; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A Amplifier

| •         |   |   |
|-----------|---|---|
| Unit No.1 | Unit No.2                                     |   |
| 250       | 250   | volts   |
| -8        | <b>-9.5</b>                                   | volts   |
| 22.5      | 15.4  |   |
| 9000      | 2000  | ohms  |
| 2500      | 7700  | $\mu$ mhos  |
| 8         | 41  | ma  |
| 18        | -   | volts   |
|           | 23  | volts   |
|           | 250<br>-8<br>22.5<br>9000<br>2500<br>8<br>-18 | Unit No.1 Unit No.2<br>250 250<br>-8 -9.5<br>22.5 15.4<br>9000 2000<br>2500 7700<br>8 41<br>-18 - |

#### Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

| Unit No.1  | Unit No.2          |  |
|------------|--------------------|--|
| Oscillator | Amplifier          |  |
| 350 max    | 550 max            | volts  |
|            | 2500 max           | volts  |
| 400 max    | 250 max            | ma   |
|            | 150 max            | ma   |
| -          | 50 max             | ma   |
| 1 max      | 10 max             | watts  |
|            |                    |  |
|            | 350 max<br>400 max | Oscillator Amplifier 350 max 550 max 2500 max 400 max 250 max 150 max 50 max |

Grid-Circuit Resistance:

For fixed-bias operation ..... 2.2 max 2.2 max megohms For cathode-bias operation ..... 2.2 max megohms

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical cycle is 2.5 milliseconds.

# HALF-WAVE VACUUM RECTIFIER

**6DQ4** 

Glass octal type used as damper tube in horizontal-deflection circuits of television receivers. Outline 13F, Outlines section. Tube requires octal socket and may be mounted in any position. Socket terminals 1, 2, 4, and



6 should not be used as tie points. Heater volts (ac/dc), 6.3; amperes,


| Damper Service                                |          |       |
|---|----------|-------|
| For operation in a 525-line, 30-frame system  |          |       |
| MAXIMUM RATINGS (Design-Maximum Values):      |          |       |
| Peak Inverse Plate Voltage#                   | 5500 max | voits |
| Peak Plate Current                            | 1000 max | ma    |
| DC Plate Current                              | 175 max  | ma    |
| Plate Dissipation                             | 6 max    | watts |
| Peak Heater-Cathode Voltage:                  |          |       |
| Heater negative with respect to cathode       | 5500 max | volts |
| Heater positive with respect to cathode       | 300□max  | volts |
| CHARACTERISTICS, Instantaneous Value:         |          |       |
| Tube Voltage Drop for plate current of 250 ma | 32       | volts |

# The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds. The dc component must not exceed 900 volts.

### **BEAM POWER TUBE**

6DQ5

Glass octal type used as horizontal deflection amplifier in color television receivers. Outline 21B, Outlines section. Tube requires octal socket and may be mounted in any position.




The dc component must not exceed 100 volts.

| Heater Voltage (ac/dc) Heater Current                  | 6.3<br>2.5 | volts<br>amperes |
|--|------------|------------------|
| Peak Heater-Cathode Voltage:                           |            | -                |
| Heater negative with respect to cathode                | 200 max    | volts            |
| Heater positive with respect to cathode                | 200=max    | volts            |
| Direct Interelectrode Capacitances (Approx.):          |            |                  |
| Grid No.1 to Plate                                     | 0.5        | pf               |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 23         | pf               |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 11         | pf               |
| Plate Resistance (Approx.)*                            | 5500       | ohms             |
| Transconductance*                                      | 10500      | umhos            |
| Mu-Factor, Grid No.2 to Grid No.1**                    | 3.3        | ,                |

<sup>•</sup> The dc component must not exceed 100 volts.

<sup>\*\*</sup> For plate and grid-No.2 volts, 125; grid-No.1 volts, -25.



# **Horizontal Deflection Amplifier**

For operation in a 525-line, 30-frame system


| MAXIMUM RATINGS (Design-Maximum Values):             |           |       |
|--|-----------|-------|
| DC Plate Voltage                                     | 990 max   | volts |
| Peak Positive-Pulse Plate Voltage†                   | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage                    | -1100 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage                   | 190 max   | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | -250 max  | volts |
| Peak Cathode Current                                 | 1100 max  | ma    |
| Average Cathode Current                              | 315 max   | ma    |
| Grid-No.2 Input                                      | 3.2 max   | watts |
| Plate Dissipation#                                   | 24 max    | watts |
| Bulb Temperature (At hottest point)                  | 220 max   | •c    |

#### MAXIMUM CIRCUIT VALUE:

Grid-No.1-Circuit Resistance:

† The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds. # An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

<sup>\*</sup> For plate volts, 175; grid-No.2 volts, 125; grid-No.1 volts, --25; plate ma., 110; grid-No.2 ma., 5.



# 6DQ6A

# **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

# **BEAM POWER TUBE**

6DQ6B
Related types:
12DQ6B, 17DQ6B

Heater Voltage (ac/dc)

Glass octal type used as horizontaldeflection-amplifier tube in high-efficiency deflection circuits of television receivers. Outline 20, **Outlines** section. Tube requires octal socket and may be mounted in any position. This



wolte

17DQ6B

may be mounted in any position. This type may be supplied with pin 1 omitted. Types 12DQ6B and 17DQ6B are identical with type 6DQ6B except for the heater ratings, as shown below.

6DQ6B

12DQ6B

| Heater Voltage (ac/dc)                        | 6.3        | 12.6    | 16.8      | volts   |
|---|------------|---------|-----------|---------|
| Heater Current                                | 1.2        | 0.6     | 0.45      | ampere  |
| Heater Warm-up Time (Average)                 | _          | 11      | 11        | seconds |
| Peak Heater-Cathode Voltage:                  |            |         |           |         |
| Heater negative with respect to cathode       | 200 max    | 200 max | 200 max   | volts   |
| Heater positive with respect to cathode       | 200 max    |         | 200 max   | volts   |
|   | 2000 Illan | 2000max | 200-Illax | VOIIS   |
| Direct Interelectrode Capacitances (Approx.)  |            |         |           |         |
| Grid No.1 to Plate                            |            |         | 0.5       | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2,      |            |         | 15        | pf      |
| Plate to Cathode, Heater, Grid No.2, and G    | rid No.3   |         | 7         | pf      |
| ☐ The dc component must not exceed 100 volts. |            |         |           |         |
| Class A, A                                    | mplifier   |         |           |         |
| CHARACTERISTICS:                              | •          |         |           |         |
| Plate Voltage                                 |            | 60      | 250       | volts   |
| Grid-No.2 Voltage                             |            | 150     | 150       | volts   |
| Grid-No.1 Voltage                             |            | 200     | -22.5     | volts   |
| Plate Resistance (Approx.)                    |            | v       | 18000     | ohms    |
|   |            | _       |           | omis    |
| Transconductance                              |            |         | 7300      |         |
| Plate Current                                 |            | 345°    | 65        | ma      |
| Grid-No.2 Current                             |            | 27°     | 1.8       | ma      |
| Grid-No.1 Voltage (Approx.) for               |            |         |           |         |
| grid-No.2 volts $=$ 150, plate ma $=$ 1,      |            |         |           |         |
| plate volts = 250                             |            |         | 42        | volts   |
| plate volts = 5000                            |            | -       | -100      | volts   |
| This value can be measured by a method involv |            |         | 1. 11 4   |         |

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| For operation in a 323-nine, 30-maine system |           |       |
|--|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |           |       |
| DC Plate-Supply Voltage                      | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage            | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage            | —1500 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage           | 220 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage        | —330 max  | volts |
| Peak Cathode Current                         | 610 max   | ma    |
| Average Cathode Current                      | 175 max   | ma    |
| Grid-No.2 Input                              |           | watts |
| Plate Dissipation•                           | 18 max    | watts |
| Bulb Temperature (At hottest point)          | 220 max   | °C    |
|  |           |       |


MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance for grid-resistor-bias operation ....... 1 max megohm

The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

• An adequate bias resistor or other means is required to protect the tube in the absence of excitation,





Miniature type containing high-mu (GT) and low-mu triodes; used as combined vertical-deflection-oscillator and vertical-deflection-amplifier tube in television receivers. Outline 6E, Outlines section. Tube requires miniature nine-

OUK/ Related types: 10DR7, 13DR7

12DD7

contact socket and may be operated in any position. Types 10DR7 and 13DR7 are identical with type 6DR7 except for the heater ratings, as shown below.

KDD7

10007

|   | ODKI    | IUDK/     | 13DK/     |         |
|---|---------|-----------|-----------|---------|
| Heater Voltage (ac/dc)                        | 6.3     | 9.7       | 13        | volts   |
| Heater Current                                | 0.9     | 0.6       | 0.45      | ampere  |
| Heater Warm-up Time (Average)                 |         | 11        | 11        | seconds |
| Peak Heater-Cathode Voltage:                  |         |           |           |         |
| Heater negative with respect to cathode       | 200 max | 200 max   | 200 max   | volts   |
| Heater positive with respect to cathode       | 2004max | 200⁴max   | 2004max   | volts   |
| Direct Interelectrode Capacitances (Approx.): | τ       | Jnit No.1 | Unit No.2 |         |
| Grid to Plate                                 |         | 4.5       | 8.5       | pf      |
| Grid to Cathode and Heater                    |         | 2.2       | 5.5       | pf      |
| Plate to Cathode and Heater                   |         | 0.34      | i         | pf      |
| ▲ The dc component must not exceed 100 volts  |         |           |           | _       |

Ine de component must not exceed 100 volts.

| Class M Miliphilic   | 51         |           |       |
|--|------------|-----------|-------|
| CHARACTERISTICS:   | Unit No.1  | Unit No.2 |       |
| Plate Voltage  | 250        | 150       | volts |
| Grid Voltage   | <b>—</b> 3 | -17.5     | volts |
| Amplification Factor   | 68         | 6         |       |
| Plate Resistance (Approx.)                                   | 40000      | 925       | ohms  |
| Transconductance   | 1600       | 6500      | μmhos |
| Grid Voltage (Approx.) for plate current of 10 $\mu$ a       | <b>5.5</b> | _         | volts |
| Grid Voltage (Approx.) for plate current of 50 $\mu a \dots$ | -          | -44       | volts |
| Plate Current  | 1.4        | 35        | ma    |
| Plate Current for grid voltage of -24 volts                  | -          | 10        | ma    |

Class & Amplifica

Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

| Oscillator | Amplifier                               |   |
|------------|---|---|
| 330 max    | 275 max                                 | volts   |
|            | 1500 max                                | volts   |
| -400 max   | -250 max                                | voits   |
| 70 max     | 175 max                                 | ma  |
| 20 max     | 50 max                                  | ma  |
| 1 max      | 7 max                                   | watts   |
|            | Oscillator 330 max400 max 70 max 20 max | Oscillator 330 max 275 max 1500 max -250 max 70 max 20 max 50 max |


#### MAXIMUM CIRCUIT VALUE:

Grid-Circuit Resistance:


For grid-resistance-bias or cathode-bias operation .

Unit No.1 Oscillator 2.2 max Unit No.2 Amplifier 2.2 max megohms

#The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.




92CM-9912T



# HIGH-MU TRIODE

6DS4
Related type:
2DS4


Nuvistor type used as grounded-cathode, neutralized rf amplifier in vhf tuners of television and FM receivers. Because of its cutoff characteristics, the 6DS4 is used in circuits to reduce cross-modulation distortion. Outline



INDEX=LARGE LUG

1, Outlines section. Tube requires nuvistor socket and may be operated in any position. Type 2DS4 is identical with type 6DS4 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage:                                | 2DS4<br>2.1<br>0.45<br>8 | 6DS4<br>6.3<br>1.35               | volts<br>ampere<br>seconds |
|---|--------------------------|-----------------------------------|----------------------------|
| Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances (Approx.): | 100 max<br>100 max       | 100 max<br>100 max                | volts<br>volts             |
| Grid to Plate Grid to Cathode, Heater, and Shell Plate to Cathode, Heater, and Shell Plate to Cathode Heater to Cathode         |                          | 0.92<br>4.3<br>1.8<br>0.18<br>1.6 | pf<br>pf<br>pf<br>pf<br>pf |
| Class A, Amplifier  |                          |                                   |                            |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Supply Voltage   |                          | 300°max                           | volts                      |
| Plate Voltage   |                          | 135 max                           | volts                      |
| Grid Voltage, Negative-bias value   |                          | 55 max                            | volts                      |
| Grid Voltage, Peak Positive value   |                          | 0 max                             | volts                      |
| Plate Dissipation   |                          | 1.5 max                           | watt                       |
| Cathode Current   | • • • • • • • • •        | 15 max                            | ma                         |
| CHARACTERISTICS:  |                          |                                   |                            |
| Plate Supply Voltage  |                          | 110                               | volts                      |
| Grid Supply Voltage   |                          | 0                                 | volts                      |
| Cathode-Bias Resistor   |                          | 130                               | ohms                       |
| Amplification Factor  |                          | 63                                |                            |
| Plate Resistance (Approx.)  |                          | 7000                              | ohms                       |
| Transconductance  |                          | 9000                              | $\mu$ mhos                 |
| Plate Current   |                          | 6.5                               | ma                         |
| Grid Voltage (Approx.) for plate current of 100 $\mu a$   |                          | <b>⊷</b> 5                        | volts                      |
| Grid Voltage (Approx.) for plate current of 10 $\mu a$  |                          | -6.8                              | volts                      |
| TYPICAL OPERATION:  |                          |                                   |                            |
| Plate Voltage   |                          | 70                                | volts                      |
| Grid Supply Voltage   |                          | 0                                 | volts                      |
| Grid Resistor   |                          | 47000                             | ohms                       |
| Amplification Factor  |                          | 68                                |                            |
| Plate Resistance (Approx.)  |                          | 5440                              | ohms                       |
| Transconductance  |                          | 12500                             | μmhos                      |
| Plate Current   |                          | 7                                 | ma                         |



#### MAXIMUM CIRCUIT VALUES:

| ıd-Cır | cuit | Resis | tance: |
|--------|------|-------|--------|
| P      | £    | 4 1.1 |        |


| Grid-Circuit Resistance:   |         |        |
|----------------------------|---------|--------|
| For fixed-bias operation   | 0.5 max |        |
| For cathode-bias operation | 2.2 max | megohm |

A plate supply voltage of 300 volts may be used provided a sufficiently large resistor is used in the plate circuit to limit the plate dissipation to 1.5 watts under any condition of operation.

### **BEAM POWER TUBE**

6DS5


Miniature type used in the audio output stages of television and radio receivers. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.



| Heater Voltage (ac/dc)                                 | 6.3     | volts  |
|--|---------|--------|
| Heater Current   | 0.8     | ampere |
| Peak Heater-Cathode Voltage:                           |         |        |
| Heater negative with respect to cathode                | 200 max | volts  |
| Heater positive with respect to cathode                | 200 max | volts  |
| Direct Interelectrode Capacitances (Approx.):          |         |        |
| Grid No.1 to Plate                                     | 0.19    | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 9.5     | pf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 6.3     | pf     |
|  |         |        |

# Amnlifier

| 275 max | volts                                |
|---------|--------------------------------------|
| 275 max | volts                                |
| 0 max   | volts                                |
| 9 max   | watts                                |
| 2.2 max | watts                                |
| 250 max | °C                                   |
|         | 275 max<br>0 max<br>9 max<br>2.2 max |



| TYPICAL OPERATION AND CHARACTERISTICS: | Cathode-Bias<br>Operation |            | Fixed-Bias<br>Operation |            |                |
|--|---------------------------|------------|-------------------------|------------|----------------|
| Plate Supply Voltage                   | 200                       | 250<br>200 | 200<br>200              | 250<br>200 | volts<br>volts |

<sup>•</sup> For operation at metal-shell temperatures up to 125°C.

|                                  | Cathode-Bias<br>Operation |                 |       | Fixed-Bias<br>Operation |          |
|----------------------------------|---------------------------|-----------------|-------|-------------------------|----------|
| Grid-No.1 Voltage                | _                         | <del></del> 7.5 |       | <del></del> 8.5         | volts    |
| Cathode-Bias Resistor            |                           | _               | 180   |                         | ohms     |
| Peak AF Grid-No.1 Voltage        | 9.2                       | 7.5             | 7.5   | 8.5                     | volts    |
| Zero-Signal Plate Current        |                           | 27              | 35    | 29                      | ma       |
| Maximum-Signal Plate Current     | 32.5                      | 25              | 36    | 32                      | ma       |
| Zero-Signal Grid-No.2 Current    |                           | 3               | 3     | 3                       | ma       |
| Maximum-Signal Grid-No.2 Current | 9                         | 9               | 9     | 10                      | ma       |
| Plate Resistance (Approx.)       | 28000                     | 28000           | 28000 | 28000                   | ohms     |
| Transconductance                 |                           | 5800            | 6000  | 5800                    | μmhos    |
| Load Resistance                  |                           | 8000            | 6000  | 8000                    | ohms     |
| Total Harmonic Distortion        | 10                        | 10              | 9     | 10                      | per cent |
| Maximum-Signal Power Output      | 2.8                       | 3.6             | 3     | 3.8                     | watts    |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:

| FOL | nxed-bias operation .  | <br>U.1 max | megonm |
|-----|------------------------|-------------|--------|
| For | cathode-bias operation | <br>1.0 max | megohm |
|     | -                      |             |        |



# **BEAM POWER TUBE**

Miniature type used as a vertical-deflection-amplifier tube in television receivers employing 110-degree picturetube systems. Outline 6E, Outlines section. Tube requires miniature ninecontact socket and may be operated

6DT5
Related type: 12DT5

in any position. Type 12DT5 is identical with type 6DT5 except for the heater ratings, as shown below.

|   | 6DT5    | 12DT5   |         |
|---|---------|---------|---------|
| Heater Voltage (ac/dc)                  | 6.3     | 12.6    | volts   |
| Heater Current                          | 1.2     | 0.6     | ampere  |
| Heater Warm-up Time (Average)           | _       | 11      | seconds |
| Peak Heater-Cathode Voltage:            |         |         |         |
| Heater negative with respect to cathode | 200 max | 200 max | volts   |
| Heater positive with respect to cathode | 200*max | 2004max | volts   |
| Transconductance*                       |         | 6200    | μmhos   |

<sup>&</sup>lt;sup>▲</sup>The dc component must not exceed 100 volts.

# Vertical-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-maximum values):             |          |       |
|--|----------|-------|
| DC Plate Voltage                                     | 315 max  | volts |
| Peak Positive-Pulse Plate Voltage#                   | 2200 max | volts |
| Grid-No.2 (Screen-Grid) Voltage                      | 285 max  | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | -250 max | volts |
| Peak Cathode Current                                 | 190 max  | ma    |
| Average Cathode Current                              | 55 max   | ma    |
| Plate Dissipation                                    | 9 тах    | watts |
| Grid-No.2 Input                                      | 2 max    | watts |
| •  |          |       |

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

|     | fixed-bias operation   | 0.5 max | megohm |
|-----|------------------------|---------|--------|
| For | cathode-bias operation | 1 max   | megohm |
|     |                        |         |        |

#The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

# SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.


6DT6

<sup>•</sup> For plate and grid-No.2 volts, 250; grid-No.1 volts, -16.5; plate ma., 44; grid-No.2 ma., 1.5.

# SHARP-CUTOFF PENTODE

6DT6A
Related types:
3DT6A, 4DT6A

Miniature type used as FM detector in television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 3DT6A and 4DT6A are identical with




type 6DT6A except for the heater ratings, as shown below.

|   | 3DT6A        | 4DT6A       | 6DT6A   |         |
|---|--------------|-------------|---------|---------|
| Heater Voltage (ac/dc)                        | 3.15         | 4.2         | 6.3     | volts   |
| Heater Current                                |              | 0.45        | 0.3     | ampere  |
| Heater Warm-up Time (Average)                 | 11           | 11          | -       | seconds |
| Peak Heater-Cathode Voltage:                  |              |             |         |         |
| Heater negative with respect to cathode       | 200 max      | 200 max     | 200 max | volts   |
| Heater positive with respect to cathode       |              | 200 max     | 200 max | volts   |
| Direct Interelectrode Capacitances (Approx.)* |              |             |         |         |
| Grid No.1 to Plate                            |              |             | 0.02    | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, C    | irid No.3, a | nd Internal |         | _       |
| Shield  |              |             | 5.8     | pf      |
| Grid No.3 to Plate                            |              |             | 1.7     | pf      |
| Grid No.1 to Grid No.3                        |              |             | 0.1     | pf      |
| Grid No.3 to Cathode, Heater, Grid No.1, C    | irid No.2, a | nd Internal |         |         |
| Shield  |              |             | 6.1     | pf      |

- The dc component must not exceed 100 volts.
- \* External shield connected to cathode.

#### Class A. Amplifier

| CHARACTERISTICS: Plate Supply Voltage                  |           | 150      | volts        |
|--|-----------|----------|--------------|
| Grid No.3 (Suppressor-Grid)                            | Connected | to catho | de at socket |
| Grid-No.2 (Screen-Grid) Supply Voltage                 |           | 100      | volts        |
| Cathode-Bias Resistor                                  |           | 560      | ohms         |
| Plate Resistance (Approx.)                             |           | 0.15     | megohm       |
| Transconductance, Grid No.1 to Plate                   |           | 1350     | μmhos        |
| Transconductance, Grid No.3 to Plate                   |           | 515      | μmhos        |
| Plate Current  |           | 1.55     | ma           |
| Grid-No.2 Current                                      |           | 1.8      | ma           |
| Grid-No.1 Voltage (Approx.) for plate current of 10 µa |           | -5.2     | volts        |
| Grid-No.3 Voltage (Approx.) for plate current of 10 µa |           | -4.2     | volts        |





#### **FM** Detector

| MAXIMUM RATINGS (Design-Maximum Values):              |   |
|---|---|
| Plate Voltage   | 330 max volts                           |
| Grid-No.3 Voltage                                     | 28 max volts                            |
| Grid-No.2 Supply Voltage                              | 330 max volts                           |
| Grid-No.2 Voltage                                     | See curve page 75                       |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max volts                             |
| Plate Dissipation                                     | 1.7 max watts                           |
| Grid-No.2 Input:                                      | *************************************** |
| For grid-No.2 voltages up to 165 volts                | 1.2 max watts                           |
| For grid-No.2 voltages between 165 and 330 volts      | See curve page 75                       |

#### **MAXIMUM CIRCUIT VALUES:**

| MAXIMUM CIRCUIT VALUES:       |          |        |
|-------------------------------|----------|--------|
| Grid-No.1-Circuit Resistance: |          |        |
| For fixed-bias operation      | 0.25 max | megohm |
| For cathode-bias operation    | 0.5 max  | megohm |





# HIGH-MU TWIN TRIODE

Miniature type used in a wide variety of applications in radio and television receivers. Especially useful in pushpull rf amplifiers or as frequency converter in FM tuners. Outline 6B, Outlines section. Tube requires min-

6DT8
Related type: 12DT8

iature nine-contact socket and may be mounted in any position. Type 12DT8 is identical with type 6DT8 except for the heater ratings. Except for heater and heater-cathode ratings, interelectrode capacitances, and basing arrangement, these types are identical with miniature type 12AT7.

|  | 6DT8    | 12DT8   |        |
|--|---------|---------|--------|
| Heater Voltage (ac/dc)   | 6.3     | 12.6    | volts  |
| Heater Current   | 0.3     | 0.15    | ampere |
| Peak Heater-Cathode Voltage:                                   |         |         |        |
| Heater negative with respect to cathode                        | 200 max | 200 max | volts  |
| Heater positive with respect to cathode                        | 200 max | 200=max | volts  |
| Direct Interelectrode Capacitances (Approx., Each Unit Noted): |         | 200     | 10113  |
| Grid to Plate  |         | 1.6*    | pf     |
| Grid to Cathode, Heater, and Internal Shield                   |         | 2.7*    | pf     |

| Plate to Cathode, Heater, and Internal Shield            | 1.6* | pf |
|--|------|----|
| Heater to Cathode  | 3●   | pf |
| Cathode to Grid, Heater, and Internal Shield (Unit No.2) | 5.3† | pf |
| Plate to Grid, Heater, and Internal Shield (Unit No.2)   | 2.8† | pf |


- The dc component must not exceed 100 volts.
- \* With external shield connected to cathode of unit under test.
- · With external shield connected to ground.
- † With external shield connected to grid of unit under test.

° For operation at metal-shell temperatures up to 135°C.

# HIGH-MU TRIODE

6DV4
Related type:
2DV4


Nuvistor type used at frequencies up to 1000 megacycles in uhf oscillator stages of television receivers. Outline 1, **Outlines** section. Tube requires nuvistor socket and may be mounted in any position. Type 2DV4 is identical



INDEX = LARGE LUG • = SHORT PIN

with type 6DV4 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)  | 2DV4<br>2.1 | 6DV4<br>6.3    | volts      |
|---|-------------|----------------|------------|
| Heater Current  | 0.45        | 0.135          | ampere     |
| Heater Warm-up Time (Average)   | 8           | _              | seconds    |
| Heater negative with respect to cathode   | 100 max     | 100 1          | nax volts  |
| Heater positive with respect to cathode  Direct Interelectrode Capacitance (Approx.): | 100 max     | 100 1          | nax volts  |
| Grid to Plate   |             | 1.8            | pf         |
| Grid to Cathode, Heater, and Shell  |             | 4.4            | pf         |
| Plate to Cathode, Heater, and Shell   |             | 1.9            | pf         |
| Plate to Cathode  |             | 0.25           | pf         |
| Heater to Cathode   |             | 1.4            | pf         |
| Grid to Cathode   |             | 3.7            | pf         |
| A   |             |                |            |
| Class A, Amplifier  | Ī           |                |            |
| MAXIMUM RATINGS (Design-Maximum Values):  |             | 200            |            |
| Plate Supply Voltage  |             | 300 n<br>125 n |            |
| Plate Voltage   |             |                |            |
| Negative-bias value   |             | 55 n           |            |
| Peak positive value   |             | 2 n            |            |
| Plate Dissipation   |             | 1 n            |            |
| Cathode Current   |             | 15 n           | nax ma     |
| CHARACTERISTICS:  |             |                |            |
| Plate Supply Voltage  |             | 75             | volts      |
| Cathode-Bias Resistor   |             | 100            | ohms       |
| Amplification Factor  |             | 35             | _          |
| Plate Resistance (Approx.)  |             | 3100           | ohms       |
| Transconductance  |             | 11500          | μmhos      |
| Grid Voltage (Approx.) for plate current of 10 $\mu a$                                |             | <del>-7</del>  | volts      |
| Plate Current   |             | 10.5           | ma         |
| TYPICAL OPERATION AS OSCILLATOR AT 950 MC:  |             |                |            |
| Plate Voltage   |             | 60             | volts      |
| Grid Voltage  |             | -2             | volts      |
| Grid Resistor   |             | 5600           | ohms       |
| Plate Current   |             | 8              | ma         |
| Grid Current  |             | 350            | μа         |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance:                                      |             |                |            |
| For fixed-bias operation  |             | 0.1 n          | nax megohm |
| For cathode-bias operation  |             |                | nax megohm |
| Tot emilione often observed   |             |                | -          |



# HALF-WAVE VACUUM RECTIFIER



Novar types used as damper tubes in horizontal-deflection circuits of color and black-and-white television receivers. Outlines 11D and 30B, respectively, Outlines section. Tubes require novar nine-contact socket and may be

# **6DW4** 6DW4B

mounted in any position. Socket terminals 1, 3, 6, and 8 should not be used as tie points; it is recommended that socket clips for these pins be removed to reduce the possibility of arc-over and to minimize leakage. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated.

| Heater Voltage (ac/dc) Heater Current                    | 6.3<br>1.2 | volts<br>amperes |
|--|------------|------------------|
| Direct Interelectrode Capacitances (Approx.):            |            |                  |
| Plate to Cathode and Heater: Cathode to Plate and Heater |            | pf<br>pf         |
| Heater to Cathode  | 2.8        | pf               |
| Damuar Camica  |            |                  |

### Damper Service

| For operation in a 525-line, 30-frame system |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |          |       |
| Peak Inverse Plate Voltage <sup>o</sup>      | 5000 max | volts |
| Peak Plate Current                           | 1300 max | ma    |
| DC Plate Current                             | 250 max  | ma    |
| Plate Dissipation                            | 8.5 max  | watts |
| Peak Heater-Cathode Voltage:                 |          |       |
| Heater negative with respect to cathode      | 5000 max | volts |
| Heater positive with respect to cathode      | 300°max  | volts |

Tube Voltage Drop for plate current of 350 ma ... 25 volts ° The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

• The dc component must not exceed 900 volts.


CHARACTERISTICS, Instantaneous Value:

• The dc component must not exceed 100 volts.

### **BEAM POWER TUBE**

**6DW5** 

Miniature type used in vertical deflection amplifier service in television re- GI(3) ceivers employing 110-degree deflection systems. Outline 6G. Outlines No section. Tube requires miniature ninecontact socket and may be operated



in any position. Heater volts (ac/dc), 6.3; amperes, 1.2; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, A                                    | mplifie | er               |                       |       |
|---|---------|------------------|-----------------------|-------|
| CHARACTERISTICS:                              |         | ntode<br>nection | Triode<br>Connection° |       |
| Plate Voltage                                 | 60      | 200              | 150                   | volts |
| Grid-No.2 Voltage                             | 150     | 150              | _                     | volts |
| Grid-No.1 Voltage                             | 0       | -22.5            | -22.5                 | volts |
| Amplification Factor                          |         |                  | 4.3                   |       |
| Plate Resistance (Approx.)                    | _       | 15000            |                       | ohms  |
| Transconductance                              |         | 5500             | _                     | μmhos |
| Plate Current                                 | 260=    | 55               | _                     | · ma  |
| Grid-No.2 Current                             | 20 •    | 2                |                       | ma    |
| Grid-No.1 Voltage (Approx.) for plate current |         |                  |                       |       |
| of 0.1 ma                                     | _       | <b>—55</b>       |                       | volts |

<sup>°</sup> With grid No.2 connected to plate.

Vertical-Deflection Amplifier

| For operation in a 525-line, 30-frame system•        |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):             |          |       |
| DC Plate Voltage                                     | 330 max  | volts |
| Peak Positive-Pulse Plate Voltage•                   | 2200 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage                   | 220 max  | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | -250 max | volts |
| Peak Cathode Current                                 | 225 max  | ma    |
| Average Cathode Current                              | 65 max   | ma    |
| Plate Dissipation                                    | 11 max   | watts |
| Grid-No.2 Input                                      | 2.5 max  | watts |

### MAXIMUM CIRCUIT VALUES:

Grid-No.1 Circuit Resistance:


For cathode-bias operation ..... 2.2 max megohms

• The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

6DX8

Miniature type used in television-re- kt ceiver applications. The triode unit is used as a sync-separator, sync-amplifier, keyed-agc, or noise-suppressor Pi tube. The pentode unit is used as a video-output tube. Outline 6E, Out-



lines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 10DX8 is identical with type 6DX8 except for the heater ratings, as shown below.

|                        | 6DX8 | 10DX8 |        |
|------------------------|------|-------|--------|
| Heater Voltage (ac/dc) | 6.3  | 10.2  | volts  |
| Heater Current         | 0.72 | 0.45  | ampere |

<sup>•</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

| Peak Heater-Cathode Voltage:                |       |       | SDX8      | 10DX8            |            |
|---|-------|-------|-----------|------------------|------------|
| Heater negative with respect to cathode     |       | 20    | 00 max    | 200 max          | volts      |
| Heater positive with respect to cathode     |       |       | 00 max    | 200 max          | volts      |
|   |       |       |           | 200 22           | , 5115     |
| Class A, A                                  | \mpli | fier  |           |                  |            |
| •   | •     | 1     | Triode    | Pentode          |            |
| MAXIMUM RATINGS (Design-Center Values):     |       |       | Unit      | Unit             |            |
| Plate Supply Voltage                        |       | 5:    | 50 max    | 550 max          | volts      |
| Peak Plate Voltage, with maximum plate curr |       |       |           |                  |            |
| 0.1 ma°                                     |       |       | 00 max    | -                | volts      |
| Plate Voltage                               |       |       | 00 max    | 300 max          | volts      |
| Grid-No.2 (Screen-Grid) Supply Voltage      |       |       |           | 550 max          | volts      |
| Grid-No.2 Voltage                           |       |       |           | 300 max          | volts      |
| Cathode Current                             |       |       | 12 max    | 40 max           | ma         |
| Grid-No.2 Input                             |       |       | _         | 1.7 max          | watts      |
| Plate Dissipation                           |       |       | 1 max     | 4 max            | watts      |
| Triode                                      |       |       |           |                  |            |
| CHARACTERISTICS: Unit                       |       | ъ     | entode Un | it               |            |
| Plate Voltage                               |       | 170   | 200       | 220              | volts      |
| Grid-No.2 Voltage                           |       | 170   | 200       | 220              | volts      |
| Grid-No.1 Voltage                           |       | -2.1  | -2.9      | -3.4             | volts      |
| Amplification Factor                        |       | -2.1  | -2.7      | —J. <del>4</del> | VOIG       |
| Mu-Factor, Grid-No.2 to Grid-No.1           |       | 36    | 36        | 36               |            |
| Plate Resistance (Approx.)                  |       | 0.1   | 0.13      | 0.15             | megohm     |
| Transconductance                            |       | 11000 | 10400     | 10000            | μmhos      |
| Plate Current                               |       | 18    | 18        | 18               | ma ma      |
| Grid-No.2 Current                           |       | 3     | 3         | 3                | ma         |
|   |       | -     | -         | -                | ша         |
| TYPICAL OPERATION OF PENTODE UNIT A         |       |       |           |                  |            |
| Plate Supply Voltage                        | 170   | 20    |           | 220              | volts      |
| Series Plate Resistor                       | 3000  | 300   |           | 3000             | ohms       |
| Grid-No.2 Voltage                           | 170   | 20    |           | 220              | volts      |
| Grid-No.1 Voltage                           | -2    | -2.   |           | <b>—3.3</b>      | volts      |
|   | 10400 | 1000  |           | 9700             | $\mu$ mhos |
| Plate Current                               | 18    | 1     |           | 18               | ma         |
| Grid-No.2 Current                           | 3.2   | 3.    | .1        | 3.1              | ma         |
| MAXIMUM CIRCUIT VALUES:                     |       |       |           |                  |            |
| Grid-No.1-Circuit Resistance:               |       | Tri   | ode Unit  | Pentode U        |            |
|   |       |       | 4         | 4                |            |

For fixed-bias operation ..... For cathode-bias operation .....

1 max 1 max megohm 3 max 2 max megohms

\* With maximum duty factor of 0.18 and maximum pulse duration of 18 microseconds.



### MEDIUM-MU TRIODE

Miniature type used as a local-oscillator tube in uhf television receivers covering the frequency range from 470 to 890 megacycles. Outline 5B, Outlines section. Tube requires miniature seven-contact socket and may be

Related types: 2DZ4, 3DZ4

mounted in any position. For curve of average plate characteristics, refer to type 6AF4A. Types 2DZ4 and 3DZ4 are identical with type 6DZ4 except for the heater ratings, as shown below.

|  | 2D <b>Z</b> 4 | 3D <b>Z</b> 4 | 6DZ4  |         |
|--|---------------|---------------|-------|---------|
| Heater Voltage (ac/dc)                         | 2.35          | 3.2           | 6.3   | volts   |
| Heater Current                                 | 0.6           | 0.45          | 0.225 | атреге  |
| Heater Warm-up Time (Average)                  | 11            | 11            |       | seconds |
| Peak Heater-Cathode Voltage:                   |               |               |       |         |
| Heater negative with respect to cathode        | 180 max       | 180 max       | 50    | volts   |
| Heater positive with respect to cathode        | 180*max       | 180*max       | 50■   | volts   |
| Direct Interelectrode Capacitances (Approx.):° |               |               |       |         |
| Grid to Plate                                  | <i>.</i>      |               | 1.8   | pf      |
| Grid to Cathode and Heater                     | <i></i> .     |               | 2.2   | pf      |
| Plate to Cathode and Heater                    |               |               | 1.3   | pf      |

<sup>\*</sup> The dc component must not exceed 100 volts.

The dc component must not exceed 25 volts.

With external shield connected to cathode.

### Class A, Amplifier

| CHARACTERISTICS:                                  |           |        |
|---|-----------|--------|
| Plate Supply Voltage                              | 80        | volts  |
| Plate Resistor                                    | 2700      | ohms   |
| Amplification Factor                              | 14        |        |
| Plate Resistance (Approx.)                        | 2000      | ohms   |
| Transconductance                                  | 6700      | μmhos  |
| Plate Current                                     | 15        | ma     |
| Grid Voltage (Approx.) for plate current of 20 µa | -11       | volts  |
| Glid Voltage (Approx.) for plate current of 20 µa | -11       | VOIIS  |
| UHF Oscillator                                    |           |        |
| MAXIMUM RATINGS (Design-Maximum Values):          |           |        |
| Plate Voltage                                     | 135 max   | volts  |
| Grid Voltage, Negative-bias value                 | -50 max   | volts  |
| Grid Current                                      | 2 max     | ma     |
|   | 20 max    | ma     |
| Cathode Current                                   |           |        |
| Plate Dissipation                                 | 2.3 max   | watts  |
| TYPICAL OPERATION AS OSCILLATOR AT 1000 MC:       |           |        |
| Plate Supply Voltage                              | 135       | volts  |
| Plate-Circuit Resistance                          | 2700      | ohms   |
| Grid Resistor                                     | 10000     | ohms   |
| Plate Current                                     | 15.5      | ma     |
| Grid Current (Approx.)                            | 800       | μа.    |
| Cita Current (Approx.)                            | 800       | μа     |
| MAXIMUM CIRCUIT VALUES:                           |           |        |
| Grid-Circuit Resistance:                          |           |        |
| For fixed-bias operation                          | Not recon | mended |
|   |           |        |

### TWIN POWER PENTODE

For cathode-bias operation .....

**6DZ7** 

CHARACTERISTICS (Each Unit):


Cathode-Bias Resistor ......

Peak AF Grid-No.1-to-Grid-No.1 Voltage ......

Zero-Signal Plate Current .....

Maximum-Signal Plate Current .....

Glass octal type used as power am- PP23 plifier tube in high-fidelity audio equipment. Outline 19B, Outlines section. Tube requires octal socket and may be operated in any position. It is especially important that this tube,



250

120

22

66

80

......

ohms

volts

ma

ma

0.5 max megohm

like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 6.3; amperes, 1.52; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

### Class A, Amplifier

| Plate Voltage                                 |          | 250      | voits      |
|---|----------|----------|------------|
| Grid-No.2 (Screen-Grid) Voltage               |          | 250      | volts      |
| Grid-No.1 (Control-Grid) Voltage              |          | 7.3      | volts      |
| Plate Resistance (Approx.)                    |          | 38000    | ohms       |
| Transconductance                              |          | 11300    | $\mu$ mhos |
| Plate Current                                 |          | 48       | ma         |
| Grid-No.2 Current                             |          | 5.5      | ma         |
| Push-Pull Class AB, An                        | nnlifier |          |            |
| MAXIMUM RATINGS (Design-Maximum Values, Per 7 |          |          |            |
| Plate Voltage                                 |          | 440 max  | volts      |
| Grid-No.2 Voltage                             |          | 300 max  | volts      |
| Grid-No.2 Input (Total)                       |          | 4 max    | watts      |
| Plate Dissipation                             |          | 13.2 max | watts      |
|   | Fixed    | Cathode  |            |
| TYPICAL OPERATION (Per Tube):                 | Bias     | Bias     |            |
| Plate Voltage                                 | 400      | 300      | volts      |
| Grid-No.2 Voltage                             | 250      | 250      | volts      |
| Grid-No.1 Voltage                             | -11      | _        | volts      |
|   |          |          |            |

22

40

100

|  | Fixed<br>Bias | Cathode<br>Bias |          |
|--|---------------|-----------------|----------|
| Zero-Signal Grid-No.2 Current              | 4             | 7               | ma       |
| Maximum-Signal Grid-No.2 Current           | 13            | 15              | ma       |
| Effective Load Resistance (Plate-to-Plate) | 9000          | 9000            | ohms     |
| Total Harmonic Distortion                  | 2.5           | 3.5             | per cent |
| Maximum-Signal Power Output                | 18            | 12              | watts    |
| MAXIMUM CIRCUIT VALUES (Each Unit):        |               |                 | _        |
| Grid-No.1-Circuit Resistance               | <i></i>       | 0.27 max        | megohm   |



### **ELECTRON-RAY TUBE**

Glass type used to indicate visually by means of a fluorescent target the effects of a change in a controlling voltage. It is used as a convenient means of indicating accurate radio-receiver tuning. Outline 13H, Outlines

**6E5** 

section. Tube requires six-contact socket. Heater volts (ac/dc), 6.3; amperes, 0.3. For additional considerations, refer to Tuning Indication with Electron-Ray Tubes in Electron Tube Applications section.

| Tuning Indicator                           |   |                      |                |
|--|---|----------------------|----------------|
| MAXIMUM AND MINIMUM RATINGS (Design-Center |   |                      | •.             |
| Plate-Supply Voltage                       | • • • • • • • • •                       | 250 max              | volts          |
| Target Voltage                             | • | {250 max<br>{125 min | volts<br>volts |
| TYPICAL OPERATION:                         |   |                      |                |
| Plate and Target Supply Voltage            | 200                                     | 250                  | volts          |
| Series Triode-Plate Resistor               | 1                                       | 1                    | megohm         |
| Target Current*†                           | 3                                       | 4                    | ma             |
| Triode-Plate Current*                      | 0.19                                    | 0.24                 | ma             |
| Triode-Grid Voltage (Approx.):             |   |                      |                |
| For shadow angle of 0°                     | <b></b> 6.5                             | 8.0                  | volts          |
| For shadow angle of 90°                    | 0                                       | 0                    | volts          |
|  |   |                      |                |

<sup>•</sup> For zero triode-grid voltage. † Subject to wide variations.

## TWIN POWER TRIODE


Discontinued type; see chart at end of section for tabulated data.

**6E6** 

### REMOTE-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

**6E7** 



### SHARP-CUTOFF TETRODE

Miniature type used as rf amplifier in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be operated in any position. Type 3EA5 is identical with type

6EA5
Related type:
3EA5

6EA5 except for the heater ratings, as shown below.

|                               | 3EA5 | 6EA5 |         |
|-------------------------------|------|------|---------|
| Heater Voltage (ac/dc)        | 2.9  | 6.3  | volts   |
| Heater Current                | 0.45 | 0.2  | ampere  |
| Heater Warm-up Time (Average) | 11   |      | seconds |


| Peak Heater-Cathode Voltage:                          |          |          |        |
|---|----------|----------|--------|
| Heater negative with respect to cathode               | 200 max  | 200 max  | volts  |
| Heater positive with respect to cathode               | 200 max  | 200 max  | volts  |
| •   | Without  | With     |        |
|   | External | External |        |
| Direct Interelectrode Capacitances:                   | Shield   | Shield   |        |
| Grid No.1 to Plate                                    | 0.06 max | 0.05 max | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and          |          |          | _      |
| Internal Shield                                       | 3.8      | 4.5      | pf     |
| Plate to Cathode, Heater, Grid No.2, and              |          | _        | _      |
| Internal Shield                                       | 2.3      | 3        | pf     |
| The dc component must not exceed 100 volts.           |          |          |        |
| *With external shield connected to cathode.           |          |          |        |
| Class A. Amplifie                                     | Г        |          |        |
| MAXIMUM RATINGS (Design-Maximum Values):              |          |          |        |
| Plate Voltage   |          | 250 max  | volts  |
| Grid-No.2 (Screen-Grid) Voltage                       |          | 150 max  | volts  |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value |          | 0 max    | volts  |
| Cathode Current                                       |          | 20 max   | ma     |
| Grid-No.2 Input                                       |          | 0.5 max  | watt   |
| Plate Dissipation                                     | •••••    | 3.25 max | watts  |
| CHARACTERISTICS:                                      |          |          |        |
| Plate Voltage   |          | 250      | volts  |
| Grid-No.2 Voltage                                     |          | 140      | volts  |
| Grid-No.1 Voltage                                     |          | -1       | volt   |
| Plate Resistance (Approx.)                            |          | 0.15     | megohm |
| Transconductance                                      |          | 8000     | μmhos  |
| Plate Current   |          | 10       | ma     |
| Grid-No.2 Current                                     |          | 0.95     | ma     |

### **DUAL TRIODE**

Grid-No.1 Voltage (Approx.) for transconductance of 100 µmhos

# 6EA7

Glass octal type containing high-mu triode and high-perveance, low-mu triode in same envelope. Used as a combined vertical deflection oscillator and vertical deflection amplifier in television receivers. Outline 13B, Out-



volts

lines section. Tube requires octal socket and may be operated in any position. Heater volts (ac/dc), 6.3; amperes, 1.05; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, Amplifie                | er -      |        |      |       |
|----------------------------------|-----------|--------|------|-------|
| CHARACTERISTICS:                 | Unit No.1 | Unit N | lo.2 |       |
| Plate Voltage                    | 250       | 60 1   | 75   | volts |
| Grid Voltage                     | 3         | 0 -    | -25  | volts |
| Amplification Factor             | 66        |        | 5.5  |       |
| Plate Resistance (Approx.)       | 30000     | - 9    | 20   | ohms  |
| Transconductance                 | 2200      | 60     | 100  | μmhos |
| Grid Voltage (Approx.):          |           |        |      |       |
| For plate current of 20 $\mu$ a  | -5.3      | -      | _    | volts |
| For plate current of 200 $\mu$ a | _         |        | -45  | volts |
| Plate Current                    | 2         | 100•   | 40   | ma    |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

### Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values):

DC Plate Voltage

Peak Positive-Pulse Plate Voltage

Oscillator


350 max

Unit No.2 Amplifier 550 max 1500 max

volts volts

| Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation              | Unit No.1<br>Oscillator<br>-400 max<br>-<br>1 max | Unit No.2<br>Amplifier<br>-250 max<br>175 max<br>50 max<br>10 max |         |
|--|---|---|---------|
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance: For grid-resistor-bias operation For cathode-bias operation | 1 max   | 1 max   | megohm  |
|  | 2.2 max   | 2.2 max   | megohms |

<sup>o</sup> The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.



### MEDIUM-MU TRIODE.... SHARP-CUTOFF PENTODE

KP,G3p Miniature type used as combined oscillator and mixer in television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. Outline 6B, Outlines section. 5EA8, 9EA8, 19EA8

Related types:

Pentode

Triode

Tube requires miniature nine-contact socket and may be mounted in any position. Types 5EA8, 9EA8, and 19EA8 are identical with type 6EA8 except for the heater ratings, as shown below.


|                                       | 5EA8      | 6EA8      | 9EA8      | 19EA8    |         |
|---------------------------------------|-----------|-----------|-----------|----------|---------|
| Heater Voltage (ac/dc)                | 4.7       | 6.3       | 9.5       | 18.9     | volts   |
| Heater Current                        | 0.6       | 0.45      | 0.3       | 0.15     | ampere  |
| Heater Warm-up Time (Average)         | 11        | 11        | 11        | 11       | seconds |
| Peak Heater-Cathode Voltage:          |           |           |           |          |         |
| Heater negative with respect          |           |           |           |          |         |
| to cathode                            | 200 m     | ax 200 ma | x 200 max | 200 max  | volts   |
| Heater positive with respect          |           |           |           |          |         |
| to cathode                            | 200 ma    | x 200 ma  | x 200 max | 200∙max  | volts   |
|                                       |           |           | Without   | With     |         |
| Direct Interelectrode Capacitances:   |           |           | External  | External |         |
| Triode Unit:                          |           |           | Shield    | Shield°  |         |
| Grid to Plate                         | . <b></b> |           | 1.7       | 1.7      | pf      |
| Grid to Cathode, Heater, Pentode (    | Cathode,  |           |           |          | -       |
| Pentode Grid No.3, and Internal       | Shield .  |           | 3         | 3.2      | pf      |
| Plate to Cathode, Heater, Pentode (   | Cathode,  |           |           |          | -       |
| Pentode Grid No.3, and Internal       | Shield .  |           | 1.4       | 1.9      | pf      |
| Cathode to Heater                     |           |           | 3         | 3■       | pf      |
| Pentode Unit:                         |           |           |           |          | _       |
| Grid No.1 to Plate                    |           |           | 0.02 max  | 0.01 max | pf      |
| Grid No.1 to Cathode, Heater, Grid    | No.2,     |           |           |          |         |
| Grid No.3, and Internal Shield        |           |           | 5         | 5        | pf      |
| Plate to Cathode, Heater, Grid No.2,  | Grid No   | .3,       |           |          | =       |
| and Internal Shield                   |           |           | 2.6       | 3.4      | pf      |
| Heater to Cathode                     |           |           | 3         | 3■       | pf      |
| 4 The de component must not avoid 100 | *** 14=   |           |           |          | _       |


- The dc component must not exceed 100 volts.
- \* With external shield connected to cathode of unit under test except as noted.
- With external shield connected to ground.

Class A, Amplifier


| MAXIMUM RATINGS (Design-Maximum Values):               | Unit    | Unit             |    |
|--|---------|------------------|----|
| Plate Voltage  | 330 max | 330 max vol      | ts |
| Grid-No.2 (Screen-Grid) Supply Voltage                 |         | 330 max vol      | ts |
| Grid-No.2 Voltage                                      | -       | See curve page 7 | 5  |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value. | 0 max   | 0 max vol        | s  |
| Plate Dissipation                                      | 2.5 max | 3.1 max wat      | s  |
| Grid-No.2 Input:                                       |         |                  |    |
| For grid-No.2 voltages up to 165 volts                 | -       | 0.55 max was     | ŧŧ |
| For grid-No.2 voltages between 165 and 330 volts.      | -       | See curve page 7 | 5  |
| -  |         |                  |    |

| CHARACTERISTICS:                             | Triode<br>Unit | Pentode<br>Unit |       |
|--|----------------|-----------------|-------|
| Plate Supply Voltage                         | 150            | 125             | volts |
| Grid-No.2 Voltage                            | _              | 125             | volts |
| Grid-No.1 Voltage                            |                | -1              | volt  |
| Cathode-Bias Resistor                        | 56             | _               | ohms  |
| Amplification Factor                         | 40             | _               |       |
| Plate Resistance (Approx.)                   | 5000           | 200000          | ohms  |
| Transconductance                             | 8500           | 6400            | umhos |
| Plate Current                                | 18             | 12              | ma    |
| Grid-No.2 Current                            | _              | 4               | ma    |
| Grid-No.1 Voltage for plate current of 10 µa | -12            | <u>_9</u>       | volts |





### HIGH-MU TRIODE-SHARP-CUTOFF PENTODE



Miniature type used in color and black-and-white television receivers. Pentode unit is used as video output amplifier; triode unit is used in syncseparator, sync-clipper, and phase-inverter circuits. Outline 6E, Outlines

section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8EB8 is identical with type 6EB8 except for the heater ratings, as shown below.


| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 6EB8<br>6.3<br>0.75 | 8EB8<br>8<br>0.6<br>11 | volts<br>ampere<br>seconds |
|--|---------------------|------------------------|----------------------------|
| Heater negative with respect to cathode  | 200 max             | 200 max                | volts                      |
| Heater positive with respect to cathode  | 200°max             | 200°max                | volts                      |
| Direct Interelectrode Capacitances:  |                     |                        |                            |
| Triode Unit:   |                     |                        |                            |
| Grid to Plate  |                     | 4.4                    | pf                         |
| Grid to Cathode and Heater   |                     | 2.4                    | pf                         |
| Plate to Cathode and Heater  |                     | 0.36                   | pf                         |
| Pentode Unit:  |                     |                        |                            |
| Grid No.1 to Plate   |                     | 0.1 max                | pf                         |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3   | 3, and              |                        | _                          |
| Internal Shield  |                     | 11                     | pf                         |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, as   |                     |                        | -                          |
| Internal Shield  |                     | 4.2                    | pf                         |
| Triode Grid to Pentode Plate   |                     | 0.018 max              | pf                         |
| Pentode Grid No.1 to Triode Plate  |                     | 0.005 max              | pf                         |
| Pentode Plate to Triode Plate  |                     | 0.17 max               | pf                         |
|  |                     |                        |                            |


For cathode-bias operation .....

| The dc component must not exceed 100 volts.  |                           |                 |                |
|--|---------------------------|-----------------|----------------|
| Class A, Amplifier   |                           |                 |                |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage   | Triode<br>Unit<br>330 max | Pento<br>Unit   |                |
| Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage   |                           | 330             |                |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Disispation                            | 0 max<br>1 max            | 0               | max volts      |
| Grid-No.2 Input: For grid-No.2 voltages up to 165 volts  | _                         | _               | max watts      |
| For grid-No.2 voltages between 165 and 330 volts   | _                         |                 | curve page 75  |
| CHARACTERISTICS: Plate Supply Voltage  | 250                       | 200             | volts          |
| Grid-No.2 Supply Voltage   |                           | 125             | volts<br>volts |
| Cathode-Bias Resistor Amplification Factor   | 100                       | 68              | ohms           |
| Plate Resistance (Approx.)  Transconductance   | 37000<br>2700             | 75000<br>12500  | ohms<br>µmhos  |
| Grid Voltage (Approx.) for plate current of 20 μa Grid-No.1 Voltage (Approx.) for plate current of | 5                         | _               | volts          |
| 100 µa Plate Current   | <u>_</u>                  | <u>-9</u><br>25 | volts<br>ma    |
| Grid-No.2 Current  |                           | 7               | ma             |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:  |                           |                 |                |
| For fixed-bias operation   | 0.5 max                   | 0.25            | max megohm     |

1.0 max

1.0 max megohm





### POWER PENTODE

**6EH5** Related types:

12EH5, 25EH5, 50EH5

Miniature type used in the audio output stage of radio and television receivers and in phonographs. This type has unusually high power sensitivity and is capable of providing relatively high power output at low plate and




screen-grid voltages with a low af grid-No. 1 driving voltage. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 12EH5, 25EH5, and 50EH5 are identical with type 6EH5 except for the heater ratings, as shown below.

0.1 max megohm

0.5 max megohm

Grid-No.1-Circuit Resistance: For fixed-bias operation

|  | 6EH5        | 12EH5      | 25EH5     | 50EH5     |             |
|--|-------------|------------|-----------|-----------|-------------|
| Heater Voltage (ac/dc)                   |             | 12.6       | 25        | 50        | volts       |
| Heater Current                           |             | 0.6        | 0.3       | 0.15      | ampere      |
| Heater Warm-up Time (Average)            |             | 11         | 0.5       | 0.13      | seconds     |
| Peak Heater-Cathode Voltage:             | . —         | 11         | _         | _         | seconus     |
| Heater negative with respect             |             |            |           |           |             |
| to cathode                               | 200 may     | 300 max    | 200 max   | 200 max   | volts       |
| Heater positive with respect             | . 200 Illax | 300 max    | 200 Illax | 200 Illax | 10113       |
| to cathode                               | 200 = may   | 200 • max  | 200=max   | 200 • max | volts       |
| Direct Interelectrode Capacitances (Appr | . 200-111ax | 200-Illax  | 200-max   | 200-Illax | TORES       |
| Grid No.1 to Plate                       |             |            |           | 0.65      | pf          |
| Grid No.1 to Cathode, Heater, Gri        | d No 2 a    | nd Grid No | . 3       | 17        | pf          |
| Plate to Cathode, Heater, Grid No.:      |             |            |           | 9         | pf          |
| riate to Cathode, Heater, Olid 140.      | z, and On   | u 140.5    |           | ,         | Pr          |
| • The dc component must not exceed 100   | ) volts.    |            |           |           |             |
| CI                                       | ass A. A    | molifier   |           |           |             |
|  |             |            |           |           |             |
| MAXIMUM RATINGS (Design-Maxim            |             |            |           | 150 max   | volts       |
| Plate Voltage                            |             |            |           | 130 max   | volts       |
| Grid-No.2 (Screen-Grid) Voltage          |             |            |           | 5.5 max   | watts       |
| Plate Dissipation                        |             |            |           | 2 max     | watts       |
| Grid-No.2 Input                          |             |            |           | 220 max   | watts<br>°C |
| Bulb Temperature (at hottest point)      |             |            |           | 220 max   | C           |
| TYPICAL OPERATION:                       |             |            |           |           |             |
| Plate Supply Voltage                     |             |            |           | 110       | volts       |
| Grid-No.2 Supply Voltage                 |             |            |           | 115       | volts       |
| Cathode-Bias Resistor                    |             |            |           | 62        | ohms        |
| Peak AF Grid-No.1 Voltage                |             |            |           | 3         | volts       |
| Zero-Signal Plate Current                |             |            |           | 42        | ma          |
| Maximum-Signal Plate Current             |             |            |           | 42        | ma          |
| Zero-Signal Grid-No.2 Current            |             |            |           | 11.5      | ma          |
| Maximum-Signal Grid-No.2 Current         |             |            |           | 14.5      | ma          |
| Plate Resistance (Approx.)               |             |            |           | 11000     | ohms        |
| Transconductance                         |             |            |           | 14600     | μmhos       |
| Load Resistance                          |             |            |           | 3000      | ohms        |
| Total Harmonic Distortion                |             |            |           | 7         | per cent    |
| Maximum-Signal Power Output              |             |            |           | 1.4       | watts       |
| •  |             |            |           |           |             |
| MAXIMUM CIRCUIT VALUES:                  |             |            |           |           |             |



For cathode-bias operation .....

### Push-Pull Class AB, Audio-Frequency Power Amplifier

MAXIMUM RATINGS: (Same as for class A1 audio-frequency power amplifier)

| TYPICAL OPERATION (Values are for 2 tubes): |      |          |
|---|------|----------|
| Plate Supply Voltage                        | 140  | volts    |
| Grid-No.2 Supply Voltage                    | 120  | volts    |
| Cathode-Bias Resistor                       | 68   | ohms     |
| Peak AF Grid-No.1 Voltage                   | 9.4  | volts    |
| Zero-Signal Plate Current                   | 47   | ma       |
| Maximum-Signal Plate Current                | 51   | ma       |
| Zero-Signal Grid-No.2 Current               | 11   | ma       |
| Maximum-Signal Grid-No.2 Current            | 17.7 | ma       |
| Effective Load Resistance (Plate-to-plate)  | 6000 | ohms     |
| Total Harmonic Distortion                   | 5    | per cent |
| Maximum-Signal Power Output                 | 3.8  | watts    |
|   |      |          |

### MAXIMUM CIRCUIT VALUES:

| irid-No.1-Circuit Resistance: |         |        |
|-------------------------------|---------|--------|
| For fixed-bias operation      | 0.1 max |        |
| For cathode-bias operation    | 0.5 max | megohm |

### SEMIREMOTE-CUTOFF PENTODE


Related types: 3EH7, 4EH7

CHARACTERISTICS:

Miniature type used as if-amplifier tube in television receivers. Outline 6C, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Types 3EH7 and 4EH7 are identical with

3FH7

**4EH7** 



6EH7

valte

volts

volts

ma

ma

μmhos

12

4.5

type 6EH7 except for the heater ratings, as shown below.

|   | 32.111   | 74.11     | 02-11 |      |          |
|---|----------|-----------|-------|------|----------|
| Heater Voltage (ac/dc)                            | 3.4      | 4.4       | 6.3   |      | volts    |
| Heater Current                                    | 0.6      | 0.45      | 0.3   |      | ampere   |
| Peak Heater-Cathode Voltage:                      |          |           |       |      | -        |
| Heater negative with respect to cathode           | 150 max  | 150 max   | 150   | max  | volts    |
| Heater positive with respect to cathode           |          |           | 150   |      | volts    |
| Direct Interelectrode Capacitances:               | 130 max  | 150 11144 |       |      | ,,,,,    |
| Grid No.1 to Plate                                |          |           | 0.005 | may  | pf       |
| Grid No.1 to Cathode, Heater, Grid No.2, G        |          |           | 0.003 | шал  | ρι       |
|   |          |           | 9     |      |          |
| Internal Shield                                   |          |           | ,     |      | pf       |
| Plate to Cathode, Heater, Grid No.2, Grid         |          |           |       |      |          |
| Internal Shield                                   |          |           | 3     |      | pf       |
| Class A. A  | mnlifier |           |       |      |          |
| •   | •        |           |       |      |          |
| MAXIMUM RATINGS (Design-Center Values):           |          |           |       |      |          |
| Plate Supply Voltage                              |          |           | 550   | max  | volts    |
| Plate Voltage                                     |          |           | 250   | max  | volts    |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive val | ue       |           | 0     | max  | volts    |
| Grid-No.2 (Screen-Grid) Supply Voltage            |          |           | 550   | max  | volts    |
| Grid-No.2 Voltage                                 |          |           | 250   | max  | volts    |
| Cathode Current                                   |          |           |       | max  | ma       |
| Grid-No.2 Input                                   |          |           |       | max  | watt     |
| Plate Dissipation                                 |          |           |       | max  | watts    |
| I mie Dissipation                                 |          |           | 4.7   | **** | · · atta |

### Plate Voltage ..... 200 Grid No.3 Connected to cathode at socket Grid-No.2 Voltage ..... 90 Grid-No.1 Voltage -2 Plate Resistance (Approx.) ..... 0.5 megohm 12500

Transconductance .....

Grid-No.2 Current

Plate Current

| TYPICAL OPERATION:              |       |         |            |           |       |
|---------------------------------|-------|---------|------------|-----------|-------|
| Plate Voltage                   | 200   | 200     | 200        | 200       | volts |
| Grid No.3                       | Co    | nnected | to cathode | at socket |       |
| Grid-No.2 Supply Voltage        | 200   | 200     | 200        | 200       | volts |
| Grid-No.2 Series Resistor       | 22000 | 22000   | 22000      | 22000     | ohms  |
| Grid-No.1 Voltage               | 19.5  | 9.5     | 6.5        | -2        | volts |
| Transconductance                | 125   | 625     | 1250       | 12500     | μmhos |
| RMS Grid-No.1 Voltage, for      |       |         |            |           |       |
| cross-modulation factor of 0.01 | 450   | 160     | 100        |           | mv    |
|                                 |       |         |            |           |       |

### MAXIMUM CIRCUIT VALUES:


Grid-No.1-Circuit Resistance .....

1 max megohm

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

**6EH8** 



Heater Voltage (ac/dc)

### SHARP-CUTOFF PENTODE

Miniature type used as if-amplifier tube in television receivers. Outline 6C, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Types 3EJ7 and 4EJ7 are identical

3EJ7

4EJ7

0.35

10

4.1

15000

OEJ/ Related types: 3EJ7, 4EJ7

valte

6EJ7

0.35

10

4.1

15000

megohm

umbos.

ma

ma

with type 6EJ7 except for the heater ratings, as shown below.

| neater voitage (ac/gc)                      | 3.4        | 4.4     | 0.3           | voits  |
|---|------------|---------|---------------|--------|
| Heater Current                              | 0.6        | 0.45    | 0.3           | ampere |
| Peak Heater-Cathode Voltage:                |            |         |               | -      |
| Heater negative with respect to cathode     | 150 max    | 150 max | 150 max       | volts  |
| Heater positive with respect to cathode     | 150 max    | 150 max | 150 max       | volts  |
| Direct Interelectrode Capacitances:         |            |         |               |        |
| Grid No.1 to Plate                          |            |         | 0.005 max     | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2,    | Grid No.3, | and     |               | -      |
| Internal Shield                             |            |         | 10            | pf     |
| Plate to Cathode, Heater, Grid No.2, Grid I |            |         |               | -      |
| Internal Shield                             |            |         | 3             | pf     |
|   |            |         |               |        |
| Class A, A                                  | mplifier   |         |               |        |
| MAXIMUM RATINGS (Design-Center Values):     |            |         |               |        |
| Plate Supply Voltage                        |            |         | 550 max       | volts  |
| Plate Voltage                               |            |         | 250 max       | volts  |
| Grid-No.2 (Screen-Grid) Supply Voltage      |            |         | 550 max       | volts  |
| Grid-No.2 Voltage                           |            |         | 250 max       | volts  |
| Cathode Current                             |            |         | 25 max        | ma     |
| Grid-No.2 Input                             |            |         | 0.9 max       | watt   |
| Plate Dissipation                           |            |         | 2.5 max       | watts  |
| CHARACTERISTICS:                            |            |         |               |        |
| Plate Voltage                               |            | 190     | 200           | volts  |
| Grid No.3                                   |            |         | ed to cathode |        |
| Grid-No.2 Voltage                           |            | 190     | 200           | volts  |
| Grid-No 1 Voltage                           |            | -2.35   | -25           | volts  |

### **MAXIMUM CIRCUIT VALUES:**

Plate Resistance (Approx.) .....

Transconductance ......

Plate Current .......

Grid-No.2 Current .....

### **BEAM POWER TUBE**

Miniature type used as vertical deflection amplifier in television receivers utilizing picture tubes having diagonal deflection angles of 110 degrees. Outline 6G, Outlines section. Tube requires miniature nine-contact



socket and may be mounted in any position. Type 8EM5 is identical with type 6EM5 except for the heater ratings, as shown below.

| ** . **  | 0EMD                  | 8EM3           |         |
|--|-----------------------|----------------|---------|
| Heater Voltage (ac/dc)   | 6.3                   | 8.4            | volts   |
| neater Current   | 0.8                   | 0.6            | ampere  |
| Heater Warm-up Time (Average)  |                       | 11             | seconds |
| Peak Heater-Cathode Voltage:   |                       | 11             | Seconds |
| Heater negative with respect to cathode  | 200 max               | 200            | 1       |
| Heater positive with respect to cathode  |                       | 200 max        | volts   |
| Direct Interelectrode Capacitances:  | 200=max               | 200*max        | volts   |
| Direct interesectione Capacitances:  |                       |                |         |
| Gride No.1 to Plate  |                       | 0.7 max        | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid N  | No 3                  | 10             | pf      |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3   |                       | 5.1            | pf      |
| Plate Resistance (Approx.)*  |                       | 0.05           | megohm  |
| Transconductance*  | • • • • • • • • • • • | 5100           |         |
| The de comments with the second secon |                       | 3100           | µmhos   |
| <ul> <li>The dc component must not exceed 100 volts.</li> </ul>  |                       |                |         |
| * For plate and grid-No.2 volts, 250; grid-No.1 volts, -18; pl   | late ma, 40; grid     | I-No.2 ma., 3. |         |
| Vertical Deflection Amp  |                       | •              |         |
| For operation in a 525-line, 30-fra  | P::::::::             |                |         |
| MAYIMIM DATINGS (Desire Control 31.2)  | ame system            |                |         |
| MAXIMUM RATINGS (Design-Center Values):  |                       |                |         |
| DC Plate Voltage   |                       | 315 max        | volts   |
| reak Positive-Pulse Plate Voltaget (Absolute Maximum)  |                       | 22004max       | volts   |
| Grid-No.2 (Screen-Grid) Voltage  |                       | 285 max        | voits   |
| Deals Manager D. 1. October 1.   |                       | 203 11.0%      | 10113   |

### Bulb Temperature (at hottest point) ..... MAXIMUM CIRCUIT VALUES:

Grid-No.2 Input ....

Grid-No.1-Circuit Resistance ... ▲ Under no circumstances should this absolute value be exceeded.

Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage .....

Peak Cathode Current .....

Average Cathode Current .....

Plate Dissipation .....

2.2 max megohm

valte

ma

ma

watts

watts

250 max

210 max


60 max


10 max


1.5 max

250 max

† The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.







### **DUAL TRIODE**

Glass octal type containing high-mu triode and high-perveance, low-mu triode in same envelope. Used as combined vertical-deflection amplifier and vertical-deflection oscillator in television receivers employing picture tubes

6EM7
Related types:

Related types: 10EM7, 13EM7

having 110-degree deflection angles and high ultor voltages. Outline 13A, Outlines section. Tube requires octal socket and may be mounted in any position. For curve of average plate characteristics, Unit No.1, refer to type 6DR7 (Unit No.1). Types 10EM7 and 13EM7 are identical with type 6EM7 except for the heater ratings, as shown below.

|   | 6EM7    | 10EM7     | 13 <b>EM</b> 7 |         |
|---|---------|-----------|----------------|---------|
| Heater Voltage (ac/dc)                        | 6.3     | 9.7       | 13             | volts   |
| Heater Current                                | 0.925   | 0.6       | 0.45           | ampere  |
| Heater Warm-up Time (Average)                 | _       | 11        | 11             | seconds |
| Peak Heater-Cathode Voltage:                  |         |           |                |         |
| Heater negative with respect to cathode       | 200 max | 200 max   | 200 max        | volts   |
| Heater positive with respect to cathode       | 200 max | 200 max   | 200 max        | volts   |
| Direct Interelectrode Capacitances (Approx.): |         | Unit No.1 | Unit No.2      |         |
| Grid to Plate                                 |         | 4.8       | 10             | pf      |
| Grid to Cathode and Heater                    |         | 2.2       | 7              | pf      |
| Plate to Cathode and Heater                   |         | 0.6       | 1.8            | pf      |
|   |         | ***       |                | P-      |

| ■ The dc component must not exceed 100 volts.    |             |           |            |
|--|-------------|-----------|------------|
| Class A, Amplifi                                 | er          |           |            |
| CHARACTERISTICS:                                 | Unit No.1   | Unit No.2 |            |
| Plate Voltage                                    | 250         | 150       | volts      |
| Grid Voltage                                     | -3          | -20       | volts      |
| Amplification Factor                             | 64          | 5.4       |            |
| Plate Resistance (Approx.)                       | 40000       | 750       | ohms       |
| Transconductance                                 | 1600        | 7200      | $\mu$ mhos |
| Grid Voltage (Approx.):                          |             |           | •          |
| For plate current of 10 $\mu$ a                  | <b>—5.5</b> | _         | volts      |
| For plate current of 100 $\mu$ a                 | _           | 45        | volts      |
| Plate Current                                    | 1.4         | 50        | ma         |
| Plate Current, for plate voltage of 60 volts and |             |           |            |
| zero grid voltage                                |             | 10        | ma         |
| Plate Current, for grid votlage of -28 volts     | _           | 95        | ma         |

### Vertical-Deflection Oscillator and Amplifier


For operation in a 525-line, 30-frame system

|  | Unit No.1  | Unit No.2 |       |
|--|------------|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator | Amplifier |       |
| DC Plate Voltage                         | 330 max    | 330 max   | volts |
| Peak Positive-Pulse Plate Voltage#       | -          | 1500 max  | volts |
| Peak Negative-Pulse Grid Voltage         | -400 max   | -250 max  | volts |
| Peak Cathode Current                     | 77 max     | 175 max   | ma    |
| Average Cathode Current                  | 22 max     | 50 max    | ma    |
| Plate Dissipation                        | 1.5 max    | 10 max    | watts |

# The duration of the voltage pulse must not exceed 15 per cent of one vertical-scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical-scanning cycle is 2.5 milliseconds.

### MAXIMUM CIRCUIT VALUES:


| Grid-Circuit Resistance | e:                       | Unit No.1          | Unit No.2                          |
|-------------------------|--------------------------|--------------------|------------------------------------|
|                         | bias operation operation | 2.2 max<br>2.2 max | 2.2 max megohms<br>2.2 max megohms |



### DIODE— REMOTE-CUTOFF PENTODE

6EQ7
Related type:
12EQ7

Miniature type used as combined if amplifier and AM detector in AM and AM/FM radio receivers. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Type




12EQ7 is identical with type 6EQ7 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)  | 6EQ7<br>6.3<br>0.3 | 12EQ7<br>12.6<br>0.15 | volts<br>ampere |
|---|--------------------|-----------------------|-----------------|
| Heater negative with respect to cathode Heater positive with respect to cathode | 200 max            | 200 max               | volts           |
|   | 200•max            | 200•max               | volts           |

The dc component must not exceed 100 volts.

| Diseast I         | nterelectrode Capacitances:  |                 |           |
|-------------------|--|-----------------|-----------|
|                   | e Unit:  |                 |           |
| Grid              | No t to Plate  | 0.002 max       | pf        |
| Grid              | No.1 to Cathode, Heater, Grid No.2, Grid No.3, and                     |                 |           |
| Īn'               | ternal Shield  | 5.5             | pf        |
| Plate             | to Cathode, Heater, Grid No.2, Grid No.3, and                          | 5               | pf        |
| In                | ternal Shielde Grid No.1 to Diode Plate                                | 0.0015 max      | pf        |
|                   | e Plate to Diode Plate   | 0.095           | pf        |
| rentou            |  |                 | •-        |
|                   | Pentode Unit as Class A, Amplifier UM RATINGS (Design-Maximum Values): |                 |           |
| MAXIM<br>Dista Va | tage   | 300 max         | volts     |
| Grid-No.          | 3 (Suppressor-Grid) Voltage:   | •••             |           |
| Posi              | tive value   | 300 max         | volts     |
| Neo:              | ative value  | -300 max        | volts     |
| Grid-No           | 2 (Screen-Grid) Supply Voltage   | 300 max         | volts     |
| Grid-No.          | 2 Voltage  | See curve       | page 75   |
| Grid-No.          | 1 (Control-Grid) Voltage:  | A               | volts     |
| Posi              | tive-bias value  | 0 max<br>50 max | volts     |
| Neg               | ative-bias value   | 3 max           | watts     |
| Plate Di          | ssipation  | 0.2 max         | watt      |
| Grid-No.          |  | O.Z man         |           |
| For               | grid-No.2 voltages up to 150 volts                                     | 0.6 max         | watt      |
| For               | grid-No.2 voltages between 150 and 300 volts                           | See curve       | page 75   |
| Rulb Te           | mperature (At hottest point)   | 150 max         | °C        |
|                   | CTERISTICS:  |                 |           |
|                   | CIERISTICS:  | 100             | volts     |
| Grid No           |  |                 |           |
| Internal          | Shield   | to cathode a    | at socket |
| Grid-No.          | 2 Voltage  | 100             | volts     |
| Grid-No.          | 1 Supply Voltage   | 0               | volts     |
| Grid-No.          | 1 Resistor (Bypassed)  |                 | megohms   |
| Plate R           | esistance (Approx.)  | 0.25            | megohm    |
|                   | ductance   | 3800<br>9       | μmhos     |
|                   | irrent   | 3.5             | ma<br>ma  |
|                   | 2 Current  | -20             | volts     |
| Grid-No.          | 1 Voltage (Approx.) for transconductance of 40 μmmos                   | -20             | VOILS     |
|                   | Diode Unit   |                 |           |
| MAXIM             | UM RATINGS (Design-Maximum Values):                                    | 1               |           |
| Plate Cu          | rrent  | 1 max           | ma        |
|                   | CTERISTICS, Instantaneous Value:                                       |                 |           |
| Tube Vo           | oltage Drop for plate current of 2 ma                                  | 10              | volts     |
|                   |  |                 |           |



### HIGH-MU TRIODE

2ER5, 3ER5

Miniature type with frame grid used in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 2ER5 and 3ER5 are identical



with type 6ER5 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)                        | 2ER5<br>2.3<br>0.6 | 3ER5<br>2.8<br>0.45            | 6ER5<br>6.3<br>0.18         | volts<br>ampere |
|---|--------------------|--------------------------------|-----------------------------|-----------------|
| Heater negative with respect to cathode       | 100 max            | 100 max                        | 100 max                     | volts           |
| Heater positive with respect to cathode       | 100 max            | 100 max<br>Without<br>External | 100 max<br>With<br>External | volts           |
| Direct Interelectrode Capacitances:           |                    | Shield                         | Shield                      |                 |
| Grid to Plate                                 |                    | 0.38                           | 0.36                        | pf              |
| Grid to Cathode, Heater, and Internal Shield  |                    | 4.4                            | 4.4                         | pf              |
| Plate to Cathode, Heater, and Internal Shield |                    | 3                              | 4                           | pf              |
| Grid to Heater                                |                    | 0.28 max                       | 0.28 max                    | pf              |
| Plate to Cathode                              |                    | 0.24                           | 0.24                        | pf              |
| Cathode to Grid                               |                    | 3.1                            | 3.1₄                        | pf              |
| Heater to Cathode                             |                    | 2.5                            | 2.54                        | pf              |

<sup>\*</sup> With external shield connected to cathode except as noted.

A With external shield connected to ground.

| CI | ass | A, | Amp | lifier |
|----|-----|----|-----|--------|
|    |     |    |     |        |

| Class A, Amplitier                                       |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Center Values):                  |          |       |
| Plate Voltage  | 250 max  | volts |
| Grid Voltage, Negative-bias value                        | - 50 max | volts |
| Cathode Current  | 20 max   | ma    |
| Plate Dissipation  | 2.2 max  | watts |
| CHARACTERISTICS:   |          |       |
| Plate Voltage  | 200      | volts |
| Grid Voltage   | -1.2     | volts |
| Amplification Factor                                     | 80       |       |
| Plate Resistance Approx.)                                | 8000     | ohms  |
| Transconductance   | 10500    | μmhos |
| Plate Current  | 10       | ma    |
| Grid Voltage (Approx.) for transconductance of 500 µmhos | 3.8      | volts |
| Grid Voltage (Approx.) for transconductance of 100 µmhos | -5.6     | volts |

### **MAXIMUM CIRCUIT VALUES:**


Grid Circuit Resistance ......

1 max megohm

### HIGH-MU TRIODE

6ES5

Miniature type used as grounded-cathode rf amplifier in vhf television receivers. Outline 5C, Outlines section. Tube requires miniature sevencontact socket and may be operated in any position.



| Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage:              | 6.3<br>0.2         | volts<br>ampere |
|---|--------------------|-----------------|
| Heater negative with respect to cathode Heater positive with respect to cathode | 100 max<br>100 max | volts<br>volts  |

| Direct Interelectrode Capacitances: Grid to Plate           | Without<br>External<br>Shield<br>0.5 max<br>3.2<br>3.2 | With<br>External<br>Shield<br>0.5 max<br>3.2<br>4 | pf<br>pf<br>pf |
|---|--|---|----------------|
| Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values): |  |   |                |
| Plate Voltage   |  | 250 max   | volts          |
| Grid Voltage, Positive-bias value                           |  | 0 max   | volts          |
| Cathode Current   |  | 22 max  | ma             |
| Plate Dissipation   |  | 2.2 max   | watts          |
| CHARACTERISTICS:  |  |   |                |
| Plate Voltage   |  | 200   | volts          |
| Grid Voltage  |  | <b>—1</b>   | volt           |
| Amplification Factor  |  | 75  |                |
| Plate Resistance (Approx.)                                  |  | 8000  | ohms           |
| Transconductance  |  | 9000  | μmhos          |
| Plate Current   |  | 10  | ma             |
| Grid Voltage (Approx.) for plate current of 100 μa          |  | <b>—6</b>   | volts          |

MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance ......

### **VARIABLE-MU TWIN TRIODE**

Miniature type with high transconductance, variable mu, and low noise; used as cascode-type amplifier in tuners of television receivers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and

6ES8
Related type:
4ES8

1 max megohm

volts

may be operated in any position. Type 4ES8 is identical with type 6ES8 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) | 4ES8<br>4<br>0.6<br>11 | 6ES8<br>6.3<br>0.365 | volts<br>ampere<br>seconds |
|---|------------------------|----------------------|----------------------------|
|   | Without<br>External    | With<br>External     |                            |
| Direct Interelectrode Capacitances:                                 | Shield                 | Shield*              |                            |
| Grid to Plate (Each Unit)   | 1.9                    | 1.9                  | pf                         |
| Plate to Cathode (Each Unit)  | 0.18                   | 0.17                 | pf                         |
| Heater to Cathode (Each Unit)                                       | 3                      | 3△                   | pf                         |
| Plate of Unit No.2 to Plate of Unit No.1                            | 0.04 max               | 0.015 max            | pf                         |
| Plate of Unit No.2 to Grid of Unit No.1                             | 0.003 max              | 0.003 max            | pf                         |
| Grid of Unit No.1 to Cathode of Unit No.2                           | 0.002 max              | 0.002 max            | pf                         |

- \* With external shield connected to cathode of unit under test except as noted.
- △ With external shield connected to ground.

### Class A, Amplifier (Each Unit)

| . 90    | 90                               | 90                                | volts                                  |
|---------|----------------------------------|-----------------------------------|--|
| . —1.2  | <b>—5</b>                        | 9                                 | volts                                  |
| . 2500  | -                                | _                                 | ohms                                   |
| . 12500 | 625                              | 125                               | $\mu$ mhos                             |
| . 15    | -                                | _                                 | ma                                     |
|         | . 90<br>1.2<br>. 2500<br>. 12500 | 1.2 -5<br>. 2500 -<br>. 12500 625 | 1.2 -5 -9<br>. 2500<br>. 12500 625 125 |

### Cascode-Type Amplifier

| MUMIXAN     | RATINGS (Design-Center Values):    |         |
|-------------|------------------------------------|---------|
| late Supply | Voltage with plate current of 0 ma | 550 mas |

| Plate Voltage (Each unit) Grid Voltage, Negative-bias value (Each unit) Cathode Current (Each unit) Plate Dissipation (Each unit) Heater-Cathode Voltage: | 130<br>-50<br>22<br>1.8 |     | volts<br>volts<br>ma<br>watts |
|---|-------------------------|-----|-------------------------------|
| Unit No.1:°  RMS voltage between cathode and heater   | 50                      | max | volts                         |
| Unit No.2:  |                         |     |                               |
| RMS voltage between cathode and heater•   | 50                      | max | volts                         |
| DC voltage between cathode and heater   | 130                     | max | volts                         |
| In a cascode-type circuit with the grid of the TYPICAL OPERATION: output unit connected to a voltage divider  |                         |     |                               |
| Supply Voltage  | 180                     |     | volts                         |
| Plate Current   | 15                      |     | ma                            |
| Transconductance  | 12500                   |     | $\mu$ mhos                    |
| Noise Figure*   | 6.5                     |     | db                            |
| Grid Voltage (Approx.) for transconductance of 125 µmhos  | 9                       |     | volts                         |
| transconductance of 125 µmhos   | 500                     |     | mv                            |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance (Each unit)   | 1 :                     | max | megohm                        |

<sup>°</sup> Grounded-cathode input unit-pins 6, 7, and 8.

- = Grounded-grid output unit-pins 1, 2, and 3.
- Cathode positive with respect to heater.


□ In order not to exceed the maximum-rated plate voltage when the cascode-type amplifier is controlled it is necessary to use a voltage divider for the grid of the grounded-grid output unit.

\* Measured with tube operating in a television tuner.

### HIGH-MU TWIN TRIODE

# **6EU7**

Miniature type used in high-gain, resistance-coupled, low-level audio-amplifier applications where low-hum and non-microphonic characteristics are important considerations, such as in microphone amplifiers and in pre-



volts

amplifiers for mono- and stereophonic phonographs. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.


| Heater Voltage (ac/dc)  | 6.3                | volts  |
|---|--------------------|--------|
| Heater Current  | 0.3                | атреге |
| Peak Heater-Cathode Voltage:  |                    | -      |
| Heater negative with respect to cathode   | 200 max            | volts  |
| Heater positive with respect to cathode   | 200 max            | volts  |
| Direct Interelectrode Capacitances (Each Unit, Approx.):                          |                    |        |
| Grid to Plate   | 1.5                | pf     |
| Grid to Cathode and Heater  | 1.6                | pf     |
| Plate to Cathode and Heater   | 0.2                | pf     |
| Equivalent Noise and Hum Voltage (Referenced to Grid, Each Unit):  Average Value* | 1.8 microvolts rms |        |

The dc component must not exceed 100 volts.

<sup>•</sup> Measured in "true rms" units under the following conditions: Heater volts (ac), 6.3; center-tap of heater transformer grounded; plate supply volts, 250; plate load resistor, 100000 ohms; cathode resistor, 2700 ohms; cathode bypass capacitor, 100  $\mu$ f; grid resistor, 0 ohms; amplifier frequency range, 25 to 10000 cps.

| CI  | ass | $A_1$ | Amplii | fier ( | Each | 1 Unit) |  |
|-----|-----|-------|--------|--------|------|---------|--|
| D ! | 3 6 |       | . 37-1 |        |      |         |  |

| Grid Voltage: Negative-bias value | <b>.</b> | —55 max | volts |
|-----------------------------------|----------|---------|-------|
| Positive-bias value               |          | 0 max   | watts |
| Plate Dissipation                 |          | 1.2 max | watts |
| CHARACTERISTICS:                  |          |         |       |
| Plate Voltage                     | 100      | 250     | volts |
| Grid Voltage                      | -1       | 2       | volts |
| Amplification Factor              | 100      | 100     |       |
| Plate Resistance (Approx.)        | 80000    | 62500   | ohms  |
| Transconductance                  | 1250     | 1600    | μmhos |
| Plate Current                     | 0.5      | 1.2     | ma    |



# P<sub>T</sub>. 3 (C<sub>p</sub>) (C<sub>p</sub>)

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined triode oscillator and pentode mixer in television receivers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Type 5EU8 is

6EU8
Related type: 5EU8

identical with type 6EU8 except for the heater ratings, as shown below.

5EU8 6EU8

| Heater Voltage (ac/dc)   | 4.7         | 6.3          | volts   |
|--|-------------|--------------|---------|
| Heater Current   | 0.6         | 0.45         | ampere  |
| Heater Warm-up Time (Average) Peak Heater-Cathode Voltage:                           | 11          | 11           | seconds |
| Heater negative with respect to cathode  | 200 max     | 200 max      | volts   |
| Heater positive with respect to cathode  The dc component must not exceed 100 volts. | 200°max     | 200°max      | volts   |
| MAXIMUM RATINGS (Design-Center Values):  | Triode Unit | Pentode Unit | :       |
| Plate Voltage  | 330 max     | 330 max      | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage   |             | 330 max      | volts   |
| Grid-No.2 Voltage  |             | See curve    | page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value                                | 0 max       | 0 max        | volts   |
| Plate Dissipation  | 3 max       | 3.1 max      | watts   |
| For grid-No.2 voltages up to 165 volts   |             | 0.55 max     | watt    |
| For grid-No.2 voltages between 165 and 330 volts CHARACTERISTICS:                    |             | See curve    |         |
| Plate Supply Voltage   | 150         | 125          | volts   |
| Grid-No.2 Supply Voltage   | 1.70        | 125          | voits   |
| one the bappy tokage   | _           | 127          | 40172   |

| Grid-No.1 Voltage                                      | -    | 1             | volt    |
|--|------|---------------|---------|
| Cathode-Bias Resistor                                  | 56   | -             | ohms    |
| Amplification Factor                                   | 40   | <del></del> . |         |
| Plate Resistance (Approx.)                             | 5000 | 80000         | ohms    |
| Transconductance                                       | 8500 | 6400          | μmhos   |
| Grid-No.1 Voltage (Approx.) for plate current of 10 μa | -12  | -9            | volts   |
| Plate Current  | 18   | 12            | ma      |
| Grid-No.2 Current                                      |      | 4             | ma      |
| Cathode Warm-up Time                                   | 35   | -             | seconds |

### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance

0.1 max


0.1 max megohm

• The cathode warm-up time is defined as the time required for the transconductance to reach 6500  $\mu$ mhos when the tube is operated from a cold start with dc plate volts = 100, grid volts = 0, and heater volts = 5.5.

### SHARP-CUTOFF TETRODE

# 6EV5

Miniature type used as rf amplifier in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be operated in any position.



| Heater Voltage (ac/dc)                                       | 6.3       | volts  |
|--|-----------|--------|
| Heater Current   | 0.2       | ampere |
| Peak Heater-Cathode Voltage:                                 |           |        |
| Heater negative with respect to cathode                      | 100 max   | volts  |
| Heater positive with respect to cathode                      | 100°max   | volts  |
| Direct Interelectrode Capacitances:                          |           |        |
| Grid No.1 to Plate   | 0.035 max | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Internal Shield | 4.5       | pf     |
| Plate to Cathode, Heater, Grid No.2, and Internal Shield     | 2.9       | pf     |
| <sup>6</sup> The dc component must not exceed 50 volts       |           |        |

a With external shield connected to cathode.


| Class A, Amplifier                                    |           |         |
|---|-----------|---------|
| MAXIMUM RATINGS (Design-Maximum Values):              |           |         |
| Plate Voltage   | 275 max   | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage                | 180 max   | volts   |
| Grid-No.2 Voltage                                     | See curve | page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max     | volts   |
| Cathode Current                                       | 20 max    | ma      |
| Grid-No.2 Input:                                      |           |         |
| For grid-No.2 voltages up to 90 volts                 | 0.2 max   | watt    |
| For grid-No.2 voltages between 90 and 180 volts       | See curve | page 75 |
| Plate Dissipation                                     | 3.25 max  | watts   |
| CHARACTERISTICS:                                      |           |         |
| Plate Voltage   | 250       | volts   |

## Plate Voltage .....

| Grid-No.2 Voltage   | 80   | volts  |
|---|------|--------|
| Grid-No.1 Voltage   | -1   | megohm |
| Plate Resistance (Approx.)                                    | 0.15 | megohm |
| Transconductance  | 8800 | μmhos  |
| Plate Current   | 11.5 | ma     |
| Grid-No.2 Current   | 0.9  | ma     |
| Grid-No.1 Voltage (Approx.) for transconductance of 100 µmhos | -4.5 | volts  |

0.5 max megohm


### HIGH-MU TWIN TRIODE



Miniature type used as a relay-control GT: tube in remote-control tuning units of television receivers. It is processed specifically for operation under standby conditions. Outline 6E, Outlines section. Tube requires miniature ninecontact socket and may be mounted in any position.

6EV7

| Heater Voltage (ac/dc) Heater Current  |           | 6.3<br>0.6         | volts<br>ampere |
|--|-----------|--------------------|-----------------|
| Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode |           | 200 max<br>200 max | volts           |
|  | Unit No.1 | Unit No.2          |                 |
| Grid to Plate  |           | 3.4                | pf              |
| Grid to Cathode and Heater   | 3         | 3                  | pf              |
| Plate to Cathode and Heater  | 0.33      | 0.23               | pf              |
| • The dc component must not exceed 100 volts.  |           |                    |                 |
| Class A, Amplifier (Eac  | h Unit)   |                    |                 |
| CHARACTERISTICS:   | •         |                    |                 |
| Plate Voltage  |           | 250                | volts           |
| Grid Voltage   |           | -2                 | volts           |
| Amplification Factor   |           | 60                 |                 |
| Plate Resistance (Approx.)   |           | 11500              | ohms            |
| Transconductance   |           | 5200<br>9.2        | μmhos           |
| Grid Voltage (Approx.) for plate current of 100 $\mu$ a  |           | 9.2<br>9           | ma<br>volts     |
|  |           | •                  | 1010            |
| Relay-Control Service (E: MAXIMUM RATINGS (Design-Maximum Values):   | ach Unit) |                    |                 |
| Plate Voltage  |           | 300 max            | volts           |
| Grid Voltage, Positive-bias value  |           | 0 max              | volts           |
| Cathode Current  |           | 20 max             | ma              |
| Plate Dissipation:   |           |                    |                 |
| When "on" time exceeds 30 seconds in any 2-minute When "on" time does not exceed 30 seconds in a             |           | 2.5 max            | watts           |
| interval   |           | 4.5 max            | watts           |




| TYPICAL OPERATION WITH 2500-OHM-RELAY LOAD: With "on" time in any 2-minute interval: Plate Supply Voltage Zero-bias Plate Current | 30 seconds<br>or less<br>250<br>18.5 | More than<br>30 seconds<br>150<br>10 | volts<br>ma |
|---|--------------------------------------|--------------------------------------|-------------|
| Grid Voltage (Approx.) for plate current of 100 $\mu a$   | <b>-9</b>                            | 5                                    | volts       |
| MAXIMUM CIRCUIT VALUE:  |                                      |                                      |             |

### SHARP-CUTOFF PENTODE

Related types: 4EW6, 5EW6

Grid-Circuit Resistance ......

Miniature type used in the gain-controlled picture-if stages of vhf television receivers operating at an intermediate frequency in the order of 40 megacycles per second. This tube features controlled plate-current cutoff



6EW6

3.9 max megohms

and high transconductance (1400 µmhos) combined with low interelectrode capacitance values. Tube is provided with separate base pins for grid No.3 and cathode to permit the use of an unbypassed cathode resistor to minimize changes in input conductance and input capacitance with bias, without causing oscillation. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Types 4EW6 and 5EW6 are identical with type 6EW6 except for the heater ratings, as shown below.

4EW6

5EW6


| Heater Voltage (ac/dc)                      | 4.2     | 5.6       | 6.3      | volts   |
|---|---------|-----------|----------|---------|
| Heater Current                              | 0.6     | 0.45      | 0.4      | ampere  |
| Heater Warm-up Time (Average)               | 11      | 11        | _        | seconds |
| Peak Heater-Cathode Voltage:                |         |           |          |         |
| Heater negative with respect to cathode     | 200 ma  | x 200 max | 200 max  | volts   |
| Heater positive with respect to cathode     | 200 ma: | x 200*max | 200 max  | volts   |
| • .   |         | Without   | With     |         |
|   |         | External  | External |         |
| Direct Interelectrode Capacitances:         |         | Shield    | Shield*  |         |
| Grid No.1 to Plate                          |         | 0.04 max  | 0.03 max | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2,    | Grid    |           |          | •       |
| No.3 and Internal Shield                    |         | 10        | 10       | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid 1 | No.3.   |           |          | •       |
| and Internal Shield                         |         | 2.4       | 3.4      | pf      |
| The dc component must not exceed 100 volts. |         |           |          |         |

- With external shield connected to cathode.

### Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):              |                   |         |
|---|-------------------|---------|
| Plate Voltage   | 330 max           | volts   |
| Grid No.3 (Suppressor-Grid) Voltage, Positive value   | 0 max             | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage                | 330 max           | volts   |
| Grid-No.2 Voltage                                     | See curve         | page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max             | volts   |
| Plate Dissipation                                     | 3.1 max           | watts   |
| Grid-No.2 Input:                                      |                   |         |
| For grid-No.2 voltages up to 165 volts                | 0.65 max          | watt    |
| For grid-No.2 voltages between 165 and 330 volts      | See curve page 75 |         |
| CHARACTERISTICS:                                      |                   |         |

| Plate Supply Voltage  |       | 125           | voits        |
|---|-------|---------------|--------------|
| Grid No.3   | Conne | cted to catho | de at socket |
| Grid-No.2 Supply Voltage                                    |       | 125           | volts        |
| Cathode-Bias Resistor                                       |       |               | ohms         |
| Plate Resistance (Approx.)                                  |       |               | megohm       |
| Transconductance  |       | 14000         | $\mu$ mhos   |
| Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu$ a |       | -3.5          | volts        |
| Plate Current   |       | 11            | ma           |
| Grid-No.2 Current   |       | 3.2           | ma           |



### **DUAL TRIODE**

Neonoval type used as combined vertical-deflection oscillator and verticaldeflection amplifier in television re-<sub>K<sub>T1</sub></sub> ceivers. Outline 10C, **Outlines** section. Tube requires neonoval nine-contact socket and may be operated in any

**6EW7** 

volts

volts

position. For curve of average plate characteristics, Unit No.1, refer to type 6DE7 (Unit No.1).

|           | 6.3                     | volts  |
|-----------|-------------------------|--------|
|           | 0.9                     | ampere |
|           |                         | -      |
|           | 200 max                 | volts  |
|           | 200°max                 | volts  |
| Unit No.1 | Unit No.2               |        |
| 4.2       | 9                       | pf     |
| 2.2       | 7                       | pf     |
| 0.4       | 1.2                     | pf     |
|           | Unit No.1<br>4.2<br>2.2 |        |

• The dc component must not exceed 100 volts.

| Ciass A, Amplifie                                       | ſ         |                |            |
|---|-----------|----------------|------------|
| CHARACTERISTICS:  | Unit No.1 | Unit No.2      |            |
| Plate Voltage   | 250       | 150            | volts      |
| Grid Voltage  | -11       | <b>—17.5</b>   | volts      |
| Amplification Factor                                    | 17.5      | 6              |            |
| Plate Resistance (Approx.)                              | 8750      | 800            | ohms       |
| Transconductance  | 2000      | 7500           | $\mu$ mhos |
| Grid Voltage (Approx.) for plate current of 10 μa       | 20        | _              | volts      |
| Grid Voltage (Approx.) for plate current of 100 $\mu$ a | -         | <del>4</del> 0 | volts      |
| Plate Current   | 5.5       | 45             | ma         |
| Plate Current for plate voltage of 60 volts and zero    |           |                |            |
| grid voltage  | _         | 95             | ma         |
| Plate Current for grid voltage of -25 volts             | _         | 8              | ma         |


### Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

|                 |       | •         |      |        |     | Unit No.1  |
|-----------------|-------|-----------|------|--------|-----|------------|
| IAXIMUM RATINGS | (Desi | ign-Maxim | um V | 'alues | s): | Oscillator |
|                 |       |           |      |        |     | A 4 A      |

Unit No.2 Amplifier DC Plate Voltage . 330 max 330 max Peak Positive-Pulse Plate Voltage ..... 1500 max

| Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation              | Unit No.1<br>Oscillator<br>—400 max<br>77 max<br>22 max<br>1.5 max | Unit No.2<br>Amplifier<br>-250 max<br>175 max<br>50 max<br>10 max | volts<br>ma<br>ma<br>watts |
|--|--|---|----------------------------|
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance: For cathode-bias operation For grid-resistor-bias operation | 2.2 max<br>2.2 max   | 2.2 max n<br>2.2 max n  |                            |

• The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.



6EX6


### BEAM POWER TUBE

Renewal type; see chart at end of section for tabulated data.

## **BEAM POWER TUBE**

Related type: 7EY6

Glass octal type used as vertical deflection amplifier in television receivers. Outline 13F, Outlines section. Tube requires octal socket and may be operated in any position. Type 7EY6 is identical with type 6EY6 ex-



cept for the heater ratings, as shown below.

|  | 6EY6               | 7EY6               |                |
|--|--------------------|--------------------|----------------|
| Heater Voltage (ac/dc)   | 6.3                | 7.2                | volts          |
| Heater Current   | 0.68               | 0.6                | ampere         |
| Heater Warm-up Time (Average)  | -                  | 11                 | seconds        |
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max<br>200•max | 200 max<br>200•max | volts<br>volts |
| ■ The dc component must not exceed 100 volts.  |                    |                    |                |

| lass | Am |  |  |
|------|----|--|--|
|      |    |  |  |
|      |    |  |  |
|      |    |  |  |

| Class A, Amplifier         |     |       |       |
|----------------------------|-----|-------|-------|
| CHARACTERISTICS:           |     |       |       |
| Plate Voltage              | 50  | 250   | volts |
| Grid-No.2 Voltage          | 250 | 250   | volts |
| Grid-No.1 Voltage          | 0   | 17.5  | volts |
| Plate Resistance (Approx.) | _   | 60000 | ohms  |

| Transconductance Grid-No.1 Voltage (Approx.) for plate current of 100 µa Plate Current Grid-No.2 Current |  | 4400<br>48<br>44<br>3 | μmhos<br>volts<br>ma<br>ma |
|--|--|-----------------------|----------------------------|
|--|--|-----------------------|----------------------------|

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

**Vertical Deflection Amplifier** 


| For operation in a 525-line, 30-frame system         |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):             |          |       |
| DC Plate Voltage                                     | 350 max  | volts |
| Peak Positive-Pulse Plate Voltage <sup>o</sup>       | 2500 max | volts |
| Grid-No.2 (Screen-Grid) Voltage                      | 300 max  | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | -250 max | volts |
| Peak Cathode Current                                 | 180 max  | ma    |
| Average Cathode Current                              | 60 max   | ma    |
| Plate Dissipation                                    | 11 max   | watts |
| Grid-No.2 Input                                      | 2.75 max | watts |
| Bulb Temperature (At hottest point)                  | 200 max  | °C    |

### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:

For fixed-bias operation 1 max megohm For cathode-bias operation 2.2 max megohms

The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.



### **BEAM POWER TUBE**

Glass octal type used as vertical deflection amplifier in television receivers. Outline 13F, Outlines section. Tube requires octal socket and may be operated in any position. Heater volts (ac/dc), 6.3; amperes, 0.8; peak

6EZ5

heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

| CHARACTERISTICS:  |      |       |       |
|---|------|-------|-------|
| Plate Voltage   | 60   | 250   | volts |
| Grid-No.2 Voltage                                       | 250  | 250   | volts |
| Grid-No.1 Voltage                                       | 0    | -20   | volts |
| Plate Resistance (Approx.)                              | -    | 50000 | ohms  |
| Transconductance  | _    | 4100  | μmhos |
| Grid-No.1 Voltage (Approx.) for plate current of 100 µa |      | 50    | volts |
| Plate Current   | 180● | 43    | ma    |
| Grid-No.2 Current                                       | 26•  | 3.5   | ma    |
|   |      |       |       |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

### **Vertical Deflection Amplifier**

For operation in a 525-line, 30-frame system

| WAANUUW KATINGS (Design-Waximum Values):             |          |       |
|--|----------|-------|
| DC Plate Voltage                                     | 350 max  | volts |
| Peak Positive-Pulse Plate Voltage <sup>o</sup>       | 2500 max | volts |
| Grid-No.2 (Screen-Grid) Voltage                      | 300 max  | volts |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage | -250 max | volts |
| Peak Cathode Current                                 | 260 max  | ma    |
| Average Cathode Current                              | 75 max   | ma    |
| Plate Dissipation                                    | 12 max   | watts |
| Grid-No.2 Input                                      | 2.75 max | watts |
| Bulb Temperature (At hottest point)                  | 200 max  | °C    |
|  |          |       |

The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

### MAXIMUM CIRCUIT VALUES:


| id-No. | 1-Circuit  | Resistance: |
|--------|------------|-------------|
| For    | fived_hiss | operation   |

| For fixed-bias operation   | 1 max megohm    |
|----------------------------|-----------------|
| For cathode-bias operation | 2.2 max megohms |

### HIGH-MU TRIPLE TRIODE

6EZ8

Miniature type used in oscillator-mixer and afc service in FM receivers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket 673 and may be operated in any position. Heater volts (ac/dc), 6.3; amperes,



0.45; peak heater-cathode volts, 100.

| Class A | , Amplifie | r (Each | Unit | Unless | Otherwise | Specified) |
|---------|------------|---------|------|--------|-----------|------------|
|         |            |         |      |        |           |            |

| MAXIMUM RATINGS (Design-Maximum Values):               | •       |       |
|--|---------|-------|
| Plate Voltage  | 330 max | volts |
| Grid Voltage:  |         |       |
| Negative-bias value                                    | 50 max  | volts |
| Positive-bias value                                    | 0 max   | volts |
| Plate Dissipation                                      | 2 max   | watts |
| Total Plate Dissipation (All plates)                   | 5 max   | watts |
| CHARACTERISTICS:                                       |         |       |
| Plate Voltage  | 125     | voits |
| Grid Voltage   | 1       | volt  |
| Amplification Factor                                   | 57      |       |
| Plate Resistance (Approx.)                             | 13600   | ohms  |
| Transconductance                                       | 4200    | µmhos |
| Grid Voltage (Approx.) for plate current of 20 $\mu a$ | -4      | volts |
| Plate Current  | 4.2     | ma    |
|  |         |       |

6**F**5

### HIGH-MU TRIODE

Renewal type: see chart at end of section for tabulated data.

6F5GT

## HIGH-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

### **POWER PENTODE**

**6F6** 

Metal type used in the audio output stage of ac receivers. This tube is capable of large power output with relatively small input voltage. Outline 2B, Outlines section. Tube re-



quires octal socket and may be NC 666-GT G3
mounted in any position. It is especially important that this tube, like other powerhandling tubes, be adequately ventilated. Heater volts (ac/dc), 6.3; amperes, 0.7; peak heater-cathode volts, 90.

### Class A, Amplifier

|  | Pentode    | Triode                  |       |
|--|------------|-------------------------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): | Connection | Connection <sup>4</sup> |       |
| Plate Voltage                            | 375 max    | 350 max                 | volts |
| Grid-No.2 (Screen-Grid) Voltage          | 285 max    | _                       | volts |
| Plate Dissipation                        | 11 max     | 10 max                  | watts |
| Grid-No.2 Input                          | 3.75 max   | _                       | watts |

| THE CALL OPENATION.              |       | tode<br>rection | Triode<br>Connection |               |
|----------------------------------|-------|-----------------|----------------------|---------------|
| TYPICAL OPERATION:               |       |                 |                      |               |
| Plate Voltage                    | 250   | 285             | 250                  | volts         |
| Grid-No.2 Voltage                | 250   | 285             | _                    | volts         |
| Grid-No.1 (Control-Grid) Voltage | -16.5 | 20              | -20                  | volts         |
| Peak AF Grid-No.1 Voltage        | 16.5  | 20              | 20                   | volts         |
| Zero-Signal Plate Current        | 34    | 38              | 31                   | ma            |
| Maximum-Signal Plate Current     | 36    | 40              | 34                   | ma            |
| Zero-Signal Grid-No.2 Current    | 6.5   | 7               | _                    | ma            |
| Maximum-Signal Grid-No.2 Current | 10.5  | 13              | -                    | ma            |
| Amplification Factor             | _     | -               | 6.8                  |               |
| Plate Resistance (Approx.)       | 80000 | 78000           | 2600                 | ohms          |
| Transconductance                 | 2500  | 2550            | 2600                 | μ <b>mhos</b> |
| Load Resistance                  | 7000  | 7000            | 4000                 | ohms          |
| Total Harmonic Distortion        | 8     | 9               | 6.5                  | per cent      |
| Maximum-Signal Power Output      | 3.2   | 4.8             | 0.85                 | watts         |

<sup>\*</sup> Grid No.2 connected to plate.

### Push-Pull Class A. Amplifier

MAXIMUM RATINGS: (Same as for class A1 amplifier)

| TYPICAL OPERATION (Values are for two tubes): |       |          |
|---|-------|----------|
| Plate Voltage                                 | 315   | volts    |
| Grid-No.2 Voltage                             | 285   | volts    |
| Grid-No.1 (Control-Grid) Voltage              | -24   | volts    |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage        | 48    | volts    |
| Zero-Signal Plate Current                     | 62    | ma       |
| Maximum-Signal Plate Current                  | 80    | ma       |
| Zero-Signal Grid-No.2 Current                 | 12    | ma       |
| Maximum-Signal Grid-No.2 Current              | 19.5  | ma       |
| Effective Load Resistance (Plate-to-plate)    | 10000 | ohms     |
| Total Harmonic Distortion                     | 4     | per cent |
| Maximum-Signal Power Output                   | 11    | watts    |

### MAXIMUM CIRCUIT VALUES:

Grid-No.1 Circuit Resistance:

For fixed-bias operation 0.1 max megohm
For cathode-bias operation 0.5 max megohm

### POWER PENTODE

Renewal types; see chart at end of section for tabulated data.

### LOW-MU TRIODE— REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

### MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

### DIODE—SHARP-CUTOFF, TWIN-PLATE TETRODE

PD 3 S GITR
NC 2 PATR

Miniature type used in frequencydivider and complex-wave generator circuits of electronic musical instruments. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position.


6FA7


6F6G 6F6GT

6F7

6F8G

| 200   | RG21 Receiving                          | 1 400 11                    | 14/PWWP                  |
|---|---|-----------------------------|--------------------------|
| Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage:  |   | 6.3<br>0.3                  | volts<br>ampere<br>volts |
| Heater negative with respect to cathode Heater positive with respect to cathode Direct Interelectrode Capacitances: Tetrode Unit: |   | 200 max<br>200•max          | volts                    |
| Grid No.1 to Plate A Grid No.1 to Plate B Grid No.1 to Cathode, Heater, Grid No.2   | and Internal Chiefs                     | 0.040<br>0.030 max<br>5.5   |                          |
| Plate A to Cathode, Heater, Grid No.2, a Plate B to Cathode, Heater, Grid No.2, a Tetrode Grid No.1 to Diode Plate                | and Internal Shield                     | 1.8<br>1.8                  | pf<br>pf<br>pf           |
| Tetrode Grid No.1 to Diode Plate  Tetrode Plate A to Diode Plate  Tetrode Plate B to Diode Plate                                  |   | 0.022<br>0.020 max<br>0.055 | pf<br>pf<br>pf           |
| • The dc component must not exceed 100 vol  | ts.                                     |                             |                          |
| Class A   | , Amplifier                             |                             |                          |
| CHARACTERISTICS (Tetrode Unit): Plate A and Plate   | B connected together                    |                             |                          |
| Plate Voltage   |   | 100                         | volts                    |
| Grid-No.2 Voltage   |   | 100                         | volts                    |
| Grid-No.1 Supply Voltage  |   | 0<br>2.2                    | volts<br>megohms         |
| Plate Resistance (Approx.)  |   | 90000                       | ohms                     |
| Transconductance  |   | 3200                        | μmhos                    |
| Plate Current   |   | 3.8                         | ma                       |
| Grid-No.2 Current   |   | 1.7                         | ma                       |
| Grid-No.1 Voltage (Approx.) for plate current   | t of 20 μa                              | -4                          | volts                    |
| Using either Plate A or B   |   | ded                         |                          |
| Plate Voltage   |   | 100<br>100                  | volts<br>volts           |
| Grid-No.2 Voltage   |   | 0                           | volts                    |
| Grid-No.1 Resistor (Bypassed)   |   | 2.2                         | megohms                  |
| Plate Resistance (Approx.)  |   | 130000                      | ohms                     |
| Transconductance  |   | 1900                        | $\mu$ mhos               |
| Plate Current   |   | 2.2                         | ma                       |
| Grid-No.2 Current   |   | 3                           | ma                       |
|   | Complex-Wave Genera                     | tor                         |                          |
| MAXIMUM RATINGS (Design-Maximum V   |   |                             |                          |
| Plate-A Voltage   |   | 330 max                     |                          |
| Plate-B Voltage   |   | 330 max<br>330 max          |                          |
| Grid-No.2 Voltage   |   |                             | e page 75                |
| Grid-No.1 (Control-Grid) Voltage:   |   |                             | _                        |
| Negative-bias value   |   | —50 max                     |                          |
| Positive-bias value   |   | 0 max                       | volts                    |
| Plate-A Dissipation   | • | 1.5 max<br>1.5 max          |                          |
| Grid-No.2 Input:  | • | 1.5 Illax                   | watts                    |
| For grid-No.2 voltages up to 165 volts.   |   | 0.65 max                    |                          |
| For grid-No.2 voltages between 165 and  | 330 VOITS                               | See curv                    | e page 75                |
| MAXIMUM CIRCUIT VALUES: Grid-No.1 Circuit Resistance:   |   |                             |                          |
| For grid-No.1 resistor-bias operation.  |   | 2.2 max                     | megohms                  |
| Dio   | de Unit                                 |                             |                          |
| MAXIMUM RATINGS (Design-Maximum V   |   |                             |                          |
| Plate Current   |   | 1 max                       | ma                       |
| CHARACTERISTICS Instantaneous 37.1  |   |                             |                          |
| CHARACTERISTICS, Instantaneous Value:<br>Tube Voltage Drop for plate current of 2 n   | 1a                                      | 10                          | volts                    |
|   |   |                             |                          |





### **DUAL TRIODE**

Glass type containing high-mu and low-mu triode units used as combined vertical-deflection oscillator and vertical-deflection amplifier in television receivers. Outline 10B, Outlines section. Tube requires miniature nine-

Related type: 13FD7

Unit No.2

contact socket and may be mounted in any position. Type 13FD7 is identical with type 6FD7 except for the heater ratings, as shown below.

|   | 6FD7    | 13FD7   |         |
|---|---------|---------|---------|
| Heater Voltage (ac/dc)                        | 6.3     | 13      | volts   |
| Heater Current                                | 0.925   | 0.45    | ampere  |
| Heater Warm-up Time (Average)                 |         | 11      | seconds |
| Peak Heater-Cathode Voltage:                  |         |         |         |
| Heater negative with respect to cathode       | 200 max | 200 max | volts   |
| Heater positive with respect to cathode       | 200 max | 200 max | volts   |
| • The dc component must not exceed 100 volts. |         |         |         |

| Class A, Amplifie                                 | r          |       |         |               |
|---|------------|-------|---------|---------------|
| CHARACTERISTICS:                                  | Unit No.1  | Uni   | t No.2  |               |
| Plate Voltage                                     | 250        | 60    | 150     | volts         |
| Grid Voltage                                      | <b>—</b> 3 | 0     | -17.5   | volts         |
| Amplification Factor                              | 64         | _     | 6       |               |
| Plate Resistance (Approx.)                        | 40000      |       | 800     | ohms          |
| Transconductance                                  | 1600       | _     | 7500    | μmhos         |
| Plate Current                                     | 1.5        | 950   | 40      | ma            |
| Grid Voltage (Approx.):                           |            |       |         |               |
| For plate current of 10 $\mu$ a                   | 5.5        |       | _       | volts         |
| For plate current of 100 $\mu a$                  |            |       | 40      | volts         |
| Transconductance, for plate current of 1 ma       | _          |       | 500     | μmhos         |
| Plate Current, for grid voltage of -25 volts      | _          |       | 6       | ma            |
| OThis value can be measured by a method involving |            | ***** | oform . | such that the |

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

### Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system Unit No.1

| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator | Amplifier |       |
|--|------------|-----------|-------|
| DC Plate Voltage                         | 330 max    | 330 max   | volts |
| Peak Positive-Pulse Plate Voltage        |            | 1500 max  | volts |
| Peak Negative-Pulse Grid Voltage         | 400        | -250 max  | volts |
| Peak Cathode Current                     | 70 max     | 175 max   | ma    |


| 202  |   |  |  |  |                                  |
|--|---|--|--|--|----------------------------------|
| Average Cathode Currer   |   |  | Unit No.1<br>Oscillator<br>20 max<br>1.5 max                                       | Unit No.2<br>Amplifier<br>50 max<br>10 max | ma<br>watts                      |
| MAXIMUM CIRCUIT Grid-Circuit Resistance: For grid-resistor-bias                          | VALUES:<br>s or cathode-bias oper                 | ation  | 2.2 max  | 2.2 max                                    | megohms                          |
| The duration of the vo<br>In a 525-line, 30-frame  | oltage pulse must not e<br>system, 15 per cent of | xceed 15 pe<br>one vertica   | r cent of one value of cycles  | ertical scanni<br>le is 2.5 mill           | ng cycle.<br>iseconds.           |
|  | BEAM PO   | WER TU   | BE   | 6 <sub>2</sub> (6)                         | <b>i</b> 1                       |
| 6FE5 Related type: 50FE5  high power output a section. Tube require 50FE5 is identical w | es octal socket and                               | ompact ste in radio a ibe has h plate an an deliver ite load re may be | reophonic nd televi- igh sensi- H d screen- relatively esistance. Out mounted in a | line 13G, cany position                    | n. Type                          |
| Heater Voltage (ac/dc)<br>Heater Current<br>Peak Heater-Cathode V                        |   |  | 6FE5<br>6.3<br>1.2   | 50FE5<br>50<br>0.15                        | volts<br>ampere                  |
| Heater positive with<br>Direct Interelectrode Ca<br>Grid No.1 to Plate                   |   |  |  | 200 max<br>200•max<br>0.44                 | volts<br>volts<br>pf             |
| Plate to Cathode, H  | de, Heater, Grid No.2<br>leater, Grid No.2, and   | Grid No.3  |  | 15<br>9                                    | pf<br>pf                         |
| • The dc component mu  |   | s.<br>Amplifier  | ,  |  |                                  |
| MAXIMUM RATINGS Plate Voltage Grid-No.2 (Screen-Grid) Grid-No.2 Input Plate Dissipation  | (Design-Maximum Va                                | lues):   |  | 175 max<br>175 max<br>2.4 max<br>14.5 max  | volts<br>volts<br>watts<br>watts |
| TYPICAL OPERATION  |   | xed Bias   | Cathod   |  |                                  |
| Plate Supply Voltage Grid-No.2 Supply Volta  |   |  | 130<br>130   | 145<br>145                                 | volts<br>volts                   |
| Grid-No.1 (Control-Grid<br>Cathode-Bias Resistor   |   | 5 —16  | 120  | 150  | volts<br>ohms                    |
| Peak AF Grid-No.1 Vol  | Itage 12.   | 5 15   | 11.9   | 15.4                                       | volts                            |
| Zero-Signal Plate Curre<br>Maximum-Signal Plate C  |   | 2 80<br>4 100  | 88<br>90   | 86<br>86                                   | ma<br>ma                         |
| Zero-Signal Grid-No.2  |   | 4 4  | 5  | 4.2  | ma                               |
| Maximum-Signal Grid-N  | `   | 5 18   | 9  | 17   | ma                               |
| Plate Resistance (Appro<br>Transconductance  | ·····   |  | 8000<br>9500   | _  | ohms<br>µmhos                    |
| Load Resistance  |   |  | 1000   | 1000                                       | ohms                             |
| Total Harmonic Distorti<br>Maximum-Signal Power  |   |  | 10<br>3.5  | 13<br>4.3                                  | per cent<br>watts                |
|  | Push-Pull Cla                                     |  |  | •  |                                  |
| MAXIMUM RATINGS:   |   |  | p  |  |                                  |
| TYPICAL OPERATION  |   |  |  |  |                                  |
| Plate Supply Voltage . Grid-No.2 Supply Voltage  |   |  | 130<br>130   | 145<br>145                                 | volts<br>volts                   |
| Cathode-Bias Resistor  | 5 <b>v</b>  |  | 75   | 75   | ohms                             |
| Peak AF Grid-No.1-to-0   | Grid-No.1 Voltage                                 |  | 25.8   | 28.8                                       | volts                            |
| Zero-Signal Plate Curre<br>Maximum-Signal Plate  | nt<br>Current                                     | •••••  | 150<br>154   | 160<br>172                                 | ma<br>ma                         |


| Zero-Signal Grid-No.2 Current              | 7.2  | 8    | ma       |
|--|------|------|----------|
| Maximum-Signal Grid-No.2 Current           | 17   | 20   | ma       |
| Effective Load Resistance (Plate-to-plate) | 1600 | 1600 | ohms     |
| Total Harmonic Distortion                  | 6    | 6    | per cent |
| Maximum-Signal Power Output                | 7    | 8.5  | watts    |

### **MAXIMUM CIRCUIT VALUES:**

| Grid-No.1-Circuit Res | istance: |
|-----------------------|----------|
|-----------------------|----------|

| For fixed-bias operation   | 0.1 max | megohm |
|----------------------------|---------|--------|
| For cathode-bias operation | 0.5 max | megohm |






### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6FG7
Related type:
5FG7

Miniature type used as combined oscillator and mixer tube in vhf television receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be



mounted in any position. Type 5FG7 is identical with type 6FG7 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)                  | 5FG7<br>4.7 | 6FG7<br>6.3 | volts   |
|---|-------------|-------------|---------|
|   |             |             |         |
| Heater Current                          | 0.6         | 0.45        | ampere  |
| Heater Warm-up Time (Average)           | 11          | 11          | seconds |
| Peak Heater-Cathode Voltage:            |             |             |         |
| Heater negative with respect to cathode | 200 max     | 200 max     | volts   |
| Heater positive with respect to cathode | 200°max     | 200°max     | volts   |
|   |             |             |         |

<sup>\*</sup> The dc component must not exceed 100 volts.

### Class A, Amplifier

| Class A, Amplifier   |                        |      |                           |                     |
|--|------------------------|------|---------------------------|---------------------|
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage                   | Triode Unit<br>330 max | 33   | ode Uni<br>0 max<br>0 max | t<br>volts<br>volts |
| Grid-No.2 Voltage  |                        | See  | curve                     | page 75             |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value . Grid-No.2 Input: | 0 max                  |      | 0 max                     | volts               |
| For grid-No.2 voltages up to 165 volts                                   | _                      | 0.5  | 5 max                     | watt                |
| For grid-No.2 voltages between 165 and 330 volts.                        | -                      | Sec  | e curve                   | page 75             |
| Plate Dissipation  | 2.5 max                |      | 3 max                     | watts               |
| CHARACTERISTICS:   |                        |      |                           |                     |
| Plate Voltage  | 125                    | 100  | 125                       | volts               |
| Grid-No.2 Voltage  | -                      | 100  | 125                       | volts               |
| Grid-No.1 Voltage  | -1                     | 0    | -1                        | volts               |
| Amplification Factor   | 43                     | _    | _                         |                     |
| Plate Resistance (Approx.)   | 5700                   | _    | 180000                    | ohms                |
| Transconductance   | 7500                   | 7400 | 6000                      | $\mu$ mhos          |
| Plate Current  | 13                     | _    | 11                        | ma                  |
| Grid-No.2 Current  | <del>-</del>           | _    | 4                         | ma                  |
| Grid-No.1 Voltage (Approx.) for plate current                            |                        |      |                           |                     |
| of 30 μa   | 6.5                    | _    | 7.5                       | volts               |

### HIGH-MU TRIODE


6FH5
Related types: 2FH5, 3FH5


Miniature type used as an rf amplifier in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires seven-contact socket and may be mounted in any position. Types 2FH5 and 3FH5 are identical

with type 6FH5 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 0.6     | 3FH5<br>3<br>0.45<br>11 | 6FH5<br>6.3<br>0.2 | volts<br>ampere<br>seconds |
|--|---------|-------------------------|--------------------|----------------------------|
| Heater negative with respect to cathode  | 100 max | 100 max                 | 100 max            | volts                      |
| Heater positive with respect to cathode  | 100 max | 100 max                 | 100 max            | volts                      |

| Direct Interelectrode Capacitances (Approx.): Grid to Plate | Without<br>External<br>Shield<br>0.52<br>3.2<br>3.2 | With<br>External<br>Shield•<br>0.52<br>3.2<br>4 | pf<br>pf<br>pf |
|---|---|---|----------------|
| Class A, Amplifie   | 7   |   |                |
| MAXIMUM RATINGS (Design-Maximum Values):                    | •   |   |                |
| Plate Voltage   |   | 150 max   | volts          |
| Grid Voltage, Positive-bias value                           |   | 0 max   | volts          |
| Cathode Current   |   | 22 max  | ma             |
| Plate Dissipation   |   | 2.2 max   | watts          |
| CHARACTERISTICS:  |   |   |                |
| Plate Voltage   |   | 135   | volts          |
| Grid Voltage  |   | -1  | volts          |
| Plate Resistance (Approx.)                                  |   | 5600  | ohms           |
| Transconductance  |   | 9000  | μmhos          |
| Plate Current   |   | 11  | ma             |
| Grid Voltage (Approx.) for plate current of 100 $\mu$ a     |   | 5.5   | volts          |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance:            |   |   |                |
| For cathode-bias operation                                  |   | 1 max   | megohm         |





### MEDIUM-MU TRIODE— THREE-PLATE TETRODE


Miniature type used in complex-wave generator applications. Sharp-cutoff tetrode unit has pair of additional plates. Outline 6B, Outlines section. Tube requires nine-contact socket and may be mounted in any position.

6FH8

| Heater Voltage (ac/dc) Heater Current Direct Interelectrode Capacitances:         | 6.3<br>0.45 | volts<br>ampere |
|---|-------------|-----------------|
| Triode Unit: Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater | 2.6         | pf<br>pf<br>pf  |

| 200   |   |  |  |
|---|---|--|--|
| Tetrode Unit:   |   |  |  |
| Grid No.1 to Plate No.2   |   | 0.06 max   | pf   |
| Grid No.1 to Cathode, Heater, Grid No.2, Plate Plate No.1B  | No.1A, and  | 4.5  | pf   |
| Plate No.2 to Cathode, Heater, Grid No.2, Plate   |   |  | p.   |
| Plate No.1B   |   | 1.4  | pf   |
| Tetrode Grid No.1 to Triode Plate   |   | 0.35 max<br>0.008 max  | pf<br>pf   |
|   |   |  | •-   |
| * With external shield connected to cathode.  |   |  |  |
| Class A, Amplifie   |   |  |  |
| CHARACTERISTICS: Triode Unit  | •   |  |  |
| Plate Voltage   |   | 100  | volts  |
| Grid Voltage  |   | -1   | volt   |
| Amplification Factor  | · · · · · · · · · · · · · · · ·                           | 40   | . •  |
| Plate Resistance (Approx.) Transconductance   |   | 7400<br>5400   | ohms<br>µmhos  |
| Plate Current   |   | 7.9  | ma   |
| Grid Voltage (Approx.) for plate current of 100 µa  |   | <del>-7</del>  | volts  |
| Tetrode Unit with Plates No.1A and No.1B Com  |   | le at Socket   |  |
| Plate-No.2 Voltage  |   | 250  | volts  |
| Grid-No.2 Voltage   |   | 250  | volts  |
| Grid-No.1 Voltage   |   | -2   | volts  |
| Plate-No.2 Resistance (Approx.)   |   | 0.75<br>4400   | megohm   |
| Transconductance, Grid No.1 to Plate No.2   |   | 7.3  | μmhos<br>ma  |
| Grid-No.2 Current   |   | 1.4  | ma   |
| Grid-No.1 Voltage (Approx.) for plate-No.2 current of 100   | <b>μa</b>   | 7  | volts  |
|   |   |  |  |
|   |   |  |  |
| Complex-Wave Gener  | rator   |  |  |
| Complex-Wave Gener MAXIMUM RATINGS (Design-Maximum Values):   | rator<br>Triode Unit                                      | Tetrode Ui   | nit  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage  |   | _  | volts  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage  | Triode Unit   |  | volts<br>volts   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage  | Triode Unit   | 200 max<br>200 max   | volts<br>volts<br>volts  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage  | Triode Unit   | 200 max<br>200 max<br>275 max<br>275 max   | volts<br>volts<br>volts<br>volts<br>volts  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage  | Triode Unit   | 200 max<br>200 max<br>275 max<br>275 max   | volts<br>volts<br>volts<br>volts   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.12 Voltage Grid-No.1 (Control-Grid) Voltage:   | Triode Unit<br>275 max<br>—<br>—<br>—                     | 200 max<br>200 max<br>275 max<br>275 max<br>See curve  | volts<br>volts<br>volts<br>volts<br>volts<br>e page 75   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.2 Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value   | Triode Unit   | 200 max<br>200 max<br>275 max<br>275 max   | volts<br>volts<br>volts<br>volts<br>volts  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation  | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curve<br>-40 max<br>0 max  | volts  |
| MAXIMUM RATINGS (Design-Maximum Values):  Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0 max<br>0.3 max   | volts watts watt   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation  | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0 max<br>0.3 max<br>0.3 max  | volts volts volts volts volts volts e page 75  volts volts volts watts watt watt   |
| MAXIMUM RATINGS (Design-Maximum Values):  Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0 max<br>0.3 max   | volts watts watt   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Input: For grid-No.2 voltages up to 137.5 volts   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curve<br>-40 max<br>0 max<br>0.3 max<br>2.3 max<br>0.45 max  | volts volts volts volts volts volts volts volts volts watts watt watt watt watt  |
| MAXIMUM RATINGS (Design-Maximum Values):  Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.2 Dissipation Grid-No.2 Input:   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curve<br>-40 max<br>0 max<br>0.3 max<br>2.3 max<br>0.45 max  | volts watts watt watt watt   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  | Triode Unit 275 max — — — — — — — — — — — — — — — — — — — | 200 max<br>200 max<br>275 max<br>275 max<br>See curve<br>-40 max<br>0 max<br>0.3 max<br>2.3 max<br>0.45 max  | volts volts volts volts volts volts volts volts volts watts watt watt watt watt  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Input: For grid-No.2 voltages up to 137.5 volts   | Triode Unit 275 max — — — — — — — — — — — — — — — — — — — | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0 max<br>0.3 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curvo  | volts watts watt watt watt watt watt watt w  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curve<br>-40 max<br>0 max<br>0.3 max<br>2.3 max<br>0.45 max  | volts watts watt watt watt watt watt watt w  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE Of Plates-No.1A, No.1B, and No.2 Voltage Grid-No.2 Voltage   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0.3 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curvo<br>Tetrode Unit<br>100<br>50                              | volts watt watt watt watt watt vatt vatt vatt  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE Of Plates-No.1A, No.1B, and No.2 Voltage Grid-No.2 Voltage   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0.3 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curvo<br>Tetrode Unit<br>100<br>50<br>1                         | volts watts watt watt watt watt volts  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.1B Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE OF  | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curve<br>-40 max<br>0 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curve<br>Tetrode Unit<br>100<br>50<br>-1<br>0.04                  | volts watts watt watt watt  vatt vatt vatt vatt vat  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE OF Plates-No.1A, No.1B, and No.2 Voltage Grid-No.1 Voltage Grid-No.1 Voltage Plate-No.1A Current Plate-No.1B Current   | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0.3 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curvo<br>Tetrode Unit<br>100<br>50<br>1                         | volts watts watt watt watt watt volts  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.1B Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE OF Plates-No.1A, No.1B, and No.2 Voltage Grid-No.2 Voltage Grid-No.1 Voltage Plate-No.1B Current Plate-No.1B Current Plate-No.1B Current Plate-No.2 Current Grid-No.2 Current                             | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0.3 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curvo<br>Tetrode Unit<br>100<br>50<br>-1<br>0.04                | volts watt watt watt vatts volts |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE OF Plates-No.1A, No.1B, and No.2 Voltage Grid-No.1 Voltage Grid-No.1 Voltage Plate-No.1A Current Plate-No.1B Current Plate-No.1B Current Plate-No.2 Current Grid-No.2 Current Grid-No.2 Current Transconductance (Approx.):      | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0.3 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curvo<br>Tetrode Unit<br>100<br>50<br>-1<br>0.04<br>0.04<br>0.3 | volts watt watt watt vatt vatts volts volts volts volts volts volts volts volts volts ma ma ma   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE OF Plates-No.1A, No.1B, and No.2 Voltage Grid-No.1 Voltage Grid-No.1 Voltage Plate-No.1A Current Plate-No.1B Current Plate-No.1C Current Grid-No.2 Current Grid-No.2 Current Grid-No.2 Current Transconductance (Approx.): Grid No.1 to Plate No.1A | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0 max<br>0.3 max<br>0.3 max<br>0.45 max<br>See curvo<br>Tetrode Unit<br>100<br>50<br>-1<br>0.04<br>0.04<br>0.04  | volts watts watt watt watt volts ma ma ma ma ma ma   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 (Screen-Grid) Supply Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation Plate-No.2 Input: For grid-No.2 voltages up to 137.5 volts For grid-No.2 voltages between 137.5 and 275 volts  TYPICAL OPERATION WITH SEPARATE PLATE OF Plates-No.1A, No.1B, and No.2 Voltage Grid-No.1 Voltage Grid-No.1 Voltage Plate-No.1A Current Plate-No.1B Current Plate-No.1B Current Plate-No.2 Current Grid-No.2 Current Grid-No.2 Current Transconductance (Approx.):      | Triode Unit 275 max                                       | 200 max<br>200 max<br>275 max<br>275 max<br>See curvo<br>-40 max<br>0.3 max<br>0.3 max<br>2.3 max<br>0.45 max<br>See curvo<br>Tetrode Unit<br>100<br>50<br>-1<br>0.04<br>0.04<br>0.3 | volts watt watt watt vatt vatts volts volts volts volts volts volts volts volts volts ma ma ma   |

MAXIMUM CIRCUIT VALUES:



#### MEDIUM-MU DUAL TRIODE

Duodecar type used as combined vertical-deflection-oscillator and vertical-deflection-amplifier tube in television receivers. Outline 8B, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in

6FJ7

any position. Heater volts (ac/dc), 6.3; amperes, 0.9; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, Amplifie                                      | r         |      |      |            |
|--|-----------|------|------|------------|
| CHARACTERISTICS:                                       | Unit No.1 | Unit | No.2 |            |
| Plate Voltage  | 250       | 150  | 250  | volts      |
| Grid Voltage   | 8         | 0    | 9.5  | volts      |
| Amplification Factor                                   | 22.5      | _    | 15.4 |            |
| Plate Resistance (Approx.)                             | 9000      | _    | 2000 | ohms       |
| Transconductance                                       | 2500      | -    | 7700 | $\mu$ mhos |
| Plate Current  | 8         | 68•  | 41   | ma         |
| Grid Voltage (Approx.) for plate current of 10 $\mu$ a | 18        |      | _    | volts      |
| Grid Voltage (Approx.) for plate current of 50 µa      | _         |      | -23  | volts      |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### **Vertical-Deflection Oscillator and Amplifier**

For operation in a 525-line, 20-frame system

|  | Unit No.1  | Unit No.2 |       |
|--|------------|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator | Amplifier |       |
| DC Plate Voltage                         | 350 max    | 550 max   | volts |
| Peak Positive-Pulse Plate Voltage        | _          | 2500 max  | volts |
| Peak Negative-Pulse Grid Voltage         | -400 max   | 250 max   | volts |
| Peak Cathode Current                     |            | 150 max   | . ma  |
| Average Cathode Current                  |            | 50 max    | ma    |
| Plate Dissipation                        | 1 max      | 10 max    | watts |
| MANIMUM CIRCUIT VALUES.                  |            |           |       |


#### MAXIMUM CIRCUIT VALUES:

Grid-Circuit Resistance:

For fixed-bias operation 2.2 max regolms
For cathode-bias operation 2.2 max regolms

- megohms

• The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.



#### **DUAL TRIODE**

Duodecar type used as combined vertical-deflection oscillator and vertical-deflection amplifier in television receivers. The high-mu triode unit No.1 is used as an oscillator, and the low-mu triode unit No.2 is used as an am-

6FM7
Related types:

Related types: 13FM7, 15FM7

plifier. Outline 8B, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Types 13FM7 and 15FM7 are identical with type 6FM7 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: |         | 13FM7<br>13<br>0.45<br>11 | 15FM7<br>14.8<br>0.45<br>11 | volts<br>ampere<br>seconds |
|--|---------|---------------------------|-----------------------------|----------------------------|
| Heater negative with respect to cathode Heater positive with respect to cathode                  | 200 max | 200 max                   | 200 max                     | volts                      |
|  | 200 max | 200•max                   | 200 max                     | volts                      |

<sup>•</sup> The dc component must not exceed 100 volts.

Class A. Amplifier

| CHARACTERISTICS:  | Unit No.1   | Unit No.2 |       |
|---|-------------|-----------|-------|
| Plate Voltage   | 250         | 175       | volts |
| Grid Voltage  | <b>—3</b>   | -25       | volts |
| Amplification Factor                                    | 66          | 5.5       |       |
| Plate Resistance (Approx.)                              | 30000       | 920       | ohms  |
| Transconductance  | 2200        | 6000      | μmhos |
| Grid Voltage (Approx.) for plate current of 20 $\mu$ a  | <b>—5.3</b> |           | volts |
| Grid Voltage (Approx.) for plate current of 200 $\mu a$ | -           | -45       | volts |
| Plate Current   | 2           | 40        | ma    |

#### Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system
Unit No. 1

|  | CHICHO.    | OHAL I VOLE |       |
|--|------------|-------------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator | Amplifier   |       |
| DC Plate Voltage                         | 350 max    | 550 max     | volts |
| Peak Positive-Pulse Plate Voltage#       | _          | 1500 max    | volts |
| Peak Negative-Pulse Plate Voltage        | -400 max   | -250 max    | volts |
| Peak Cathode Current                     | _          | 175 max     | ma    |
| Average Cathode Current                  | _          | 50 max      | ma    |
| Plate Dissipation†                       | 1 max      | 10 max      | watts |
|  |            |             |       |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-Circuit Resistance:

| For fixed-bias operation   | 1 max   | 1 max megohm    |
|----------------------------|---------|-----------------|
| For cathode-bias operation | 2.2 max | 2.2 max megohms |


# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

† An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

# TWIN DIODE --- HIGH-MU TRIODE

#### 6FM8

Miniature type used as combined FM tol(3) detector and af voltage amplifier in FM receivers. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be operated in any position. Heater volts (ac/dc),



Unit No.2

6.3; amperes, 0.45; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Triode Unit as Class A, Amplifier  MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value | 330 max<br>0 max | volts<br>volts |
|---|------------------|----------------|
| Plate Dissipation   | 1.1 max          | watts          |
| CHARACTERISTICS: Plate Voltage Grid Voltage   | 250<br>-3        | volts<br>volts |
| Amplification Factor Plate Resistance (Approx.)   | 70<br>58000      | ohms           |
| Transconductance  | 1200             | μmhos          |
| Plate Current   | 1                | ma             |
| Diode Units (Each Unit)   |                  |                |

| Plate | Current |        |          |        |        |
|-------|---------|--------|----------|--------|--------|
| CHAI  | RACTER  | STICS. | Instanta | aneous | Value: |

MAXIMUM RATINGS (Design-Maximum Values):

Tube Voltage Drop for plate current of 20 ma .....

| 5 | max |  |
|---|-----|--|
| • |     |  |

ma

#### HIGH-MU TRIODE

Miniature type with frame grid used as rf-amplifier tube in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.

6FQ5A

| Heater Voltage (ac/dc)                                     | 6.3     | volts  |
|--|---------|--------|
| Heater Current   | 0.18    | ampere |
| Peak Heater-Cathode Voltage:                               |         | •      |
| Heater negative with respect to cathode                    | 100 max | volts  |
| Heater positive with respect to cathode                    | 100 max | volts  |
| Direct Interelectrode Capacitances:                        |         |        |
| Grid to Plate  | 0.52    | pf     |
| Grid to Cathode, Heater, and Internal Shield               | 5       | pf     |
| Plate to Cathode, Heater, and Internal Shield              | 3.5     | pf     |
| Heater to Cathode  | 2.54    | pf     |
| With external shield connected to cathode except as noted. |         |        |
| △ With external shield connected to ground.                |         |        |
| Class A. Amplifier   |         |        |
| MAXIMUM RATINGS (Design-Maximum Values):                   |         |        |
|  | 200     | volts  |
| Plate Voltage  | 200 max | AOICE  |


| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage | 200 max | volts |
|--|---------|-------|
| Grid Voltage, Negative-bias value                      | -50 max | volts |
| Average Cathode Current                                | 22 max  | ma    |
| Plate Dissipation                                      | 2.5 max | watts |
| CHARACTERISTICS:                                       |         |       |
| Plate Voltage  | 135     | volts |
| Grid Voltage   | -1.2    | volts |
| Amplification Factor                                   | 74      |       |
| Plate Resistance (Approx.)                             | 6300    | ohms  |
| Transconductance                                       | 12000   | μmhos |
| Plate Current  | 8.9     | ma    |
| Grid Voltage (Approx.) for plate current of 100 μa     | 4.5     | volts |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-Circuit Resistance:

For cathode-bias operation .....

1 max megohm



#### MEDIUM-MU TWIN TRIODE

Miniature type used as combined vertical- and horizontal-deflection oscillator in television receivers. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Type

6FQ7
Related type:
8FQ7

8FQ7 is identical with type 6FQ7 except for the heater ratings. Except for direct interelectrode capacitances, these types are identical with miniature type 6CG7. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 6FQ7<br>6.3<br>0.6<br>11 | 8FQ7<br>8.4<br>0.45<br>— | volts<br>ampere<br>seconds |
|--|--------------------------|--------------------------|----------------------------|
| Heater negative with respect to cathode Heater positive with respect to cathode                  | 200 max                  | 200 max                  | volts                      |
|  | 200=max                  | 200=max                  | volts                      |

| Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater | Unit No.1<br>3.6<br>2.4 | Unit No.2<br>3.8<br>2.4 | pf<br>pf |
|--|-------------------------|-------------------------|----------|
| Plate of Unit No.1 to Plate of Unit No.2.  | 0.34                    | 0.26                    | pf<br>pf |

<sup>•</sup> The dc component must not exceed 100 volts.


#### **BEAM HEXODE**

6FS5
Related type: 2FS5

**MAXIMUM CIRCUIT VALUES:** 

Grid-No.1-Circuit Resistance, for fixed-bias operation .....

Miniature type used as rf-amplifier tube in vhf television receivers. In this tube, grid No.1 is the control grid, grid No.2 is a focusing grid, grid No.3 is the screen grid, and grid No.4 is the suppressor grid. Grid No.2 is inter-




0.5 max megohm

suppressor grid. Grid No.2 is internally connected to the cathode and grid No.4, and aligned with grid No.3. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 2FS5 is identical with type 6FS5 except for the heater ratings, as shown below.

|   | 2FS5     | 6FS5     |         |
|---|----------|----------|---------|
| Heater Voltage (ac/dc)                          | 2.4      | 6.3      | volts   |
| Heater Current                                  | 0.6      | 0.2      | ampere  |
| Heater Warm-up Time (Average)                   | 11       |          | seconds |
| Peak Heater-Cathode Voltage:                    |          |          |         |
| Heater negative with respect to cathode         | 200 max  | 200 max  | volts   |
| Heater positive with respect to cathode         | 200°max  | 200°max  | volts   |
|   | Without  | With     |         |
|   | External | External |         |
| Direct Interelectrode Capacitances:             | Shield   | Shield.  |         |
| Grid No.1 to Plate                              | 0.03     | 0.016    | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid   |          |          |         |
| No.3, and Grid No.4                             | 4.8      | 4.8      | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, |          | ***      | •       |
| and Grid No.4                                   | 2        | 2.8      | pf      |
| A *** 1   |          |          |         |

| and Old 17017 .,  | 2.0                                     | γ.     |
|---|---|--------|
| ° The dc component must not exceed 100 volts.                     |   |        |
| •   |   |        |
| • With external shield connected to pin 7.                        |   |        |
| Class A, Amplifier  |   |        |
| MAXIMUM RATINGS (Design-Maximum Values):                          |   |        |
| Plate Voltage   | 300 max                                 | volts  |
| Grid-No.3 (Screen-Grid) Voltage                                   | 150 max                                 | volts  |
| Grid-No.1 (Control-Grid) Voltage:                                 |   |        |
| Negative-bias value   | -50 max                                 | volts  |
| Positive-bias value   | 0 max                                   | volts  |
| Cathode Current   | 20 max                                  | ma     |
| Grid-No.3 Input   | 0.15 max                                |        |
| Plate Dissipation   | 3.25 max                                | watts  |
| auto Dissipation (1177)   | • |        |
| CHARACTERISTICS:  |   |        |
| Plate Voltage   | 275                                     | volts  |
| Grid-No.3 Voltage   | 135                                     | volts  |
| Grid-No.1 Voltage   | -0.2                                    | volt   |
| Plate Resistance (Approx.)  | 0.24                                    | megohm |
| Transconductance  | 10000                                   | μmhos  |
| Plate Current   | 9                                       | ma ma  |
| Grid-No.3 Current   | 0.17                                    | ma     |
| Grid-No.1 Voltage (Approx.) for transconductance of 100 μmhos     | -5                                      | volts  |
| Offic-140.1 Voltage (Approx.) for transconductance of 100 minutes | -3                                      | VOICS  |



#### SHARP-CUTOFF TETRODE

Miniature type used as rf amplifier in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires seven-contact socket and may be mounted in any position.

6FV6

| Heater Current   | 0.2     | ampere |
|--|---------|--------|
| Peak Heater-Cathode Voltage:                                 |         |        |
|  |         |        |
| Heater negative with respect to cathode                      | 00 max  | volts  |
| Heater positive with respect to cathode                      | 00*max  | volts  |
| Direct Interelectrode Capacitances:°                         |         |        |
| Grid No.1 to Plate 0.  | .03 max | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Internal Shield | 4.5     | pf     |
| Plate to Cathode, Heater, Grid No.2, and Internal Shield     | 3       | pf     |
| Cathode to Heater  | 2.7•    | pf     |

- o With external shield connected to cathode except as noted.
- · With external shield connected to ground.


| Class | $A_1$ | Amplifier |  |
|-------|-------|-----------|--|
|       |       |           |  |

| MAXIMUM RATINGS (Design-Maximum Values):                    |          |            |
|---|----------|------------|
| Plate Voltage   | 275 max  | volts      |
| Grid-No.2 (Screen-Grid) Supply Voltage                      | 180 max  | volts      |
| Grid-No.2 Voltage   | See cur  | ve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value       | 0 max    |            |
| Cathode Current   | 20 max   |            |
| Grid-No.2 Input:  | 20 11147 |            |
| For grid-No.2 voltages up to 90 volts                       | 0.5 max  | watt       |
| For grid-No.2 voltages between 90 and 180 volts             |          | ve page 75 |
| Plate Dissipation   | 2 max    |            |
| Tace Dissipation  |          |            |
| CHARACTERISTICS:  |          |            |
| Plate Voltage   | 125      | volts      |
| Grid-No.2 Voltage   | 80       | volts      |
| Grid-No.1 Voltage   | -1       | volt       |
| Plate Resistance (Approx.)                                  | 0.1      | megohm     |
| Transconductance  | 8000     | μmhos.     |
| Plate Current   | 10       | ma         |
| Grid-No.2 Current   | 1.5      | ma         |
| Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu$ a | -6       | volts      |
| MAXIMUM CIRCUIT VALUES:                                     |          |            |
| MARKET CALCULATION CANCELL CALCULATION CO.                  |          | _          |

MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.

6FV8

0.5 max megohm



Grid-No.1-Circuit Resistance ....

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in television receivers as combined oscillator and amplifier. Triode is used as vertical deflection oscillator; pentode is used as if or general-purpose amplifier. Outline 6B. Outlines section. Tube

6FV8A Related type:

requires nine-contact socket and may be operated in any position. Type 5FV8 is identical with type 6FV8A except for the heater ratings, as shown below.

|  | 5FV8                          | 6FV8A                      |                    |
|--|-------------------------------|----------------------------|--------------------|
| Heater Voltage (ac/dc)   | 4.7                           | 6.3                        | volts              |
| Heater Current   | 0.6                           | 0.45                       | ampere             |
| Heater Warm-up Time (Average)  Peak Heater-Cathode Voltage:                          | 11                            | 11                         | seconds            |
| Heater negative with respect to cathode Heater positive with respect to cathode      | 200 max<br>200°max            | 200 max<br>200°max         | volts<br>volts     |
| Direct Interelectrode Capacitances: Triode Unit:                                     | Without<br>External<br>Shield | With<br>External<br>Shield |                    |
| Grid to Plate  | 1.8                           | 1.8                        | pf                 |
| Grid to Cathode, Heater, Pentode Cathode, Pentode Grid No.3, and Internal Shield     | 2.8                           | 2.8                        | pf                 |
| Plate to Cathode, Heater, Pentode Cathode,<br>Pentode Grid No.3, and Internal Shield | 1.5                           | 2                          | pf                 |
| Pentode Unit: Grid No.1 to Plate   | 0.02 max                      | 0.01 max                   | pf                 |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield              | 5                             | 5                          | pf                 |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield                  | 2                             | 3                          | pf                 |
| Pentode Plate to Triode Plate  | 0.15 max                      | 0.03 max                   | pf                 |
| ° The dc component must not exceed 100 volts.  |                               |                            |                    |
| Class A, Amplifie<br>Pentode Unit  | r                             |                            |                    |
| MAXIMUM RATINGS (Design-Center Values):  |                               |                            | _                  |
| Plate Voltage  |                               | 330 max                    | volts              |
| Grid-No.2 (Screen-Grid) Supply Voltage   | • • • • • • • • • •           | 330 max                    | volts              |
| Grid-No.2 Voltage  |                               | See curve<br>0 max         | e page 15<br>volts |
| Plate Dissipation  |                               | 2.3 max                    | watts              |
| Grid-No.2 Input:   |                               | 2.5 IIIda                  | Walts              |
| For grid-No.2 voltages up to 165 volts   |                               | 0.55 max                   | watt               |
| For grid-No.2 voltages between 165 and 330 volts                                     |                               | See curve                  |                    |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:                                |                               |                            |                    |
| Oligitation Resistance.  |                               |                            |                    |

For fixed-bias operation ..... 0.25 max megohm For cathode-bias operation ..... 1 max megohm

|  | Triode    | Pentode |            |
|--|-----------|---------|------------|
| CHARACTERISTICS:                                       | Unit      | Unit    |            |
| Plate Voltage  | 125       | 125     | volts      |
| Grid-No.2 Voltage                                      |           | 125     | volts      |
| Grid-No.1 Voltage                                      | <b>-1</b> | -1      | volt       |
| Amplification Factor                                   | 45        | _       |            |
| Plate Resistance (Approx.)                             | 5600      | 200000  | ohms       |
| Transconductance                                       | 8000      | 6500    | $\mu$ mhos |
| Grid-No.1 Voltage (Approx.) for plate current of 20 µa | 7.5       | 9       | volts      |
| Plate Current  | 12        | 12      | ma         |
| Grid-No.2 Current                                      | _         | 4       | ma         |

#### Vertical-Deflection Oscillator—Triode Unit

For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values):

| WAARUUU KAIRUUS (Design-Maximum values). |          |       |
|--|----------|-------|
| DC Plate Voltage                         | 330 max  | volts |
| Peak Negative-Pulse Grid Voltage         | -250 max | volts |
| Peak Cathode Current                     | 70 max   | ma    |
| Average Cathode Current                  | 20 max   | ma    |
| Plate Dissipation                        | 2 max    | watts |

## MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance:

3 max megohms For cathode-bias operation .....

#### **BEAM POWER TUBE**

Glass octal type used as horizontaldeflection amplifier in television receivers. Outline 19B, Outlines section. Tube requires octal socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 1.2; peak

6FW5

heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): |          |       |
|--|----------|-------|
| DC Plate Voltage                         | 770 max  | volts |
| Peak Positive-Pulse Plate Voltage        | 6500 max | voits |
| DC Grid-No.2 (Screen-Grid) Voltage       | 220 max  | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -330 max | volts |
| DC Grid-No.1 (Control-Grid) Voltage      | 55 max   | volts |
| Peak Cathode Current                     | 610 max  | ma    |
| Average Cathode Current                  | 175 max  | ma    |
| Grid-No.2 Input                          | 3.6 max  | watts |
| Plate Dissipation•                       | 18 max   | watts |
| Bulb Temperature (At hottest point)      | 220 max  | °C    |

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance ......


1 max megohm

- \*The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

#### MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

6FW8



#### **DUAL TRIODE**

Duodecar type used as combined vertical-deflection oscillator and vertical-deflection amplifier in television receivers. The high-mu triode unit No.1 is used as an oscillator, and the low-mu triode unit No.2 is used as an am-

6FY7
Related type:
15FY7

plifier. Outline 8D, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Type 15FY7 is identical with type 6FY7 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)   | 6FY7<br>6.3        | 15FY7<br>14.7      | volts          |
|--|--------------------|--------------------|----------------|
| Heater Current   | 1.05               | 0.45               | ampere         |
| Heater Warm-up Time (Average)  | _                  | 11                 | seconds        |
| Peak Heater-Cathode Voltage:   |                    |                    |                |
| Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max<br>200=max | 200 max<br>200•max | volts<br>volts |

The dc component must not exceed 100 volts.

Class A. Amplifier

| CHARACTERISTICS:                                       | Unit No.1 | Unit No.2 |            |
|--|-----------|-----------|------------|
| Plate Voltage  | 250       | 150       | volts      |
| Grid Voltage   | -3        | -17.5     | volts      |
| Amplification Factor                                   | 65        | 6         |            |
| Plate Resistance (Approx.)                             | 40500     | 800       | ohms       |
| Transconductance                                       | 1600      | 7500      | $\mu$ mhos |
| Grid Voltage (Approx.) for plate current of 30 $\mu$ a | 5.5       | -         | volts      |
| Grid Voltage (Approx.) for plate current of 50 $\mu$ a | _         | <b>55</b> | volts      |
| Plate Current  | 1.4       | 45        | ma         |
| Plate Current (Approx.) for grid voltage of -25 volts. | _         | 10        | ma         |

#### Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator | Amplifier |       |
|--|------------|-----------|-------|
| DC Plate Voltage                         | 330 max    | 275 max   | volts |
| Peak Positive-Pulse Plate Voltage#       |            | 2000 max  | volts |
| Peak Negative-Pulse Plate Voltage        | -400 max   | -250 max  | volts |
| Peak Cathode Current                     | 70 max     | 175 max   | ma    |
| Average Cathode Current                  | 20 max     | 50 max    | ma    |
| Plate Dissipation                        | 1 max      | 7†max     | watts |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-Circuit Resistance 2.2 max megohms

#The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds. † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

6G6G


#### **POWER PENTODE**

Renewal type; see chart at end of section for tabulated data.

#### BEAM POWER TUBE— SHARP-CUTOFF PENTODE

6G11

Duodecar type used as FM detector GSP and audio-frequency output amplifier in television receivers. Outline 8B, CIP Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Heater




Unit No 2

volts (ac/dc), 6.3; amperes, 1.2; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Beam Power Tube Unit as Class A<sub>1</sub> Amplifier MAXIMUM RATINGS (Design-Maximum Values):

| Plate Voltage Grid-No.2 (Screen-Grid) Voltage | 150 max<br>135 max | volts<br>volts |
|---|--------------------|----------------|
| Average Cathode Current                       | 65 max             | ma             |
| Plate Dissipation                             |                    | watts          |
| Grid-No.2 Input                               | 1.8 max            | watts          |
| TYPICAL OPERATION:                            |                    |                |
| Plate Voltage                                 | 120                | volts          |
| Grid-No.2 Voltage                             | 110                | volts          |
| Grid-No.1 (Control-Grid) Voltage              | -8                 | volts          |
| Peak AF Grid-No.1 Voltage                     | 8                  | volts          |
| Zero-Signal Plate Current                     | 49                 | ma             |
| Maximum-Signal Plate Current                  | 50                 | ma             |
| Zero-Signal Grid-No.2 Current                 | 4                  | ma             |
| Maximum-Signal Grid-No.2 Current              | 8.5                | ma             |
| Plate Resistance (Approx.)                    | 10000              | ohms           |

| Transconductance                                       | 7500        | μmhos      |
|--|-------------|------------|
| Load Resistance  | 2500        | ohms       |
| Total Harmonic Distortion                              | 10          | per cent   |
| Maximum-Signal Power Output                            | 2.3         | watts      |
| Pentode Unit as Class A, Amplifier                     |             |            |
| CHARACTERISTICS:                                       |             |            |
| Plate Supply Voltage                                   | 150         | volts      |
| Grid-No.3 (Suppressor-Grid) Voltage                    | 0           | volts      |
| Grid-No.2 (Screen-Grid) Supply Voltage                 | 100         | volts      |
| Cathode-Bias Resistor                                  | 560         | ohms       |
| Plate Resistance (Approx.)                             | 0.15        | megohm     |
| Transconductance, Grid No.1 to Plate                   | 1000        | $\mu$ mhos |
| Transconductance, Grid No.3 to Plate                   | 400         | $\mu$ mhos |
| Plate Current  | 1.3         | ma         |
| Grid-No.2 Current                                      | 2           | ma         |
| Grid-No.1 Voltage (Approx.) for plate current of 10 μa | <b></b> 4.5 | volts      |
| Grid-No.3 Voltage (Approx.) for plate current of 10 μa | -4.5        | volts      |
| Pentode Unit as FM Detector                            |             |            |
| MAXIMUM RATINGS (Design-Maximum Values):               |             |            |
| Plate Voltage  | 330 ma      | x volts    |
| Grid-No.3 Voltage                                      | 28 ma       | x volts    |
| Grid-No.2 Supply Voltage                               | 330 ma      | x volts    |
| Grid-No.2 Voltage                                      | See cur     | ve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  | 0 ma        | x volts    |
| Plate Dissipation                                      | 1.7 ma      | x watts    |
| Grid-No.2 Input:                                       |             |            |
| For grid-No.2 voltages up to 165 volts                 | 1.1 ma      | x watts    |
| For grid-No.2 voltages between 165 and 330 volts       | See cur     | ve page 75 |



#### **BEAM POWER TUBE**

Neonoval type used as horizontal-deflection amplifier in television receivers. Outline 10E, Outlines section. Tube requires neonoval nine-contact socket and may be mounted in any position. Typical instantaneous characteristics

**6GB5** Related type: 13GB5

13.3

volts

2.2 max megohms

(measured with recurrent waveform such that maximum ratings are not exceeded): plate volts, 75; grid-No.2 volts, 200; grid-No.1 volts, -10; plate ma., 440; grid-No.2 ma., 37. Type 13GB5 is identical with type 6GB5 except for heater ratings, as shown below.

> 6GB5 6.3

| Heater Current                                | 1.30      | V.0      | amberes |
|---|-----------|----------|---------|
| Peak Heater-Cathode Voltage:                  |           |          |         |
| Heater negative with respect to cathode       | 250 max   | 250 max  | volts   |
| Heater positive with respect to cathode       | 250°max   | 250°max  | volts   |
| * The dc component must not exceed 125 volts. |           |          |         |
| Horizontal-Deflection Am                      |           |          |         |
| For operation in a 525-line, 30-fra           | me system |          |         |
| MAXIMUM RATINGS (Design-Maximum Values):      |           |          |         |
| DC Grid-No.2 (Screen-Grid) Voltage            |           | 275 max  | volts   |
| Peak Positive-Pulse Plate Voltage             |           | 7700 max | volts   |
| DC Grid-No.2 (Screen-Grid) Voltage            |           | 275 max  | volts   |
| Average Cathode Current                       |           | 275 max  | ma      |
| Grid-No.2 Input.                              |           | 5 max    | watts   |
| Plate Dissipation                             |           | 17 max   | watts   |
| MAXIMIM CIRCUIT VALUES.                       |           |          |         |

Heater Voltage (ac/dc) ......

Grid-No.1-Circuit Resistance .....

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10


• Grid-No.2 input may reach 6 watts for plate-dissipation values below 11 watts.

An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

#### **BEAM POWER TUBE**

#### 6GC5

Neonoval type used as output tube in audio-amplifier applications. Outline 10D, **Outlines** section. Tube requires neonoval nine-contact socket and may be mounted in any position.




| Heater Voltage (ac/dc)                                 | 6.3     | volts  |
|--|---------|--------|
| Heater Current   | 1.2     | ampere |
| Peak Heater-Cathode Voltage:                           |         | •      |
| Heater negative with respect to cathode                | 200 max | volts  |
| Heater positive with respect to cathode                | 200 max | volts  |
| Direct Interelectrode Capacitances (Approx.):          |         |        |
| Grid No.1 to Plate                                     | 0.9     | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 18      | ρf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 7       | pf     |

• The dc component must not exceed 100 volts.

#### Class A, Amplifier


| MAXIMUM RATINGS (Design-Maximum Values): |         |       |
|--|---------|-------|
| Plate Voltage                            | 220 max | volts |
| Grid-No.2 (Screen-Grid) Voltage          | 140 max | volts |
| Grid-No.2 Input                          | 1.4 max | watts |
| Plate Dissipation                        | 12 max  | watts |




| TYPICAL OPERATION AND CHARACTERISTICS: |                 |       |          |
|--|-----------------|-------|----------|
| Plate Voltage                          | 110             | 200   | volts    |
| Grid-No.2 Voltage                      | 110             | 125   | volts    |
| Grid-No.1 Voltage                      | <del></del> 7.5 | _     | volts    |
| Cathode-Bias Resistor                  |                 | 180   | ohms     |
| Peak AF Grid-No.1 Voltage              | 7.5             | 8.5   | volts    |
| Zero-Signal Plate Current              | 49              | 46    | ma       |
| Maximum-Signal Plate Current           | 50              | 47    | ma       |
| Zero-Signal Grid-No.2 Current          | 4               | 2.2   | ma       |
| Maximum-Signal Grid-No.2 Current       | 10              | 8.5   | ma       |
| Plate Resistance (Approx.)             | 13000           | 28000 | ohms     |
| Transconductance                       | 8000            | 8000  | μmhos    |
| Load Resistance                        | 2000            | 4000  | ohms     |
| Total Harmonic Distortion              | 10              | 10    | per cent |
| Maximum-Signal Power Output            | 2.1             | 3.8   | watts    |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:





#### **BEAM POWER TUBE**

Duodecar type used as horizontal-deflection-amplifier tube in television receivers. Outline 15A, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Types 12GE5 and

6GE5 Related types: 12GE5, 17GE5

17GE5 are identical with type 6GE5 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)                  | 6GE5<br>6.3<br>1.2 | 12GE5<br>12.6<br>0.6<br>11 | 17GE5<br>16.8<br>0.45<br>11 | volts<br>ampere<br>seconds |
|---|--------------------|----------------------------|-----------------------------|----------------------------|
| Heater negative with respect to cathode | 200 max            |                            | 200 max                     | volts                      |
| Heater positive with respect to cathode | 200•max            |                            | 200=max                     | volts                      |

<sup>\*</sup> The dc component must not exceed 100 volts.

#### Class A, Amplifier

| GIASS A <sub>1</sub> Ampliner                         |      |       |        |
|---|------|-------|--------|
| CHARACTERISTICS:                                      |      |       |        |
| Plate Voltage   | 60   | 250   | volts  |
| Grid-No.2 (Screen-Grid) Voltage                       | 150  | 150   | volts  |
| Grid-No.1 (Control-Grid) Voltage                      | 0    | -22.5 | volts  |
| Triode Amplification Factor*                          | _    | 4.4   |        |
| Plate Resistance (Approx.)                            | _    | 18000 | ohms   |
| Transconductance                                      | -    | 7300  | μmhos. |
| Plate Current   | 345● | 65    | ma     |
| Grid-No.2 Current                                     | 27•  | 1.8   | ma     |
| Grid-No.1 Voltage (Approx.) for plate current of 1 ma | _    | -42   | volts  |

<sup>\*</sup> Triode connection (grid No.2 tied to plate); plate and grid-No.2 volts = 150.

<sup>•</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

| For operation in a 525-line, 30-frame system |           |       |
|--|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |           |       |
| DC Plate Supply Voltage                      | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage#           | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage            | -1500 max | volts |
| DC Grid-No.2 Voltage                         | 220 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage        | 330 max   | volts |
| DC Grid-No.1 Voltage                         | -55 max   | volts |
| Peak Cathode Current                         | 550 max   | ma    |
| Average Cathode Current                      | 175 max   | ma    |
| Plate Dissipation†                           | 17.5 max  | watts |
| Grid-No.2 Input                              | 3.5 max   | watts |
| Bulb Temperature (At hottest point)          | 200 max   | °C    |

MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance .....

1 max megohm


#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

† An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

#### **BEAM POWER TUBE**

6GF5

Duodecar type used as horizontal-deflection amplifier in television receivers. Outline 8D, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Heater volts (ac/dc),



6.3; amperes, 1.2; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Class A<sub>1</sub> Amplifier

| 60   | 250                        | volts   |
|------|----------------------------|---|
| 150  | 150                        | volts   |
| 0    | -26.5                      | volts   |
| _    | 4.2                        |   |
| _    | 0.26                       | megohm  |
| _    | 4700                       | $\mu$ mhos  |
| 345● | 34                         | ma  |
| 33•  | 1.6                        | ma  |
|      | -46                        | volts   |
|      | 150<br>0<br>-<br>-<br>345• | 150 150<br>0 -26.5<br>- 4.2<br>- 0.26<br>- 4700<br>345• 34<br>33• 1.6 |

- \* Triode connection (grid No.2 connected to plate); plate and grid-No.2 volts = 150.
- These values can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

| For operation in a 525-line, 30-frame system             |          |       |
|--|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):                 |          |       |
| DC Plate Supply Voltage                                  | 770 max  | volts |
| Peak Positive-Pulse Plate Voltage#                       | 5000 max | volts |
| Peak Negative-Pulse Plate Voltage                        | 1500 max | volts |
| DC Grid-No.2 Voltage                                     | 220 max  | volts |
| Peak Negative-Pulse Grid-No.1 Voltage                    | -330 max | volts |
| Negative DC Grid-No.1 Voltage                            | —55 max  | volts |
| Peak Cathode Current                                     | 500 max  | ma    |
| Average Cathode Current                                  | 160 max  | ma    |
| Plate Dissipation†                                       | 9 max    | watts |
| Grid-No.2 Input  | 2.5 max  | watts |
| Bulb Temperature (At hottest point)                      | 200 max  | °C    |
| 1.5 / 1.77 / 1.7 / C.T. C.T. C.T. C.T. C.T. C.T. C.T. C. |          |       |

#### MAXIMUM CIRCUIT VALUES:

 # The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds. † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

# NC

#### **DUAL TRIODE**

Novar types containing high-mu and high-perveance, low-mu triode units used as combined vertical-deflection oscillator and vertical-deflection amplifiers in television receivers. Outlines 11A and 30A, respectively, Outlines

# 6GF7

10GF7, 10GF7A, 13GF7. 13GF7A

section. Tubes require novar nine-contact socket and may be mounted in any position. For curves of average plate characteristics for Unit No.1 and Unit No.2, refer to types 6DR7 (Unit No.1) and 6EM7, respectively. Types 10GF7 and 10GF7A and types 13GF7 and 13GF7A are identical with types 6GF7 and 6GF7A except for the heater ratings, as shown below.

|  | 6GF7  | 10GF7           | 13GF7     |         |
|--|-------|-----------------|-----------|---------|
|  | 6GF7A | 10 <b>GF</b> 7A | 13GF7A    |         |
| Heater Voltage (ac/dc)                       | 6.3   | 9.7             | 13        | volts   |
| Heater Current                               |       | 0.6             | 0.45      | ampere  |
| Heater Warm-up Time (Average)                | _     | 11              | 11        | seconds |
| Peak Heater-Cathode Voltage:                 |       |                 |           |         |
| Heater negative with respect to cathode      |       | ax 200 max      | 200 max   | volts   |
| Heater positive with respect to cathode      | 200=m | ax 200 max      | 200 = max | volts   |
| Direct Interelectrode Capacitances (Approx.) |       | Unit No.1       | Unit No.2 |         |
| Grid to Plate                                |       | 4.6             | 9         | pf      |
| Grid to Cathode and Heater                   |       | 2.4             | 6.5       | pf      |
| Plate to Cathode and Heater                  |       | 0.26            | 1.4       | pf      |

The dc component must not exceed 100 volts.

| Class A, Amplifie                                   | r           |           |       |
|---|-------------|-----------|-------|
| CHARACTERISTICS:                                    | Unit No.1   | Unit No.2 |       |
| Plate Voltage                                       | 250         | 150       | volts |
| Grid Voltage  | 3           | -20       | volts |
| Amplification Factor                                | 64          | 5.4       |       |
| Plate Resistance (Approx.)                          | 40000       | 750       | ohms  |
| Transconductance                                    | 1600        | 7200      | μmhos |
| Grid Voltage (Approx.):                             |             |           |       |
| For plate current of 10 $\mu a$                     | <b></b> 5.5 | _         | volts |
| For plate current of 100 μa                         | -           | -45       | volts |
| Plate Current                                       | 1.4         | 50        | ma    |
| For plate voltage of 60 volts and zero grid voltage | _           | 95        | ma    |
| For grid voltage of -28 volts                       | _           | 10        | ma    |
|   |             |           |       |

#### Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system Unit No.1 Unit No.2 MAXIMUM RATINGS (Design-Maximum Values): Oscillator Amplifier DC Plate Voltage ..... 330 max 330 max volts Peak Positive-Pulse Plate Voltage (Absolute Maximum)# 1500 max volts -400 max -250 max Peak Negative-Pulse Grid Voltage ...... volts Peak Cathode Current ..... 77 max 175 max ma Average Cathode Current ...... 22 max 50 max ma Plate Dissipation ...... 1.5 max 11 max watts

#### MAXIMUM CIRCUIT VALUES:

Grid-Circuit Resistance:

For grid-resistor-bias or cathode-bias operation ... 2.2 max 2.2 max megohms

Under no circumstances should this absolute value be exceeded.

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

# **6GH8**

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6GH8A
Related type:
5GH8

Miniature type used in multivibratortype horizontal-deflection circuits in cape at television receivers. Also used for agcamplifier or sync-separator applications in such receivers. Outline 6B, Outlines section. Tube requires minia-



ture nine-contact socket and may be mounted in any position. This type is specially controlled to assure low interelectrode leakage. Type 5GH8 is identical with type 6GH8A except for the heater ratings, as shown below.


| Heater Voltage (ac/dc)  | 5GH8<br>4.7           | 6GH8A<br>6.3 | volts   |
|---|-----------------------|--------------|---------|
|   |                       |              |         |
| Heater Current  | 0.6                   | 0.45         | ampere  |
| Heater Warm-up Time (Average)                                   | 11                    | 11           | seconds |
| Peak Heater-Cathode Voltage:                                    |                       |              |         |
| Heater negative with respect to cathode                         | 200 max               | 200 max      | volts   |
| Heater positive with respect to cathode                         | 200 <b>•</b> max      | 200 = max    | volts   |
| Direct Interelectrode Capacitances:                             |                       |              |         |
| Triode Unit:  |                       |              |         |
| Grid to Plate   |                       | 1.7          | pf      |
| Grid to Cathode, Heater, Pentode Grid No.3, Pentode             | . Cathode.            |              |         |
| and Internal Shield   |                       | 3            | pf      |
| Plate to Cathode, Heater, Pentode Grid No.3, Pentode            |                       | 3            | P       |
|   |                       | 1.4          |         |
| and Internal Shield   |                       |              | pf      |
| Heater to Cathode   | · · · · · · · · · · · | 3            | pf      |
| Pentode Unit:   |                       |              | _       |
| Grid No.1 to Plate  |                       | 0.02 max     | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, as          | nd Internal           |              |         |
| Shield  |                       | 5            | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, an              | d Internal            |              |         |
| Shield  |                       | 2.6          | pf      |
| Heater to Cathode, Grid No.3, and Internal Shield               |                       | 3            | pf      |
| zation to democify direction, and amount different contractions |                       | -            |         |


• The dc component must not exceed 100 volts.


| Class A. Amplifie                                      | r           |              |            |
|--|-------------|--------------|------------|
| CHARACTERISTICS:                                       | Triode Unit | Pentode Unit | _          |
| Plate Voltage  | 125         | 125          | volts      |
| Grid-No.2 Voltage                                      | -           | 125          | volts      |
| Grid-No.1 Voltage                                      | <b>—1</b>   | -1           | volts      |
| Amplification Factor                                   | 46          | _            |            |
| Plate Resistance (Approx.)                             | 5400        | 200000       | ohms       |
| Transconductance                                       | 8500        | 7500         | $\mu$ mhos |
| Plate Current  | 13.5        | 12           | ma         |
| Grid-No.2 Current                                      | _           | 4            | ma         |
| Grid-No.1 Voltage (Approx.) for plate current of 10 µa | -8          | -8           | volts      |

| Horizontal-Deflection Osc<br>For operation in a 525-line, 30-fra   |           |                                    |                      |
|--|-----------|------------------------------------|----------------------|
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage: |           | Pentode Unit<br>350 max<br>330 max | volts<br>volts       |
| Positive-bias value Peak negative value Peak Cathode Current   | 0 max<br> | 0 max<br>175 max<br>300 max        | volts<br>volts<br>ma |

|                               | Triode Unit | Pentode Unit |        |
|-------------------------------|-------------|--------------|--------|
| Average Cathode Current       | _           | 20 max       | ma     |
| Grid-No.2 Input               | -           | 0.55 max     | watt   |
| Plate Dissipation             | 2.5 max     | 2.5 max      | watts  |
| MAXIMUM CIRCUIT VALUES:       |             |              |        |
| Grid-No.1-Circuit Resistance: |             |              |        |
| For fixed-bias operation      | 2.2 max     | 2.2 max me   |        |
| For cathode-bias operation    | 2.2 max     | 2.2 max me   | egohms |







#### **BEAM POWER TUBE**

Novar types used in high-efficiency horizontal-deflection-amplifier circuits of television receivers. Outlines 18A and 32, respectively, **Outlines** section. Tubes require novar nine-contact socket and may be operated in any

6GJ5 6GJ5A

Related types: 12GJ5, 12GJ5A, 17GJ5, 17GJ5A

position. For curve of average characteristics see type 6GW6. Types 12GJ5 and

12GJ5A and types 17GJ5 and 17GJ5A are identical with types 6GJ5 and 6GJ5A except for the heater ratings, as shown below.

| · · · · · · · · · · · · · · · · · · ·         | 6GJ5      | 12GJ5     | 17GJ5   |         |
|---|-----------|-----------|---------|---------|
|   | 6GJ5A     | 12GJ5A    | 17GJ5A  |         |
| Heater Voltage (ac/dc)                        | 6.3       | 12.6      | 16.8    | volts   |
| Heater Current                                | 1.2       | 0.6       | 0.45    | ampere  |
| Heater Warm-up Time (Average)                 |           | 11        | 11      | seconds |
| Peak Heater-Cathode Voltage:                  |           |           |         |         |
| Heater negative with respect to cathode       | 200 max   | x 200 max | 200 max | volts   |
| Heater positive with respect to cathode       | 200 = max | x 200 max | 200 max | volts   |
| Direct Interelectrode Capacitances (Approx.): |           |           | •       |         |
| Grid No.1 to Plate                            | <i></i>   |           | 0.26    | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, an   | d Grid No | 0.3       | 15      | pf      |
| Plate to Cathode, Heater, Grid No.2, and Gri  | id No.3   |           | 6.5     | pf      |
|   |           |           |         | •       |

The dc component must not exceed 100 volts.

#### Class A, Amplifier

|   | 1 riode    |         |            |        |
|---|------------|---------|------------|--------|
|   | Connection | Pentode | Connection |        |
| Plate Voltage                               | 150        | 60      | 250        | volts  |
| Grid-No.2 Voltage                           | 150        | 150     | 150        | volts  |
| Grid-No.1 Voltage                           | -22.5      | 0       | -22.5      | volts  |
| Mu-Factor, grid No.2 to grid No.1           | 4.4        | -       |            |        |
| Plate Resistance (Approx.)                  |            | _       | 15000      | ohms   |
| Transconductance                            |            | _       | 7100       | μmhos. |
| Plate Current                               |            | 3900    | 70         | ma     |
| Grid-No.2 Current                           |            | 320     | 2.1        | ma     |
| Grid-No.1 Voltage for plate current of 1 ma |            | _       | 42         | volts  |
|   |            |         |            |        |

<sup>□</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

| For operation in a 525-line, 30-frame system |           |       |
|--|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |           |       |
| DC Plate Supply Voltage                      | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage*           | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage            | -1500 max | volts |
| DC Grid-No.2 Voltage                         | 220 max   | volts |
| DC Grid-No.1 Voltage                         | 55 max    | volts |
| Peak Negative-Pulse Grid-No.1 Voltage        | -330 max  | volts |
| Peak Cathode Current                         | 550 max   | ma    |
| Average Cathode Current                      | 175 max   | ma    |
| Plate Dissipation•                           | 17.5 max  | watts |
| Grid-No.2 Input                              | 3.5 max   | watts |
| Bulb Temperature (at hottest point)          |           | ""C   |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:

For grid-resistor-bias operation• ......


1 max megohm

- \* The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**6GJ7** 

Miniature type used as combined oscillator and mixer tube in television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. Outline 6J, Outlines section. Tube requires miniature nine-



contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.41; peak heater-cathode volts, 110.

| Class A, Amplifier                                |             |             |        |
|---|-------------|-------------|--------|
| MAXIMUM RATINGS (Design-Maximum Values):          | Triode Unit | Pentode Uni | t      |
| Plate-Supply Voltage                              | 600 max     | 600 max     | volts  |
| DC Plate Voltage                                  | 140 max     | 275 max     | volts  |
| Grid-No.2 (Screen-Grid) Supply Voltage            | _           | 600 max     | volts  |
| DC Grid-No.2 Voltage                              |             | 275 max     | volts  |
| DC Grid-No.1 (Control-Grid) Voltage               | _           | -50 max     | volts  |
| Cathode Current                                   | 22 max      | 20 max      | ma     |
| Plate Dissipation                                 | 1.8 max     | 2.4 max     | watts  |
| Grid-No.2 Input                                   | _           | 0.55 max    | watt   |
| CHARACTERISTICS:                                  |             |             |        |
| DC Plate Voltage                                  | 100         | 170         | volts  |
| DC Grid-No.2 Voltage                              |             | 120         | volts  |
| DC Grid-No.1 Voltage                              | <b>—3</b>   | -1.2        | volts  |
| Amplification Factor                              | 20          | 55*         |        |
| Plate Resistance (Approx.)                        | _           |             | megohm |
| Transconductance                                  | 9000        | 11000       | μmhos  |
| Grid-No.1 Voltage for grid-No.1 current of 0.3 μa | -1.3 max    | -1.3 max    | volts  |
| Plate Current                                     | 15          | 10          | ma     |
| Grid-No.2 Current                                 | =           | 3           | ma     |
| MAXIMUM CIRCUIT VALUES:                           |             |             |        |
| Grid-No.1-Circuit Resistance:                     |             |             |        |
| For fixed-bias operation                          | 0.5 max     | 1 max       | megohm |
| For cathode-bias operation                        | 0.5 max     | 2.2 max n   |        |
| * Grid No.2 to grid No.1.                         |             |             |        |

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

6GJ8



#### HIGH-MU TRIODE

Miniature type with frame grid used as grounded-cathode rf-amplifier tube in vhf tuners of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be operated in any position.

6GK5
Related types:

2GK5, 3GK5, 4GK5

Types 2GK5, 3GK5, and 4GK5 are identical with type 6GK5 except for the heater ratings, as shown below.

|                                    | 2GK5             | 3GK5 | 4GK5      | 6GK5    |           |
|------------------------------------|------------------|------|-----------|---------|-----------|
| Heater Voltage (ac/dc)             | 2.3              | 2.8  | 4.0       | 6.3     | volts     |
| Heater Current                     | 0.6              | 0.45 | 0.3       | 0.18    | ampere    |
| Heater Warm-up Time (Average)      | ) 11             | 11   | 11        | _       | seconds   |
| Peak Heater-Cathode Voltage:       |                  |      |           |         |           |
| Heater negative with respect t     | 0                |      |           |         |           |
| cathode                            | 100 max          | 100  | max 100 i | max 100 | max volts |
| Heater positive with respect to    | )                |      |           |         |           |
| cathode                            | 100 max          | 100  | max 100 i | max 100 | max volts |
| Direct Interelectrode Capacitances | (Approx.):*      |      |           |         |           |
| Grid to Plate                      |                  |      |           | 0.52    | pf        |
| Grid to Cathode, Heater, and       | Internal Shiel   | d    |           | 5       | pf        |
| Plate to Cathode, Heater, and      | d Internal Shiel | d    |           | 3.5     | pf        |
| Heater to Cathode                  |                  |      |           | 2.5     |           |
|                                    |                  |      |           |         |           |

- " With external shield connected to cathode, except as noted.
- With external shield and internal shield connected to ground.


Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):                  |         |        |
|---|---------|--------|
| Plate Voltage   | 200 max | volts  |
| Grid Voltage:   |         |        |
| Negative-bias value                                       | 50 max  | volts  |
| Positive-bias value                                       | 0 max   | volts  |
| Average Cathode Current                                   | 22 max  | ma     |
| Plate Dissipation   | 2.5 max | watts  |
| CHARACTERISTICS:  |         |        |
| Plate Voltage   | 135     | volts  |
| Grid Voltage  | 1       | volts  |
| Amplification Factor                                      | 78      |        |
| Plate Resistance (Approx.)                                | 5400    | ohms   |
| Transconductance  | 15000   | μmhos. |
| Plate Current   | 11.5    | ma     |
| Grid Voltage (Approx.) for transconductance of 150 µmhos  | -4.2    | volts  |
| Grid Voltage (Approx.) for transconductance of 1500 µmhos | -2.5    | volts  |
| Input Resistance.   | 275     | ohms   |
| Input Capacitance•  | 11.2    | μμf    |
| Noise Figure  | 4.7     | db     |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-Circuit Resistance:


□ For a neutralized triode amplifier at a frequency of 200 Mc with signal source impedance adjusted for minimum noise output.



#### **POWER PENTODE**


6GK6
Related type:

Miniature type used in the output 63 stage of audio amplifying equipment 18 and also in the video output stage of television receivers. Outline 6G, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position.



|                               | OGKO | 10040 |         |
|-------------------------------|------|-------|---------|
| Heater Voltage (ac/dc)        | 6.3  | 16    | volts   |
| Heater Current                | 0.76 | 0.3   | ampere  |
| Heater Warm-up Time (Average) | _    | 11    | seconds |

| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode Heater positive with respect to cathode Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Shield |          | 100 max<br>100 max<br>0.14 max | volts<br>volts<br>pf |
|---|----------|--------------------------------|----------------------|
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and<br>Shield   | Internal | 7                              | pf                   |
| Class A, Amplifier  |          |                                |                      |
| MAXIMUM RATINGS (Design-Maximum Values):  |          |                                |                      |
| Plate Supply Voltage  |          | 600 max                        | volts                |
| Plate Voltage   |          | 330 max                        | volts                |
| Grid-No.2 Supply Voltage  |          | 605 max                        | volts                |
| Grid-No.2 (Screen-Grid) Voltage   |          | 330 max                        | volts                |
| Grid-No.1 (Control-Grid) Voltage, Negative-bias value   |          | -100 max                       | volts                |
| Cathode Current   |          | 65 max                         | ma                   |
| Plate Dissipation   |          | 13.2 max                       | watts                |
| Grid-No.2 Input. Peak   |          | 4 max                          | watts                |
| Grid-No.2 Input, Average  |          | 2 max                          | watts                |
|   |          |                                |                      |
| CHARACTERISTICS AND TYPICAL OPERATION:  |          |                                |                      |
| Plate Supply Voltage  |          | 250                            | volts                |
| Grid-No.2 Supply Voltage  |          | 250                            | volts                |
| Cathode-Bias Resistor   |          | 135                            | ohms                 |
| Mu-Factor, Grid No.2 to Grid No.1   |          | 19                             | -                    |
| Plate Resistance (Approx.)  |          | 38000                          | ohms                 |
| Transconductance  |          | 11300                          | μmhos                |
| Peak AF Grid-No.1 Voltage   |          | 7.3                            | volts                |
| Zero-Signal Plate Current   |          | 48                             | ma                   |
| Maximum-Signal Plate Current  |          | 50.6                           | ma                   |
| Zero-Signal Grid-No.2 Current   |          | 5.5                            | ma                   |
| Maximum-Signal Grid-No.2 Current  |          | 10                             | ma                   |
| Effective Load Resistance   |          | 5200                           | ohms                 |
| Total Harmonic Distortion   |          | 10                             | per cent             |
| Maximum-Signal Power Output   |          | 5.7                            | watts                |
|   |          |                                |                      |



Push-Pull Class AB, and B Amplifier MAXIMUM RATINGS: (Same as for class A1 amplifier)

| TYPICAL OPERATION,                        | Class AB <sub>1</sub> |            | Class B    |            |       |
|---|-----------------------|------------|------------|------------|-------|
| (Values are for two tubes): Plate Voltage | 250<br>250            | 300<br>300 | 250<br>250 | 300<br>300 | volts |

|  | Class AB <sub>1</sub> |      |       | Class B |          |
|--|-----------------------|------|-------|---------|----------|
| Grid-No.1 Voltage                          | _                     | _    | -11.6 | -14.7   | volts    |
| Cathode-Bias Resistor                      | 130                   | 130  | _     | _       | ohms     |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage     | 22.4                  | 28   | 22.4  | 28      | volts    |
| Zero-Signal Plate Current                  | 62                    | 72   | 20    | 15      | ma       |
| Maximum-Signal Plate Current               | 75                    | 92   | 75    | 92      | ma       |
| Zero-Signal Grid-No.2 Current              | 7                     | 8    | 2.2   | 1.6     | ma       |
| Maximum-Signal Grid-No.2 Current           | 15                    | 22   | 15    | 22      | ma       |
| Effective Load Resistance (plate to plate) | 8000                  | 8000 | 8000  | 8000    | ohms     |
| Total Harmonic Distortion                  | 3                     | 4    | 3     | 4       | per cent |
| Maximum-Signal Power Output                | 11                    | 17   | 11    | 17      | watts    |


#### **MAXIMUM CIRCUIT VALUES:**

| Grid-No.1-Circuit Resistance: |         |        |
|-------------------------------|---------|--------|
| For fixed-bias operation      | 0.3 max |        |
| For cathode-bias operation    | 1 max   | megohm |

#### **DUAL TRIODE**

6GL7

Glass type containing high-mu triode and high-perveance, low-mu triode in same envelope. Used as combined vertical-deflection-oscillator and verticaldeflection-amplifier tube in television receivers. Outline 13B, Outlines sec-



tion. Tube requires octal socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 1.05; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

| CHARACTERISTICS:                 | Unit No.1 | Unit No.2  |       |
|----------------------------------|-----------|------------|-------|
| Plate Voltage                    | 250       | 175        | volts |
| Grid Voltage                     | <b>—3</b> | <b>—25</b> | volts |
| Amplification Factor             | 66        | 5          |       |
| Plate Resistance (Approx.)       | 30000     | 780        | ohms  |
| Transconductance                 | 2200      | 6400       | μmhos |
| Grid Voltage (Approx.):          |           |            |       |
| For plate current of 20 $\mu$ a  | -5.3      | _          | volts |
| For plate current of 200 $\mu$ a | _         | <b>-60</b> | volts |
| Plate Current                    | 2         | 46         | ma    |

## Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): | Unit No.1<br>Oscillator | Unit No.2<br>Amplifier |       |
|--|-------------------------|------------------------|-------|
| DC Plate Voltage                         | 350 max                 | 550 max                | volts |
| Peak Positive-Pulse Plate Voltage        | _                       | 1500□max               | volts |
| Peak Negative-Pulse Grid Voltage         | -400 max                | —250 max               | volts |
| Peak Cathode Current                     | _                       | 175 max                | ma    |
| Average Cathode Current                  | _                       | 50 max                 | ma    |
| Plate Dissipation •                      | 1 max                   | 10 max                 | watts |


#### **MAXIMUM CIRCUIT VALUES:**

Grid-Circuit Resistance:

| For fixed-bias operation   | 1 max   | 1 max megohm    |
|----------------------------|---------|-----------------|
| For cathode-bias operation | 2.2 max | 2.2 max megohms |

<sup>□</sup> The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

An adequate bias resistor or other means is required to protect the tube in the absence of excitation.



#### **POWER PENTODE**

Neonoval type used as power amplifier in radio receivers and audio amplifiers. Outline 10D, Outlines section. Tube requires neonoval ninecontact socket and may be mounted in any position. Heater volts (ac/dc),

**6GM5** 

6.3; amperes, 0.8; peak heater-cathode volts, 200 max (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| C | ass | A, | Am | oli | fier |
|---|-----|----|----|-----|------|
|   |     |    |    |     |      |

| MAXIMUM RATINGS (Design-Maximum Values): |         |          |
|--|---------|----------|
| Plate Voltage                            | 550 max | volts    |
| Grid-No.2 (Screen-Grid) Voltage          | 440 max | volts    |
| Cathode Current                          | 85 max  | ma       |
| Plate Dissipation                        | 19 max  | watts    |
| Grid-No.2 Input                          | 3.3*max | watts    |
| TYPICAL OPERATION AND CHARACTERISTICS:   |         |          |
| Plate Voltage                            | 300     | volts    |
| Grid-No.2 Voltage                        | 300     | volts    |
| Grid-No.1 (Control-Grid) Voltage         | -10     | volts    |
| Peak AF Grid-No.1 Voltage                | 10      | volts    |
| Zero-Signal Plate Current                | 60      | ma       |
| Maximum-Signal Plate Current             | 75      | ma       |
| Zero-Signal Grid-No.2 Current            | 8       | ma       |
| Maximum-Signal Grid-No.2 Current         | 15      | ma       |
| Plate Resistance (Approx.)               | 29000   | ohms     |
| Transconductance                         | 10200   | μmhos    |
| Load Resistance                          | 3000    | ohms     |
| Total Harmonic Distortion                | 13      | per cent |
| Maximum-Signal Power Output              | 11      | watts    |
|  |         |          |

<sup>\*</sup> Grid-No.2 input may reach 6 watts during peak levels of speech and music signals.



#### SEMIREMOTE-CUTOFF PENTODE

Miniature type used in gain-controlled picture-if stages of television receivers operating at intermediate frequencies in the order of 40 megacycles. Tube features high transconductance and relatively low capacitances. Outline

6GM6 Related types: 4GM6, 5GM6

----

5C, Outlines section. Tube requires seven-contact socket and may be mounted in any position. Types 4GM6 and 5GM6 are identical with type 6GM6 except for the heater ratings, as shown below.

|   | 4UM0        | JGM6               | 6GM6            |         |
|---|-------------|--------------------|-----------------|---------|
| Heater Voltage (ac/dc)  | 4.2         | 5.6                | 6.3             | volts   |
| Heater Current  | 0.6         | 0.45               | 0.4             | ampere  |
| Heater Warm-up Time (Average) Peak Heater-Cathode Voltage:    | 11          | 11                 | -               | seconds |
| Heater negative with respect to cathode                       | 200 max     | 200 max            | 200 max         | volts   |
| Heater positive with respect to cathode                       | 200 max     | 200 max<br>Without | 200 max<br>With | volts   |
|   |             | External           | External        |         |
| Direct Interelectrode Capacitances:                           |             | Shield             | Shield°         |         |
| Grid No.1 to Plate  | • • • • • • | 0.036 max          | 0.026 max       | pf      |
| Grid No.3, and Internal Shield                                |             | 10                 | 10              | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid and Internal Shield |             | 2.4                | 3.4             | pf      |
| The dc component must not exceed 100 volts.                   |             |                    |                 |         |


<sup>- ----</sup>

<sup>&</sup>quot;With external shield connected to cathode,

Class A, Amplifier

| 330 max       | volts v  |
|---------------|--|
| 0 max         | volts  |
| 330 max       | volts  |
| See cur       | rve page 75  |
|               |  |
| 3.1 max       | watts  |
|               |  |
| 0.65 max      | watt   |
| See cui       | rve page 75  |
|               |  |
| 125           | volts  |
| ted to cathod | e at socket  |
| 125           | volts  |
| 56            | ohms   |
| 0.2           | megohm   |
| 13000         | μmhos  |
| 15            | volts  |
| 14            | ma   |
| 3.4           | ma   |
|               | 0 max<br>3.1 max<br>0.65 max<br>See cut<br>125<br>ted to cathod<br>125<br>56<br>0.2<br>13000<br>15<br>14 |






#### HIGH-MU TRIODE-SHARP-CUTOFF PENTODE

Related types: 8GN8, 10GN8

Miniature type used in color and black-and-white television receivers. Triode unit is used as sync-separator, sync-clipper, phase inverter, or soundif amplifier. Pentode unit is used in output stage of video amplifier. Out-



line 6E, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. For direct interelectrode capacitances, refer to type 6EB8; curve for average plate characteristics of triode unit is same as for type 6EB8. Types 8GN8 and 10GN8 are identical with type 6GN8 except for the heater ratings, as shown below.

|                        | 6GN8 | 8GN8 | 10GN8 |        |
|------------------------|------|------|-------|--------|
| Heater Voltage (ac/dc) | 6.3  | 8    | 10.5  | volts  |
| Heater Current         | 0.75 | 0.6  | 0.45  | ampere |

| Heater Warm-up Time (Average)  | 6GN8<br>— | 8GN8<br>11 | 10GN8<br>11 | seconds |
|--|-----------|------------|-------------|---------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max   | 200 max    | 200 max     | volts   |
|  | 200°max   | 200°max    | 200°max     | volts   |

<sup>\*</sup> The dc component must not exceed 100 volts.


#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):              |         | Pentode Unit<br>330 max | volts   |
|---|---------|-------------------------|---------|
| Plate Voltage   | 330 max |                         |         |
| Grid-No.2 (Screen-Grid) Supply Voltage                |         | 330 max                 | volts   |
| Grid-No.2 Voltage                                     |         | See curve               | page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max   | 0 max                   | volt    |
| Plate Dissipation                                     | 1 max   | 5 max                   | watts   |
| Grid-No.2 Input:                                      |         |                         |         |
| For grid-No.2 voltages up to 165 volts                | _       | 1.1 max                 | watts   |
| For grid-No.2 voltages between 165 and 330 volts      |         | See curve               | page 75 |
|   |         |                         |         |

| CHARACTERISTICS:                                  | Triode Unit | Pento | de Unit |       |
|---|-------------|-------|---------|-------|
| Plate Supply Voltage                              | 250         | 60    | 200     | volts |
| Grid-No.2 Supply Voltage                          |             | 150   | 150     | volts |
| Grid-No.1 Voltage                                 |             | 0     |         | volts |
| Cathode-Bias Resistor                             | _           | _     | 100     | ohms  |
| Amplification Factor                              | 010         | -     | _       |       |
| Plate Resistance (Approx.)                        | 37000       | _     | 60000   | ohms  |
| Transconductance                                  | 2700        | _     | 11500   | μmhos |
| Grid Voltage (Approx.) for plate current of 20 μa | <b></b> 5   | -     | -       | volts |
| of 100 μa   |             | _     | -10     | volts |
| Plate Current                                     | 2           | 55=   | 25      | ma    |
| Grid-No.2 Current                                 | <u> </u>    | 18=   | 5.5     | ma    |

| MAXIMUM CIRCUIT VALUES:   | Triode Unit      | Pentode Unit                    |
|---|------------------|---------------------------------|
| Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation | 0.5 max<br>1 max | 0.25 max megohm<br>1 max megohm |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.




# 6GT5

Related types: 12GT5, 12GT5A, 17GT5, 17GT5A

#### **BEAM POWER TUBE**

Novar types used as horizontal-deflection amplifiers in television receivers. Outlines 17B and 31A, respectively, Outlines section. Tubes require novar nine-contact socket and may mounted in any position. For curve



of average characteristics, refer to type 6GW6. Types 12GT5 and 12GT5A and types 17GT5 and 17GT5A are identical with types 6GT5 and 6GT5A except for the heater ratings, as shown below.

|   | 6GT5<br>6GT5A | 12GT5<br>12GT5A | 17GT5<br>17GT5A |         |
|---|---------------|-----------------|-----------------|---------|
| Heater Voltage (ac/dc)                        | 6.3           | 12.6            | 16.8            | volts   |
| Heater Current                                | 1.2           | 0.6             | 0.45            | ampere  |
| Heater Warm-up Time (Average)                 | -             | 11              | 11              | seconds |
| Peak Heater-Cathode Voltage:                  |               | *               |                 |         |
| Heater negative with respect to cathode       | 200 max       | 200 max         | 200 max         | volts   |
| Heater positive with respect to cathode       | 200□max       | 200□max         | 200□max         | volts   |
| Direct Interelectrode Capacitances (Approx.): |               |                 |                 |         |
| Grid No.1 to Plate                            |               |                 | 0.26            | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, ar   | id Grid No    | .3              | 15              | pf      |
| Plate to Cathode, Heater, Grid No.2, and G    | rid No.3 .    |                 | 6.5             | pf      |

The dc component must not exceed 100 volts.

#### Class A, Amplifier

|  | Triode     | Pe   | ntode      |       |
|--|------------|------|------------|-------|
| CHARACTERISTICS:                             | Connection | Con  | nection    |       |
| Plate Voltage                                | 150        | 60   | 250        | volts |
| Grid-No.2 (Screen-Grid) Voltage              | 150        | 150  | 150        | volts |
| Grid-No.1 (Control-Grid) Voltage             | 22.5       | 0    | -22.5      | volts |
| Mu Factor, grid No.2 to grid No.1            | 4.4        | _    |            |       |
| Plate Resistance (Approx.)                   |            |      | 15000      | ohms  |
| Transconductance                             |            | _    | 7100       | μmhos |
| Plate Current                                | -          | 390* | 70         | ma    |
| Grid-No.2 Current                            | _          | 32*  | 2.1        | ma    |
| Grid-No.1 Voltage (Approx.) for plate ma = 1 | _          | -    | <b>—42</b> | volts |

<sup>\*</sup> These values can be measured by a method involving a recurrent waveform such that the plate dissipation and grid-No.2 input will will not exceed their maximum ratings.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values):

| William Coll Addition (Design Management Value) |           |       |
|---|-----------|-------|
| DC Plate Supply Voltage                         | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage               | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage               | -1500 max | volts |
| DC Grid-No.2 Voltage                            | 220 max   | volts |
| DC Grid-No.1 Voltage                            | 55 max    | volts |
| Peak Negative-Pulse Grid-No.1 Voltage           | —330 max  | volts |
| Peak Cathode Current                            | 550 max   | ma    |
| Average Cathode Current                         | 175 max   | ma    |
| Grid-No.2 Input                                 | 3.5 max   | watts |
| Plate Dissipation•                              | 17.5 max  | watts |
| Bulb Temperature (At hottest point)             | 240 max   | °C    |
|   |           |       |

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

For grid-resistor-bias operation• 1 max megohm

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- An adequate bias resistor or other means is required to protect the tube in the absence of excitation.


#### **BEAM HEXODE**

Miniature type used as rf amplifier in vhf television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 2GU5 is identical with type 6GU5 ex-

6GU5
Related type:
2GU5

cept for heater ratings, as shown below.

|   | 2GU5         | 6GU5            |           |
|---|--------------|-----------------|-----------|
| Heater Voltage (ac/dc)                              | 2.4          | 6.3             | volts     |
| Heater Current                                      | 0.6          | 0.22            | ampere    |
| Heater Warm-up Time (Average)                       | 11           | -               | seconds   |
| Peak Heater-Cathode Voltage:                        | ••           |                 | SCCOMOS   |
| Heater negative with respect to cathode             | 200 max      | 200 max         | volts     |
| Heater positive with respect to cathode             | 200 max      | 200 max         | volts     |
| Direct Interelectrode Capacitances:                 | avv mar      | 200 2222        | 10213     |
| Grid No.1 to Plate                                  |              | 0.018           | pf        |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.   |              | 0.010           | Pr        |
| and Grid No.4                                       |              | 7               | pf        |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and | Grid No 4    | 3.2             | pf        |
| 1 200 10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0            | . 0124 110.1 | 7.4             | PL        |
| • The dc component must not exceed 100 volts.       |              |                 |           |
| Class A. Amplifier                                  |              |                 |           |
| MAXIMUM RATINGS (Design-Maximum Values):            |              |                 |           |
| Plate Voltage                                       |              | 300 max         | volts     |
| Grid-No.2 (Screen-Grid) Voltage                     |              | 150 max         | volts     |
| DC Grid-No.1 (Control-Grid) Voltage:                |              | 100 11111       | , 0113    |
| Positive bias value                                 |              | 0 max           | volts     |
| Negative-bias value                                 |              | -50 max         | volts     |
| DC Cathode Current                                  |              | 20 max          | ma        |
| Plate Dissipation                                   |              | 3 max           | watts     |
| Grid-No.2 Input                                     |              |                 | megohm    |
|   |              | Old Millie      | megomin   |
| CHARACTERISTICS:                                    |              |                 |           |
| Plate Voltage                                       | 135          | 275             | volts     |
| Grid-No.2 Voltage                                   | 135          | 135             | volts     |
| Grid-No.1 Voltage                                   | -0.4         | -0.4            | volts     |
| Grid No.3   | Connec       | ted to cathode  | at socket |
| Plate Resistance (Approx.)                          | 0.67         | 0.165           | megohms   |
| Transconductance                                    | 15000        | 15500           | μmhos     |
| Plate Current                                       | 9            | 10              | ma        |
| Grid-No.2 Current                                   | 0.25         | 0.17            | ma        |
| Grid-No.1 Voltage (Approx.) for transconductance of |              |                 |           |
| 100 μmhos   | -6.2         | <del></del> б.5 | volts     |
|   |              |                 |           |



MAXIMUM CIRCUIT VALUE: Grid-No.1-Circuit Resistance:

For fixed-bias operation ......

#### MEDIUM-MU TWIN TRIODE

Miniature type used in the matrixing circuits of color television receivers employing series-connected heater strings. Also used in phase-inverter, multivibrator, and general purpose amplifier applications. Outline 6E,


**6GU7** 

0.5 max megohm


Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc) | 6.3 | volts          |
|------------------------|-----|----------------|
| Heater Current         | 0.6 | amper <b>e</b> |

| Heater Warm-up Time (Average)  | 11             | seconds                 |
|--|----------------|-------------------------|
| Heater negative with respect to cathode  | 200 max        | volts                   |
| Heater positive with respect to cathode  |                | volts                   |
| Direct Interelectrode Capacitances (Approx.): Unit N   | No.1 Unit No.2 | VOILS                   |
| Grid to Plate  |                | pf                      |
| Grid to Cathode and Heater   |                | pf                      |
| Plate to Cathode and Heater 0.4  |                | pf                      |
| Plate of Unit No.1 to Plate of Unit No.2   |                | pf                      |
|  |                | -                       |
| The dc component must not exceed 100 volts.  |                |                         |
| Class A. Amplifier (Each United MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation | 330 max        | volts<br>volts<br>watts |
| CHARACTERISTICS:   |                |                         |
| Plate Voltage  | 250            | volts                   |
| Grid Voltage   |                | volts                   |
| Amplification Factor   |                | 70113                   |
| Plate Resistance (Approx.)   |                | ohms                    |
| Transconductance   |                | µmhos                   |
| Grid Voltage (Approx.) for plate current of 50 µ2  |                | volts                   |
| Plate Current  | 11.5           | ma                      |
| Plate Current for grid voltage of -14 volts  | 4              | ma                      |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance:   |                |                         |




For fixed-bias operation .....



#### **BEAM POWER TUBE**

Related type: 17GV5

Duodecar type used as horizontal-deflection amplifier in television receivers. Outline 16A, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Type 17GV5 is identical



1 max megohm

with type 6GV5 except for the heater ratings, as shown below.

**6GV8** 

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode |          | 6GV5<br>6.3<br>1.2<br>—<br>200 max<br>200•max | 17GV5<br>16.8<br>0.45<br>11<br>200 max<br>200°max | volts<br>ampere<br>seconds<br>volts<br>volts |
|--|----------|---|---|--|
| • The dc component must not exceed 100 volts.  |          |   |   |  |
| Class A, A   | mplifier |   |   |  |
| CHARACTERISTICS:   |          |   |   |  |
| Plate Voltage  | 5000     | 60  | 250   | volts  |
| Grid-No.2 (Screen-Grid) Voltage  | 150      | 150   | 150   | volts  |
| Grid-No.1 (Control-Grid) Voltage   | _        | 0   | -22.5   | volts  |
| Plate Resistance (Approx.)   | _        | _   | 18000   | ohms   |
| Transconductance   |          | _   | 7300  | μmhos  |
| Triode Amplification Factor  | _        | _   | 4.4*  | -  |
| Plate Current  | _        | 345=  | 65  | ma   |
| Grid-No.2 Current  | _        | 27•   | 1.8   | ma   |
| of 1 ma  | 100      | _   | <b>—42</b>  | volts  |


\* Grid No.2 tied to plate: plate and grid-No.2 volts, 150; grid-No.1 volts, -22.5.

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

| For operation in a 525-line, 30-frame system |           |       |
|--|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |           |       |
| DC Plate Supply Voltage                      | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage#           | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage            | -1500 max | volts |
| DC Grid-No.2 Voltage                         | 220 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage        | -330 max  | volts |
| DC Grid-No.1 Voltage                         | 55 max    | volts |
| Peak Cathode Current                         | 550 max   | ma    |
| Average Cathode Current                      | 175 max   | ma    |
| Plate Dissipation†                           | 17.5 max  | watts |
| Grid-No.2 Input                              | 3.5 max   | watts |
| Bulb Temperature (At hottest point)          | 200 max   | °C    |
| MAXIMUM CIRCUIT VALUES:                      |           | •     |

#### HIGH-MU TRIODE— POWER PENTODE



excitation.

Miniature type used for sync-amplifier and video-output applications Kp in television receivers. Outline 6G, G3p Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Heater volts

(ac/dc), 6.3; amperes, 0.9; peak heater-cathode volts, 220.

ak heater-cathode volts,

Class A, Amplifier MAXIMUM RATINGS (Absolute-Maximum Values): Triode Unit Pentode Unit Plate Supply Voltage ..... 550 max 550 max volts Peak Plate Voltage° 2000 max volts DC Plate Voltage 250 max 250 max volts Grid-No.2 (Screen-Grid) Supply Voltage ..... 550 max volts Grid-No.2 Voltage ..... 250 max volts Peak Cathode Current. 200 max ma Average Cathode Current ...... 15 max 75 max ma Grid-No.2 Input ..... 2 max watts Plate Dissipation ..... 0.5 max 7 max watts


| CHARACTERISTICS: Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 Voltage | Triode Unit<br>100<br>-<br>-0.8 | 50<br>170 | ntode<br>65<br>210<br>—1 | 170<br>170 | volts<br>volts |
|---|---------------------------------|-----------|--------------------------|------------|----------------|
| Amplification Factor  | 50                              |           |                          |            |                |
| Mu-Factor, Grid No.1 to Grid No.2   |                                 | _         | _                        | 7          |                |
| Plate Resistance (Approx.)  | 7600                            | _         | -2                       | 5000       | ohms           |
| Transconductance  | 6500                            |           |                          | 7500       | μmhos          |
| Plate Current   | 5                               | 200       | 240•                     | 41         | ma             |
| Grid-No.2 Current   | -                               | 404       | 50•                      | 2.7        | ma             |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:                                   |                                 |           |                          |            |                |
| For fixed-bias operation  | 1 max                           |           | 1 :                      | max        | megohm         |
| For cathode-bias operation  | 3.3 max                         |           | 2.2                      | max        | megohms        |

- \* Maximum pulse duration 5 per cent of a cycle with a maximum of 1 millisecond.
- Maximum pulse duration 200 microseconds. If a larger flyback is required, this value may be reduced to 100 ma with a maximum pulse duration of 400 microseconds.
- This value can be measured by a method involving a recurrent waveform such that the maximum tube ratings will not be exceeded.

#### **BEAM POWER TUBE**

6GW6
Related types:
12GW6, 17GW6

Glass octal type used as horizontaldeflection amplifier in high-efficiency deflection circuits of television receivers. Outline 20, Outlines section. Tube requires octal socket and may be operated in any position. Types



12GW6 and 17GW6 are identical with type 6GW6 except for the heater ratings, as shown below.

|   | 6GW6      | 12GW6     | 17GW6   |         |
|---|-----------|-----------|---------|---------|
| Heater Voltage (ac/dc)                        | 6.3       | 12.6      | 16.8    | volts   |
| Heater Current                                | 1.2       | 0.6       | 0.45    | ampere  |
| Heater Warm-up Time (Average)                 |           | 11        | 11      | seconds |
| Peak Heater-Cathode Voltage:                  |           |           |         |         |
| Heater negative with respect to cathode       | 200 ma:   | x 200 max | 200 max | volts   |
| Heater positive with respect to cathode       | 200□ma:   | k 200⊏max | 200□max | volts   |
| Direct Interelectrode Capacitances (Approx.): |           |           |         |         |
| Grid No.1 to Plate                            |           |           | 0.5     | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, an   | id Grid N | o.3       | 17      | pf      |
| Plate to Cathode, Heater, Grid No.2, and Gr   | id No.3.  |           | 7       | pf      |
|   |           |           |         |         |

□ The dc component must not exceed 100 volts.

#### Class A, Amplifier

| CHARACTERISTICS:                                      |      |       |       |
|---|------|-------|-------|
| Plate Voltage   | 60   | 250   | volts |
| Grid-No.2 Voltage                                     | 150  | 150   | volts |
| Grid-No.1 Voltage                                     | 0    | -22.5 | volts |
| Plate Resistance (Approx.)                            | _    | 15000 | ohms  |
| Transconductance                                      |      | 7100  | μmhos |
| Plate Current   | 390* | 70    | ma    |
| Grid-No.2 Current                                     | 32*  | 2.1   | ma    |
| Grid-No.1 Voltage (Approx.) for plate current of 1 ma | _    | -42   | voits |
|   |      |       |       |

\* This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|--|-----------|-------|
| DC Plate Supply Voltage                  | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage        | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage        | -1500 max | volts |
| DC Grid-No.2 (Screen-Grid) Voltage       | 220 max   | volts |
| DC Grid-No.1 (Control-Grid) Voltage      | —55 max   | volts |


| Peak Negative-Pulse Grid-No.1 Voltage | -330 max | volts |
|---------------------------------------|----------|-------|
| Peak Cathode Current                  | 550 max  | ma    |
| Average Cathode Current               | 175 max  | ma    |
| Grid-No.2 Input                       | 3.5 max  | watts |
| Plate Dissipation•                    | 17.5 max | watts |
| Bulb Temperature (At hottest point)   | 240 max  | °C    |
| MAXIMIM CIPCIIT VALUES.               |          |       |


Grid-No.1-Circuit Resistance:

For grid resistor-bias operation .....

1 max megohm

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle.
   In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- An adequate bias resistor or other means is required to protect the tube in the absence of excitation.





#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Kp. G3p Miniature type used in preamplifier and audio output stages of audio equipment and television receivers.

Outline 6G, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

## 6GW8/ ECL86

Heater volts (ac/dc), 6.3; amperes, 0.7; peak heater-cathode volts, 100.

| Glass A <sub>1</sub> Ampine                           |             |              |       |
|---|-------------|--------------|-------|
| MAXIMUM RATINGS (Design-Center Values):               | Triode Unit | Pentode Unit |       |
| Plate Supply Voltage                                  | 550 max     | 550 max      | volts |
| Plate Voltage   | 300 max     | 300 max      | volts |
| Grid-No.2 (Screen-Grid) Supply Voltage                | _           | 550 max      | volts |
| Grid-No.2 Voltage                                     | _           | 300 max      | volts |
| Grid-No.1 (Control-Grid) Voltage, Negative-bias value | -1.3 max    | —1.3 max     | volts |
| Cathode Current                                       | 55 max      | 8 max        | ma    |
| Plate Dissipation                                     | 0.5 max     | 9 max        | watts |
| Grid-No.2 Input                                       | -           | 1.5 max      | watts |
| CHARACTERISTICS:                                      |             |              |       |
| Plate Voltage   | 250         | 250          | volts |
| Grid-No.2 Voltage                                     | _           | 250          | volts |
| Grid-No.1 Voltage                                     | -1.7        | <b>—7</b>    | volts |
| Amplification Factor                                  | 100         | 21*          |       |
| Plate Resistance (Approx.)                            | -           | 45000        | ohms  |
| Transconductance                                      | 1600        | 10000        | μmhos |
| Plate Current   | 1.2         | 36           | ma    |
| Grid-No.2 Current                                     | _           | 5.5          | ma    |
| * Grid No.2 to grid No.1.                             |             |              |       |

#### SHARP-CUTOFF PENTODE

6GX6
Related type:
5GX6

For fixed-bias operation

For cathode-bias operation .....


Miniature type used for FM sounddetector service in locked-oscillator, quadrature-grid FM detector circuits, as combined detector, limiter, and audio-voltage driver. Tube has two independent control grids, and has





0.22 max megohm 0.47 max megohm

independent control grids, and has controlled heater warm-up time for use in circuits employing series-connected heater strings. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 5GX6 is identical with type 6GX6 except for the heater ratings, as shown below.

|  | 5GX6        | 6GX6             |             |
|--|-------------|------------------|-------------|
| Heater Voltage (ac/dc)   | 4.7         | 6.3              | volts       |
| Heater Current   | 0.6         | 0.45             | ampere      |
| Heater Warm-up Time (Average)  | 11          | 11               | seconds     |
| Peak Heater-Cathode Voltage:   |             |                  |             |
| Heater negative with respect to cathode  | 200 max     | 200 max          | volts       |
| Heater positive with respect to cathode  | 200 = max   | 200 <b>=</b> max | volts       |
| Direct Interelectrode Capacitances (Approx.):  |             |                  | _           |
| Grid No.1 to Plate   |             | 0.026            | pf          |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, ar   | nd Internal |                  | _           |
| Shield   |             | 8                | pf          |
| Grid No.1 to Grid No.3   |             | 0.12             | pf          |
| Grid No.3 to Plate   |             | 1.6              | pf          |
| Grid No.3 to Cathode, Heater, Grid No.1, Grid No.2,  |             |                  |             |
| Internal Shield  |             | 6.5              | pf          |
| <ul> <li>The dc component must not exceed 100 volts.</li> </ul>  |             |                  |             |
| -  |             |                  |             |
| Class A, Amplifier   |             |                  |             |
| CHARACTERISTICS:   |             |                  |             |
| Plate Supply Voltage   |             | 150              | volts       |
| Grid-No.3 Supply Voltage   |             | 0                | volts       |
| Grid-No.2 Supply Voltage   |             | 100              | volts       |
| Grid-No.1 Supply Voltage   |             | 0                | volts       |
| Cathode-Bias Resistor  |             | 180              | ohms        |
| Plate Resistance (Approx.)   |             | 0.14             | megohm      |
| Transconductance, grid No.1 to plate   |             | 3700             | μmhos       |
| Transconductance, grid No.3 to plate   |             | 750              | μmhos       |
| Plate Current  |             | 3.7              | ma          |
| Grid-No.2 Current  |             | _7<br>_7         | ma<br>volts |
| Grid-No.3 Supply Voltage (Approx.) for plate current of 20   | μa          | /<br>4.5         | volts       |
| Grid-No.1 Supply Voltage (Approx.) for plate current of 20   | μ <b>a</b>  | -4.3             | VOILS       |
| FM Sound Detector  | į.          |                  |             |
|  |             |                  |             |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage   |             | 300 max          | volts       |
| Grid-No.3 (Control-Grid) Voltage:  |             | Joo max          | 10113       |
| Negative value (dc and peak ac)  |             | -100 max         | volts       |
| Positive value (dc and peak ac)  |             | 25 max           | volts       |
| Grid-No.2 (Screen-Grid) Supply Voltage   |             | 300 max          | volts       |
| Grid-No.2 Voltage  |             | See curv         | e page 75   |
| Grid-No.1 (Control-Grid) Voltage:  |             |                  | • •         |
| Negative-bias value  |             | -50 max          | volts       |
| Positive-bias value  |             | 0 max            | volts       |
| Plate Dissipation  |             | 1.7 max          | watts       |
| Grid-No.3 Input  |             | 0.1 max          | watt        |
| Grid-No.2 Input:   |             |                  |             |
| For grid-No.2 voltages up to 150 volts   |             | 1.0 max          | watt        |
| For grid-No.2 voltages between 150 and 300 volts   |             | See curv         | e page 75   |
| MAXIMUM CIRCUIT VALUES:  |             |                  |             |
| Grid-No.3-Circuit Resistance   |             | 0.68 max         | megohm      |
| Grid-No.1-Circuit Resistance:  |             |                  |             |
| The state of the s |             | 0.22 may         | macchm      |







#### SHARP-CUTOFF PENTODE

Miniature type used in gated-agc-amplifier circuits and as a noise-inverter tube in television receivers. Tube has two independent control grids, and has controlled heater warm-up time for use in circuits employing series-

6GY6

connected heater strings. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. For curves of average characteristics, refer to type 6GX6.

| Heater Voltage (ac/dc)        | 6.3  | volts   |
|-------------------------------|------|---------|
| Heater Current                | 0.45 | ampere  |
| Heater Warm-up Time (Average) | 11   | seconds |

| 310   | KCA         | Receiving      | 1 noe            | Manuai                |
|---|-------------|----------------|------------------|-----------------------|
| Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode. |             |                | 200 ma<br>200•ma |                       |
| Direct Interelectrode Capacitances: Grid No.1 to Plate  |             |                | 0.026            | pf                    |
| Shield  |             |                | 8                | pf                    |
| Grid No.1 to Grid No.3  |             |                | 0.12             | pf                    |
| Grid No.3 to Plate  |             |                | 1.6              | pf                    |
| Grid No.3 to Cathode, Heater, Plate, Gr<br>Internal Shield  |             |                | 6.5              | pf                    |
| • The dc component must not exceed 100 vo   | olts.       |                |                  |                       |
| Class A   | A, Amplifie | er             |                  |                       |
| CHARACTERISTICS:  |             |                |                  |                       |
| Plate Supply Voltage  |             |                | 150              | volts                 |
| Grid-No.3 Supply Voltage  |             |                | 0<br>100         | volts<br>volts        |
| Grid-No.2 Supply Voltage  |             |                | 0                | volts                 |
| Cathode-Bias Resistor   |             |                | 180              | ohms                  |
| Plate Resistance (Approx.)  |             |                | 0.14             | megohm                |
| Transconductance, Grid No.1 to Plate  |             |                | 3700             | $\mu$ mhos            |
| Transconductance, Grid No.3 to Plate  |             |                | 750              | μhmos                 |
| Plate Current   |             |                | 3.7              | ma                    |
| Grid-No.2 Current   |             |                | 3<br>7           | ma<br>volts           |
| Grid-No.1 Supply Voltage (Approx.) for plate  | current of  | 20 μa<br>20 μa | -4.5             | volts                 |
| Gated AGC Amplif  |             |                |                  |                       |
| · · · ·   |             | -mame system   |                  |                       |
| MAXIMUM RATINGS (Design-Maximum \ Plate Voltage   |             |                | 300 ma           | x volts               |
| Peak Positive-Pulse Plate Voltage   |             |                | 600 ma           |                       |
| Grid-No.3 (Control-Grid) Voltage:   |             |                |                  |                       |
| Negative-bias value   |             |                | —100 ma          |                       |
| Positive-bias value   |             |                | 0 ma             |                       |
| Grid-No.2 (Screen-Grid) Supply Voltage  |             |                | 300 ma           |                       |
| Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage:   |             |                | See cu           | rve page 75           |
| Negative-bias value   |             |                | -50 ma           | x volts               |
| Positive-bias value   |             |                | 0 ma             |                       |
| Plate Dissipation   |             |                | 1.7 ma           | x watts               |
| Grid-No.2 Input:  |             |                | _                |                       |
| For grid-No.2 voltages up to 150 volts<br>For grid-No.2 voltages between 150 and                              | 300 volts   |                | 1 ma<br>See cu   | x watt<br>rve page 75 |
| MANUFACING CINCILLY WATTIES.  |             |                |                  |                       |
| MAXIMUM CIRCUIT VALUES: Grid-No.3-Circuit Resistance  |             |                | 0.68 ma          | x megohm              |
| Olig-No.5-Circuit Resistance  |             |                | 0.00 IIIa        | . megoniii            |

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

For fixed-bias operation .....


For cathode-bias operation .....

#### HIGH-MU TRIPLE TRIODE

6GY8

Grid-No.1-Circuit Resistance:

Miniature type used in rf-amplifier, mixer, and automatic-frequency-control service in FM radio receivers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position.



0.22 max megohm

0.47 max megohm

Heater volts (ac/dc), 6.3; amperes, 0.45; peak heater-cathode volts, 100.

Class A, Amplifier

| Values are for each unit, exce                          | pt as noted |              |       |
|---|-------------|--------------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage  |             | 330 max      | volts |
| Grid Voltage, Positive-bias value                       |             | 0 max        | volts |
| Plate Dissipation                                       |             | 2 max        | watts |
| Total Plate Dissipation (All plates)                    |             | 5 max        | watts |
|   | Unit        | Units        |       |
| CHARACTERISTICS:  | No.1        | No.2 or No.3 |       |
| Plate Supply Voltage                                    | 125         | 125          | volts |
| Grid Voltage  |             | -1           | volts |
| Cathode-Bias Resistor                                   | 220         | _            | ohms  |
| Amplification Factor                                    | 63          | 63           |       |
| Plate Resistance (Approx.)                              | 14000       | 14000        | ohms  |
| Transconductance  | 4500        | 4500         | μmhos |
| Plate Current   | 4.5         | 4.5          | ma    |
| Grid Voltage (Approx.), for plate current of 20 $\mu a$ | _           | -4           | volts |



#### **POWER PENTODE**

Miniature type used in audio output stages of radio and television receivers employing series-connected heater strings. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any

Related type: 4G75

6GZ5

1 max megohm

position. Type 4GZ5 is identical with type 6GZ5 except for the heater ratings, as shown below.

4GZ5

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)  | 4G25<br>4<br>0.6<br>11 | 6.3<br>0.38        | volts<br>ampere<br>seconds |
|--|------------------------|--------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max<br>200=max     | 200 max<br>200•max | volts<br>volts             |
| The dc component must not exceed 100 volts.  |                        |                    |                            |
| Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values):  |                        |                    |                            |
| Plate Voltage  |                        | 300 max            | volts                      |
| Grid-No.2 (Screen-Grid) Voltage  |                        | 300 max            | volts                      |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  |                        | 0 max              | volts                      |
| Average Cathode Current  |                        | 30 max             | ma                         |
| Plate Dissipation  |                        | 4.8 max            | watts                      |
| Grid-No.2 Input  |                        | 1.1 max            | watts                      |
| Bulb temperature (At hottest point)  |                        | 200 max            | •c                         |
| TYPICAL OPERATION:   |                        |                    |                            |
| Plate Supply Voltage   | 250                    | 250                | volts                      |
| Grid-No.2 Supply Voltage   | 250                    | 250                | volts                      |
| Cathode-Bias Resistor  | 270                    | 270•               | ohms                       |
| Peak AF Grid-No.1 Voltage  | 9.8                    | 2,3                | volts                      |
| Zero-Signal Plate Current  | 16                     | 16                 | ma                         |
| Maximum-Signal Plate Current   | 16                     | 16                 | ma                         |
| Zero-Signal Grid-No.2 Current  | 2.7                    | 2.7                | ma                         |
| Maximum-Signal Grid-No.2 Current   | 5                      | -:-                | ma                         |
| Plate Resistance (Approx.)   | _                      | 0.15               | megohm                     |
| Transconductance   | _                      | 8400               | umhos                      |
| Load Resistance  | 15000                  | 15000              | ohms                       |
| Total Harmonic Distortion  | 10                     | 10                 | per cent                   |
| Maximum-Signal Power Output  | 1.8                    | 1.1                | watts                      |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:  |                        |                    |                            |
| For fixed-bias operation   |                        | 05 max             | megohm                     |
|  |                        | U.J IIIAA          | THE POINT                  |

For cathode-bias operation .....

· Bypassed.

#### TWIN DIODE

6H6 Related type: 12H6 Metal type used as detector, low-voltage rectifier, and ave tube. Except for the common heater, the two diode units are independent of each other. For diode detector considerations, refer to Electron Tube Applica-



tions section. Type 12H6 is identical with type 6H6 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)                      | 6H6<br>6.3 | 12H6<br>12.6 | volts  |
|---|------------|--------------|--------|
| Heater Current Peak Heater-Cathode Voltage: | 0.3        | 0.15         | ampere |
| Heater negative with respect to cathode     | 330 max    | 330 max      | volts  |
| Heater positive with respect to cathode     | 330 max    | 330 max      | volts  |
| Rectifier or Doub                           | ler        |              |        |
| MAXIMUM RATINGS:                            |            |              |        |
| Peak Inverse Plate Voltage                  |            | 420 max      | volts  |
| Peak Plate Current (Per Plate)              |            | 48 max       | ma     |
| DC Output Current (Per Plate)               |            | 8 max        | ma     |
| TYPICAL OPERATION AS HALF-WAVE RECTIFIER*:  |            |              |        |
| AC Plate Voltage (Per Plate, rms)           | 117        | 150          | volts  |
| (Per Plate)°                                | 15         | 40           | ohms   |
| DC Output Current (Per Plate)               | 8          | 8            | ma     |
| TYPICAL OPERATION AS VOLTAGE DOUBLER:       | Half-Wave  | Full-Wave    |        |
| AC Plate Voltage (Per Plate, rms)           | 117        | 117          | volts  |
| Min. Total Effective Plate-Supply Impedance |            |              |        |
| (Per Plate)°                                | 30         | 15           | ohms   |
| DC Output Current                           | 8          | 8            | ma     |

<sup>\*</sup> In half-wave service, the two units may be used separately or in parallel.

#### Installation and Application

Type 6H6 requires an octal socket and may be mounted in any position. Outline 29B, Outlines section.

For detection, the diodes may be utilized in a full-wave circuit or in a half-wave circuit. In the latter case, one plate only, or the two plates in parallel, may be employed. For the same signal voltage, the use of the half-wave arrangement will provide approximately twice the rectified voltage as compared with the full-wave arrangement.


For automatic volume control, the 6H6 may be used in circuits similar to those employed for any of the twin-diode types of tubes. The only difference is that the 6H6 is more adaptable because each diode has its own separate cathode.

6H6GT

#### TWIN DIODE

Discontinued type; see chart at end of section for tabulated data.

 $<sup>^{\</sup>circ}$  When a filter-input capacitor larger than 40  $\mu f$  is used, it may be necessary to use more plate-supply impedance than the value shown to limit the peak plate current to the rated value.



#### HIGH-MU TRIODE

Miniature type used as rf-amplifier tube in vhf television tuners. Outline 5A, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 6HA5 and related type 3HA5

6HA5
Related type:
3HA5

are electrically identical with miniature types 6HM5/6HA5 and 3HM5/3HA5, respectively.



#### **BEAM POWER TUBE**

Duodecar type used as horizontal-deflection amplifier in television receivers. Outline 15B, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Heater volts (ac/dc).

6HB5

6.3; amperes, 1.5; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Class A, Amplifier

| CHARACTERISTICS:                              |      |      |       |       |
|---|------|------|-------|-------|
| Plate Voltage                                 | 5000 | 60   | 130   | volts |
| Grid-No.2 (Screen-Grid) Voltage               | 130  | 130  | 130   | volts |
| Grid-No.1 (Control-Grid) Voltage              |      | 0    | -20   | volts |
| Triode Amplification Factor                   |      | _    | 4.7*  |       |
| Plate Resistance (Approx.)                    | _    | _    | 11000 | ohms  |
| Transconductance                              |      | _    | 9100  | μmhos |
| Plate Current                                 | _    | 410= | 50    | ma    |
| Grid-No.2 Current                             | _    | 24=  | 1.75  | ma    |
| Grid-No.1 Voltage (Approx.) for plate current |      |      |       |       |
| of 1 ma                                       | 66   |      | 33    | volts |

\* Grid No.2 tied to plate; plate and grid-No.2 volts, 130; grid-No.1 volts, -20.

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|--|-----------|-------|
| DC Plate Supply Voltage                  | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage#       | 6000 max  | volts |
| Peak Negative-Pulse Plate Voltage        | -1500 max | volts |
| DC Grid-No.2 Voltage                     | 220 max   | volts |
| DC Grid-No.1 Voltage                     | 55 max    | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -330 max  | volts |
| Peak Cathode Current                     | 800 max   | ma    |
| Average Cathode Current                  | 230 max   | ma    |
| Plate Dissipation†                       | 18 max    | watts |
| Grid-No.2 Input                          | 3.5 max   | watts |
| Bulb Temperature (At hottest point)      | 220 max   | •c    |

#### MAXIMUM CIRCUIT VALUE:

Grid-No.1-Circuit Resistance .....

1 max megohm


#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds. † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

**KHRK** 

#### **POWER PENTODE**

6HB6
Related type:
15HB6

Miniature type used as vertical deflection-amplifier tube in television receivers. Outline 6G, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 15HB6 is identical



15HR6

with type 6HB6 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)  Heater Current  Heater Warm-up Time (Average)  Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode  | <br>                                   | 6.3<br>0.76<br>—<br>200 max<br>200°max | 14.7<br>0.3<br>11<br>200 max<br>200°max                      | volts<br>ampere<br>seconds<br>volts<br>volts        |
|--|--|--|--|---|
| The dc component must not exceed 100 volts.  |  |  |  |   |
| CHARACTERISTICS: Plate Supply Voltage Grid No.3 Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Mu-Factor, Grid No.2 to Grid No.1 Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 µa | 250<br>0<br>-<br>-<br>-<br>150•<br>37• | 125<br>                                | 250 sted to cathode 250 — 100 33 24000 20000 40 6.2 —13      | volts<br>volts<br>ohms<br>ohms<br>µmhos<br>ma<br>ma |
| <ul> <li>This value can be measured by a method inv<br/>maximum tube ratings will not be exceeded.</li> </ul>  | olving                                 | a recurrent wa                         | veform such  | that the  |
| Vertical-Deflectic For operation in a 525-lir MAXIMUM RATINGS (Design-Maximum Values DC Plate Voltage Peak Positive-Pulse Plate Voltage DC Grid-No.2 (Screen-Grid) Voltage DC Grid-No.1 (Control-Grid) Voltage Grid-No.2 Input Plate Dissipation                                       | ne, 30-fi                              | ame system                             | 350 max<br>2500 max<br>300 max<br>100 max<br>2 max<br>10 max | volts<br>volts<br>volts<br>volts<br>watts           |

The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical-scanning cycle is 2.5 milliseconds,


#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**6HB7** 

MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation .....

For cathode-bias operation ......

Miniature type used as combined oscillator and mixer tube in television
receivers utilizing an intermediate frequency in the order of 40 megacycles
per second, and employing seriesconnected heater strings. Outline 6B.



1 max megohm

2.2 max megohms


Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc) Heater Current                            | 6.3<br>0.45 | volts<br>ampere |
|--|-------------|-----------------|
| Heater Warm-up Time (Average)                                    | 11          | seconds         |
| Peak Heater-Cathode Voltage:                                     |             |                 |
| Heater negative with respect to cathode                          | 200 max     | volts           |
| Heater positive with respect to cathode                          | 200•max     | volts           |
| Direct Interelectrode Capacitances:4                             |             |                 |
| Triode Unit:   |             |                 |
| Grid to Plate  | 1.9         | pf              |
| Grid to Cathode, Heater, Pentode Grid No.3, and Internal Shield  | 3           | pf              |
| Plate to Cathode, Heater, Pentode Grid No.3, and Internal Shield | 1.9         | pf              |
| Pentode Unit:  |             | -               |
| Grid No.1 to Plate   | 0.010 max   | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and          |             | •               |
| Internal Shield  | 5           | pf              |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal     | •           |                 |
| Shield   | 3.4         | pf              |
| Heater to Cathode.   | 3.8         | pf              |
| Treater to Camboo-   | 5.0         | P               |
| • The dc component must not exceed 100 volts.                    |             |                 |

- A With external shield connected to cathode except as noted.
- With external shield connected to ground.

Class A Amplifier

| Class A <sub>1</sub> Ampliner                    |             |                   |
|--|-------------|-------------------|
| MAXIMUM RATINGS (Design-Maximum Values):         | Triode Unit | Pentode Unit      |
| Plate Voltage                                    | 330 max     | 330 max volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage           | -           | 330 max volts     |
| Grid-No.2 Voltage                                | _           | See curve page 75 |
| Grid-No.1 (Control-Grid) Voltage:                |             |                   |
| Positive-bias value                              | 0 max       | 0 max volts       |
| Plate Dissipation                                | 2.5 max     | 3.1 max watts     |
| Grid-No.2 Input:                                 |             |                   |
| For grid-No.2 voltages up to 165 volts           | _           | 0.55 max watt     |
| For grid-No.2 voltages between 165 and 330 volts | _           | See curve page 75 |
|  |             |                   |



| CHARACTERISTICS:  | Triode Unit | Pentode Unit |        |
|---|-------------|--------------|--------|
| Plate Supply Voltage  | 150         | 125          | volts  |
| Grid-No.2 Supply Voltage                                    | _           | 125          | volts  |
| Grid-No.1 Supply Voltage                                    | 0           | -1           | volts  |
| Cathode-Bias Resistor                                       | 56          | _            | ohms   |
| Amplification Factor  | 40          | _            |        |
| Plate Resistance (Approx.)                                  | 0.005       | 0.2          | megohm |
| Transconductance  | 8500        | 6400         | μmhos  |
| Plate Current   | 18          | 12           | ma     |
| Grid-No.2 Current   | _           | 4            | ma     |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu a$ | -12         | <b>-9</b>    | volts  |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:

For fixed-bias operation

For cathode-bias operation


Triode Unit

0.5 max

0.25 max megohm

1 max


0.5 max megohm



#### BEAM POWER TUBE

6HE5

Duodecar type used as vertical-deflection amplifier in television receivers. Outline 8D, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Heater volts (ac/dc),



6.3; amperes, 0.8; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

### Class A, Amplifier

| CHARACTERISTICS:   |      |           |          |
|--|------|-----------|----------|
| Plate Voltage  | 60   | 250       | volts    |
| Grid-No.2 (Screen-Grid) Voltage                              | 250  | 250       | volts    |
| Grid-No.1 (Control-Grid) Voltage                             | 0    | <b>20</b> | volts    |
| Plate Resistance (Approx.)                                   | _    | 50000     | ohms     |
| Transconductance   |      | 4100      | μmhos    |
| Plate Current  | 180• | 43        | ma       |
| Grid-No.2 Current  | 20=  | 3.5       | ma       |
| Grid-No.1 Voltage (Approx.) for plate current of 100 $\mu$ a | _    | 50        | volts    |
|  |      | 6         | 46-4 46- |

 This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.


# Vertical Deflection Amplifier For operation in a 525-line, 30-frame system

| For operation in a 323-time, 30-traine system |          |       |
|---|----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):      |          |       |
| DC Plate Voltage                              |          | volts |
| Peak Positive-Pulse Plate Voltage#            | 2500 max | volts |
| Grid-No.2 Voltage                             | 300 max  | volts |
| Peak Cathode Current                          | 260 max  | ma    |
| Average Cathode Current                       | 75 max   | ma    |
| Plate Dissipation;                            | 12 max   | watts |
| Grid-No.2 Input†                              | 2.75 max | watts |
| Bulb Temperature (At hottest point)           | 200 max  | °C    |
|   |          |       |

# MAXIMUM CIRCUIT VALUES:

For fixed-bias operation 1 max megohm For cathode-bias operation 2.2 max megohms

#The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds. † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.



#### **BEAM POWER TUBE**

Duodecar type used as horizontal-deflection amplifier in color television receivers. Outline 16B, **Outlines** section. Tube requires duodecar twelvecontact socket and may be mounted in any position. Heater volts (ac/dc),

6HF5

6.3; amperes, 2.25; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

# Class A, Amplifier

| 5000        | 70           | 175   | volts   |
|-------------|--------------|---|---|
| 125         | 125          | 125   | volts   |
| _           | 0            | -25   | volts   |
|             | _            | 3*  |   |
| _           | _            | 5600  | ohms  |
| _           | -            | 11300   | $\mu$ mhos  |
|             | 570 <b>-</b> | 125   | ma  |
| <del></del> | 34=          | 4.5   | ma  |
|             |              |   |   |
| -140        | -            | 54  | volts   |
|             | 125          | 5000 70<br>125 125<br>— 0<br>— — —<br>— — —<br>— 570• | 5000 70 175<br>125 125 125<br>- 0 -25<br>3*<br>5600<br>11300<br>- 570• 125<br>- 34• 4.5 |

- \* Grid No.2 tied to plate; plate and grid-No.2 volts, 125; grid-No.1 volts, -25.
- This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.


#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM KATINGS (Design-Maximum values).              |                   |       |
|---|-------------------|-------|
| DC Plate Supply Voltage                               |                   | volts |
| Peak Positive-Pulse Plate Voltage# (Absolute Maximum) | 7500 <b>⁴</b> max | volts |
| Peak Negative-Pulse Plate Voltage                     | -1100 max         | volts |
| DC Grid-No.2 Voltage                                  | 190 max           | volts |
| Peak Negative-Pulse Grid-No.1 Voltage                 | -250 max          | volts |
| Peak Cathode Current                                  | 1100 max          | ma    |
| Average Cathode Current                               | 315 max           | ma    |
| Plate Dissipation†                                    | 28 max            | watts |
| Grid-No.2 Input                                       | 5.5 max           | watts |
| Bulb Temperature (At hottest point)                   | 225 max           | *C    |

#### MAXIMUM CIRCUIT VALUE:

- #The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- <sup>4</sup> Under no circumstances should this absolute value be exceeded.
- † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.



# HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receivers. The triode unit is used in high-gain, sound-if stages and in sync-separator, sync-clipper, and phase-inverter circuits; pentode unit is used as video-

OHF8
Related type:

output amplifier. Outline 6E, Outlines section. Tube requires miniature ninecontact socket and may be operated in any position. For curves of average characteristics, refer to type 6AW8A for the triode unit and to type 6EB8 for the pentode unit. Type 10HF8 is identical with type 6HF8 except for the heater ratings, as shown below.

|   |            | 6HF8                    | 10HF8     |           |
|---|------------|-------------------------|-----------|-----------|
| Heater Voltage (ac/dc)                          |            | 6.3                     | 10.5      | volts     |
| Heater Current                                  |            | 0.75                    | 0.45      | ampere    |
| Heater Warm-up Time (Average)                   |            | _                       | 11        | seconds   |
| Peak Heater-Cathode Voltage:                    |            |                         |           |           |
| Heater negative with respect to cathode         |            | 200 max                 | 200 max   | c volts   |
| Heater positive with respect to cathode         |            | 200 max                 | 200 max   | volts     |
| Direct Interelectrode Capacitances:             |            |                         |           |           |
| Triode Unit:                                    |            |                         |           |           |
| Grid to Plate                                   |            |                         | 3.5       | pf        |
| Grid to Cathode, Heater, Pentode Cathode,       | Grid No.1  |                         | 5.5       | ρ.        |
|   |            |                         | 2.8       | pf        |
| and Internal Shield                             |            |                         | 2.0       | pr        |
| Plate to Cathode, Heater, Pentode Cathode,      |            |                         |           |           |
| and Internal Shield                             | . <b></b>  | · · · · · · · · · · · · | 2.6       | pf        |
| Pentode Unit:                                   |            |                         |           |           |
| Grid No.1 to Plate                              |            |                         | 0.1 max   | pf        |
| Grid No.1 to Cathode, Heater, Grid No.2,        | Grid No.3, | ,                       |           |           |
| and Internal Shield                             |            |                         | 10        | pf        |
| Plate to Cathode, Heater, Grid No.2, Grid       | No.3.      |                         |           |           |
| and Internal Shield                             |            |                         | 4.2       | pf        |
| Triode Grid to Pentode Plate                    |            |                         | 0.015 max |           |
| • The dc component must not exceed 100 volts.   |            |                         |           | •         |
|   |            |                         |           |           |
| Class A, A                                      | lmplifier  |                         |           |           |
| MAXIMUM RATINGS (Design-Maximum Value           | es):       | Triode Unit             | Pentode U | nit       |
| Plate Voltage                                   |            | 330 max                 | 330 max   | c volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage          |            | <del>-</del>            | 330 max   | volts     |
| Grid-No.2 Voltage                               |            |                         | See curv  | e page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias |            | 0 max                   | 0 max     |           |
| Plate Dissipation                               |            | 1 max                   | 5 ma      |           |
| Grid-No.2 Input:                                | • • • • •  | I IIIua                 | 2 1114    |           |
| For grid-No.2 voltages up to 165 volts          |            |                         | 1.1 max   | watts     |
|   |            | -                       |           |           |
| For grid-No.2 voltages between 165 and 330      | voits      |                         |           | e page 75 |
| CHARACTERISTICS:                                | Triode Un  | it <b>Pent</b> o        | de Unit   |           |
| Plate Supply Voltage                            | 200        | 45                      | 200       | volts     |
| Grid-No.2 Supply Voltage                        |            | 125                     | 125       | volts     |
| Grid-No.1 Voltage                               | -2         | 0                       | _         | volts     |
| Cathode-Bias Resistor                           |            | _                       | 68        | ohms      |
| Amplification Factor                            | 70         |                         |           |           |
| Plate Resistance (Approx.)                      | 17500      | _                       | 75000     | ohms      |
| Transconductance (Approx.)                      | 4000       | _                       | 12500     | μmhos     |
| Plate Current                                   | 4          | 40•                     |           | ma        |
|   | •          | 15•                     |           |           |
| Grid-No.2 Current                               |            | 13-                     | ,         | ma        |
| Grid-No.1 Voltage (Approx.) for plate current   |            |                         | •         | •.        |
| of 100 μa                                       | _          | _                       | <b>-9</b> | volts     |
| Grid-No.1 Voltage (Approx.) for plate current   | _          |                         |           |           |
| of 20 μa  | <b>–</b> 6 | _                       | _         | volts     |
| MAXIMUM CIRCUIT VALUES:                         |            |                         |           |           |
| Grid-No.1-Circuit Resistance:                   |            | Triode Unit             | Pentode U | nit       |
| For fixed-bias operation                        |            | 0.5 max                 |           | k megohm  |
|   |            | 1 max                   |           | megohm    |
| For cathode-bias operation                      |            | Linax                   | 1 max     | megonin   |

# **BEAM POWER TUBE**

• This value can be measured by a method involving a recurrent waveform such that the

6HG5

maximum ratings of the tube will not be exceeded.

Miniature type used in the audio output stages of television receivers. This type has a controlled cathode warm-up time to minimize extraneous sound during receiver warm-up. Outline 5D, Outlines section. Tube requires min-



iature seven-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc)  | 6.3<br>0.45<br>14 min | volts<br>ampere<br>seconds |
|---|-----------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode   | 200 max               | volts                      |
| Heater positive with respect to cathode   | 200•max               | volts                      |
| Direct Interelectrode Capacitances:  Grid No.1 to Plate  Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3  Plate to Cathode, Heater, Grid No.2, and Grid No.3 | 0.4<br>8<br>8.5       | pf<br>pf<br>pf             |

#Time interval between application of voltages and rise of plate current to 1 ma; heater volts, 6.3; plate and grid-No.2 volts, 250; cathode-bias resistor, 680 ohms.

• The dc component must not exceed 100 volts.

# Class A, Amplifier

|  | •     |         |          |
|--|-------|---------|----------|
| MAXIMUM RATINGS (Design-Maximum Values): |       | 275 max | volts    |
| Plate Voltage                            |       |         |          |
| Grid-No.2 (Screen-Grid) Voltage          |       | 275 max | volts    |
| Plate Dissipation                        |       | 12 max  | watts    |
| Grid-No.2 Input                          |       | 2 max   | watts    |
| Bulb Temperature (At hottest point)      |       | 250 max | °C       |
| TYPICAL OPERATION AND CHARACTERISTICS:   |       |         |          |
| Plate Voltage                            | 180   | 250     | volts    |
| Grid-No.2 Voltage                        | 180   | 250     | volts    |
| Grid-No.1 (Control-Grid) Voltage         | -8.5  | -12.5   | volts    |
| Peak AF Grid-No.1 Voltage                | 8.5   | 12.5    | volts    |
| Zero-Signal Plate Current                | 29    | 45      | ma       |
| Maximum-Signal Plate Current             | 30    | 47      | ma       |
| Zero-Signal Grid-No.2 Current            | 3     | 4.5     | ma       |
| Maximum-Signal Grid-No.2 Current         | 4     | 7       | ma       |
| Plate Resistance (Approx.)               | 58000 | 52000   | ohms     |
| Transconductance                         | 3700  | 4100    | μmhos    |
| Load Resistance                          | 5500  | 5000    | ohms     |
| Total Harmonic Distortion                | 8     | 8       | per cent |
| Maximum-Signal Power Output              | 2     | 4.5     | watts    |
|  |       |         |          |

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:


For fixed-bias operation

For cathode-bias operation

0.1 max megohm

For cathode-bias operation

0.5 max megohm




#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

# 6HG8

Miniature type with frame-grid pentode unit used as combined oscillator and mixer tube in vhf television receivers. Outline 6B, Outlines section.

Tube requires miniature nine-contact socket and may be mounted in any



position. Heater volts (ac/dc), 6.3; amperes, 0.34; peak heater-cathode volts, 100.


| Class A, Amplifier                       |             |            |        |
|--|-------------|------------|--------|
| MAXIMUM RATINGS (Design-Maximum Values): | Triode Unit | Pentode Ur | nit    |
| Plate Voltage                            | 125 max     | 250 max    | volts  |
| Grid-No.2 (Screen-Grid) Voltage          |             | 150 max    | volts  |
| Cathode Current                          | 15 max      | 18 max     | ma     |
| Plate Dissipation                        | 1.5 max     | 2 max      | watts  |
| Grid-No.2 Input                          | -           | 0.5 max    | watt   |
| CHARACTERISTICS:                         |             |            |        |
| Plate Voltage                            | 100         | 170        | volts  |
| Grid-No.2 Voltage                        | _           | 150        | volts  |
| Grid-No.1 (Control-Grid) Voltage         | <b>—3</b>   | -1.2       | volts  |
| Amplification Factor                     | 17          | -          |        |
| Mu-Factor, Grid No.2 to Grid No.1        | _           | 70         |        |
| Plate Resistance (Approx.)               |             | 0.35       | megohm |
| Transconductance                         | 5500        | 12000      | μmhos  |
| Plate Current                            | 14          | 10         | ma     |
| Grid-No.2 Current                        | _           | 3.3        | ma     |
| MAXIMUM CIRCUIT VALUES:                  |             |            |        |
| Grid-No.1-Circuit Resistance:            |             |            |        |
| For fixed-bias operation                 |             | 0.25 max   | megohm |
| For cathode-bias operation               | 0.5 max     | 0.5 max    | megohm |

#### **BEAM POWER TUBE**

6HJ5
Related type:
21HJ5

plate current of 1 ma .......

Duodecar type used as horizontal-deflection amplifier in television receivers. Outline 15C, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Type 21HJ5 is identical



-70

volts

with type 6HJ5 except for heater ratings, as shown below.

|  |       |           | 6HJ5       | 21HJ5     |         |
|--|-------|-----------|------------|-----------|---------|
| Heater Voltage (ac/dc)                                     |       |           | 6.3        | 21.5      | volts   |
| Heater Current   |       |           | 2.25       | 0.6       | amperes |
| Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: |       |           | -          | 11        | seconds |
| Heater negative with respect to cath                       | ode . |           | 200 max    | 200 max   | volts   |
| Heater positive with respect to cath                       | ode . |           | 200*max    | 200*max   | volts   |
| * The dc component must not exceed 100                     | volts | •         |            |           |         |
| Clas   | s A,  | Amplifier |            |           |         |
| CHARACTERISTICS:   | -     | ·         |            |           |         |
| Plate Voltage  | 20    | 40        | 60         | 135       | volts   |
| Grid-No.2 (Screen-Grid) Voltage                            | 110   | 110       | 135        | 135       | volts   |
| Grid No.3  |       | Connected | to cathode | at socket |         |
| Grid-No.1 (Control-Grid) Voltage                           | 0     | 0         | 0          | -22       | volts   |
| Triode Amplification Factor                                |       |           | _          | 4.2       |         |
| Plate Resistance (Approx.)                                 | _     | -         |            | 5000      | ohms    |
| Transconductance   | _     | _         | _          | 10000     | μmhos   |
| Plate Current  | 240=  | 400=      | 540=       | 80        | ma      |
| Grid-No.2 Current  | 160=  | 42•       | 48=        | 5.5       | ma      |
|  |       |           |            |           |         |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### **Horizontal Deflection Amplifier**


For operation in a 525-line, 30-frame system

| - 0. oprimion in a rat init, it interes ayarm |           |       |
|---|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):      |           |       |
| DC Plate Supply Voltage                       | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage#            | 7000 max  | volts |
| Peak Negative-Pulse Plate Voltage             | -1500 max | volts |
| DC Grid-No.3 Voltage                          | 70 max    | volts |
| DC Grid-No.2 Voltage                          | 220 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage         | -330 max  | volts |
| Peak Cathode Current                          | 1000 max  | ma    |
| Average Cathode Current                       | 280 max   | ma    |
| Plate Dissipation†                            | 24 max    | watts |
| Grid-No.2 Input                               | 6 max     | watts |
| Bulb Temperature (At hottest point)           | 240 max   | °C    |
|   |           |       |

# MAXIMUM CIRCUIT VALUE: Grid-No.1-Circuit Resistance

#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10

† An adequate bias resistor or other means is required to protect the tube in the absence of excitation.



# DIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined video-detector and if-amplifier tube in television receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

**6HJ8** 

0.55 max

3.2 max

See curve page 75

1 max megohm

| •  |           |           |
|--|-----------|-----------|
| Heater Voltage (ac/dc)                                       | 6.3       | volts     |
| Heater Current   | 0.45      | ampere    |
| Heater Warm-up Time (Average)                                | 11        | seconds   |
| Peak Heater-Cathode Voltage:                                 | ••        | 500011115 |
| Heater negative with respect to cathode                      | 200 max   | volts     |
| Heater positive with respect to cathode                      | 200 max   | volts     |
| Direct Interelectrode Capacitances:                          | 200 max   | 10113     |
| Diode Unit:  |           |           |
| Plate to Cathode and Heater                                  | 2.4       | -6        |
| Cathode to Plate and Heater                                  | 3         | pf        |
| Pentode Unit:  | 3         | pf        |
|  | 0.015 max | _e        |
| Grid No.1 to Plate   | 0.015 max | pf        |
| and Internal Shield  | 7         | ρf        |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal | ,         | ρι        |
| Shield   | 3.2       | pf        |
| Diode Plate to Pentode Grid No.1                             | 0.005 max | pf        |
| Diode Cathode to Pentode Plate                               | 0.15 max  |           |
| Diode Plate to Pentode Plate                                 | 0.035 max | pf        |
| Diode Plate to Pentode Plate                                 | 0.033 max | pf        |
| Pontado Unit ao Class A Amplifica                            |           |           |
| Pentode Unit as Class A, Amplifier                           |           |           |
| MAXIMUM RATINGS (Design-Maximum Values):                     |           |           |
| Plate Voltage  | 330 max   | volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                       | 330 max   | volts     |
| Grid-No.2 Voltage  | See curve | page 75   |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value        | 0 max     | volts     |
| Grid-No.2 Input:   |           |           |
|  |           |           |

For grid-No.2 voltages up to 165 volts .....

For grid-No.2 voltages between 165 and 330 volts .....

Plate Dissipation .....

| CHARACTERISTICS:  |            |           |
|---|------------|-----------|
| Plate Supply Voltage                                      | 125        | volts     |
| Grid No.3   | to cathode | at socket |
| Grid-No.2 Supply Voltage                                  | 125        | volts     |
| Cathode-Bias Resistor                                     | 56         | ohms      |
| Plate Resistance (Approx.)                                | 0.2        | megohm    |
| Transconductance  | 9300       | μmhos     |
| Plate Current   | 11.5       | ma        |
| Grid-No.2 Current   | 3.6        | ma        |
| Grid-No.1 Voltage (Approx.) for plate current of 20 μa    | 6          | volts     |
| Grid-No.1 Voltage (Approx.) for plate current of 2 ma and |            |           |
| no cathode-bias resistor                                  | -3         | volts     |
| Diode Unit  |            |           |
| MAXIMUM RATINGS (Design-Maximum Values):                  |            |           |
| DC Plate Current  | 5 max      | ma        |
| DC Flate Cuttent  | J max      | ma        |
|   |            |           |
| CHARACTERISTICS, Instantaneous Value:                     |            | •.        |
| Tube Voltage Drop for plate current of 50 ma              | 10         | volts     |

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**6HL8** 

MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance .....

Miniature type used in a wide variety of applications in television receivers employing series-connected heater strings. The triode unit is used as a sync-separator or voltage-amplifier tube, and the pentode unit is used as




a video if-amplifier, agc-amplifier, or reactance tube. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A <sub>1</sub> Amplifier  MAXIMUM RATINGS (Design-Maximum Values):  Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts | Triode Unit 330 max  0 max 2.5 max           | 0 ma<br>2.5 ma<br>0.55 ma                                   | x volts x volts e page 75 x volts x watts                   |
|---|--|---|---|
| CHARACTERISTICS: Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 µa  | 125<br>-1<br>40<br>5000<br>7000<br>12.5<br>- | 125<br>125<br>-1<br>-<br>150000<br>10000<br>12<br>4.5<br>-7 | volts<br>volt<br>volt<br>ohms<br>µmhos<br>ma<br>ma<br>volts |

1 max

megohm




#### HIGH-MU TRIODE

6)IS Miniature type used as rf-amplifier tube in vhf television tuners. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 3HM5/3HA5 is identical with type 6HM5/6HA5 except for heater ratings, as shown below.

# 6HM5/ 6HA5

Related type: 3HM5/3HA5

| Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode   |                              |                                       | HM5/3HA5<br>2.7<br>0.45<br>110 max<br>110 max                  | 6HM5/6HA<br>6.3<br>0.18<br>110 max<br>110 max     | volts<br>amperes<br>volts<br>volts                           |
|--|------------------------------|---------------------------------------|--|---|--|
| Class A MAXIMUM RATINGS (Design-Maximum V DC Plate Voltage DC Plate Supply Voltage Grid Voltage Cathode Current Plate Dissipation  | alues):                      | · · · · · · · · · · · · · · · · · · · |  | 220 max<br>600 max<br>50 max<br>22 max<br>2.6 max | volts<br>volts<br>volts<br>ma<br>watts                       |
| CHARACTERISTICS AND TYPICAL OPERATION: DC Plate Supply Voltage Plate-Load Resistor Internal-Shield Voltage DC Grid Voltage Cathode-Bias Resistor Amplification Factor Transconductance Plate Current DC Grid Current Grid-No.1 Voltage for one-per-cent transconductance | Fixed 135 0 -1 72 14500 11.5 | Bias<br>135<br>0<br>-2.7<br>-<br>1500 | Cathe<br>135<br>1000<br>0<br>-<br>0<br>80<br>20000<br>19<br>10 | de Bias<br>135<br>5600<br>0<br>                   | volts<br>ohms<br>volts<br>volts<br>ohms<br>µmhos<br>ma<br>µa |



# SEMIREMOTE-CUTOFF PENTODE

Miniature type used as if-amplifier tube in FM receivers employing seriesconnected heater strings. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type

19HR6

19HR6 is identical with type 6HR6 except for the heater ratings, as shown below.

|   | 6HR6     | 19HR6     |         |
|---|----------|-----------|---------|
| Heater Voltage (ac/dc)                                  | 6.3      | 18.9      | volts   |
| Heater Current  | 0.45     | 0.15      | ampere  |
| Heater Warm-up Time (Average)                           | 11       | 17        | seconds |
| Peak Heater-Cathode Voltage:                            |          |           |         |
| Heater negative with respect to cathode                 | 200 max  | 200 max   | volts   |
| Heater positive with respect to cathode                 | 200 max  | 200*max   | volts   |
| Direct Interelectrode Capacitances:                     |          |           |         |
| Grid No.1 to Plate                                      |          | 0.006 max | ρf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and | Internal |           | •       |
| Shield  |          | 8.8       | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and     | Internal |           | _       |
| Shield  |          | 5.2       | pf      |
|   |          |           | -       |

<sup>•</sup> The dc component must not exceed 100 volts.

13.2

4.3

ma

ma

| Class | A. | Am | plifier |
|-------|----|----|---------|
|-------|----|----|---------|

| MAXIMUM RATINGS (Design-Maximum Values):                     |            |           |
|--|------------|-----------|
| Plate Supply Voltage   | 300 max    | volts     |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value          | 0 max      | volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                       | 300 volts  | volts     |
| Grid-No.2 Voltage  | See curve  | e page 75 |
| Grid-No.1 (Control-Grid) Voltage:                            |            |           |
| Negative-bias value  | -50 max    | volts     |
| Positive-bias value  | 0 max      | volts     |
| Plate Dissipation  | 3 max      | watts     |
| Grid-No.2 Input:   |            |           |
| For grid-No.2 voltages up to 150 volts                       | 1 max      | watt      |
| For grid-No.2 voltages between 150 and 300 volts             | See curve  | page 75   |
| CHARACTERISTICS:   |            |           |
| Plate Supply Voltage   | 200        | volts     |
| Grid No.3  |            |           |
| Grid-No.2 Supply Voltage                                     | 115        | volts     |
| Grid-No.1 Supply Voltage                                     | Õ          | volts     |
| Cathode-Bias Resistor  | 68         | ohms      |
| Plate Resistance (Approx.)                                   | 0.5        | megohm    |
| Transconductance   | 8500       | μmhos     |
| Grid-No.1 Voltage (Approx.) for transconductance of 60 μmhos | <b>—15</b> | volts     |
|  |            |           |


#### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:

Plate Current .....

Grid-No.2 Current


For fixed-bias operation 0.5 max megohm
For cathode-bias operation 1 max megohm



# SHARP-CUTOFF PENTODE

6HS6
Related type:
19HS6

Miniature type used as if-amplifier and limiter tube in FM receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 19HS6 is identical with type



6HS6 except for the heater ratings, as shown below.

|                               | 6HS6 | 19HS6 |         |
|-------------------------------|------|-------|---------|
| Heater Voltage (ac/dc)        | 6.3  | 18.4  | volts   |
| Heater Current                | 0.45 | 0.15  | ampere  |
| Heater Warm-up Time (Average) | 11   | 17    | seconds |

| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 6HS6<br>200 max<br>200•max | 19HS6<br>200 max<br>200•max | volts<br>volts |
|--|----------------------------|-----------------------------|----------------|
| Direct Interelectrode Capacitances: Grid No.1 to Plate   |                            | 0.006 max                   | volts          |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,  |                            | 0.000 HIAX                  | 10113          |
| and Internal Shield  |                            | 8.8                         | pf             |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield  |                            | 5.2                         | pf             |

The dc component must not exceed 100 volts.

| * The ac component must not exceed 100 voits.       |    |                   |         |
|---|----|-------------------|---------|
| Class A, Amplifier                                  |    |                   |         |
| MAXIMUM RATINGS (Design-Maximum Values):            |    |                   |         |
| Plate Supply Voltage                                |    | 300 max           | volts   |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive Value |    | 0 max             | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage              |    | 300 max           | volts   |
| Grid-No.2 Voltage                                   |    | See curve         | page 75 |
| Grid-No.1 (Control-Grid) Voltage:                   |    |                   |         |
| Negative-bias value                                 |    | 50 max            | volts   |
| Positive-bias value                                 |    | 0 max             | volts   |
| Plate Dissipation                                   |    | 3 max             | watts   |
| Grid-No.2 Input:                                    |    |                   |         |
| For grid-No.2 voltages up to 150 volts              |    | 1 max             | watt    |
| For grid-No.2 voltages between 150 and 300 volts    |    | See curve         | page 75 |
| CHARACTERISTICS:                                    |    |                   |         |
| Plate Supply Voltage                                | 75 | 150               | volts   |
| Grid No.3   |    | cted to cathode a |         |
| Grid-No.2 Supply Voltage                            | 75 | 75                | volts   |
| Grid-No.1 Supply Voltage                            | ő  | Ö                 | volts   |
| Cathode-Bias Resistor                               | 68 | 68                | ohms    |
| Amplification Factors                               | 50 | 30                |         |

 Plate Supply Voltage
 75
 150
 volts

 Grid No.3
 Connected to cathode at socket

 Grid-No.2 Supply Voltage
 75
 volts

 Grid-No.1 Supply Voltage
 0
 0
 volts

 Cathode-Bias Resistor
 68
 68
 ohms

 Amplification Factor\*
 50
 —


 Plate Resistance (Approx.)
 —
 0.5
 megohm

 Transconductance
 —
 9500
 μmhos

 Plate Current
 —
 8.8
 ma

 Grid-No.2 Current
 —
 2.8
 ma

 Grid-No.1 Voltage (Approx.) for plate current of 20 μa
 —
 -4
 volts



#### **MAXIMUM CIRCUIT VALUES:**

| Grid-No.1-Circuit Resistance |  |  |
|------------------------------|--|--|
|------------------------------|--|--|


| For fixed-bias operation   | 0.5 max | megohm |
|----------------------------|---------|--------|
| For cathode-bias operation | 1 max   | megohm |

<sup>•</sup> Triode connection (grid No.2 connected to plate).

# SHARP-CUTOFF TWIN PENTODE

6HS8
Related type:
3HS8, 4HS8

Miniature type used in agc amplifier, sync, and noise-limiting circuits of television receivers. One pentode unit is used as combined sync separator and sync clipper; second pentode unit is used as agc amplifier. Outline 6E,





Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Type 3HS8 and 4HS8 are identical with type 6HS8 except for the heater ratings, as shown below.

|  | 3HS8      | 4HS8              | 6H\$8     |         |
|--|-----------|-------------------|-----------|---------|
| Heater Voltage (ac/dc)                                     | 3.15      | 4.2               | 6.3       | volts   |
| Heater Current   | 0.6       | 0.45              | 0.3       | ampere  |
| Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 11        | 11                | -         | seconds |
| Heater negative with respect to cathode                    | 200 max   | 200 max           | 200 max   | volts   |
| Heater positive with respect to cathode                    | 200 max   | 200 • max         | 200 = max | volts   |
| Direct Interelectrode Capacitances:                        |           |                   |           |         |
| Grid No.3 to Plate (Each Unit)                             | <b></b> . |                   | 2         | pf      |
| Grid No.1 to All Other Electrodes                          | <i></i>   |                   | 6         | pf      |
| Grid No.3 (Each Unit) to All Other Electrod                | es        |                   | 3.6       | pf      |
| Plate (Each Unit) to All Other Electrodes                  |           |                   | 3         | pf      |
| Grid No.3 (Unit No.1) to Grid No.3 (Unit N                 | lo.2)     |                   | 0.015 max | pf      |
| The dc component must not exceed 100 volts.                |           |                   |           | -       |
| - The de component must not exceed 100 voits.              |           |                   |           |         |
| Class A, A   | Amnlifier |                   |           |         |
| MAXIMUM RATINGS (Design-Maximum Values                     |           |                   |           |         |
| Plate Voltages (Each Unit)                                 |           |                   | 300 max   | volts   |
| Grid-No.3 (Suppressor-Grid) Voltage (Each Unit             |           |                   | Joo max   | 10113   |
| Peak positive value  | .,.       |                   | 50 max    | volts   |
| DC negative value  |           |                   | -50 max   | volts   |
| DC positive value  |           |                   | 3 max     | volts   |
| Grid-No.2 (Screen-Grid) Voltage                            |           |                   | 150 max   | volts   |
| Grid-No.1 (Control-Grid) Voltage, Negative-bias            |           |                   | -50 max   | volts   |
| Cathode Current  |           |                   | 12 max    | ma      |
| Plate Dissipation (Each Unit)                              |           |                   | 1.1 max   | watts   |
| Grid-No.2 Input  |           |                   | 0.75 max  | watt    |
| <b>™</b>   |           | • • • • • • • • • | 0110 221  |         |
| CHARACTERISTICS:   |           | _                 |           |         |
| With One Unit  |           |                   | 100       | volts   |
| Plate Voltage  |           | 100               | 100       | volts   |
| Grid-No.3 Voltage  |           | 0<br>67.5         | 67.5      | volts   |
| Grid-No.2 Voltage  |           | 07.5              | 67.3      | volts   |
| Grid-No.1 Voltage  |           | U                 | 450       | umhos   |
| Transconductance, Grid-No.1-to-Plate                       |           | 1100              | 450       | μmhos   |
| Plate Current  |           | 1100              |           | ma ma   |
| Grid-No.3 Voltage (Approx.) for plate current of           |           | _                 | -3.5      | volts   |
| Grid-No.1 Voltage (Approx.) for plate current of           |           | _                 | -2.3      | volts   |
|  |           |                   | 2.5       | 70113   |
| With Both Uni  |           |                   |           | _       |
| Plate Voltage (Each Unit)                                  |           | 100               | 100       | volts   |
| Grid-No.3 Voltage (Each Unit)                              |           | -10               | . 0       | volts   |
| Grid-No.2 Voltage  |           | 67.5              | 67.5      | volts   |
| Grid-No.1 Voltage  |           | Ö                 |           | volts   |
| Plate Current (Each Unit)                                  |           |                   | 2         | ma      |
| Grid-No.2 Current  |           | 7                 | 4.4       | ma      |
| Cathode Current  |           | 7.1               | 8.5       | ma      |
| MAXIMUM CIRCUIT VALUES:                                    |           |                   |           |         |
| Grid-No.3-Circuit Resistance (Each Unit)                   |           |                   | 0.5 max   | megohm  |
| Grid-No.1-Circuit Resistance                               |           |                   | 0.5 max   | megohm  |
|  |           |                   |           | -       |

<sup>•</sup> With plate and grid No.3 of other unit connected to ground.

<sup>□</sup> Adjusted to give grid-No.1 current of 0.1 milliampere.







# SHARP-CUTOFF PENTODE

Miniature type used as sound-detector tube in FM and television receivers employing series-connected heater strings. Tube has two independent control grids. Outline 5C, Outlines section. Tube requires miniature


6HZ6


seven-contact socket and may be mounted in any position.


| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: | 6.3<br>0.45<br>11  | volts<br>ampere<br>seconds |
|--|--------------------|----------------------------|
| Heater negative with respect to cathode  Heater positive with respect to cathode                 | 200 max<br>200=max | volts<br>volts             |

Direct Interelectrode Capacitances (Approx.):

| Grid No.1 to Plate   | 0.023      | pf         |
|--|------------|------------|
| and Internal Shield  | 8.2        | -6         |
| Grid No.1 to Grid No.3   | 0.09       | pf<br>pf   |
| Grid No.3 to Plate   | 1.6        |            |
| Grid No.3 to Cathode, Heater, Grid No.1, Grid No.2, Plate,         | 1.0        | pf         |
| and Internal Shield  | 7.2        | рf         |
| <ul> <li>The dc component must not exceed 100 volts.</li> </ul>    |            | •          |
| Class A. Amplifier   |            |            |
| CHARACTERISTICS:   |            |            |
| Plate Supply Voltage   | 150        | volts      |
| Grid-No.3 Supply Voltage   | 0          | volts      |
| Grid-No.2 Supply Voltage   | 100        | volts      |
| Grid-No.1 Supply Voltage   | 0          | volts      |
| Cathode-Bias Resistor  | 180        | ohms       |
| Plate Resistance (Approx.)   | 0.11       | megohm     |
| Transconductance, Grid No.1 to Plate                               | 3400       | $\mu$ mhos |
| Transconductance, Grid No.3 to Plate                               | 600        | μmhos      |
| Plate Current  | 3.2        | ma         |
| Grid-No.2 Current  | 3.2        | ma         |
| Grid-No.3 Supply Voltage (Approx.) for plate current of 20 $\mu$ a | <b>—</b> 7 | volts      |
| Grid-No.1 Supply Voltage (Approx.) for plate current of 20 $\mu a$ | 4.5        | volts      |
| FM Sound Detector  |            |            |
| MAXIMUM RATINGS (Design-Maximum Values):                           |            |            |
| Plate Voltage  | 300 max    | volts      |
| Grid-No.3 (Control-Grid) Voltage:                                  |            |            |
| Negative value (dc and peak ac)                                    | 100 max    | volts      |
| Positive value (dc and peak ac)                                    | 25 max     | volts      |
| Grid-No.2 (Screen-Grid) Supply Voltage                             | 300 max    | volts      |
| Grid-No.2 Voltage  | See curv   | e page 75  |
| Grid-No.1 (Control-Grid) Voltage:                                  |            |            |
| Negative-bias value  | -50 max    | volts      |
| Positive-bias value  | 0 max      | volts      |
| Plate Dissipation  | 1.7 max    | watts      |
| Grid-No.3 Input  | 0.1 max    | watt       |
| Grid-No.2 Input:   |            |            |
| For grid-No.2 voltages up to 150 volts                             | 1 max      | watt       |
| For grid-No.2 voltages between 150 and 300 volts                   | See curv   | e page 75  |
| MAXIMUM CIRCUIT VALUES:  |            |            |
| Grid-No.3-Circuit Resistance                                       | 0.68 max   | megohm     |
| Grid-No.1-Circuit Resistance:                                      | -          |            |
| For fixed-bias operation   | 0.22 max   | megohm     |
| For cathode-bias operation   | 0.47 max   |            |
| *****  |            |            |







### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Duodecar type used in television receivers. The triode unit is used as a voltage amplifier or sync separator, and the pentode unit as a video amplifier. Outline 8E, Outlines section. Tube requires duodecar nine-contact

6HZ8

socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 1.125; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A <sub>1</sub> Amplifier  MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage, Positive bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts | Triode Unit 300 max  - 0 max 1 max | Pentode Ur<br>300 max<br>330 max<br>See curve<br>0 max<br>8 max                    | volts<br>volts<br>page 75<br>volts<br>watts     |
|--|------------------------------------|--|---|
|  | _                                  | See curve  | page /3   |
| CHARACTERISTICS: Plate Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current   | 200<br>                            | 60 250<br>170 170<br>0 —<br>100<br>— 100<br>— 0.14<br>— 12600<br>90* 29<br>22.5* 6 | volts<br>volts<br>ohms<br>megohm<br>µmhos<br>ma |
| of 10 $\mu$ a  | <b></b> 5                          | 11.5   | volts   |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation  | 0.5 max<br>1 max                   |  | megohm<br>megohm                                |

This value can be measured by a method involving a recurrent waveform such that the

maximum ratings of the tube will not be exceeded.

# 6J5 6J5GT

# MEDIUM-MU TRIODE

Renewal types; see chart at end of section for tabulated data.

# 6J6


# MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.

# MEDIUM-MU TWIN TRIODE

6J6A
Related type:

Miniature type used as combined rf power amplifier and oscillator or as twin af amplifier. With push-pull arrangement of the grids and the plates in parallel this type can also be used as a mixer at frequencies as high as



6J6A

600 megacycles per second. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Type 5J6 is identical with type 6J6A except for the heater ratings, as shown below.

**5J6** 

|  | 230                       | 03071                                   |                                      |
|--|---------------------------|---|--------------------------------------|
| Heater Voltage (ac/dc)   | 4.7                       | 6.3                                     | volts                                |
| Heater Current   | 0.6                       | 0.45                                    | ampere                               |
| Heater Warm-up Time (Average)  | 11                        | 11                                      | seconds                              |
| Peak Heater-Cathode Voltage:   |                           |   |                                      |
| Heater negative with respect to cathode  | 100 max                   | 100 max                                 | volts                                |
| Heater positive with respect to cathode  | 100 max                   | 100 max                                 | volts                                |
| Treater positive with respect to cathode   | Without                   | With                                    | 10113                                |
| Direct Interelectrode Capacitances   | External                  | External                                |                                      |
|  | Shield                    | Shield                                  |                                      |
| (Each Unit, Approx.):  | 1.6                       | 1.6                                     | -6                                   |
| Grid to Plate  | 2.2                       | 2.6                                     | pf                                   |
| Grid to Cathode and Heater   | 0.4                       |   | pf                                   |
| Plate to Cathode and Heater (Unit No.1)  |                           | 1.6                                     | pf                                   |
| Plate to Cathode and Heater (Unit No.2)  | 0.4                       | 1                                       | pf                                   |
| Class A <sub>1</sub> Amplifier (Each MAXIMUM RATINGS (Design-Center Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation                       |                           | 300 max<br>0 max<br>1.5 max             | volts<br>volts<br>watts              |
| CHARACTERISTICS: Plate Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current                                  |                           | 100<br>50†<br>38<br>7100<br>5300<br>8.5 | volts<br>ohms<br>ohms<br>µmhos<br>ma |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation  † Value is for both units operating at the specified condition | · · · · · · · · · · · · · | Not recor<br>0.5 max                    |                                      |

| raphy   |        |
|---------|--------|
|         |        |
|         |        |
| 300 max | volts  |
|         |        |
| 40 max  | volts  |
| 0 max   | volts  |
|         | 40 max |

| Plate Current Grid Current Plate Input Plate Dissipation  | 15 max<br>8 max<br>4.5 max<br>1.5 max | ma<br>ma<br>watts<br>watts                  |
|---|---------------------------------------|---|
| TYPICAL PUSH-PULL OPERATION (Both Units): Plate Voltage Grid Voltage* Plate Current Grid Current (Approx.) Driving Power (Approx.) Power Output (Approx.) | 150<br>10<br>30<br>16<br>0.35<br>3.5  | volts<br>volts<br>ma<br>ma<br>watt<br>watts |

Obtained by grid resistor (625 ohms), cathode-bias resistor (220 ohms), or fixed supply.

# SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

**6J7** 

# SHARP-CUTOFF PENTODE


Discontinued types; see chart at end of section for tabulated data.

6J7G 6J7GT

# TRIODE—HEPTODE CONVERTER

Discontinued type; see chart at end of section for tabulated data.

**6J8G** 



#### POWER PENTODE— BEAM POWER TUBE

Duodecar type used in FM and television receivers. The pentode unit is used in audio power-output stages, and the beam power unit is used as a gated-beam discriminator in FM and television limiter and discriminator

6J10 Related type:

applications. Outline 8B, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Type 13J10 is identical with type 6J10 except for heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)  | 6J10<br>6.3<br>0.95 | 13J10<br>13.2<br>0.45<br>11 | volts<br>ampere<br>seconds |
|--|---------------------|-----------------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max<br>200•max  | 200 max<br>200*max          | volts<br>volts             |
| The dc component must not exceed 100 volts.  |                     |                             |                            |

• The ac component must not exceed 100 voits.

| - · · · · · · · · · · · · · · · · · · ·  |         |       |
|--|---------|-------|
| Pentode Unit as Class A, Amplifier       |         |       |
| MAXIMUM RATINGS (Design-Maximum Values): |         |       |
| Plate Voltage                            | 275 max | volts |
| Grid-No.2 (Screen-Grid) Voltage          | 275 max | volts |
| Plate Dissipation                        | 10 max  | watts |
| Grid-No.2 Input                          | 2 max   | watts |

| CHARACTERISTICS AND TYPICAL OPERATION: |      |          |
|--|------|----------|
| Plate Voltage                          | 250  | volts    |
| Grid-No.2 Voltage                      | 250  | volts    |
| Grid-No.1 Voltage                      | 8    | volts    |
| Peak AF Grid-No.1 Voltage              | 8    | volts    |
| Plate Resistance (Approx.)             | 0.1  | megohm   |
| Transconductance                       | 6500 | μmhos    |
| Zero-Signal Plate Current              | 35   | ma       |
| Maximum-Signal Plate Current           | 39   | ma       |
| Zero-Signal Grid-No.2 Current          | 2.5  | ma       |
| Maximum-Signal Grid-No.2 Current       | 7    | ma       |
| Load Resistance                        | 5000 | ohms     |
| Total Harmonic Distortion (Approx.)    | 10   | per cent |
| Maximum-Signal Power Output            | 4.2  | watts    |
|  |      |          |

#### MAXIMUM CIRCUIT VALUES:

| Grid-No.1-Circuit Resistance: |  |
|-------------------------------|--|
| For fixed-bias operation      |  |


| beam Power Unit as Gated-Beam Discriminato   | Ī                                      |                         |
|--|--|-------------------------|
| MAXIMUM RATINGS (Design-Maximum Values): Plate Supply Voltage Grid-No.2 (Accelerator-Grid) Voltage Peak Positive Grid-No.1 Voltage | 330 max<br>110 max<br>60 max<br>13 max | volts<br>volts<br>volts |
| Average Cathode Current  | 13 max                                 | ma                      |

# **6JB6** 6JB6A

Related types: 12JB6, 12JB6A, 17JB6, 17JB6A

# **BEAM POWER TUBE**

Novar types used as high-efficiency horizontal-deflection-amplifier tubes in television receivers. Outlines 18A and 32, respectively. Outlines section. Tubes require novar nine-contact socket and may be mounted in any



position. Types 12JB6 and 12JB6A and types 17JB6 and 17JB6A are identical with types 6JB6 and 6JB6A except for the heater ratings, as shown below.

|   | 6JB6<br>6JB6A | 12JB6<br>12JB6A | 17JB6<br>17JB6A |         |
|---|---------------|-----------------|-----------------|---------|
| Heater Voltage (ac/dc)                        | 6.3           | 12.6            | 16.8            | volts   |
| Heater Current                                | 1.2           | 0.6             | 0.45            | ampere  |
| Heater Warm-up Time (Average)                 |               | 11              | 11              | seconds |
| Peak Heater-Cathode Voltage:                  |               |                 |                 |         |
| Heater negative with respect to cathode       | 200 max       | 200 max         | 200 max         | volts   |
| Heater positive with respect to cathode       | 200 max       | 200 max         | 200 max         | volts   |
| Direct Interelectrode Capacitances (Approx.): |               |                 |                 |         |
| Grid No.1 to Plate                            |               |                 | 0.2             | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2,      |               |                 | 15              | pf      |
| Plate to Cathode, Heater, Grid No.2, and      | Grid No.3     |                 | 6               | pf      |

<sup>•</sup> The dc component must not exceed 100 volts.

#### Class A. Amplifier

| 01400 M <sub>1</sub> M            | p           |             |         |           |
|-----------------------------------|-------------|-------------|---------|-----------|
| CHARACTERISTICS:                  | Triode      | Per         | itode   |           |
|                                   | Connection  | n⁴ Conn     | ection  |           |
| Plate Voltage                     | 150         | 60          | 150     | volts     |
| Grid No.3 (Suppressor Grid)       | C           | onnected to | cathode | at socket |
| Grid No.2 (Screen-Grid) Voltage   | -           | 150         | 150     | volts     |
| Grid No.1 (Control-Grid) Voltage  | 22.5        | 0           | -22.5   | volts     |
| Mu-Factor, Grid No.2 to Grid No.1 | 4.4         | _           |         |           |
| Plate Resistance (Approx.)        | <del></del> |             | 15000   | ohms      |
| Transconductance                  | _           | _           | 7100    | μmhos     |
| Plate Current                     | _           | 390□        | 70      | ma        |

|  | Triode<br>Connection* | Pentode<br>Connection |       |
|--|-----------------------|-----------------------|-------|
| Grid-No.2 Current                            | _                     | 320 2.1               | ma    |
| Grid-No.1 Voltage for plate current of 1 ma. | _                     | <b>— —42</b>          | volts |

Grid No.2 connected to plate.

□ This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

|                      | For operation in a 525-line, 30-trame system | 1 |
|----------------------|--|---|
| MAXIMUM RATING       | S (Design-Maximum Values):                   |   |
| DC Plate Supply Volt | age  |   |


| DC Plate Supply Voltage               | 770 max   | volts |
|---------------------------------------|-----------|-------|
| Peak Positive-Pulse Plate Voltage#    | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage     | -1500 max | volts |
| DC Grid-No.3 Voltage†                 | 70 max    | volts |
| DC Grid-No.2 Voltage                  | 220 max   | volts |
| DC Grid-No.1 Voltage                  | —55 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage | -330 max  | volts |
| Peak Cathode Current                  | 550 max   | ma    |
| Average Cathode Current               | 175 max   | ma    |
| Plate Dissipation•                    | 17.5 max  | watts |
| Grid-No.2 Input                       | 3.5 max   | watts |
| Bulb Temperature (At hottest point)   | 240 max   | *C    |
|                                       |           |       |


#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

#The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

- † For horizontal-deflection service, a positive voltage may be applied to grid No.3 to minimize "snivets" intereference in both vhf and uhf television receivers. A typical value for this purpose is 30 volts.
- An adequate bias resistor or other means is required to protect the tube in the absence of excitation.





# SHARP-CUTOFF PENTODE

Miniature type with frame grid used in if-amplifier stages of television receivers utilizing intermediate frequencies in the order of 40 megacycles. Tube features high transconductance at low B-supply voltages. Outline 6B,

6JC6
Related types:
3JC6, 4JC6

6JC6

13

3.2

ma

ma volts

4JC6

Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Types 3JC6 and 4JC6 are identical with type 6JC6 except for the heater ratings, as shown below.


3JC6


| Heater Voltage (ac/dc)                          | 3.5        | 4.5     | 6.3                  | volts     |
|---|------------|---------|----------------------|-----------|
| Heater Current                                  | 0.6        | 0.45    | 0.3                  | ampere    |
| Heater Warm-up Time (Average)                   | 11         | 11      | •                    | seconds   |
| Peak Heater-Cathode Voltage:                    |            |         |                      |           |
| Heater negative with respect to cathode         | 200 max    | 200 max | 200 max              | volts     |
| Heater positive with respect to cathode         | 200 max    | 200=max | 200*max              | volts     |
| Direct Interelectrode Capacitances:             |            |         |                      |           |
| Grid No.1 to Plate                              |            |         | 0.019 max            | pf        |
| Grid No.1 to Cathode, Heater, Grid No.2,        | Grid No.3, | and     |                      | -         |
| Internal Shield                                 |            |         | 8.2                  | pf        |
| Plate to Cathode, Heater, Grid No.2, Grid       | No.3, and  | l       |                      | •         |
| Internal Shield                                 |            |         | 3                    | pf        |
|   |            |         |                      | •         |
| • The dc component must not exceed 100 volts.   |            |         |                      |           |
| Class A, I                                      | Amnlifier  |         |                      |           |
| MAXIMUM RATINGS (Design-Maximum Valu            |            |         |                      |           |
| Plate Voltage                                   |            |         | 330 max              | volts     |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive v |            |         | 0 max                | volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage          |            |         | 330 max              | volts     |
| Grid-No.2 Voltage                               |            |         | See curve            |           |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias |            |         | 0 max                | volts     |
| Grid-No.2 Input:                                | value      |         | U max                | VOILS     |
| For grid-No.2 voltages up to 165 volts          |            |         | 0.6 max              | watt      |
| For grid-No.2 voltages between 165 and 33       |            |         |                      |           |
| Plate Dissipation                               |            |         | See curve<br>2.5 max |           |
| Flate Dissipation                               |            |         | 2.5 max              | watts     |
| CHARACTERISTICS:                                |            |         |                      |           |
| Plate Supply Voltage                            |            |         | 125                  | volts     |
| Grid No.3                                       |            |         | to cathode           | at socket |
| Grid-No.2 Supply Voltage                        |            |         | 125                  | volts     |
| Cathode-Bias Resistor                           |            |         | 56                   | ohms      |
| Plate Resistance (Approx.)                      |            |         | 0.18                 | megohm    |
| Transconductance                                |            |         | 15000                | μmhos     |
| Dista Consent                                   |            |         |                      | <b></b>   |

# Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 μa MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

Plate Current .....





#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined vhf oscillator and mixer tube in television receivers employing series-connected heater strings. Outline 6B, **Outlines** section. Tube requires miniature ninecontact socket and may be mounted

6JC8

in any position. Heater volts (ac/dc), 6.3; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, Amplitier  |                             |          |  |                |
|---|-----------------------------|----------|--|----------------|
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage | Triode Unit<br>275 max<br>— | 27<br>27 | ode Unit<br>15 max<br>15 max<br>15 curve | volts<br>volts |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value   | Λ                           |          | 0 max                                    | volts          |
|   | 0 max                       |          |  |                |
| Plate Dissipation   | 1.7 max                     | 2        | .3 max                                   | watts          |
| For grid-No.2 voltages up to 137.5 volts  |                             | 0.4      | 5 max                                    | watt           |
| For grid-No.2 voltages between 137.5 and 275 volts  |                             | See      | curve p                                  | page 75        |
| CHARACTERISTICS:  |                             |          |  |                |
| Plate Voltage   | 125                         | 100      | 125                                      | volts          |
| Grid-No.2 Voltage   |                             | 70       | 125                                      | volts          |
| Grid-No.1 Voltage   | -1                          | Ö        | -1                                       | volt           |
| Amplification Factor  | 40                          | _        | -  |                |
| Plate Resistance (Approx.)  | 6000                        |          | 300000                                   | ohms           |
| Transconductance  | 6500                        | 5700     | 5500                                     | μmhos          |
| Plate Current   | 12                          | 5,00     | 9  | ma             |
| Grid-No.2 Current   |                             |          | 2.2                                      |                |
| Grid-No.1 Voltage (Approx.) for plate current of 20 µa  | _7                          |          | 6.5                                      | volts          |
| Official voltage (Approx.) for plate cultent of 20 µa   | -,                          | _        | 0.5                                      | voits          |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:   |                             |          |  | •              |
| For fixed-bias operation  | _                           | 0.       | 1 max r                                  | negohm         |
| For cathode-bias operation  | _                           |          | 5 max r                                  |                |
|   |                             | ٠.       |  |                |



# SHARP-CUTOFF PENTODE

Miniature type used as if-amplifier tube in television receivers utilizing an intermediate frequency in the order of 40 megacycles. Outline 6B, Outlines section. Tube requires miniature pipe-contact socket and may be

OJDO
Related types:
3JD6, 4JD6

mounted in any position. Types 3JD6 and 4JD6 are identical with type 6JD6

3JD6 6JD6 4JD6 3.5 4.5 6.3 volts Heater Voltage (ac/dc) ...... Heater Current ... 0.6 0.45 0.3 ampere Heater Warm-up Time (Average) ..... 11 11 seconds Peak Heater-Cathode Voltage: 200 max 200 max Heater negative with respect to cathode ... 200 max volts Heater positive with respect to cathode ... 200 max 200 = max 200 max volts Direct Interelectrode Capacitances: Grid No.1 to Plate 0.019 max pf Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield ..... 8.2 pf Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield ....... 3 pf


except for the heater ratings, as shown below.

The dc component must not exceed 100 volts.

Class A, Amplifier


| Oldoo M. Miller   |           |         |
|---|-----------|---------|
| MAXIMUM RATINGS (Design-Maximum Values):                      |           |         |
| Plate Voltage   | 330 max   | volts   |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value           | 0 max     | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage                        | 330 max   | volts   |
| Grid-No.2 Voltage   | See curve | page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value         | 0 max     | volts   |
| Grid-No.2 Input:  |           |         |
| For grid-No.2 voltages up to 165 volts                        | 0.6 max   | watts   |
| For grid-No.2 voltages between 165 and 330 volts              | See curve | page 75 |
| Plate Dissipation   | 2.5 max   | watts   |
| Trace Dissipation   |           |         |
| CHARACTERISTICS:  |           |         |
| Plate Supply Voltage  | 125       | volts   |
| Grid-No.3 Voltage   | 0         | volts   |
| Grid-No.2 Supply Voltage                                      | 125       | volts   |
| Grid-No.1 Supply Voltage                                      | 0         | volts   |
| Cathode-Bias Resistor   | 56        | ohms    |
| Plate Resistance (Approx.)                                    | 160000    | ohms    |
| Transconductance  | 14000     | µmhos   |
| Plate Current   | 15        | μππα ma |
|   | 4         | ma      |
| Grid-No.2 Current   | 4.5       |         |
| Grid-No.1 Voltage (Approx.) for transconductance of 600 μmhos | 4.5       | volts   |
| MAXIMUM CIRCUIT VALUES:                                       |           |         |
| Grid-No.1-Circuit Resistance:                                 |           |         |
| For fixed-bias operation                                      | 0.25      | manahm  |
|   | 0.25 max  |         |
| For cathode-bias operation                                    | ı max     | megohm  |





#### **BEAM POWER TUBE**


6JE6 6JE6A Novar types used as horizontal-deflection-amplifier tubes in color television receivers. Outlines 18B and 32A, respectively, **Outlines** section. Tubes require novar nine-contact socket and may be mounted in any position.




| Heater Voltage (ac/dc) Heater Current  | 6.3<br>2.5         | volts<br>amperes |
|--|--------------------|------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode | 200 max<br>200*max | volts<br>volts   |

| Direct Interelectrode Capacitances (Approx.):          |      |    |
|--|------|----|
| Grid No.1 to Plate                                     | 0.44 | pf |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 21   | ρf |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 11   | pf |

<sup>\*</sup> The dc component must not exceed 100 volts.





Class A, Amplifier

|                                  | Triode      |       | ntode   |           |
|----------------------------------|-------------|-------|---------|-----------|
| CHARACTERISTICS:                 | Connection* | Con   | nection |           |
| Plate Voltage                    | 125         |       | 175     | volts     |
| Grid No.3 (Suppressor Grid)      | Connecte    | ed to | cathode | at socket |
| Grid-No.2 (Screen-Grid) Voltage  |             | 125   | 125     | volts     |
| Grid-No.1 (Control-Grid) Voltage | 25          | 0     | 25      | volts     |
| Amplification Factor             | 3.3         | _     |         |           |
| Plate Resistance (Approx.)       | -           |       | 5500    | ohms      |
| Transconductance                 | _           | _     | 10500   | μmhos     |

|   | Triode<br>Connection* | Pentode<br>Connection |       |
|---|-----------------------|-----------------------|-------|
| Plate Current   | _                     | 580† 115              | ma    |
| Grid-No.2 Current                                     | -                     | 40† 5                 | ma    |
| Grid-No.1 Voltage (Approx.) for plate current of 1 ma | _                     | <b>— —55</b>          | volts |

† This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

▲ Grid No.2 connected to plate.

Horizontal-Deflection Amplifier

| For operation in a 525-line, 30-frame system |           |       |
|--|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |           |       |
| DC Plate Supply Voltage                      | 990 max   | volts |
| Peak Positive-Pulse Plate Voltage            | 7000 max  | volts |
| Peak Negative-Pulse Plate Voltage            | -1100 max | volts |
| DC Grid-No.3 Voltage•                        | 75 max    | volts |
| DC Grid-No.2 Voltage                         | 190 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage        | 250 max   | volts |
| Peak Cathode Current                         | 1100 max  | ma    |
| Average Cathode Current                      | 315 max   | ma    |
| Grid-No.2 Input                              | 3.2 max   | watts |
| Plate Dissipation                            | 24 max    | watts |
| Bulb Temperature (At hottest point)          | 240 max   | °C    |
|  |           |       |

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:


For grid-resistor-bias operation \(^{\text{O}}\) \( \text{...} \) \( \text{max megohm} \) \( \text{...} \) \( \text{10 max megohms} \) \( \text{...} \) \( \text{...} \) \( \text{max megohms} \)

- The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- In this service, a positive voltage may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 30 volts.
- <sup>12</sup> An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

6JE8
Related type:

Miniature type used in television receivers. The triode unit is used as a voltage amplifier or sync separator, and the pentode unit as a video amplifier. Outline 6E, **Outlines** section. Tube requires miniature nine-contact




socket and may be mounted in any position. Type 11JE8 is identical with type 6JE8 except for heater ratings, as shown below.

| -                        | · ·                    |           |             |              |         |
|--------------------------|------------------------|-----------|-------------|--------------|---------|
|                          |                        |           | 6JE8        | 11JE8        |         |
| Heater Voltage (ac/dc)   |                        |           | 6.3         | 10.9         | volts   |
| Heater Current           |                        |           | 0.78        | 0.45         | ampere  |
| Heater Warm-up Time (A   | Average)               |           | _           | 11           | seconds |
| Peak Heater-Cathode Vo   | ltage:                 |           |             |              |         |
| Heater negative with     | respect to cathode     |           | 200 max     | 200 max      | volts   |
|                          | respect to cathode     |           | 200 max     | 200 • max    | volts   |
| • The dc component mus   | t not exceed 100 volts | s.        |             |              |         |
|                          | Class A.               | Amplifier |             |              |         |
| MAXIMUM RATINGS          |                        |           | Triode Unit | Pentode Unit |         |
| Plate Voltage            |                        |           | 300 max     | 330 max      | volts   |
| Grid-No.2 (Screen-Grid)  |                        |           |             | 330 max      | volts   |
| Citation (bettern Offic) | Supply Chage           |           | _           | 330 IIIdx    | 10113   |

Grid-No.2 Voltage — See curve page 75
Grid-No.1 (Control-Grid) Voltage Positive-bias value 0 max 0 max volts
Plate Dissipation 1 max 5 max watts
Grid-No.2 Input:
For plate voltages up to 165 volts — 1.5\*max watts
For plate voltages between 165 and 330 volts — See curve page 75

| CHARACTERISTICS:  | Triode Unit   | Pentode Unit     |
|---|---------------|------------------|
| Plate Voltage   | 200           | 60 250 volts     |
| Grid-No.2 Voltage   |               | 170 170 volts    |
| Grid-No.1 Voltage   | 2             | 0 — volts        |
| Cathode-Bias Resistor                                       |               | 82 ohms          |
| Amplification Factor  | 70            |                  |
| Plate Resistance (Approx.)                                  |               | 0.14 megohm      |
| Transconductance  | 4200          | — 12000 μmhos    |
| Plate Current   | 4.5           | 48= 22 ma        |
| Grid-No.2 Current   |               | 12 <b>=</b> 4 ma |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ a | <del></del> 5 | − −10 volts      |
| MAXIMUM CIRCUIT VALUES:                                     |               |                  |
| Grid-No.1-Circuit Resistance:                               |               |                  |
| For fixed-bias operation                                    | 0.5 max       | 0.25 max megohm  |
| For cathode-bias operation                                  | 1 max         | 1 max megohm     |

- \* Grid-No.2 input may reach 2 watts for plate-dissipation values of 4 watts or less.
- This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.



#### **BEAM POWER TUBE**

Novar types used as horizontal-deflection amplifier tubes in low-B, black-and-white television receivers. Outlines 17B and 31B, respectively, Outlines section. Tubes require novar nine-contact socket and may be mounted

6JG6 6JG6A

Related types: 17JG6, 17JG6A, 22JG6, 22JG6A


in any position. Types 17JG6 and 17JG6A and types 22JG6 and 22JG6A are identical with types 6JG6 and 6JG6A except for heater ratings, as shown below.


|  | 6JG6      | 17JG6  | 22JG6      |         |
|--|-----------|--------|------------|---------|
|  | 6JG6A     | 17JG6A | 22JG6A     |         |
| Heater Voltage (ac/dc)                     | 6.3       | 16.8   | 22         | volts   |
| Heater Current                             | 1.6       | 0.6    | 0.45       | amperes |
| Heater Warm-up Time (Average)              | _         | 11     | 11         | seconds |
| Peak Heater-Cathode Voltage:               |           |        |            |         |
| Heater negative with respect to cathode    |           |        | 200 max    | volts   |
| Heater positive with respect to cathode    |           |        | 200#max    | volts   |
| Direct Interelectrode Capacitances:        |           |        | 200# 11124 | 10113   |
| Grid No.1 to Plate                         |           |        | 0.7        | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2,   |           |        | 22         | pf      |
| Plate to Cathode, Heater, Grid No.2, and C | irid No.3 | 1      | 79         | pf      |
|  |           |        | ,          | 24      |

# The dc component must not exceed 100 volts.

| Class A,                                       | Amplifier                    |          |                         |               |
|--|------------------------------|----------|-------------------------|---------------|
| CHARACTERISTICS: Plate Voltage                 | Triode=<br>Connection<br>125 |          | ntode<br>nection<br>130 | volts         |
| Grid No.3 (Suppressor Grid)                    |                              | Connect  | ed to cath              | ode at socket |
| Grid-No.2 (Screen-Grid) Voltage                |                              | 125<br>0 | 125<br>—20              | volts         |
| Amplification Factor                           |                              | -        | -20                     | volts         |
| Plate Resistance (Approx.)                     |                              | _        | 12000                   | ohms          |
| Transconductance                               |                              | 525•     | 10000<br>80             | μmhos         |
| Grid-No.2 Current Grid-No.1 Voltage (Approx.), |                              | 32.      | 2.5                     | ma<br>ma      |
| for plate current of 1 ma                      | -                            | -        | -40                     | volts         |

- •With grid No.2 connected to plate at socket.
- This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.





# Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values):  |           |       |
|---|-----------|-------|
| DC Plate Supply Voltage                   | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage         | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage         | -1500 max | volts |
| DC Grid-No.3 Voltage*                     | 75 max    | volts |
| DC Grid-No.2 Voltage                      | 220 max   | volts |
| DC Grid-No.1 Voltage, Negative-bias value | —55 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage     | -330 max  | volts |
| Peak Cathode Current                      | 950 max   | ma    |
| Average Cathode Current                   | 275 max   | ma    |
| Plate Dissipation†                        | 17 max    | watts |
| Grid-No.2 Input                           | 3.5 max   | watts |
| Bulb Temperature (At hottest point)       | 220 max   | °C    |

#### MAXIMUM CIRCUIT VALUES:


Grid-No.1 Circuit Resistance:

For grid-No.1-resistor-bias operation .....

2.2 max megohms

□ The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

- \* In a horizontal-deflection-amplifier service, a positive voltage (typical value, 30 volts) may be applied to grid No.3 to reduce "snivets" interference, which may occur in both vhf and uhf television receivers.
- † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.



# SEMIREMOTE-CUTOFF PENTODE

Miniature type used in the gain-controlled picture if-amplifier stages of television receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. For curves

**6JH6** 

---

of average plate characteristics, refer to type 6BZ6.

| Heater Voltage (ac/dc)                          |           | 6.3                 | volts  |
|---|-----------|---------------------|--------|
| Heater Current                                  |           | 0.3                 | ampere |
| Peak Heater-Cathode Voltage:                    |           |                     |        |
| Heater negative with respect to cathode         |           | 200 max             | volts  |
| Heater positive with respect to cathode         |           | 200 max             | volts  |
| •   | Without   | With                |        |
|   | External  | External            |        |
| Direct Interelectrode Capacitances:             | Shield    | Shield <sup>□</sup> |        |
| Grid No.1 to Plate                              | 0.025 max | 0.015 max           | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid   |           |                     | • -    |
| No.3, and Internal Shield                       | 7         | 7                   | pf     |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, |           |                     | •      |
| and Internal Shield                             | 2         | 3                   | pf     |
| The de commonent must not exceed 100 volts      |           |                     |        |

- The dc component must not exceed 100 volts.
- With external shield connected to cathode.

# Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):              |                   |
|---|-------------------|
| Plate Voltage   | 300 max volts     |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value   | 0 max volts       |
| Grid-No.2 (Screen-Grid) Supply Voltage                | 300 max volts     |
| Grid-No.2 Voltage                                     | See curve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max volts       |
| Grid-No.2 Input:                                      |                   |
| For grid-No.2 voltages up to 150 volts                | 0.55 max watt     |
| For grid-No.2 voltages between 150 and 300 volts      | See curve page 75 |

# CHARACTERISTICS:

| riate Supply Voltage                                       |           | 123        | YOILS      |
|--|-----------|------------|------------|
| Grid No.3  | Connected | to cathode | at socket  |
| Grid-No.2 Supply Voltage                                   |           | 125        | volts      |
| Cathode-Bias Resistor                                      |           | 56         | ohms       |
| Plate Resistance (Approx.)                                 |           | 0.26       | megohm     |
| Transconductance   |           | 8000       | $\mu$ mhos |
| Transconductance Range for grid-No.1 voltage of -4.5 volts |           |            |            |
| cathode-bias resistor of 56 ohms                           |           | 400-900    | μmhos      |

Grid-No.1 Voltage (Approx.) for transconductance of 50  $\mu$ mhos and no cathode-bias resistor —19 volts Plate Current 14 ma Grid-No.2 Current 3.6 ma

#### MAXIMUM CIRCUIT VALUES:


Grid-No.1-Circuit Resistance:

For fixed-bias operation 0.25 max megohm
For cathode-bias operation 1 max megohm

#### **BEAM-DEFLECTION TUBE**

**6JH8** 

Miniature type used in color-demodulator and burst-gate circuits in color television receivers. This type has two plates and two deflecting electrodes; the control grid varies beam deflection. Outline 6E, Outlines section.



Tube requires miniature nine-contact socket and may be mounted in any position. Pin 5 should be connected to cathode at socket. The 6JH8 should be so located in the equipment that it is not subjected to stray magnetic fields. Heater volts (ac/dc), 6.3; amperes, 0.3.

| Color | T۷ | Demo | dulator |
|-------|----|------|---------|
|-------|----|------|---------|

| MAXIMUM RATINGS (Design-Maximum Values):              |          |       |
|---|----------|-------|
| Plate Voltage (Each Plate)                            | 330 max  | volts |
| Peak Deflecting-Electrode Voltage (Each Electrode):   |          |       |
| Negative value  | —165 max | volts |
| Positive value  | 165 max  | volts |
| Grid-No.3 (Accelerating-Grid) Voltage                 | 330 max  | volts |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max    | volts |
| Cathode Current                                       | 33 max   | ma    |
| Plate Dissipation (Each Plate)                        |          | watts |
| Grid-No.3 Input                                       | 1 max    | watt  |
|   |          |       |

#### MAXIMUM CIRCUIT VALUES:

| ilu-140.1 Circuit Resistance. |          |         |
|-------------------------------|----------|---------|
| For fixed-bias operation      | 0.1 max  | megohin |
| For cathode-bias operation    | 0.25 max | megohm  |

Class A, Amplifier

With both plates connected together and with both deflecting electrodes connected to cathode at socket

| CHARACTERISTICS:   |      |       |
|--|------|-------|
| Plate-No.1 Supply Voltage                                    | 250  | volts |
| Plate-No.2 Supply Voltage                                    | 250  | volts |
| Grid-No.3 Voltage  | 250  | volts |
| Cathode-Bias Resistor  | 220  | ohms  |
| Transconductance   | 4400 | μmhos |
| Total Plate Current  | 14   | ma    |
| Grid-No.3 Current  |      | ma    |
| Grid-No.1 Voltage (Approx.) for total plate current of 10 ua | -13  | volts |
| •                      |      |       |

#### DUAL TRIODE

6JK8


Miniature type used as combined rfamplifier and mixer-oscillator tube in KT2 FM tuners. Unit No.1 is a mediummu triode unit used as an oscillator- cT2 mixer, and unit No.2 is a high-mu triode unit used as an rf amplifier.



Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage:               | 6.3<br>0.4         | volts<br>ampere |
|--|--------------------|-----------------|
| Heater negative with respect to cathode  Heater positive with respect to cathode | 100 max<br>100 max | volts<br>volts  |

| Direct Interelectrode Capacitances: Grid to Plate Grid to Cathode, Heater, and Internal Shield Plate to Cathode, Heater, and Internal Shield Heater to Cathode Grid of Unit No.1 to Grid of Unit No.2 Plate of Unit No.1 to Plate of Unit No.2     |  | Unit No.2<br>0.6<br>5<br>4<br>2.8<br>0.003 max<br>0.009 max      | pf<br>pf<br>pf<br>pf<br>pf<br>pf                        |
|--|--|--|---|
| Class A, Amplifier   |  |  |   |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage DC Cathode Current Plate Dissipation  | Unit No.1<br>Oscillator<br>165 max<br>-50 max<br>22 max<br>1 max | Unit No.2<br>RF Amplifie<br>200 max<br>50 max<br>22 max<br>2 max | volts<br>volts<br>ma<br>watts                           |
| CHARACTERISTICS: Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.): For plate current of 20 µa For transconductance of 150 µmhos For transconductance of 1500 µmhos | 100<br>-11<br>55<br>8000<br>6800<br>5.3<br>-4.4                  | 135<br>-1.2<br>70<br>5400<br>13000<br>10<br>-5.5<br>-2.8         | volts<br>volts<br>ohms<br>µmhos<br>ma<br>volts<br>volts |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance:   |  |  |   |



### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as FM converter and rf-amplifier tube in radio receivers employing series-connected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any

6JN8
Related Type: 19JN8

1 max megohm

1 max

position. Type 19JN8 is identical with type 6JN8 except for heater ratings, as shown below.

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage:                                      | 6JN8<br>6.3<br>0.45<br>11 | 19JN8<br>18.9<br>0.15 | volts<br>ampere<br>seconds |
|---|---------------------------|-----------------------|----------------------------|
| Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances:*  Pentode Unit: | 200 max<br>200•max        | 200 max<br>200 max    | volts<br>volts             |
| Grid No.1 to Plate  |                           | 0.01                  | pf                         |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, an Shield   |                           | 5.5                   | pf                         |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Shield  | i Internal                | 3.4                   | pf                         |
| Grid to Plate   |                           | 1.7                   | pf                         |
| Grid to Cathode, Heater, Pentode Cathode, Grid No.<br>and Internal Shield Plate to Cathode, Heater, Pentode Cathode, Grid No.         |                           | 3.2                   | pf                         |
| and Internal Shield   |                           | 2.2                   | pf                         |

<sup>•</sup> The dc component must not exceed 100 volts.

For cathode-bias operation .....

<sup>\*</sup> With external shield connected to cathode of unit under test.

| Class A, Amplifier                                     |                    |              |        |
|--|--------------------|--------------|--------|
| MAXIMUM RATINGS (Design-Maximum Values):               | Triode Unit        | Pentode Unit |        |
| Plate Voltage  | 300 max            | 300 max      | volts  |
| Grid-No.2 (Screen-Grid) Supply Voltage                 | _                  | 300 max      | volts  |
| Grid-No.2 Voltage                                      | _                  | See curve p  | age 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  | 0 max              | 0 max        | volts  |
| Plate Dissipation                                      | 2.5 max            | 2.5 max      | watts  |
| Grid-No.2 Input:                                       |                    |              |        |
| For grid-No.2 voltages up to 150 volts                 | _                  | 0.55 max     | watt   |
| For grid-No.2 voltages between 150 and 300 volts       | -                  | See curve p  | age 75 |
| CHARACTERISTICS:                                       |                    |              |        |
| Plate Voltage  | 125                | 125          | voits  |
| Grid-No.2 Voltage                                      |                    | 125          | volts  |
| Grid-No.1 Voltage                                      | -1                 | -1           | volt   |
| Amplification Factor                                   | 46                 |              | ,,,,   |
| Plate Resistance (Approx.)                             | 5400               | 200000       | ohms   |
| Transconductance                                       | 8500               | 7500         | μmhos  |
| Plate Current  | 13.5               | 12           | ma     |
| Grid-No.2 Current                                      | _                  | 4            | ma     |
| Grid-No.1 Voltage (Approx.) for plate current of 10 µa | 8                  | 8            | volts  |
| MAXIMUM CIRCUIT VALUES:                                |                    |              |        |
| Grid-No.1-Circuit Resistance:                          |                    |              |        |
| For fixed-bias operation                               | 2.2 max            | 2.2 may m    |        |
| For cathode-bias operation                             | 2.2 max<br>2.2 max | 2.2 max me   |        |
| Tot cadiode ones operation                             | 2.2 max            | 2.2 max me   | Roums  |

# 6JT6 6JT6A

Related types: 12JT6A, 17JT6, 17JT6A

# **BEAM POWER TUBE**

Novar types used as horizontal deflection amplifiers in high-efficiency deflection circuits of black-and-white television receivers employing wideangle or high-voltage picture tubes. Tubes require novar nine-contact



socket and may be mounted in any position. Outlines 17C and 31A, respectively, Outlines section. Types 12JT6 and 12JT6A and types 17JT6 and 17JT6A are identical with types 6JT6 and 6JT6A except for heater ratings, as shown below.

|  | 6JT6<br>6JT6A | 12JT6<br>12JT6A | 17JT6<br>17JT6A |         |
|--|---------------|-----------------|-----------------|---------|
| Heater Voltage (ac/dc)                     | 6.3           | 12.6            | 16.8            | volts   |
| Heater Current                             |               | 0.6             | 0.45            | amperes |
| Heater Warm-up Time (Average)              |               | 11              | 11              | seconds |
| Peak Heater-Cathode Voltage:               |               |                 |                 |         |
| Heater negative with respect to cathode    |               |                 | 200 max         | volts   |
| Heater positive with respect to cathode    |               |                 | 200 • max       | volts   |
| Direct Interelectrode Capacitances:        |               |                 |                 |         |
| Grid No.1 to Plate                         |               |                 | 0.26            | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, a |               |                 | 15              | pf      |
| Plate to Cathode, Heater, Grid No.2, and C | irid No.3     | 3               | 6.5             | pf      |

<sup>•</sup> The dc component must not exceed 100 volts.

#### Class A, Amplifier

| CHARACTERISTICS:                                      |       |                |             |
|---|-------|----------------|-------------|
| Plate Voltage   | 60    | 250            | volts       |
| Grid No.3 (Suppressor Grid)                           | Conne | cted to cathod | e at socket |
| Grid-No.2 (Screen-Grid) Voltage                       | 150   | 150            | volts       |
| Grid-No.1 (Screen-Grid) Voltage                       | 0     | -22.5          | volts       |
| Triode Amplification Factor                           | _     | 4.4*           |             |
| Plate Resistance (Approx.)                            |       | 15000          | ohms        |
| Transconductance                                      | _     | 7100           | μmhos       |
| Plate Current   | 390=  | 70             | . ma        |
| Grid-No.2 Current                                     | 32•   | 2.1            | ma          |
| Grid-No.1 Voltage (Approx.) for plate current of 1 ma | _     | -42            | volts       |
|   |       |                |             |

<sup>\*</sup> Grid No.2 connected to plate; plate and grid-No.2 volts, 150; grid-No.1 volts, -22.5.

<sup>•</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

1 max megohm

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values):  |           |       |
|---|-----------|-------|
| DC Plate Supply Voltage                   | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage#        | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage         | -1500 max | volts |
| DC Grid-No.3 Voltage <sup>a</sup>         | 70 max    | volts |
| DC Grid-No.2 Voltage                      | 220 max   | volts |
| DC Grid-No.1 Voltage, Negative-bias value | —55 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage     | —330 max  | volts |
| Peak Cathode Current                      | 550 max   | ma    |
| Average Cathode Current                   | 175 max   | ma    |
| Plate Dissipation†                        | 17.5 max  | watts |
| Grid-No.2 Input                           | 3.5 max   | watts |
| Bulb Temperature (At hottest point)       | 240 max   | °C    |


#### **MAXIMUM CIRCUIT VALUE:**


Grid-No.1-Circuit Resistance:
For grid-resistor-bias operation

# The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle.

- In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

  A positive voltage may be applied to grid No.3 to reduce interference from "snivets" which may occur in television receivers. A typical value for this voltage is 30 volts.
- † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.





#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type with frame-grid pentode unit used in television receivers. The triode unit is used as a voltageamplifier or sync-separator tube, and the pentode unit is used as a videoamplifier tube. Outline 10A, Outlines

6JT8

section, except base is small-button miniature 9-pin. Tube requires miniature nine-contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.725; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts   | Triode Unit 330 max - 0 max 1 max                     | Pentode Unit 330 max volts 330 max volts See curve page 75 0 max volts 4 max watts 1.1 max watts See curve page 75 |
|--|---|--|
| CHARACTERISTICS: Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 µa Grid-No.1 Voltage (Approx.) for plate current of 20 µa | 250<br>-2<br>100<br>37000<br>2700<br>1.5<br>-<br>-5.3 | 35 200 volts 100 100 volts 0 — volts - 82 ohms - 50000 ohms - 20000 µmhos 50° 17 ma 17° 3.5 ma5 volts - volts      |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation  | 0.5 max<br>1 max                                      | 0.25 max megohm<br>1 max megohm  |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.


### QUADRUPLE DIODE

# 8UL6 A8UL6

DC Output Current .....

Miniature types used in phase-detector and noise-immune, color-killer circuits of color television receivers; also used in bridge-matrixing circuits in FM stereo multiplex equipment.


Outlines 6E and 6B, respectively, Out-



9 max

lines section. Units 1 and 2 are shielded from units 3 and 4 to minimize coupling between the series-connected pairs of diodes. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc) 6.3 volts Heater Current 0.6 ampere Peak Heater-Cathode Voltage: Heater negative with respect to cathode 300 max volts Heater positive with respect to cathode 300 max volts Direct Interelectrode Capacitances (Approx.): Plate of Unit No.1 and Cathode of Unit No.2 to Cathode of Unit No.1 1 1.8 pf Plate of Unit No.1 and Cathode of Unit No.2 to Plate of Unit No.2 2 pf |
|---|
| Heater Current 0.6 ampere Peak Heater-Cathode Voltage: Heater negative with respect to cathode 300 max volts Heater positive with respect to cathode 300 max volts Direct Interelectrode Capacitances (Approx.): Plate of Unit No.1 and Cathode of Unit No.2 to Cathode of Unit No.1 1  |
| Peak Heater-Cathode Voltage: Heater negative with respect to cathode 300 max volts Heater positive with respect to cathode 300 max volts Direct Interelectrode Capacitances (Approx.): Plate of Unit No.1 and Cathode of Unit No.2 to Cathode of Unit No.1 1.8 pf Plate of Unit No.1 and Cathode of Unit No.2 to Plate of   |
| Heater negative with respect to cathode   |
| Heater positive with respect to cathode 300 max volts  Direct Interelectrode Capacitances (Approx.):  Plate of Unit No.1 and Cathode of Unit No.2 to Cathode of  Unit No.1 1.8 pf  Plate of Unit No.1 and Cathode of Unit No.2 to Plate of  |
| Direct Interelectrode Capacitances (Approx.): Plate of Unit No.1 and Cathode of Unit No.2 to Cathode of Unit No.1   |
| Plate of Unit No.1 and Cathode of Unit No.2 to Cathode of Unit No.1   |
| Unit No.1   |
| Plate of Unit No.1 and Cathode of Unit No.2 to Plate of   |
|   |
| Unit No.2 2.2 pf  |
|   |
| Plate of Unit No.2 to Heater and Internal Shield 0.62 pf  |
| Plate of Unit No.3 and Cathode of Unit No.4 to Cathode of   |
| Unit No.3 1.9 pf  |
| Plate of Unit No.3 and Cathode of Unit No.4 to Plate of   |
|   |
| Unit No.4   |
| Plate of Unit No.4 to Heater and Internal Shield 0.94 pf  |
| Cathode of Unit No.1 to Heater and Internal Shield 1.8 pf   |
| Cathode of Unit No.3 to Heater and Internal Shield  |
|   |
| MAXIMUM RATINGS (Design-Maximum Values, Each Unit):   |
| Peak Inverse Plate Voltage  |
| Peak Plate Current 54 max volts   |



# HIGH-MU TRIODE— SHARP-CUTOFF PENTODE


Miniature type used in a wide variety of applications in television receivers, particularly those having low-voltage "B" supplies and employing seriesconnected heater strings. The triode unit is used in sound-if, keyed-agc,

6JV8
Related type:
8JV8

sync-separator, sync-amplifier, and noise-suppression circuits. The pentode unit is especially useful as a video amplifier tube. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Type 8JV8 is identical with type 6JV8 except for the heater ratings, as shown below.

|   | 6JV8      | 8JV8      |         |
|---|-----------|-----------|---------|
| Heater Voltage (ac/dc)                              | 6.3       | 8.5       | volts   |
| Heater Current                                      | 0.6       | 0.45      | ampere  |
| Heater Warm-up Time (Average)                       | 11        | 11        | seconds |
| Peak Heater-Cathode Voltage:                        |           |           |         |
| Heater negative with respect to cathode             | 200 max   | 200 max   | volts   |
| Heater positive with respect to cathode             | 200 = max | 200 • max | volts   |
| Direct Interelectrode Capacitances (Approx.):       |           |           |         |
| Triode Unit:  |           |           |         |
| Grid to Plate                                       |           | 2.2       | pf      |
| Grid to Cathode and Heater                          |           | 3         | pf      |
| Plate to Cathode and Heater                         |           | 2         | pf      |
| Pentode Unit:                                       |           |           |         |
| Grid No.1 to Plate                                  |           | 0.08 max  | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, |           |           |         |
| Internal Shield                                     |           | 8         | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and |           |           |         |
| Internal Shield                                     |           | 3.2       | pf      |
| Pentode Grid No.1 to Triode Plate                   |           | 0.012 max | pf      |
| Pentode Plate to Triode Plate                       |           | 0.24 max  | pf      |

• The dc component must not exceed 100 volts.



Class A, Amplifier


| MAXIMUM RATINGS (Design-Maximum                       | Values):    |     | riode<br>Jnit | Pentode<br>Unit |            |
|---|-------------|-----|---------------|-----------------|------------|
| Plate Voltage   |             | 330 | max           | 330 max         | volts      |
| Grid-No.2 (Screen-Grid) Voltage                       |             |     |               | 330 max         | volts      |
| Grid-No.1 (Control-Grid) Voltage:                     |             |     |               |                 |            |
| Positive-bias value                                   |             | 0   | max           | 0 max           | volts      |
| Negative-bias value                                   |             | 50  | max           | 50 max          | volts      |
| Plate Dissipation                                     |             | 1.1 | max           | 4 max           |            |
| Grid-No.2 Input                                       |             | _   | •             | 1.7 max         | watts      |
| CHARACTERISTICS:                                      | Triode Unit | P   | entode (      | Jnit            |            |
| Plate Voltage   | 200         | 60  | 125           | 200             | volts      |
| Grid-No.2 Voltage                                     | _           | 200 | 125           | 200             | volts      |
| Grid-No.1 Voltage                                     | -2          | 0   | -1            | -2.9            | volts      |
| Amplification Factor                                  | 70          | _   | _             | _               |            |
| Plate Resistance (Approx.)                            | 0.0175      |     | 0.1           | 0.15            | megohm     |
| Transconductance                                      | 4000        |     | 11500         | 10700           | $\mu$ mhos |
| Plate Current   | 4           | 51• | 22            | 22              | ma         |
| Grid-No.2 Current                                     | -           | 14• | 4             | 4               | ma         |
| Grid-No.1 Voltage (Approx.) for plate                 |             |     |               |                 | _          |
| current of 20 μa                                      | 5           | -   | <b></b> 5.5   | -9              | volts      |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Current Resistance: |             |     |               |                 |            |
| For fixed-bias operation                              |             | 0.5 | max           | 0.25 max        | megohm     |
| For cathode-bias operation                            |             | 1   | max           | 1 max           | megohm     |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### MEDIUM-MU TRIODE— BEAM POWER TUBE

**6JZ8** 

Duodecar type used in combined vertical-deflection-oscillator and vertical-deflection-amplifier applications in tel-evision receivers. Outline 8B, Outlines section. Tube requires duodecar twelve-contact socket and may be



mounted in any position. Heater volts (ac/dc), 6.3; amperes, 1.2; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when heater is positive with respect to cathode).

| Class A,                                      | Amplifier   |       |          |       |
|---|-------------|-------|----------|-------|
|   | Triode Unit | Pent  | ode Unit |       |
| Plate Voltage                                 | 150         | 45    | 120      | volts |
| Grid-No.2 (Screen-Grid) Voltage               |             | 110   | 110      | volts |
| Grid-No.1 (Control-Grid) Voltage              | <b>—5</b>   | 0     | -8       | volts |
| Amplification Factor                          | 20          |       | _        |       |
| Plate Resistance (Approx.)                    | 8500        | -     | 11700    | ohms  |
| Transconductance                              | 2350        |       | 7100     | μmhos |
| Plate Current                                 | 5.5         | 122 - | 46       | ma    |
| Grid-No.2 Current                             | _           | 16.5  | 3.5      | ma    |
| Grid-No.1 Voltage (Approx.) for plate current |             |       |          |       |
| of 10 μa                                      |             |       | _        | volts |
| Grid-No.1 Voltage (Approx.) for plate current |             |       |          |       |
| of 100 μa                                     | _           |       | -25      | volts |
|   |             |       |          |       |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

# Vertical Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

| Tot operation in a 325-mic, 30-m         | Triode<br>Unit | Beam Power<br>Unit |       |
|--|----------------|--------------------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator     | Amplifier          |       |
| DC Plate Voltage                         | 250 max        | 250 max            | volts |
| Pack Positive-Pulse Plate Voltage#       |                | 2000 max           | voite |

| DC Grid-No.2 Voltage                  | _        | 200 max  | volts   |
|---------------------------------------|----------|----------|---------|
| Peak Negative-Pulse Grid-No.1 Voltage | -400 max | —150 max | volts   |
| Peak Cathode Current                  | 70 max   | 245 max  | ma      |
| Average Cathode Current               | 20 max   | 70 max   | ma      |
| Plate Dissipation                     | 1 max    | 7 max    | watts   |
| Grid-No.2 Input                       | _        | 1.8 max  | watts   |
| MAXIMUM CIRCUIT VALUES:               |          |          |         |
| Grid-No.1-Circuit Resistance:         |          |          |         |
| For fixed-bias operation              | 1 max    | 1 max    | megohm  |
| For cathode-bias operation            | 2.2 max  | 2.2 max  | megohms |

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

#### HIGH-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

6K5GT



Heater Current .....

#### **POWER PENTODE**

Glass octal type used in output stage of radio receivers and, triode-connected, as a vertical deflection amplifier in television receivers. It is capable of delivering moderate power output with relatively small input

6K6GT

6.3

0.4

volts

ampere

voltage. Tube may be used singly or in push-pull. This type may be supplied with pin No.1 omitted. Tube requires octal socket and may be mounted in any position. Outline 13D, Outlines section. It is especially important that this tube, like other power-handling tubes, be adequately ventilated.

Heater Voltage (ac/dc) .....

| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode Heater positive with respect to cathode Direct Interelectrode Capacitances (Approx.): |           |                   | 200 max<br>200*max                       | volts<br>volts                   |
|---|-----------|-------------------|--|----------------------------------|
| Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3                                |           | 0.5<br>5.5<br>6.0 | pf<br>pf<br>pf                           |                                  |
| * The dc component must not exceed 100 volts  | s.        |                   |  |                                  |
| Class A, A  | Amplifi   | er                |  |                                  |
| MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.2 (Screen-Grid) Voltage Plate Dissipation Grid-No.2 Input                                      |           |                   | 315 max<br>285 max<br>8.5 max<br>2.8 max | volts<br>volts<br>watts<br>watts |
| TYPICAL OPERATION:  |           |                   |  |                                  |
| Plate Voltage   | 100       | 250               | 315                                      | volts                            |
| Grid-No.2 Voltage   | 100       | 250               | 250                                      | volts                            |
| Grid-No.1 (Control-Grid) Voltage  | <u>-7</u> | -18               | -21                                      | volts                            |
| Peak AF Grid-No.1 Voltage   | 7         | 18                | 21                                       | volts                            |
| Zero-Signal Plate Current   | 9         | 32                | 25.5                                     | ma                               |
| Maximum-Signal Plate Current  | 9.5       | 33                | 28                                       | ma                               |
| Zero-Signal Grid-No.2 Current   | 1.6       | 5.5               | 4.0                                      | ma                               |
| Maximum-Signal Grid-No.2 Current  | 3         | 10                | 9  | ma                               |
| Plate Resistance (Approx.)  |           | 90000             | 110000                                   | ohms                             |
| Transconductance  | 1500      | 2300              | 2100                                     | $\mu$ mhos                       |
| Load Resistance   | 12000     | 7600              | 9000                                     | ohms                             |
| Total Harmonic Distortion   | 11        | 11                | 15                                       | per cent                         |
| Maximum-Signal Power Output   | 0.35      | 3.4               | 4.5                                      | watts                            |

| TYPICAL PUSH-PULL OPERATION (values are                 |            |              |          |
|---|------------|--------------|----------|
| for two tubes):   | Fixed Bias | Cathode Bias |          |
| Plate Supply Voltage                                    | 285        | 285          | volts    |
| Grid-No.2 Supply Voltage                                | 285        | 285          | volts    |
| Grid-No.1 Voltage                                       | 25.5       |              | volts    |
| Cathode-Bias Resistor                                   | -          | 400          | ohms     |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage                  | 51         | 51           | volts    |
| Zero-Signal Plate Current                               | 55         | 55           | ma       |
| Maximum-Signal Plate Current                            | 72         | 61           | ma       |
| Zero-Signal Grid-No.2 Current                           | 9          | 9            | ma       |
| Maximum-Signal Grid-No.2 Current                        | 17         | 13           | ma       |
| Effective Load Resistance (Plate-to-plate)              | 12000      | 12000        | ohms     |
| Total Harmonic Distortion                               | 6          | 4            | per cent |
| Maximum-Signal Power Output                             | 10.5       | 9.8          | watts    |
| CHAD ACTEDICTICS (Tale 4. Comments and                  |            |              |          |
| CHARACTERISTICS (Triode Connection)*:                   |            | 4.7.4        |          |
| Plate Voltage   |            | 250          | volts    |
| Grid-No.1 Voltage                                       |            | -18          | volts    |
| Plate Current   |            | 37.5         | ma       |
| Transconductance  |            | 2700         | μmhos    |
| Amplification Factor                                    | <i></i>    | 6.8          |          |
| Plate Resistance (Approx.)                              |            | 2500         | ohms     |
| Grid-No.1 Voltage (Approx.) for plate current of 0.5 ma |            | 48           | volts    |
| MAXIMUM CIRCUIT VALUES:                                 |            |              |          |
| Grid-No.1-Circuit Resistance:                           |            |              |          |
| For fixed-bias operation                                |            | 0.1 mar      | megohm   |
| For cathode-bias operation                              |            |              |          |
| Tot camoue-oras operation                               |            | o.s max      | megohm   |

<sup>\*</sup> Grid-No.2 connected to plate.

VPICAL PUSHIBLE OPERATION (Values are

# Vertical Deflection Amplifier (Triode Connection)\*

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS:                                      |           |       |
|---|-----------|-------|
| DC Plate Voltage                                      | 315 max   | volts |
| Peak Positive-Pulse Plate Voltage† (Absolute maximum) | 1200° max | volts |
| Peak Negative-Pulse Grid-No.1 Voltage                 | -250 max  | volts |
| Peak Cathode Current                                  | 75 max    | ma    |
| Average Cathode Current                               | 25 max    | ma    |
| Plate Dissipation                                     | 7 max     | watts |
|   |           |       |

#### MAXIMUM CIRCUIT VALUE: Grid-No.1-Circuit Resistance:

For cathode-bias operation .....

2.2 max megohms

† The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

6K7

# REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6K7G

# REMOTE-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

6K7GT

# **REMOTE-CUTOFF PENTODE**

Renewal type; see chart at end of section for tabulated data.

<sup>\*</sup> Grid No.2 connected to plate.

<sup>&</sup>quot;Under no circumstances should this absolute value be exceeded.

#### TRIODE-HEXODE CONVERTER

Renewal type; see chart at end of section for tabulated data.

**6K8** 

### TRIODE-HEXODE CONVERTER

Discontinued types; see chart at end of section for tabulated data.

6K8G 6K8GT

### THREE-UNIT TRIODE

Discontinued type; see chart at end of section for tabulated data.

6K11




Duodecar type containing one mediummu and two high-mu triode units used as combined agc, sync, and noise-inverter tube in television receivers employing series-connected heater strings. Outline 8A, Outlines section.

6K11/6Q11

(the dc component must not exceed 100 volts when the heater is positive with respect Heater volts (ac/dc), 6.3; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

### Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):               | Unit<br>No.1 | Units Nos.<br>2 and 3 |       |
|--|--------------|-----------------------|-------|
| Plate Voltage  | 330 max      | 330 max               | volts |
| Grid Voltage:  |              |                       |       |
| Negative-bias value                                    | -50 max      | —50 max               | volts |
| Positive-bias value                                    | 0 max        | 0 max                 | volts |
| Cathode Current  | 20 max       | -                     | ma    |
| Plate Dissipation                                      | 2.75 max     | 0.3 max               | watts |
| CHARACTERISTICS:                                       |              |                       |       |
| Plate Voltage  | 250          | 250                   | volts |
| Grid Voltage   | 8.5          | -2                    | volts |
| Amplification Factor                                   | 17           | 100                   |       |
| Plate Resistance (Approx.)                             | 7700         | 62500                 | ohms  |
| Transconductance                                       | 2200         | 1600                  | μmhos |
| Plate Current  | 10.5         | 1.2                   | ma    |
| Grid Voltage (Approx.) for plate current of 10 $\mu$ a | -24          | _                     | volts |
|  |              |                       |       |



### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receivers employing series-connected heater strings. The triode unit is used in sync-separator circuits; the pentode unit has two independent control

6KA8
Related type:

-50 max

volts

grids and is used in gated-agc-amplifier and noise-inverter circuits. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For curves of average plate characteristics for triode unit, refer to type 6AW8A. Type 8KA8 is identical with type 6KA8 except for the heater ratings, as shown below.

| radings, as shown below.   |                         |  |  |
|--|-------------------------|--|--|
| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage: Heater negative with respect to cathode Heater positive with respect to cathode Direct Interelectrode Capacitances: Triode Unit: Grid to Plate Grid to Cathode, Heater, and Internal Shield Plate to Cathode, Heater, and Internal Shield Pentode Unit: Grid-No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No and Internal Shield Grid No.1 to Grid No.3 Grid No.3 to Plate |                         | 8KA8<br>8.4<br>0.45<br>11<br>200 max<br>200*max<br>2.2<br>2.8<br>2.2<br>0.1 max<br>9.5<br>0.5<br>2.2 | volts<br>ampere<br>seconds<br>volts<br>volts<br>pf<br>pf<br>pf |
| Grid No.3 to All Other Electrodes, Heater, and Intern  | nai Snieid              | 7  | pf   |
| • The dc component must not exceed 100 volts.  |                         |  |  |
| Class A, Amplifie  MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage  Grid Voltage:   |                         | Triode Unit  | volts  |
| Positive-bias value  |                         | 0 max  | volts  |
| Negative-bias value  |                         | -50 max  | volts  |
| Plate Dissipation  |                         | 1.1 max  | watts  |
| CHARACTERISTICS: Plate Supply Voltage Grid-No.3 Supply Voltage Grid-No.2 Supply Voltage  | Triode Unit<br>200<br>— | Pentode Unit<br>150<br>0<br>100  | volts<br>volts<br>volts  |
| Grid-No.1 Supply Voltage Cathode-Bias Resistor Amplification Factor  | -2<br>-70               | 180  | volts<br>ohms  |
| Plate Resistance (Approx.)   | 17500                   | 100000   | ohms   |
| Transconductance, Grid No.1 to Plate   | 4000                    | 4400   | μmhos  |
| Transconductance, Grid No.3 to Plate   | <del>-</del>            | 600<br>4   | μmhos<br>ma  |
| Grid-No.1 Supply Voltage (Approx.):  |                         | 2.8  | ma   |
| For plate current of 10 µa   | 5                       | -  | volts  |
| For plate current of 20 $\mu$ a  | _                       | -4   | volts  |
| of 20 μa   | -                       | <b>—7</b>  | volts  |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance:   |                         | Triode Uni   |  |
| For fixed-bias operation   |                         | 0.25 max   | megonm   |
|  |                         | 1 11144  | megomm   |
| Gated AGC Amplifier and No   | oise Inverter           | Daniela II-  |  |
| MAXIMUM RATINGS (Design-Maximum Values): DC Plate Voltage  |                         | Pentode Uni<br>300 max   | volts  |
| Peak Positive-Pulse Plate Voltage  |                         | 600 max  | volts  |
| Positive-bias value  |                         | 0 max  | volts  |
| Negative-bias value  |                         | 100 max<br>300 max   | volts<br>volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage   |                         |  | e page 75  |
| Grid-No.1 (Control-Grid) Voltage: Positive-bias value  |                         | 0 max  | volts  |

Negative-bias value .....

watts


2 max


Plate Dissipation

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

#### **MAXIMUM CIRCUIT VALUES:**

| Grid-No.3-Circuit Resistance Grid-No.1-Circuit Resistance: | 0.68 max | megohm           |
|--|----------|------------------|
| For fixed-bias operation For cathode-bias operation        |          | megohm<br>megohm |






#### MEDIUM-MU TRIODE SHARP-CUTOFF PENTODE

## 6KD8

Miniature type used as combined vhf <sup>2p</sup>(oscillator and mixer tube in television receivers. Outline 6B, **Outlines** section. Tube requires miniature ninecontact socket and may be mounted in any position. Heater volts (ac/dc),




6.3; amperes, 0.4; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, Amplifier                                     |             |            |            |
|--|-------------|------------|------------|
| MAXIMUM RATINGS (Design-Maximum Values):               | Triode Unit | Pentode Un | it         |
| Plate Voltage  | 330 max     | 330 max    | volts      |
| Grid-No.2 (Screen-Grid) Supply Voltage                 |             | 330 max    | volts      |
| Grid-No.2 Voltage                                      | _           | See curv   | e page 75  |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value. | 0 max       | 0 max      | volts      |
| Plate Dissipation                                      | 2.5 max     | 3 max      | watts      |
| For grid-No.2 voltages up to 165 volts                 |             | 0.55 max   | wait       |
| For grid-No.2 voltages between 165 and 330 volts       |             | See curv   | e page 75  |
| CHARACTERISTICS:                                       |             |            |            |
| Plate Voltage  | 125         | 125        | volts      |
| Grid-No.2 Voltage                                      |             | 110        | volts      |
| Grid-No.1 Voltage                                      | -1          | 1          | volt       |
| Amplification Factor                                   | 40          |            |            |
| Plate Resistance (Approx.)                             | _           | 0.2        | megohm     |
| Transconductance                                       | 7500        | 5000       | $\mu$ mhos |
| Plate Current  | 13.5        | 9.5        | ma         |
| Grid-No.2 Current                                      |             | 3.5        | ma         |
| Grid-No.1 Voltage (Approx.) for plate current of 20 µa | 9           | 8          | volts      |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:  |             |            |            |
| For fixed-bias operation                               | 0.5 max     | 0.5 max    | megohm     |
| For cathode-bias operation                             | 1 max       | 1 max      | megohm     |

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6KE8
Related type:

Miniature type with frame-grid pentode unit used as combined oscillator-mixer tube in television receivers using an intermediate frequency in the order of 40 megacycles. Outline 6B, Outlines section. Tube requires min-



iature nine-contact socket and may be mounted in any position. Type 5KE8 is identical with type 6KE8 except for the heater ratings, as shown below.

|  | 5KE8                        | 6KE8    |         |
|--|-----------------------------|---------|---------|
| Heater Voltage (ac/dc)                             | 5.6                         | 6.3     | volts   |
| Heater Current                                     | 0.45                        | 0.4     | ampere  |
| Heater Warm-up Time (Average)                      | 11                          | _       | seconds |
| Peak Heater-Cathode Voltage:                       |                             |         |         |
| Heater negative with respect to cathode            | 200 max                     | 200 max | volts   |
| Heater positive with respect to cathode            | 200 • max                   | 200 max | volts   |
| Direct Interelectrode Capacitances:                |                             |         |         |
| Triode Unit:                                       |                             |         |         |
| Grid to Plate                                      |                             | 1.3     | pf      |
| Grid to Cathode, Heater, Pentode Cathode, Pentode  | Grid                        |         | •       |
| No.3, and Internal Shield                          |                             | 2.4     | pf      |
| Plate to Cathode, Heater, Pentode Cathode, Pentode |                             |         | •       |
| and Internal Shield                                | · · · · · · · · · · · · · · | 2       | рf      |
|  |                             |         | •       |


volts volts


| Pentode Unit: Grid No.1 to Plate   | 0.3.                | 0.015 max          | pf                 |
|--|---------------------|--------------------|--------------------|
| and Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, an   |                     | 5                  | pf                 |
| Shield   |                     | 3.4<br>5.5         | pf<br>pf           |
| metale to mode canode and remode camode  |                     | J.J -              | P.                 |
| <ul> <li>The dc component must not exceed 100 watts.</li> <li>With external shield connected to cathode of unit unde</li> <li>With external shield connected to ground.</li> </ul> | r test, except a    | s noted.           |                    |
| Class A, Amplific  | Pr                  |                    |                    |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage   | Triode Unit 280 max | 280 max<br>280 max | volts<br>volts     |
| Grid-No.2 Voltage  | 0 max               | See curve<br>0 max | c page /5<br>volts |
| Cathode Current  | 20 max              | 20 max             | ma                 |
| Plate Dissipation Grid-No.2 Input:   | 2 max               | 2 max              | watts              |
| For grid-No.2 voltages up to 140 volts   | _                   | 0.5 max            | watt               |
| For grid-No.2 voltages between 140 and 280 volts   | -                   | See curve          |                    |
| CHARACTERISTICS:   | Triode Unit         | Pentode Unit       |                    |
| Plate Supply Voltage   | 125                 | 125                | volts              |
| Grid-No.2 Supply Voltage   | _                   | 125                | volts              |
| Grid-No.1 Supply Voltage   | 0                   | 0                  | volts              |
| Cathode-Bias Resistor  | 68                  | 33                 | ohm:               |
| Amplification Factor   | 40                  | 405000             |                    |
| Plate Resistance (Approx.)  Transconductance   | 5000                | 125000             | ohms               |
| Plate Current  | 8000<br>13          | 12000<br>10        | μmhos              |
| Grid-No.2 Current  | 13                  | 2.8                | ma                 |
| Grid-No.1 Voltage (Approx.):   |                     | 2.0                | ma                 |
| Ear plate execut 100   |                     |                    |                    |

MAXIMUM CIRCUIT VALUES:

For plate current 100  $\mu a$ For plate current of 50  $\mu a$ 

Grid-No.1-Circuit Resistance: For fixed-bias operation ..... 0.5 max 0.25 max megohm For cathode-bias operation ..... 1 max 0.5 max megohm






### DIODE— SHARP-CUTOFF PENTODE

6KL8
Related type:

Miniature type used in combined ifamplifier and AM-detector service in
AM and AM/FM broadcast receivers.
Pentode unit may also be used as an
rf- or if-amplifier or limiter tube; the
diode unit may be used for avc or



17VT 0


detection. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For curves of average plate characteristics for pentode unit, refer to type 6AU6A. Type 12KL8 is identical with type 6KL8 except for the heater ratings, as shown below.

AVT 0

|   | OVTO    | 14KL8      |         |
|---|---------|------------|---------|
| Heater Voltage (ac/dc)                              | 6.3     | 12.6       | volts   |
| Heater Current                                      | 0.3     | 0.15       | ampere  |
| Heater Warm-up Time (Average)                       |         | 17         | seconds |
| Peak Heater-Cathode Voltage:                        |         |            |         |
| Heater negative with respect to cathode             | 200 max | 200 max    | volts   |
| Heater positive with respect to cathode             | 200 max | 200 = max  | volts   |
| Direct Interelectrode Capacitances:                 |         |            |         |
| Pentode Unit:                                       |         |            |         |
| Grid No.1 to Plate                                  |         | 0.002 max  | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3  | 3       |            | •       |
| and Internal Shield                                 |         | 6          | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and |         | -          |         |
| Shield  |         | 5          | pf      |
| Pentode Grid No.1 to Diode Plate                    |         | 0.0015 max | pf      |
| Pentode Plate to Diode Plate                        |         | 0.09       | pf      |
|   |         |            | -       |

| Pentode Plate to Diode Plate  | 0.0015 max<br>0.09 | pi<br>pf |
|---|--------------------|----------|
| • The dc component must not exceed 100 volts.                               |                    |          |
| Pentode Unit as Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values): |                    |          |
| Plate Voltage   | 300 max            | volts    |
| Negative value  | -300 max           | volts    |
| Positive value  | 300 max            | volts    |
| Grid-No.2 (Screen-Grid) Supply Voltage                                      | 300 max            | volts    |
| Grid-No.2 Voltage   | See curve          | page 75  |

| Grid-No.1 (Control-Grid) Voltage:                           |         |           |
|---|---------|-----------|
| Positive-bias value   | 0 max   | volts     |
| Negative-bias value   | 50 max  | volts     |
| Grid-No.3 Input   |         | watt      |
| Grid-No.2 Input:  |         |           |
| For grid-No.2 voltages up to 150 volts                      | 0.6 max | watt      |
| For grid-No.2 voltages between 150 and 300 volts            |         | e page 75 |
| Plate Dissipation   |         | watts     |
| Bulb Temperature (At hottest point)                         |         | °C        |
| Build Temperature (At nottest point)                        |         | ŭ         |
| CHARACTERISTICS:  |         |           |
| Plate Voltage   | 100     | volts     |
| Grid No.3   |         |           |
| Internal Shield   |         |           |
| Grid-No.2 Voltage   |         | volts     |
| Grid-No.1 Supply Voltage                                    |         | voits     |
| Grid-No.1 Resistor (Bypassed)                               |         | megohms   |
| Plate Resistance (Approx.)                                  |         | megohm    |
| Transconductance  |         | umhos     |
| ***************************************                     |         |           |
| Plate Current   |         | ma        |
| Grid-No.2 Current   |         | ma        |
| Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu a$ | 4.2     | volts     |
|   |         |           |
| Diode Unit  |         |           |
| -1500 - 1110  |         |           |
| MAXIMUM RATINGS (Design-Maximum Values):                    |         |           |
| Plate Current   | 1 max   | ma        |
|   |         |           |
| CHARACTERISTICS, Instantaneous Value:                       |         |           |
| Tube Voltage Drop for plate current of 2 ma                 | 10      | volts     |
|   |         |           |



### DIODE— THREE-PLATE TETRODE

GITR Miniature type used in frequencydivider and complex-wave generator circuits of electronic musical instru-Para ments. In such circuits the tetrode unit can provide three independent output-signal voltages; the diode unit

6KM8


can be used as a key in a vibrato circuit. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc) Heater Current   | 6.3<br>0.3           | volts<br>ampere |
|---|----------------------|-----------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances: | 200 max<br>200*max   | volts<br>volts  |
| Tetrode Unit:   |                      |                 |
| Grid No.1 to Plate No.1A Grid No.1 to Plate No.1B   | 0.02 max<br>0.02 max | pf<br>pf        |
| Grid No.1 to Plate No.2   | 0.02 max             | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, and Internal Shield  | 5.5                  | pf              |
| Plate No.1A to Cathode, Heater, Grid No.2, and Internal Shield  | 1.2                  | pf              |
| Plate No.1B to Cathode, Heater, Grid No.2, and Internal Shield  | 1.3                  | pf              |
| Plate No.2 to Cathode, Heater, Grid No.2, and Internal Shield   | 1.8                  | pf              |
| Tetrode Grid No.1 to Diode Plate  | 0.024 max            | pf              |
| Tetrode Plate No.1A to Diode Plate  | 0.18                 | pf              |
| Tetrode Plate No.1B to Diode Plate  | 0.024                | pf              |
| Tetrode Plate No.2 to Diode Plate   | 0.013                | pf              |

The dc component must not exceed 100 volts.


#### Tetrode Unit as Class A. Amplifier Plates No. 1A, 1B, and 2 connected together


| CHARACTERISTICS:   |         |                                       |           |            |
|--|---------|---------------------------------------|-----------|------------|
| Plate Voltage  |         |                                       | 100       | volts      |
| Grid-No.2 Voltage  |         |                                       | 100       | volts      |
| Grid-No.1 Supply Voltage   |         |                                       | 0         | volts      |
| Grid-No.1 Resistor (Bypassed)  |         |                                       | 2.2       | megohms    |
| Plate Resistance (Approx.)   |         |                                       | 30000     | ohms       |
| Transconductance   |         |                                       | 3400      | μmhos      |
| Plate Current  |         |                                       | 4.2       | ma         |
| Grid-No.2 Current  |         |                                       | 1.7       | ma         |
| Grid-No.1 Voltage (Approx.) for plate current o  |         |                                       | -4        | volts      |
| Gild-ive.i voltage (rippiess) for plate entent e   | . 20 ,2 |                                       | •         |            |
| Triode Connection—Plates No.1A, : CHARACTERISTICS:   | 1B, and | 2 connected to 1                      | grid No.2 |            |
| Plate Voltage  |         |                                       | 100       | volts      |
|  |         |                                       | 100       | volts      |
| Grid-No.1 Supply Voltage   |         |                                       | 2.2       | megohms    |
| Grid-No.1 Resistor (Bypassed)  |         |                                       |           |            |
| Transconductance   |         |                                       | 4500      | μmhos      |
| Amplification Factor   |         |                                       | 45        |            |
| Plate Current  |         | · · · · · · · · · · · · · · · · · · · | 5.5       | ma         |
| Separate plate operation; plat   |         | under test group                      | dad       |            |
| Plate  | 1A      | 1B                                    | 2         |            |
| Plate Voltage  | 100     | 100                                   | 100       | volts      |
|  | 100     | 100                                   | 100       | volts      |
| Grid-No.2 Voltage  | 100     | 0                                     | 100       | volts      |
| Grid-No.1 Supply Voltage   | 2.2     | 2.2                                   | 2.2       | megohms    |
| Grid-No.1 Resistor (Bypassed)  | 2000    | 2000                                  | 1800      | umhos      |
| Transconductance   | 0.1     | 0.1                                   | 0.12      | megohm     |
| Plate Resistance (Approx.)   |         |                                       |           |            |
| Plate Current  | 2.3     | 2.3                                   | 2.1       | ma         |
| Grid-No.2 Current  | 3.8     | 3.8                                   | 3.3       | ma         |
| Tetrode Unit as Frequency Divid  | er and  | Complex-Way                           | e General | or         |
| MAXIMUM RATINGS (Design-Maximum Val  |         | oumplox man                           |           |            |
|  |         |                                       | 330 ma    | x volts    |
| Plate Voltage (Each plate)   |         |                                       | 330 ma    |            |
| Grid-No.2 (Screen-Grid) Supply Voltage   |         |                                       |           |            |
| Grid-No.2 Voltage  |         |                                       | See cur   | ve page 75 |
| Grid-No.1 (Control-Grid) Voltage:  |         |                                       | _         |            |
| Positive-bias value  |         |                                       | 0 ma      |            |
| Negative-bias value  |         |                                       | —50 ma    | x volts    |
| Grid-No.2 Input:   |         |                                       |           |            |
| For grid-No.2 voltages up to 165 volts   |         |                                       | 0.65 ma   |            |
| For grid-No.2 voltages between 165 and 330   | volts   |                                       | See cur   | ve page 75 |
| THE A TOUR PORT OF A TOUR ASSESSMENT OF A TOUR ASSE |         |                                       |           |            |



#### MAXIMUM CIRCUIT VALUES:

| Grid-No.1-Circuit Resistance: For grid-No.1-resistor-bias operation                | 2.2 max megohms |       |
|--|-----------------|-------|
| Diode Unit   |                 |       |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Current                             | 1 max           | ma    |
| CHARACTERISTICS, Instantaneous Values: Tube Voltage Drop for plate current of 2 ma | 10              | volts |





### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in a variety of applications in television receivers. The pentode unit is used as an if-amplifier tube, and the triode unit as a sync-separator or voltage-amplifier tube. Outline 6B, Outlines section.

**6KT8** 

Tube requires miniature nine-contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.6; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A. Amplifier Pentode Unit MAXIMUM RATINGS (Design-Maximum Values): Triode Unit 330 max volts 330 max Plate Voltage .... Grid-No.2 (Screen-Grid) Supply Voltage ..... 330 max volts See curve page 75 Grid-No.2 Voltage 0 max volts Grid-No.1 (Control-Grid) Voltage, Positive-bias value 0 max 2.5 max watts 1 max Plate Dissipation 0.55 max watt For grid-No.2 voltages up to 165 volts ..... See curve page 75 For grid-No.2 voltages between 165 and 330 volts **CHARACTERISTICS:** volts Plate Voltage ...... volts volts


Amplification Factor .....

| Plate Resistance (Approx.)                                  | 31300   | 130000    | Oillis     |
|---|---------|-----------|------------|
| Transconductance  | 3200    | 10000     | $\mu$ mhos |
| Plate Current   | 1.8     | 12        | ma         |
| Grid-No.2 Current   |         | 4.5       | ma         |
| Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu a$ | -3.5    | <b>—7</b> | volts      |
| MAXIMUM CIRCUIT VALUES:                                     |         |           |            |
| Grid-No.1-Circuit Resistance:                               |         |           |            |
| For fixed-bias operation                                    | 0.5 max |           | x megohm   |
| For cathode-bias operation                                  | 1 max   | 1 ma      | x megohm   |

#### HIGH-MU TRIODE-SHARP-CUTOFF PENTODE

Related type:

Miniature type with frame-grid pentode unit used in black-and-white television receivers. The triode unit is used in general-purpose voltage-amplifier, sync-separator, and sound-if-



ohms

ohms

μmhos

amplifier applications. The pentode unit is used as a video output tube. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For curves of average plate characteristics for triode unit, refer to type 6AW8A. Type 11KV8 is identical with type 6KV8 except for the heater ratings, as shown below.

70

21000

23000

17500

|  | 6KV8    | 11KV8     |         |
|--|---------|-----------|---------|
| Heater Voltage (ac/dc)                               | 6.3     | 10.9      | volts   |
| Heater Current                                       | 0.775   | 0.45      | ampere  |
| Heater Warm-up Time (Average)                        | _       | 11        | seconds |
| Peak Heater-Cathode Voltage:                         |         |           |         |
| Heater negative with respect to cathode              | 200 max | 200 max   | volts   |
| Heater positive with respect to cathode              | 200•max | 200∗max   | volts   |
| Direct Interelectrode Capacitances (Approx.):        |         |           |         |
| Triode Unit:   |         |           |         |
| Grid to Plate  |         | 3.7       | pf      |
| Grid to Cathode, Heater, Pentode Cathode, Pentode C  |         |           |         |
| and Internal Shield                                  |         | 2.5       | pf      |
| Plate to Cathode, Heater, Pentode Cathode, Pentode C |         |           | _       |
| and Internal Shield                                  |         | 2.4       | pf      |
| Triode Grid to Pentode Plate                         |         | 0.015 max |         |
| Pentode Unit:  |         |           | _       |
| Grid No.1 to Plate                                   |         | 0.09 max  | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.    |         |           | _       |
| Internal Shield                                      |         | 13        | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, ar   |         |           |         |
| Internal Shield                                      |         | 4.8       | pf      |
| Pentode Plate to Triode Plate                        |         | 0.17 max  | pf      |

Cathode-Bias Resistor .....

Amplification Factor Plate Resistance (Approx.)


Transconductance ....


| • The dc component must not exceed 100 volts.  |                        |            |                   |                  |
|--|------------------------|------------|-------------------|------------------|
| Class A, Amplifier   |                        |            |                   |                  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage   | Triode Unit<br>300 max | 30         | tode Un<br>00 max | volts            |
| Grid-No.2 (Screen-Grid) Supply Voltage   | _                      |            |                   | volts<br>page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation                                  | 0 max<br>1 max         |            | 0 max<br>5 max    | volts<br>watts   |
| Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts | _                      | S.         | 1 max             | watt<br>page 75  |
| CHARACTERISTICS:   |                        | 36         | e cuive           | page 73          |
| Plate Supply Voltage   | 200                    | 125<br>125 | 200<br>125        | voits<br>voits   |
| Grid-No.1 Supply Voltage   | <b>—</b> 2             | 0          | 0                 | volts            |

Pentode Unit

| Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 μa | <u>-4</u><br>4.5 | 3.1<br>-3.8 | 3.1<br>-3.8 | ma<br>volts |
|---|------------------|-------------|-------------|-------------|
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation          | 0.5 max          |             | 0.1 max     | megohm      |
| For cathode-bias operation  | 1 max            |             | 0.25 max    |             |

Triode Unit





### HIGH-MU TRIODE— BEAM POWER TUBE

Novar types used in combined vertical-deflection-oscillator and vertical-deflection-amplifier applications in black-and-white television receivers having low-voltage "B" supplies. Outlines 11C and 30A, respectively, Out-

# 6KY8 6KY8A

Related types: 15KY8, 15KY8A

lines section. Tubes require novar nine-contact socket and may be mounted in any position. Types 15KY8 and 15KY8A are identical with types 6KY8 and 6KY8A, except for heater ratings, as shown below.


|   | 6KY8<br>6KY8A | 15KY8<br>15KY8A |         |
|---|---------------|-----------------|---------|
| Heater Voltage (ac/dc)                              | 6.3           | 15              | volts   |
| Heater Current                                      | 1.1           | 0.45            | amperes |
| Heater Warm-up Time (Average)                       | _             | 11              | seconds |
| Peak Heater-Cathode Voltage:                        |               |                 |         |
| Heater negative with respect to cathode             | 200 max       | 200 max         | volts   |
| Heater positive with respect to cathode             | 200•max       | 200•max         | volts   |
| Direct Interelectrode Capacitances (Approx.):       |               |                 |         |
| Triode Unit:  |               |                 | _       |
| Grid to Plate                                       |               | 0.44            | pf      |
| Grid to Cathode and Heater                          |               | 15              | pf      |
| Plate to Cathode and Heater                         |               | 7               | pf      |
| Pentode Unit:                                       |               |                 | _       |
| Grid No.1 to Plate                                  |               | 0.048           | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid I |               | 2.6             | pf      |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3. |               | 0.28            | pf      |
|   |               |                 |         |


<sup>•</sup> The dc component must not exceed 100 volts.

Class A. Amplifier

| Class A <sub>1</sub>                          | Ampiniei    |      |         |      |            |
|---|-------------|------|---------|------|------------|
| CHARACTERISTICS:                              | Triode Unit | Bean | n Power | Unit |            |
| Plate Voltage                                 | 250         | 50   | 135     | 120  | volts      |
| Grid-No.2 (Screen-Grid) Voltage               | _           | 120  | 120     | *    | volts      |
| Grid-No.1 (Control-Grid) Voltage              | 3           | 0    | 10      | 10   | volts      |
| Amplification Factor                          | 64          | _    | _       | 7    |            |
| Plate Resistance (Approx.)                    | 40000       |      | 18000   | _    | ohms       |
| Transconductance                              | 1600        | _    | 8400    | _    | $\mu$ mhos |
| Plate Current                                 | 1.4         | 170• | 39      | _    | ma         |
| Grid-No.2 Current                             |             | 20●  | 3       | _    | ma         |
| Grid-No.1 Voltage (Approx.) for plate current |             |      |         |      |            |
| of 1 ma                                       | _           | _    | -24     | _    | volts      |

- \* Triode connection, grid No.2 connected to plate at socket.
- This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.






# Vertical-Deflection Oscillator and Amplifier

| For operation in a 323-line, 30-         | mame system |            |       |
|--|-------------|------------|-------|
| •  | Triode      | Beam Power |       |
|  | Unit        | Unit       |       |
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator  | Amplifier  |       |
| DC Plate Voltage                         | 330 max     | 300 max    | volts |
| Peak Positive-Pulse Plate Voltage#       |             |            |       |
| (Absolute Maximum)                       |             | 2200†max   | volts |
| DC Grid-No.2 Voltage                     |             | 150 max    | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -400 max    | 250 max    | volts |
| Peak Cathode Current                     | 77 max      | 200 max    | ma    |
| Average Cathode Current                  | 22 max      | 60 max     | ma    |
| Plate Dissipation                        | 1.5 max     | 12 max     | watts |
| Grid-No.2 Input                          | ***         | 1.9 max    | watts |
| MANUFACTOR CINCELL MARRIES.              |             |            |       |

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined oscillator and mixer in vhf television receivers. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Heater voltage (ac/dc), 6.3;

6KZ8

amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A. Amplifier MAXIMUM RATINGS (Design-Maximum Values): Triode Unit Pentode Unit 330 max 330 max volts Plate Voltage ..... Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage 330 max volte See curve page 75 Grid-No.1 (Control-Grid) Voltage, Positive-bias value 0 max 0 max volts 2.5 max Plate Dissipation ..... 2.5 max watts Grid-No.2 Input: 0.55 max watt For grid-No.2 voltages up to 165 volts ... For grid-No.2 voltages between 165 and 330 volts See curve page 75 CHARACTERISTICS: 125 125 volts Grid-No.2 Voltage ..... 125 volts Grid-No.1 Voltage ..... volt Amplification Factor ..... 46 200000 ohms Plate Resistance (Approx.) 5400 7500 8500 μmhos Transconductance ..... 12 13.5 Plate Current ...... ma Grid-No.2 Current ..... ma Grid-No.1 Voltage (Approx.) for plate current of 10 μa volts MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation 0.25 max 0.25 max megohm For cathode-bias operation ..... 0.5 max 0.5 max megohm

#### MEDIUM-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

6L6G

6L5G

# 6L6GB

#### BEAM POWER TUBE

Renewal type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**

# **6L6** 6L6GC

Metal type 6L6 and glass octal type 6L6GC are used in the output stage of audio amplifying equipment, especially units designed to have ample reserve of power-delivering ability. These types provide high power output, sen-



sitivity, and high efficiency. Power output at all levels has low third- and higherorder harmonics. Type 6L6, Outline 4, type 6L6GC, Outline 19D; Outlines section. Tubes require an octal socket and may be mounted in any position. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Type 6L6GC can be used in place of type 6L6 and may be supplied with pin 1 omitted.

| Heater Voltage (ac/dc) Heater Current                                 |         | 6.3<br>0.9   | volts<br>ampere |
|---|---------|--------------|-----------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode | 180 max | 200 max      | volts           |
| Heater positive with respect to cathode                               | 180 max | 200 max      | volts           |
| Direct Interelectrode Capacitances (Approx.):                         | 6L6*    | 6L6GC<br>0.6 |                 |
| Grid No.1 to Plate  | 0.4     | 0.6          | pf              |
| Grid No.3   | 10      | 10           | pf              |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3                    | 12      | 6.5          | pf              |

<sup>\*</sup> With pin 1 connected to pin 8.

Class A, Amplifier

| ·                                | -     | 6L6           | 6L6GC       |            |
|----------------------------------|-------|---------------|-------------|------------|
|                                  |       | Design-Center | Design-Maxi | mum        |
| MAXIMUM RATINGS:                 |       | Values        | Values      |            |
| Plate Voltage                    |       | 360 max       | 500 max     | volts      |
| Grid-No.2 (Screen-Grid) Voltage  |       | 270 max       | 450≜max     | volts      |
| Plate Dissipation                |       | 19 max        | 30 max      | watts      |
| Grid-No.2 Input                  |       | 2.5 max       | 5 max       | watts      |
| TYPICAL OPERATION:               |       |               |             |            |
| Plate Voltage                    | 250   | 300           | 350         | volts      |
| Grid-No.2 Voltage                | 250   | 200           | 250         | volts      |
| Grid-No.1 (Control-Grid) Voltage | -14   | 12.5          | -18         | volts      |
| Peak AF Grid-No.1 Voltage        | 14    | 12.5          | 18          | volts      |
| Zero-Signal Plate Current        | 72    | 48            | 54          | ma         |
| Maximum-Signal Plate Current     | 79    | 55            | 66          | ma         |
| Zero-Signal Grid-No.2 Current    | 5     | 2.5           | 2.5         | ma         |
| Maximum-Signal Grid-No.2 Current | 7.3   | 4.7           | 7           | ma         |
| Plate Resistance (Approx.)       | 22500 | 35000         | 33000       | ohms       |
| Transconductance                 | 6000  | 5300          | 5200        | $\mu$ mhos |
| Load Resistance                  | 2500  | 4500          | 4200        | ohms       |
| Total Harmonic Distortion        | 10    | 11            | 15          | per cent   |
| Maximum-Signal Power Output      | 6.5   | 6.5           | 10.8        | watts      |

In push-pull circuits where grid No.2 of each tube is connected to a tap on the plate winding of the output transformer, this maximum rating is 500 volts.

Class A. Amplifier (Triode Connection)†

| 1 1                       | 6L6           | 6L6GC          |
|---------------------------|---------------|----------------|
|                           |               | Design-        |
| MAXIMUM RATINGS:          | Center Values | Maximum Values |
| Plate Voltage             | 275 max       | 450 max volts  |
| Plate Dissipation (Total) | 19 max        | 30 max watts   |

| TYPICAL OPERATION:              |      |          |
|---------------------------------|------|----------|
| Plate Voltage                   | 250  | volts    |
| Grid-No.1 Voltage               | -20  | volts    |
| Peak AF Grid-No.1 Voltage       | 20   | volts    |
| Zero-Signal Plate Current       | 40   | ma       |
| Maximum-Signal Plate Current    | 44   | ma       |
| Plate Resistance (Approx.)      | 1700 | ohms     |
| Amplification Factor            | 8    |          |
| Transconductance                | 4700 | μmhos    |
| Load Resistance                 | 5000 | ohms     |
| Total Harmonic Distortion       | 5    | per cent |
| Maximum-Signal Power Output     | 1.4  | watts    |
| † Grid No.2 connected to plate. |      |          |

### Push-Pull Class A, Amplifier

#### MAXIMUM RATINGS:

| (Same as for Class A <sub>1</sub> Amplifier)  |      |              |          |
|---|------|--------------|----------|
| TYPICAL OPERATION (Values are for two tubes): |      |              |          |
| Plate Voltage                                 | 250  | 270          | volts    |
| Grid-No.2 Voltage                             | 250  | 270          | volts    |
| Grid-No.1 Voltage                             | -16  | <b>—17.5</b> | volts    |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage        | 32   | 35           | ' volts  |
| Zero-Signal Plate Current                     | 120  | 134          | ma       |
| Maximum-Signal Plate Current                  | 140  | 155          | ma       |
| Zero-Signal Grid-No.2 Current                 | 10   | 11           | ma       |
| Maximum-Signal Grid-No.2 Current              | 16   | 17           | ma       |
| Effective Load Resistance (Plate-to-plate)    | 5000 | 5000         | ohms     |
| Total Harmonic Distortion                     | 2    | 2            | per cent |
| Maximum-Signal Power Output                   | 14.5 | 17.5         | watts    |

#### Push-Pull Class AB, Amplifier


#### **MAXIMUM RATINGS:**

(Same as for Class At Amplifier)

| TYPICAL OPERATION                          |       |       |            |       |
|--|-------|-------|------------|-------|
| (Values are for two tubes):                |       | 6L6   | 6L6GC      |       |
| Plate Voltage                              | 360   | 360   | 450        | volts |
| Grid-No.2 Voltage                          | 270   | 270   | 400        | volts |
| Grid-No.1 Voltage                          | -22.5 | -22.5 | <b>—37</b> | volts |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage     | 45    | 45    | 70         | volts |
| Zero-Signal Plate Current                  | 88    | 88    | 116        | ma    |
| Maximum-Signal Plate Current               | 132   | 140   | 210        | ma    |
| Zero-Signal Grid-No.2 Current              | 5     | 5     | 5.6        | ma    |
| Maximum-Signal Grid-No.2 Current           | 15    | 11    | 22         | ma    |
| Effective Load Resistance (Plate-to-plate) | 6600  | 3800  | 5600       | ohms  |

AVERAGE PLATE CHARACTERISTICS

92CM-10327T



| Total Harmonic Distortion   | 2<br>18  | 1.8<br>55  | per cent<br>watts                                    |
|---|--|--|--|
| Push-Pull Class AB Ar  MAXIMUM RATINGS: (Same as for Class A1 Amplifier)  |  | <b>J</b>   | Watts  |
| TYPICAL OPERATION (Values are for two tubes): Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate) Total Harmonic Distortion Maximum-Signal Power Output | 360<br>225<br>-18<br>52<br>78<br>142<br>3.5<br>11<br>6000<br>2 | 360<br>270<br>-22.5<br>72<br>88<br>205<br>5<br>16<br>3800<br>2 | volts volts volts volts ma ma ma ohms per cent watts |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation   | •                        |  | x megohm<br>x megohm                                 |

6L7

#### PENTAGRID MIXER

Renewal type; see chart at end of section for tabulated data.

**6L7G** 


#### PENTAGRID MIXER

Discontinued type; see chart at end of section for tabulated data.

### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

6LC8
Related type:
8LC8

Miniature type used in color and black-and-white television receivers. Pentode unit is used in noise-immune gated-agc-amplifier circuits, and the triode unit in sync-separator circuits. Outline 6E, Outlines section. Tube



requires miniature nine-contact socket and may be mounted in any position. Type 8LC8 is identical with type 6LC8 except for heater ratings, as shown below. For curves of average plate characteristics, refer to type 6KA8.

|   | PTC8         | 8LC8     |         |
|---|--------------|----------|---------|
| Heater Voltage (ac/dc)                                  | 6.3          | 8.4      | volts   |
| Heater Current  | 0.6          | 0.45     | ampere  |
| Heater Warm-up Time (Average)                           | 11           | 11       | seconds |
| Peak Heater-Cathode Voltage:                            |              |          |         |
| Heater negative with respect to cathode                 | 200 max      | 200 max  | volts   |
| Heater positive with respect to cathode                 | 200 max      | 200 max  | volts   |
| Direct Interelectrode Capacitances:                     |              |          |         |
| Triode Unit:  |              |          |         |
| Grid to Plate   |              | 2.2      | pf      |
| Grid to Cathode, Heater, Pentode Grid No.3, and Inte    |              | 2.8      | pf      |
| Plate to Cathode, Heater, Pentode Grid No.3, and Inte   | ernal Shield | 2.2      | pf      |
| Pentode Unit:   |              |          | •       |
| Grid No.1 to Plate                                      |              | 0.10 max | pf      |
| Grid No.1 to Cathode, Heater, Grid No.3, Triode Ca      |              |          | •       |
| Internal Shield   |              | 10       | pf      |
| Grid No.3, Triode Cathode, and Internal Shield to Plate |              | 3.4      | pf      |
| Grid No.1 to Grid No.3, Triode Cathode, and Internal    | Shield       | 0.36     | pf      |
| Grid No.3, Triode Cathode, and Internal Shield to Plat  |              |          | •       |
| Heater, Grid No.1, and Grid No.2                        |              | 12.5     | pf      |
|   |              |          | •       |
| The dc component must not exceed 100 volts              |              |          |         |

The dc component must not exceed 100 volts.

| Class A, Amplifie   | er     |             |           |
|---|--------|-------------|-----------|
| MAXIMUM RATINGS (Design-Maximum Values):                        |        | Triode Un   | uit       |
| Plate Voltage   |        | 300 max     | volts     |
| Grid Voltage:   |        |             |           |
| Positive-bias value   |        | 0 max       | volts     |
| Negative-bias value   |        | -50 max     | volts     |
| Plate Dissipation   |        | 1.1 max     | Watts     |
|   |        |             |           |
|   | Triode | Pentode     |           |
| CHARACTERISTICS:  | Unit   | Unit        | _         |
| Plate Supply Voltage  | 200    | 150         | volts     |
| Grid-No.2 Supply Voltage  |        | 100         | volts     |
| Grid-No.1 Voltage   | -2     | <del></del> | volts     |
| Cathode-Bias Resistor   | -      | 180         | ohms      |
| Amplification Factor  | 70     |             |           |
| Plate Resistance (Approx.)                                      | 17500  | 100000      | ohms      |
| Transconductance, Grid No.1 to Plate                            | 4000   | 4400        | μmhos     |
| Transconductance, Grid No.3 to Plate                            | -      | 600         | μmhos     |
| Plate Current   | 4      | 4           | ma        |
| Grid-No.2 Current   |        | 2.8         | ma        |
| Grid-No.1 Voltage (Approx.):                                    |        |             |           |
| For plate current of 10 µa                                      | -5     |             | volts     |
| For plate current of 20 µa                                      | -      | -4          | volts     |
| Grid-No.3 Voltage (Approx.) for plate current of 20 µa          | _ `    | <i>—</i> 7∗ | volts     |
|   |        | -           |           |
| MAXIMUM CIRCUIT VALUES:   |        |             |           |
| Grid-Circuit Resistance:  |        | Triode Uni  | t         |
| For fixed-bias operation  |        | 0.25 max    | megohm    |
| For cathode-bias operation                                      |        | 1 max       | megohm    |
|   |        |             |           |
| * With no external connection to triode plate and triode        | grid.  |             |           |
| Gated AGC Amplifier and No<br>For operation in a 525-line, 30-f |        |             |           |
| MAXIMUM RATINGS (Design-Maximum Values):                        |        | Pentode Un  | it        |
| DC Plate Voltage  |        | 300 max     | volts     |
| Peak Positive-Pulse Plate Voltage                               |        | 600 max     | volts     |
| Grid-No.3 (Control-Grid) Voltage:                               |        | ooo max     | VOILS     |
| Positive-bias value   |        | A           | volts     |
|   |        | 0 max       |           |
| Negative-bias value   |        | -100 max    | volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                          |        | 300 max     | volts     |
| Grid-No.2 Voltage   |        | See curv    | e page 75 |
| Grid-No.1 (Control-Grid) Voltage:                               |        | _           |           |
| Positive-bias value   |        | 0 max       | volts     |
| Negative-bias value   |        | —50 max     | volts     |
| Plate Dissipation   |        | 2 max       | watts     |
| Grid-No.2 Input:  |        |             |           |
| For grid-No.2 voltages up to 150 volts                          |        | 1.1 max     | watts     |
| For grid-No.2 voltages between 150 and 300 volts                |        | See curv    | e page 75 |
| MAXIMUM CIRCUIT VALUES:   |        |             |           |

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.


#### HIGH-MU TRIODE-SHARP-CUTOFF PENTODE

6LF8

Grid-No.1-Circuit Resistance: For fixed-bias operation . . .

For cathode-bias operation ......

Miniature type used in video-amplifier stages of color-television receivers and in other applications where operation of a triode in the positive-grid region is desirable. Outline 6E, Outlines section. Tube requires miniature ninecontact socket and may be mounted in any position.



0.5 max megohm


1 max megohm

| Heater Voltage (ac/dc)   | 6.3        | volts   |
|--|------------|---------|
| Heater Current   | 0.6        | ampere  |
| Heater Warm-up Time (Average)                                  | 11         | seconds |
| Peak Heater-Cathode Voltage:                                   |            |         |
| Heater negative with respect to cathode                        | 200 max    | volts   |
| Heater positive with respect to cathode                        | 200 • max  | volts   |
| Direct Interelectrode Capacitances:                            |            |         |
| Triode Unit:   |            |         |
| Grid to Plate  | 2.2        | pf      |
| Grid to Cathode, Heater, Pentode Cathode, Pentode Grid No.3,   |            | •       |
| and Internal Shield  | 3.2        | pf      |
| Plate to Cathode, Heater, Pentode Cathode, Pentode Grid. No.3, |            | -       |
| and Internal Shield  | 1.8        | pf      |
| Pentode Unit:  | 0          | ,       |
| Grid No.1 to Plate   | 0.06 max   | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and        | O.OO IIIAA | γ.      |
|  | 10         | pf      |
| Internal Shield  | 10         | pı      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and            | 2.6        | e       |
| Internal Shield  | 3.6        | pf      |
| Pentode Grid No.1 to Triode Plate                              | 0.008 max  | pf      |
| Pentode Plate to Triode Plate                                  | 0.15 max   | pf      |

<sup>•</sup>The dc component must not exceed 100 volts.


Class A Amplifier

| VIA33 A AIIIPIIIICI                              |       |         |      |          |         |
|--|-------|---------|------|----------|---------|
| MAXIMUM RATINGS (Design-Maximum Values):         | Trio  | le Unit | Pent | ode Unit | ;       |
| Plate Voltage                                    | 330   | max     | 33   | 0 max    | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage           | _     |         | 33   | 0 max    | volts   |
| Grid-No.2 Voltage                                |       |         | Se   | e curve  | page 75 |
| Grid-No.1 (Control-Grid) Voltage:                |       |         |      |          | • •     |
| Positive-bias value                              | 4     | max     |      | 0 max    | volts   |
| Negative-bias value                              | -55   | max     | -5   | 5 max    | volts   |
| Plate Dissipation                                | 1.1   | max     | 3.7  | 5 max    | watts   |
| Grid-No.2 Input:                                 |       |         |      |          |         |
| For grid-No.2 voltages up to 165 volts           |       |         | 1.   | 1 max    | watts   |
| For grid-No.2 voltages between 165 and 330 volts | _     |         | See  | curve    | page 75 |
| Grid-No.1 Current                                | 8     | max     |      | 0 max    | ma      |
| CHARACTERISTICS:                                 |       |         |      |          |         |
| Plate Voltage                                    | 200   | 40      | 75   | 100      | volts   |
| Grid-No.2 Voltage                                | _     |         | 150  | 150      | volts   |
| Grid-No.1 Voltage                                | -2    | 3       | 0    | -2.5     | volts   |
| Amplification Factor                             | 70    | 40      | _    | _        |         |
| Plate Resistance (Approx.)                       | 17500 | 10000   | -    | 200000   | ohms    |
| Transconductance                                 | 4000  | 4000    | _    | 11000    | μmhos   |
| Plate Current                                    | 4     | 11      | 50=  | 20       | ma      |



| Grid-No.2 Current Grid-No.1 Current Grid-No.1 Voltage (Approx.) for plate current of 20 μα | 0<br>-5 | 2.7 | 0    | 0<br>-8 | ma<br>volts |
|--|---------|-----|------|---------|-------------|
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation             | 0.5     | max | 0.25 | max 1   | negohm      |
| For cathode-bias operation   |         | max |      |         | negohm      |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.



### MEDIUM-MU TRIODE-SEMIREMOTE-CUTOFF PENTODE

Miniature type used in a wide variety KP,G3P of circuit applications in color and black-and-white television receivers. The pentode unit is used in burstamplifier circuits, and the triode unit as a general-purpose amplifier tube.

**6LM8** 


Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.


| Heater Voltage (ac/dc)  | 6.3<br>0.45        | volts<br>ampere |
|---|--------------------|-----------------|
| Peak Heater-Cathode Voltage:  | 200                | volts           |
| Heater negative with respect to cathode   | 200 max<br>200•max | volts           |
| Direct Interelectrode Capacitances:   | 200 211            |                 |
| Triode Unit:  |                    |                 |
| Grid to Plate   | 1.8                | pf              |
| Grid to Cathode, Heater, Pentode Cathode, Pentode Grid No.3,                      | 2.2                |                 |
| and Internal Shield   | 3.2                | pf              |
| Plate to Cathode, Heater, Pentode Cathode, Pentode Grid No.3, and Internal Shield | 1.9                | pf              |
| Pentode Unit:   |                    | -               |
| Grid No.1 to Plate  | 0.015 max          | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No. 3, and                          |                    |                 |
| Internal Shield   | 5.5                | pf              |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield               | 3.8                | pf              |
| Heater to Cathode (Each Unit)   | 3.2                | pf              |
| Activities Comments (Each Cine)   |                    | •               |

<sup>•</sup> The dc component must not exceed 100 volts.

Class A. Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):              | Triode Unit | Pentode Unit      |
|---|-------------|-------------------|
| Plate Voltage   | 330 max     | 350 max volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                | _           | 330 max volts     |
| Grid-No.2 Voltage                                     |             | See curve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max       | 0 max volts       |
| Plate Dissipation                                     | 2.5 max     | 2.5 max volts     |
| Grid-No.2 Input:                                      |             |                   |
| For grid-No.2 voltages up to 165 volts                | _           | 0.55 max watts    |
| For grid-No.2 voltages between 165 and 330 volts      | -           | See curve page 75 |





| CHARACTERISTICS:           |      |        |            |
|----------------------------|------|--------|------------|
| Plate Voltage              | 125  | 125    | volts      |
| Grid-No.2 Voltage          |      | 125    | volts      |
| Grid-No.1 Voltage          | —1   | 2      | volts      |
| Amplification Factor       | 46   | _      |            |
| Plate Resistance (Approx.) | 5400 | 150000 | ohms       |
| Transconductance           | 8500 | 6000   | $\mu$ mhos |

| 12 ma<br>4 ma<br>—14 volts        | 13.5<br>———————————————————————————————————— | Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 μα                     |
|-----------------------------------|--|--|
| 0.25 max megohm<br>0.5 max megohm | 0.5 max<br>1 max                             | MAXIMUM CIRCUIT VALUES:  Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation |
| 6N5                               | in chart at                                  | Refer to type 6AB5/6N5 in end of section.  |
| 6N6G                              | E<br>art at end                              | DIRECT-COUPLE POWER TRIODI Discontinued type; see cha of section for tabulated                             |
| 6N7<br>6N7GT                      | E at end of                                  | MEDIUM-MU TW POWER TRIODI Renewal types; see chart a section for tabulated of                              |
| 6P5GT                             | art at end                                   | MEDIUM-MU TRIC<br>Discontinued type; see cha<br>of section for tabulated                                   |
| 6P7G                              | ENTODE<br>art at end                         | LOW-MU TRIODE REMOTE-CUTOFF PE Discontinued type; see cha of section for tabulated                         |
| 6 <b>Q</b> 7                      | DE<br>at end of                              | TWIN DIODE—<br>HIGH-MU TRIOD<br>Renewal type; see chart a<br>section for tabulated of                      |
| 6Q7G<br>6Q7GT                     | DE<br>part at end                            | TWIN DIODE—<br>HIGH-MU TRIOD<br>Discontinued types; see cha<br>of section for tabulated                    |
| <b>(011</b>                       | ODE  | THREE-UNIT TRIC  |

Discontinued type; see chart at end of section for tabulated data.

6Q11

# 6R7

#### TWIN DIODE— MEDIUM-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

# 6R7G 6R7GT

### TWIN DIODE— MEDIUM-MU TRIODE

Discontinued types; see chart at end of section for tabulated data.

# **6**S4

### **MEDIUM-MU TRIODE**

Discontinued type; see chart at end of section for tabulated data.

### MEDIUM-MU TRIODE

6**S**4**A** 

Heater Voltage (ac/dc) .....

For cathode-bias operation ......

Miniature type having high perveance used as vertical deflection amplifier in television receivers. This type has a controlled heater warm-up time for use in television receivers employing series-connected heater strings. Out-



6.3

2.2 max megohms

volts

line 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| reater voicage (ac, ac,   | 0.5       | 10113   |
|---|-----------|---------|
| Heater Current  | 0.6       | ampere  |
| Heater Warm-up Time (Average)                                   | 11        | seconds |
| Peak Heater-Cathode Voltage:                                    |           |         |
| Heater negative with respect to cathode                         | 200 max   | volts   |
| Heater positive with respect to cathode                         | 200 max   | volts   |
| Direct Interelectrode Capacitances (Approx.):                   | 200-Illax | VOIIS   |
| Grid to Plate   | 2.4       | _e      |
|   |           | pf      |
| Grid to Cathode and Heater                                      | 4.2       | pf      |
| Plate to Cathode and Heater                                     | 0.6       | pf      |
| <ul> <li>The dc component must not exceed 100 volts.</li> </ul> |           |         |
| Class A, Amplifier  |           |         |
| CHARACTERISTICS:  |           |         |
| Plate Voltage   | 250       | volts   |
| Grid Voltage  | 8         | volts   |
| Amplification Factor  | 16.5      | ,0115   |
| Plate Resistance (Approx.)                                      | 3700      | ohms    |
| Transconductance  | 4500      | µmhos   |
| Plate Current   | 24        | ma ma   |
| Plate Current for grid voltage of -15 volts                     | 4         | ma      |
| Grid Voltage (Approx.) for plate current of 50 $\mu$ a          | -22       | volts   |
| Office voltage (Approx.) for plate current of 50 µa             | -22       | VOILS   |
| Vertical Deflection Amplifier                                   |           |         |
| For operation in a 525-line, 30-frame system                    |           |         |
| MAXIMUM RATINGS (Design-Maximum Values):                        |           |         |
| DC Plate Voltage  | 550 max   | volts   |
| Peak Positive-Pulse Plate Voltage†                              | 2200 max  | volts   |
| Peak Negative-Pulse Grid Voltage                                | -250 max  | volts   |
| Peak Cathode Current  | 105 max   | ma      |
| Average Cathode Current   | 30 max    | ma      |
| Plate Dissipation   | 8.5 max   | watts   |
| •   |           | = 110   |
| MAXIMUM CIRCUIT VALUE:  |           |         |
| Grid-Circuit Resistance:  |           |         |

† The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

REMOTE-CUTOFF PENTODE

Discontinued types; see chart at end of section for tabulated data.

6\$7 6\$7G

### TRIPLE-DIODE— HIGH-MU TRIODE

Renewal type; see chart at end of of section for tabulated data.

6S8GT



## PENTAGRID CONVERTER

Metal type used as converter in superheterodyne circuits. It is similar in performance to type 6BE6. For general discussion of pentagrid types, see Frequency Conversion in Electron Tube Applications section. This tube

6SA7
Related type:
12SA7

has excellent frequency stability. Tube requires octal socket and may be mounted in any position. Outline 2A, Outlines section. Type 12SA7 is identical with type 6SA7 except for the heater ratings, as shown below.

|  | 6SA7   | 12SA7     |        |
|--|--------|-----------|--------|
| Heater Voltage (ac/dc)                               | 6.3    | 12.6      | volts  |
| Heater Current                                       | 0.3    | 0.15      | ampere |
| Peak Heater-Cathode Voltage:                         |        |           |        |
| Heater negative with respect to cathode              | 90 max | 90 max    | volts  |
| Heater positive with respect to cathode              | 90 max | 90 max    | volts  |
| Direct Interelectrode Capacitances:                  |        |           |        |
| Grid No.3 to All Other Electrodes (RF Input)         |        | 9.5*      | pf     |
| Plate to All Other Electrodes (Mixer Output)         |        | 9.5*      | pf     |
| Grid No.1 to All Other Electrodes (Osc. Input)       |        | 7*        | pf     |
| Grid No.3 to Plate                                   |        | 0.25 max* | pf     |
| Grid No.3 to Grid No.1                               |        | 0.15 max* | pf     |
| Grid No.1 to Plate                                   |        | 0.06 max* | pf     |
| Grid No.1 to Shell, Grid No.5, and All Other Electro |        | 0.00 man  | ν.     |
| except Cathode                                       |        | 4.4       | pf     |
| Grid No.1 to Cathode                                 |        | 2.6       | pf     |
| Cathode to Shell, Grid No.5, and All Other Electrode |        | 2.0       | pı     |
|  |        | 5         | -6     |
| except Grid No.1                                     |        | 3         | pf     |
| * With shell connected to cathode.                   |        |           |        |

With shell connected to cathode.

TYPICAL OPERATION:

|         |         |                | Converter |
|---------|---------|----------------|-----------|
| MAXIMUM | RATINGS | (Design-Center | Values):  |

| Plate Voltage                             | 300 max | voits |
|---|---------|-------|
| Grids-No.2-and-No.4 (Screen-Grid) Voltage |         | volts |
| Grids-No.2-and-No.4 Supply Voltage        | 300 max | volts |
| Grid-No.3 (Control-Grid) Voltage:         |         |       |
| Negative bias value                       | -50 max | volts |
| Positive bias value                       | 0 max   | volts |
| Plate Dissipation                         | 1.0 max | watt  |
| Grids-No.2-and-No.4 Input                 | 1.0 max | watt  |
| Cathode Current                           | 14 max  | ma    |

| TITLE OF ENATION                     | Separate | LACITATION |              |              |
|--------------------------------------|----------|------------|--------------|--------------|
| Plate Voltage                        |          | 100        | 250          | volts        |
| Grid No.5 and shell                  |          | Connec     | ted to catho | de at socket |
| Grids-No.2-and-No.4 Voltage          |          | 100        | 100          | volts        |
| Grid-No.3 Voltage                    |          | 2          | -2           | volts        |
| Grid-No.1 (Oscillator-Grid) Resistor |          | 20000      | 20000        | ohms         |
| Plate Resistance (Approx.)           |          | 0.5        | 1.0          | megohm       |
|                                      |          |            |              |              |

Separate Excitations

| Conversion Transconductance   | 425  | 450       | μmhos .          |
|-------------------------------|------|-----------|------------------|
| of 10 µmhos                   | -25  | -25       | volts            |
| transconductance of 100 µmhos | -9   | <b>_9</b> | vol <b>ts</b> أُ |
| Plate Current                 | 3.3  | 3.5       | ma               |
| Grids-No.2-and-No.4 Current   | 8.5  | 8.5       | . ma             |
| Grid-No.1 Current             | 0.5  | 0.5       | ma i             |
| Cathode Current               | 12.3 | 12.5      | ma j             |

NOTE: The transconductance between grid No.1 and grids No.2 and No.4 connected to plate (not oscillating) is 4500  $\mu$ mhos under the following conditions: grids No.1, No.3 at 0 volts; grids No.2 and No.4 and plate at 100 volts; grid No.5 and shell are connected to cathode at socket.

† The characteristics shown with separate excitation correspond very closely to those obtained in a self-excited oscillator circuit operating with zero bias.

6SA7GT

#### PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

6SB7Y

#### PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

6SC7

### HIGH-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

6SF5 6SF5GT

## HIGH-MU TRIODE

Renewal types; see chart at end of section for tabulated data.

6SF7

### DIODE— REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6SG7


# SEMIREMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6SH7

### **SHARP-CUTOFF PENTODE**

Renewal type; see chart at end of section for tabulated data.



#### SHARP-CUTOFF PENTODE

Metal type used as rf amplifier and biased detector. As a detector, this type is capable of delivering large audio-frequency output voltage with relatively small input voltage. Outline 2A, Outlines section. Tube requires

6SJ7
Related type:
12SJ7

octal socket and may be mounted in any position. Type 12SJ7 is identical with type 6SJ7 except for the heater ratings, as shown below.

| Water Walter (co./de)                                 | 6SJ7<br>6.3 | 12SJ7<br>12.6 | volts  |
|---|-------------|---------------|--------|
| Heater Voltage (ac/dc)                                |             |               |        |
| Heater Current  | 0.3         | 0.15          | ampere |
| Peak Heater-Cathode Voltage:                          |             |               |        |
| Heater negative with respect to cathode               | 90 max      | 90 max        | volts  |
| Heater positive with respect to cathode               | 90 max      | 90 max        | volts  |
| Direct Interelectrode Capacitances:                   |             |               |        |
| Pentode Connection:                                   |             |               |        |
| Grid No.1 to Plate                                    |             | 0.005 max     | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No. | o.3         | 6.0           | pf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3.   |             | 7.0           | pf     |
| Triode Connection:                                    |             |               | _      |
| Grid No.1 to Plate                                    |             | 2.8           | pf     |
| Grid No.1 to Cathode and Heater                       |             | 3.4           | pf     |
| Plate to Cathode and Heater                           |             | 11            | pf     |
| Trace to Caulouc and Heater                           |             | **            | PL     |

- \* With shell connected to cathode.
- With grids No.2 and No.3 connected to plate.

#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Center Values):               | Triode<br>Connection* | Pentode<br>Connection |         |
|---|-----------------------|-----------------------|---------|
| Plate Voltage   | 250 max               | 300 max               | volts   |
| Grid-No.2 (Screen-Grid) Voltage                       | -                     | See curve             | page 75 |
| Grid-No.2 Supply Voltage                              | _                     | 300 max               | volts   |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max                 | 0 max                 | volts   |
| Plate Dissipation                                     | 2.5 max               | 2.5 max               | watts   |
| Grid-No.2 Input:                                      |                       |                       |         |
| For grid-No.2 voltages up to 150 volts                | _                     | 0.7 max               | watt    |
| For grid-No.2 voltages between 150 and 300 volts      | _                     | See curve             | page 75 |
|   |                       |                       |         |

|                                       |      | riode    | P            | entode   |           |
|---------------------------------------|------|----------|--------------|----------|-----------|
| TYPICAL OPERATION:                    |      | nection* | Cor          | nection  |           |
| Plate Voltage                         | 180  | 250      | 100          | 250      | volts     |
| Grid No.3                             |      | _        | Connected to | cathode  | at socket |
| Grid-No.2 Voltage                     | -    | _        | 100          | 100      | volts     |
| Grid-No.1 Voltage                     | 6    | -8.5     | -3           | -3       | volts     |
| Amplification Factor                  | 19   | 19       |              |          |           |
| Plate Resistance (Approx.)            | 8250 | 7600     | 700000       | <b>†</b> | ohms      |
| Transconductance                      | 2300 | 2500     | 1575         | 1650     | μmhos     |
| Grid-No.1 Voltage (Approx.) for plate |      |          |              |          | ,         |
| current of 10 µa                      |      | _        | -8           | 8        | volts     |
| Plate Current                         | 6.0  | 9.2      | 2.9          | 3.0      | volts     |
| Grid-No.2 Current                     | -    | _        | 0.9          | 0.8      | ma        |

<sup>\*</sup> Grids No.2 and No.3 connected to plate.

### SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

6SJ7GT

<sup>†</sup> Greater than 1 megohm.

# 6SK7 6SK7GT


### REMOTE-CUTOFF PENTODE

Renewal types; see chart at end of section for tabulated data.

#### HIGH-MU TWIN TRIODE

6SL7GT
Related type:
12SL7GT

Glass octal type used as phase inverter in radio equipment. Each unit amplifier circuits. Outline 13D, Outsocket and may be mounted in any lines section. Tube requires octal may also be used in resistance-coupled



position. Except for the common heater, each triode unit is independent of the other. For typical operation as phase inverter or resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 12SL7GT is identical with type 6SL7GT except for the heater ratings, as shown below.

|   | 6SL7GT    | 12SL7GT   |        |
|---|-----------|-----------|--------|
| Heater Voltage (ac/dc)                        | 6.3       | 12.6      | volts  |
| Heater Current                                | 0.3       | 0.15      | ampere |
| Peak Heater-Cathode Voltage:                  |           |           |        |
| Heater negative with respect to cathode       | 90 max    | 90 max    | volts  |
| Heater positive with respect to cathode       | 90 max    | 90 max    | volts  |
| Direct Interelectrode Capacitances (Approx.): | Unit No.1 | Unit No.2 |        |
| Grid to Plate                                 | 2.8       | 2.8       | pf     |
| Grid to Cathode and Heater                    | 3.0       | 3.4       | pf     |
| Plate to Cathode and Heater                   | 3.8       | 3.2       | pf     |
| Plate to Cathode and Heater                   | 3.8       | 3.2       |        |

With external shield connected to cathode.

Plate Voltage .....

# Class A<sub>1</sub> Amplifier MAXIMUM RATINGS (Design-Center Values):

| Grid Voltage, Positive-bias value | 0 max | volts |
|-----------------------------------|-------|-------|
| Plate Dissipation                 | 1 max | watt  |
| CHARACTERISTICS:                  |       |       |
| Plate Voltage                     | 250   | volts |
| Grid Voltage                      | 2     | volts |
| Amplification Factor              |       |       |
| Plate Resistance (Approx.)        | 44000 | ohms  |
| Transconductance                  | 1600  | μmhos |
| Plote Current                     | 2.3   |       |

6SN7GT 6SN7GTA


### MEDIUM-MU TWIN TRIODE

Discontinued types; see chart at end of section for tabulated data.

### MEDIUM-MU TWIN TRIODE

6SN7GTB
Related types:
12SN7GTA

Glass octal type used as combined vertical oscillator and vertical deflection amplifier, and as horizontal deflection oscillator, in television receivers. Each unit may also be used in multivibrator or resistance-coupled



300 max

volts


amplifier circuits in radio equipment. This type has a controlled heater warm-up

time to permit use in series-connected heater strings. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any position. Except for the common heater, each triode unit is independent of the other. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 12SN7GTA is identical with type 6SN7GTB except for the heater ratings, as shown below.

|  | 6SN7GTB                                  | 12SN7GTA   |  |
|--|--|--|--|
| Heater Voltage (ac/dc)   | 6.3                                      | 12.6   | volts  |
| Heater Current   | 0.6                                      | 0.3  | ampere   |
| Heater Warm-up Time (Average)  | 11                                       | -  | seconds  |
| Heater negative with respect to cathode  | 200 max                                  | 200 max  | volts  |
| Heater positive with respect to cathode  | 200°max                                  | 200°max  | volts  |
| Direct Interelectrode Capacitances (Approx.):  | Unit No1                                 | Unit No2   |  |
| Grid to Plate  | 4.0                                      | 3.8  | pf   |
| Grid to Cathode and Heater   | 2.2                                      | 2.6  | pf   |
| Plate to Cathode and Heater  | 0.7                                      | 0.7  | pf   |
| The dc component must not exceed 100 volts.  |  |  |  |
| Class A <sub>1</sub> Amplifier (Eacl MAXIMUM RATINGS (Design-Center Values):   | h Unit)                                  |  |  |
| Plate Voltage  |  | 450 max  | volts  |
| Cathode Current  |  | 20 max   | ma   |
| Plate Dissipation:   |  | 20 Hax   | ша   |
| For either plate   |  | 5 max  | watts  |
| For both plates with both units operating  |  | 7.5 max  | Watts  |
| CHARACTERISTICS:   |  | 710 111415   | ***************************************                  |
| Plate Voltage  | 90                                       | 250  | volts  |
| Grid Voltage   | 0  | <del></del> 8  | volts  |
| Amplification Factor   | 20                                       | 20   | VOILS  |
| Plate Resistance (Approx.)   | 6700                                     | 7700   | ohms   |
| Transconductance   | 3000                                     | 2600   | umhos  |
| Plate Current  | 10                                       | 9  | ma   |
| Plate Current for grid voltage of -12.5 volts  |  | 1.3  | ma   |
| Grid Voltage (Approx.) for plate current of 10 μa  | -7                                       | 18   | volts  |
| MAXIMUM CIRCUIT VALUE:   |  |  |  |
| Grid-Circuit Resistance:   |  |  |  |
| For fixed-bias operation   |  | 1.0 max  | megohm   |
|  |  |  | mogomic  |
| Oscillator (Each Un  |  |  |  |
| For operation in a 525-line, 30-fr   | rame system<br>Vertical                  | Horizontal   |  |
|  | Deflection                               | Deflection   |  |
| MAXIMUM RATINGS (Design-Center Values):  | Oscillator                               | Oscillator   |  |
| DC Plate Voltage   | 450 max                                  | 450 max  | volts  |
| Peak Negative-Pulse Grid Voltage   | -400 max                                 | -600 max   | volts  |
| Peak Cathode Current   | 70 max                                   | 300 max  | ma   |
| Average Cathode Current  | 20 max                                   | 20 max   | ma   |
|  |  |  |  |
| Plate Dissipation:   |  |  |  |
| For either plate   | 5 max                                    | 5 max  | Watts  |
| For either plate For both plates with both units operating   | 5 max<br>7.5 max                         | 5 max<br>7.5 max   | Watts<br>Watts   |
| For either plate   | 7.5 max                                  |  |  |
| For either plate For both plates with both units operating   |  |  | watts  |
| For either plate For both plates with both units operating  MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance   | 7.5 max<br>2.2 max                       | 7.5 max  | watts  |
| For either plate For both plates with both units operating MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr  | 7.5 max<br>2.2 max<br>(Each Unit)        | 7.5 max  | watts  |
| For either plate For both plates with both units operating  MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr  MAXIMUM RATINGS (Design-Center Values):  | 7.5 max  2.2 max (Each Unit) rame system | 7.5 max<br>2.2 max   | watts  |
| For either plate For both plates with both units operating  MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr  MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max  | watts<br>megohm<br>volts                                 |
| For either plate For both plates with both units operating MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum)   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500=max   | watts megohm  volts volts                                |
| For either plate For both plates with both units operating MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage  | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500 max   | watts megohm  volts volts volts                          |
| For either plate For both plates with both units operating  MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr  MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500*max250 max 70 max   | watts megohm  volts volts volts volts ma                 |
| For either plate For both plates with both units operating MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500 max   | watts megohm  volts volts volts                          |
| For either plate For both plates with both units operating MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vartical Deflection Amplifier For operation in a 525-line, 30-fr MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation:  | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500=max -250 max 70 max 20 max                                | watts megohm  volts volts volts volts ma ma              |
| For either plate For both plates with both units operating  MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr  MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: For either plate   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500=max250 max 70 max 20 max 5 max                            | watts megohm  volts volts volts ma ma watts              |
| For either plate For both plates with both units operating  MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr  MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: For either plate For both plates with both units operating   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500=max -250 max 70 max 20 max 75 max 7.5 max                 | watts megohm  volts volts volts ma ma  watts watts       |
| For either plate For both plates with both units operating MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: For either plate For both plates with both units operating # The duration of the voltage pulse must not exceed 15 pe   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500=max —250 max 70 max 20 max 20 max 7.5 max 7.5 max 7.5 max | watts megohm  volts volts volts volts ma ma watts watts  |
| For either plate For both plates with both units operating  MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr  MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: For either plate For both plates with both units operating  # The duration of the voltage pulse must not exceed 15 pe In a 525-line, 30-frame system, 15 per cent of one vertice | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500=max —250 max 70 max 20 max 20 max 7.5 max 7.5 max 7.5 max | watts megohm  volts volts volts volts ma ma watts watts  |
| For either plate For both plates with both units operating MAXIMUM CIRCUIT VALUE: Grid-Circuit Resistance  Vertical Deflection Amplifier For operation in a 525-line, 30-fr MAXIMUM RATINGS (Design-Center Values): DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: For either plate For both plates with both units operating # The duration of the voltage pulse must not exceed 15 pe   | 7.5 max 2.2 max (Each Unit) rame system  | 7.5 max 2.2 max 450 max 1500=max —250 max 70 max 20 max 20 max 7.5 max 7.5 max 7.5 max | watts megohm  volts volts volts volts ma ma  watts watts |

#### MAXIMUM CIRCUIT VALUE:


Grid-Circuit Resistance:



#### TWIN DIODE— HIGH-MU TRIODE

6SQ7
Related type: 12SQ7

Metal type used as combined detector, amplifier, and avc tube in radio receivers. Outline 2A, Outlines section. Tube requires octal socket and may be mounted in any position. Diodebiasing of the triode unit is not suit-



able because of the probability of triode plate-current cutoff even with relatively small signal voltages applied to the diode circuit. Type 12SQ7 is identical with type 6SQ7 except for the heater ratings, as shown below.

| TV                                       | 6SQ7              | 12SQ7    | 14     |
|--|-------------------|----------|--------|
| Heater Voltage (ac/dc)                   | 6.3               | 12.6     | volts  |
| Heater Current                           | 0.3               | 0.15     | ampere |
| Peak Heater-Cathode Voltage:             |                   |          |        |
| Heater negative with respect to cathode  | 90 max            | 90 max   | volts  |
| Heater positive with respect to cathode  | 90 max            | 90 max   | volts  |
| Direct Interelectrode Capacitances:      |                   |          |        |
| Triode Unit:                             |                   |          |        |
| Grid to Plate                            |                   | 1.6      | pf     |
| Grid to Cathode and Heater               |                   | 3.2      | pf     |
| Plate to Cathode and Heater              |                   | 3        | pf     |
| Either Diode Plate to Cathode and Heater |                   | 3.3 max  |        |
|  |                   |          | pf     |
| Triode Grid to Plate of Diode No.1       |                   | 0.03 max | pf     |
| Triode Grid to Plate of Diode No.2       | • • • • • • • • • | 0.04 max | pf     |
| Triode Unit as Class A, A                | mplifier          |          |        |
| MAXIMUM RATINGS (Design-Center Values):  |                   |          | _      |
| Plate Voltage                            |                   | 300 max  | volts  |
| Grid Voltage, Positive-bias value        |                   | 0 max    | volts  |
| Plate Dissipation                        |                   | 0.5 max  | watt   |
| CHARACTERISTICS:                         |                   |          |        |
| Plate Voltage                            | 100               | 250      | volts  |
| Grid Voltage                             | <b>—</b> i        | -2       | volts  |
| Amplification Factor                     | 100               | 100      | . 0113 |


| 1 conneur Dava   | 307                                |
|--|------------------------------------|
| Plate Resistance (Approx.)         110000           Transconductance         925           Plate Current         0.5                         | 85000 ohms<br>1175 μmhos<br>1.1 ma |
| Diode Units  |                                    |
| MAXIMUM RATING (Design-Center Value): Plate Current (Each Unit)  | 1.0 max ma                         |
| Two diode plates are placed around a cathode, the sleeve of which in unit. Each diode plate has its own base pin. For diode operation curves |                                    |
| TWIN TRIODE— HIGH-MU TRIODE Renewal type; see chart at end of section for tabulated data.  | 6SQ7GT                             |
| TWIN DIODE— MEDIUM-MU TRIODE Renewal type; see chart at end of section for tabulated data.   | 6SR7                               |
| REMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.  | 6SS7                               |
| TWIN DIODE—  MEDIUM-MU TRIODE  Discontinued type; see chart at end of section for tabulated data.  | 6 <b>ST7</b>                       |
| TWIN DIODE— HIGH-MU TRIODE Discontinued type; see chart at end of section for tabulated data.  | 6S <b>Z</b> 7                      |
| MEDIUM-MU TRIODE Renewal type; see chart at end of section for tabulated data.   | 6T4                                |
| TWIN DIODE— HIGH-MU TRIODE Discontinued type; see chart at end of section for tabulated data.  | 6T7G                               |
| TRIPLE DIODE— HIGH-MU TRIODE Discontinued type; see chart at end   | 6 <b>T</b> 8                       |

Discontinued type; see chart at end of section for tabulated data.

### TRIPLE DIODE— HIGH-MU TRIODE

6T8A
Related type:

Miniature type used as combined audio amplifier, AM detector, and FM detector in AM/FM radio receivers. Diode unit No.1 is used for AM detection, and diode units No.2 and No.3 are used for FM detection. This type



has a controlled heater warm-up time for use in receivers employing seriesconnected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 5T8 is identical with type 6T8A except for the heater ratings, as shown below.

|  | 5 <b>T</b> 8 | 6T8A        |         |
|--|--------------|-------------|---------|
| Heater Voltage (ac/dc)                               | 4.7          | 6.3         | volts   |
| Heater Current                                       | 0.6          | 0.45        | ampere  |
| Heater Warm-up Time (Average)                        | 11           | 11          | seconds |
| Peak Heater-Cathode Voltage:                         |              |             |         |
| Heater negative with respect to cathode              | 200 max      | 100 max     | volts   |
| Heater positive with respect to cathode              | 200 max#     | 100 max     | volts   |
|  | Without      | With        |         |
| Direct Interelectrode Capacitances:                  | External     | External    |         |
| Triode Unit:   | Shield       | Shield*     |         |
| Grid to Plate  | 1.7          | 1.7         | pf      |
| Grid to Cathode, Internal Shield (pin 7), and Heater | 1.6          | 1.7         | pf      |
| Plate to Cathode, Internal Shield (pin 7), and       | . 1.0        | 4.7         | þī      |
|  | 1.2          | 2.4         |         |
| Heater   | 1.2          | 2.4         | pf      |
| Diode Units:   |              |             |         |
| Diode-No.1 Plate to Cathode, Internal Shield         |              |             |         |
| (pin 7), and Heater                                  | 3.8          | 3.8         | pf      |
| Diode-No.2 Plate to Cathode, Internal Shield         |              |             |         |
| (pin 3), and Heater                                  | 3.8          | 3.8●        | pf      |
| Diode-No.3 Plate to Cathode, Internal Shield         |              |             | •       |
| (pin 7), and Heater                                  | 3.4          | 3.6         | pf      |
| Diode-No.2 Cathode, Internal Shield (pin 3) to All   | •••          |             | ρ.      |
| Other Electrodes, and Heater                         | 7.5          | 8.5         | pf      |
| Triode Grid to any Diode Plate                       | 0.034 max    | 0.034 max   | pf      |
| Thous one to any Diodo Hate                          | U.UJT IIIAX  | U.UJ4 IIIAX | μı      |

- # The dc component must not exceed 100 volts.
- \* With external shield connected to pin 7 except as noted.
- With external shield connected to pin 3.
- With external shield connected to pins 4 and 5.

Plate Voltage

# Triode Unit as Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values):


| Grid Voltage, Positive-bias value  |       | 0 max   | volts      |
|--|-------|---------|------------|
| Plate Dissipation  |       | 1.1 max | watts      |
| CHARACTERISTICS:   |       |         |            |
|  |       |         |            |
| Plate Voltage  | 100   | 250     | volts      |
| Grid Voltage   | _1    | 3       | volts      |
| Amplification Factor   | 70    | 70      | 10113      |
| The state of the s |       |         |            |
| Plate Resistance (Approx.)   | 54000 | 58000   | ohms       |
| Transconductance   | 1300  | 1200    | μmhos      |
| Transconductance   |       | 1200    | $\mu$ mmos |
| Plate Current  | 0.8   | 1.0     | ma         |

#### **Diode Units**

| MAXIMUM RATINGS (Design-Maximum | Values): |
|---------------------------------|----------|
| Plate Current (Each Unit)       | •        |

330 max

volts





### BEAM POWER TUBE— SHARP-CUTOFF PENTODE

Duodecar type used as combined FM detector and audio-frequency output amplifier in television receivers. The beam power unit is used in af output stages, and the sharp-cutoff, dual-control pentode unit is used as an FM

6T10

detector. Outline 8B, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.95; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode). For maximum ratings and characteristics, refer to type 6AL11.

### **ELECTRON-RAY TUBE**

Renewal type; see chart at end of section for tabulated data.

**6U5** 

### **REMOTE-CUTOFF PENTODE**

Discontinued type; see chart at end of section for tabulated data.

**6U7G** 

### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE


Discontinued type; see chart at end of section for tabulated data.

**6U8** 

#### MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE

Related type: 5U8, 9U8A

Miniature type used as combined os- G2P(3 cillator and mixer tube in television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. This type has a controlled heater warm-up time for use in tele-



vision receivers employing series-controlled heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Types 5U8 and 9U8A are identical with type 6U8A except for the heater ratings, as shown below.

|   | 5U8       | 6U8A      | 9U8A      |         |
|---|-----------|-----------|-----------|---------|
| Heater Voltage (ac/dc)                                      | 4.7       | 6.3       | 9.45      | volts   |
| Heater Current  | 0.6       | 0.45      | 0.3       | атреге  |
| Heater Warm-up Time (Average)  Peak Heater-Cathode Voltage: | 11        | 11        | 11        | seconds |
| Heater negative with respect to cathode                     | 200 max   | 200 max   | 200 max   | volts   |
| Heater positive with respect to cathode                     | 200 = max | 200 max   | 200=max   | volts   |
|   |           | Without   | With      |         |
| Direct Interelectrode Capacitances:                         |           | External  | External  |         |
| Triode Unit:  |           | Shield    | Shield*   |         |
| Grid to Plate   |           | 1.8       | 1.8       | pf      |
| Grid to Cathode, Heater, Pentode Cathode, P                 | entode    |           |           |         |
| Grid No.3, and Internal Shield                              |           | 2.8       | 2.8       | pf      |
| Plate to Cathode, Heater, Pentode Cathode,                  |           |           |           |         |
| Pentode Grid No.3, and Internal Shield                      |           | 1.5       | 2         | pf      |
| Pentode Unit:   |           |           |           |         |
| Grid No.1 to Plate  |           | 0.010 max | 0.006 max | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2,                    | Grid      |           |           |         |
| No.3, and Internal Shield                                   |           | 5.0       | 5.0       | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid                   | No.3,     |           |           |         |
| and Internal Shield   |           | 2.6       | 3.5       | pf      |
| Triode Cathode to Heater                                    |           | 3         | 3●        | pf      |
| Pentode Cathode, Pentode Grid No.3, and In                  | nternal   |           |           |         |
| Shield to Heater  |           | 3         | 3∙        | pf      |
| Pentode Grid No.1 to Triode Plate                           |           | 0.2 max   | 0.2 max   | pf      |
| Pentode Plate to Triode Plate                               |           | 0.1 max   | 0.02 max  | pf      |
|   |           |           |           |         |

| The dc component must not exceed 100 volts.                 |             |              |            |
|---|-------------|--------------|------------|
| ▲ With external shield connected to pin 4 except as noted.  |             |              |            |
| • With external shield connected to pin 6.                  |             |              |            |
| Class A, Amplifie   | r           |              |            |
| MAXIMUM RATINGS (Design-Maximum Values):                    | Triode Unit | Pentode U    | Init       |
| Plate Voltage   | 330 max     | 330 ma:      | x volts    |
| Grid-No.2 (Screen-Grid) Supply Voltage                      | _           | 330 ma       |            |
| Grid-No.2 Voltage   | _           |              | ve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value       | 0 max       | 0 max        |            |
| Plate Dissipation   | 2.5 max     | 3 ma         | x watts    |
| Grid-No.2 Input:  |             |              |            |
| For grid-No.2 voltages up to 165 volts                      |             | 0.55 max     |            |
| For grid-No.2 voltages between 165 and 330 volts            | _           | See curv     | e page 75  |
| CHARACTERISTICS:  | Triode Unit | Pentode Unit |            |
| Plate Voltage   | 125         | 125          | volts      |
| Grid-No.2 Voltage   | _           | 110          | volts      |
| Grid-No.1 Voltage   | -1          | -1           | volts      |
| Amplification Factor  | . 40        | _            |            |
| Plate Resistance (Approx.)                                  | -           | 0.2          | megohm     |
| Transconductance  | 7500        | 5000         | μmhos      |
| Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu$ a | 9           | -8           | volts      |
| Plate Current   | 13.5        | 9.5          | ma         |
| Grid-No.2 Current   | -           | 3.5          | ma         |

#### THREE-UNIT TRIODE


Duodecar type used in a variety of amplifier applications. Units No.1 and 7. No.3 are medium-mu triode units, and unit No.2 is a high-mu triode unit. 3 Outline 8A, Outlines section. Tube requires duodecar twelve-contact socket

6U10

and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (this value may reach 275 for units No.1 and No.3 when the heater is negative with respect to the cathode; the dc component must not exceed 100 volts).

| Class A, Ampliner  |                                  |                         |            |
|--|----------------------------------|-------------------------|------------|
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage: DC Grid Voltage: | Units Nos.<br>1 and 3<br>330 max | Unit<br>No.2<br>330 max | volts      |
| Positive-bias value  | 0 max                            | 0 max                   | volts      |
| Negative-bias value  | -50 max                          | -50 max                 | volts      |
| Average Cathode Current  | 20 max                           | -                       | ma         |
| Plate Dissipation  | 2 max                            | 1 max                   | watts      |
| CHARACTERISTICS:   |                                  |                         |            |
| Plate Voltage  | 200                              | 200                     | volts      |
| Grid Voltage   | 6                                | 1.5                     | volts      |
| Amplification Factor   | 17.5                             | 90                      |            |
| Plate Resistance (Approx.)   | 7700                             | 61000                   | ohms       |
| Transconductance   | 2300                             | 1600                    | $\mu$ mhos |
| Plate Current  | 9.6                              | 1.2                     | ma         |
| For plate current of 100 µa  | 15                               |                         | volts      |
| For plate current of 35 $\mu a$  | _                                | <b>-3</b>               | volts      |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance:                         |                                  |                         |            |
| For fixed-bias operation   | 1 max                            | 0.5 max                 | megohm     |
| For cathode-bias operation   | 2.2 max                          |                         | negohms    |

\* This value may reach 10 megohms provided the plate-supply voltage and load resistance are such that the plate dissipation can never exceed 0.5 watt.



### HALF-WAVE VACUUM RECTIFIER

Miniature type used as a damper tube in horizontal deflection circuits of television receivers. Outline 7B, Outlines section. Tube requires miniature ninecontact socket and may be mounted in any position. It is especially important

**6V3A** 

that this tube, like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 6.3; amperes, 1.75.

#### Damper Service

For operation in a 525-line, 30-frame system

| MANUFACTED BARRIOG CO. C. C. A. S. S. S.                    |             |       |
|---|-------------|-------|
| MAXIMUM RATINGS (Design-Center Values):                     |             |       |
| Peak Inverse Plate Voltage# (Absolute Maximum)              | 6000† max   | volts |
| Peak Plate Current  | 800 max     | ma    |
| DC Plate Current  | 135 max     | ma    |
| Peak Heater-Cathode Voltage:                                |             |       |
| Heater negative with respect to cathode# (Absolute Maximum) | 6750† = max | volts |
| Heater positive with respect to cathode                     | 300° mar    | volte |

- # The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- † Under no circumstances should this absolute value be exceeded.
- The dc component must not exceed 750 volts.
- o The dc component must not exceed 100 volts.

# 6V6GT

#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**

6V6 6V6GTA

Related types: 5V6GT, 12V6GT Metal type 6V6 and glass octal type 6V6GTA are used as output amplifiers in automobile, battery-operated, and other receivers in which reduced plate-current drain is desirable. Outlines 2B and 13D, respectively, **Outlines** sec-



volts

ohms

tion. Tubes require octal socket and may be mounted in any position. These tubes are equivalent in performance to type 6AQ5A. Refer to type 6AQ5A for average plate characteristic curves. Types 5V6GT and 12V6GT are identical with type 6V6GTA except for the heater ratings, as shown below.

|   | 5V6GT        | 6V6      | 6V6GTA    | 12V6GT    |         |
|---|--------------|----------|-----------|-----------|---------|
| Heater Voltage (ac/dc)                  | 4.7          | 6.3      | 6.3       | 12.6      | volts   |
| Heater Current                          | 0.6          | 0.45     | 0.45      | 0.225     | ampere  |
| Heater Warm-up Time (Average)           | 11           | -        | 11        | _         | seconds |
| Peak Heater-Cathode Voltage:            |              |          |           |           |         |
| Heater negative with respect to         |              |          |           |           |         |
| cathode                                 | 200 max      | 200 ma   | x 200 max | 200 max   | volts   |
| Heater positive with respect to         |              |          |           |           |         |
| cathode                                 | 200 = max    | 200 = ma | x 200=max | 200 • max | volts   |
| Direct Interelectrode Capacitances (App | prox.):      |          | 6V6°      | 6V6GTA    |         |
| Grid No.1 to Plate                      |              |          | 0.3       | 0.7       | pf      |
| Grid No.1 to Cathode, Heater, Gri       | d No.2, and  |          |           |           | -       |
| Grid No.3                               |              |          | 10        | 9.0       | pf      |
| Plate to Cathode, Heater, Grid No       | .2, and Grid | No.3     | 11        | 7.5       | pf      |

<sup>•</sup> The dc component must not exceed 100 volts.

Grid-No.1 (Control-Grid) Voltage .....

Plate Resistance (Approx.)

Amplification Factor ......

#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Value |     |       |         |          |
|---------------------------------------|-----|-------|---------|----------|
| Plate Voltage                         |     |       | 350 max | volts    |
| Grid-No.2 (Screen-Grid) Voltage       |     |       | 315 max | volts    |
| Plate Dissipation                     |     |       | 14 max  | watts    |
| Grid-No.2 Input                       |     |       | 2.2 max | watts    |
| TYPICAL OPERATION:                    |     |       |         |          |
| Plate Voltage                         | 180 | 250   | 315     | volts    |
| Grid-No.2 Voltage                     |     | 250   | 225     | volts    |
| Grid-No.1 (Control-Grid) Voltage      |     | -12.5 | -13     | volts    |
| Peak AF Grid-No.1 Voltage             |     | 12.5  | 13      | volts    |
| Zero-Signal Plate Current             |     | 45    | 34      | ma       |
| Maximum-Signal Plate Current          |     | 47    | 35      | ma       |
| Zero-Signal Grid-No.2 Current         |     | 4.5   | 2.2     | ma       |
| Maximum-Signal Grid-No.2 Current      |     | 7     | 6       | ma       |
| Plate Resistance (Approx.)            |     | 50000 | 80000   | ohms     |
| Transconductance                      |     | 4100  | 3750    | μmhos    |
| Load Resistance                       |     | 5000  | 8500    | ohms     |
| Total Harmonic Distortion             |     | 8     | 12      | per cent |
| Maximum-Signal Power Output           |     | 4.5   | 5.5     | watts    |
| CHARACTERISTICS (Triode Connection):▲ |     |       |         |          |
| Plate Voltage                         |     |       | 250     | volts    |

<sup>\*</sup> With shell connected to cathode.

Transconductance

5000

| Plate Current Grid-No.1 Voltage (Approx.) for plate current of 0.5 ma   |            | 49.5<br>—36 | μmnos<br>ma<br>volts |
|---|------------|-------------|----------------------|
| ▲ Grid No.2 connected to plate.   |            |             | , , , ,              |
| Push-Puil Class A <sub>1</sub> Amp<br>MAXIMUM RATINGS (Same as for class A <sub>1</sub> amplifier)                      | olifier    |             |                      |
| TYPICAL OPERATION (Values are for two tubes):   |            |             |                      |
| Plate Voltage   | 250        | 285         | volts                |
| Grid-No.2 Voltage   | 250        | 285         | volts                |
| Grid-No.1 (Control-Grid) Voltage  | -15        | 19          | volts                |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage  | 30         | 38          | volts                |
| Zero-Signal Plate Current   | 70         | 70          | ma                   |
| Maximum-Signal Plate Current  | 79         | 92          | ma                   |
| Zero-Signal Grid-No.2 Current   | 5          | 4           | ma                   |
| Maximum-Signal Grid-No.2 Current  | 13         | 13.5        | ma                   |
| Effective Load Resistance (Plate-to-Plate)  | 10000      | 8000        | ohms                 |
| Total Harmonic Distortion   | 5          | 3.5         | per cent             |
| Maximum-Signal Power Output   | 10         | 14          | watts                |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation               |            |             | megohm<br>megohm     |
| Vertical Deflection Amplifier (Triod<br>For operation in a 525-line, 30-fra<br>MAXIMUM RATINGS (Design-Maximum Values): | ime system |             |                      |
| DC Plate Voltage  |            | 350 max     | volts                |
| Peak Positive-Pulse Plate Voltage#  |            | 1200 max    | volts                |
| Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage  |            | 275 max     | volts                |
| Peak Cathode Current Average Cathode Current  |            | 115 max     | ma                   |
| Plate Dissipation   |            | 40 max      | ma                   |
| Trace Dissipation   |            | 10 max      | watts                |
| MAXIMUM CIRCUIT VALUE:  |            |             |                      |

Grid-No.1-Circuit Resistance: A Grid No.2 connected to plate.

For cathode-bias operation ...

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

#### TWIN DIODE-LOW-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

**6V7G** 

2.2 max megohms



### FULL-WAVE VACUUM RECTIFIER

Glass octal type used as damper tube in television receivers. Outline 13D, Outlines section. This type may be supplied with pin No.1 omitted. Tube requires octal socket and may be mounted in any position. Socket ter-

6W4GT

minals 1, 2, 4, and 6 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Powerrectifier operation of this type is not recommended.

| Heater Voltage (ac) | 6.3 | volts   |
|---------------------|-----|---------|
| Heater Current      | 1.2 | amneres |

| Direct Interelectrode Capacitances (Approx.):  Plate to Cathode and Heater | 6        | nf.   |
|--|----------|-------|
|  |          | pľ    |
| Cathode to Plate and Heater  | 13       | pf    |
| Heater to Cathode  | 7        | pf    |
| Damper Service   |          |       |
| For operation in a 525-line, 30-frame system                               |          |       |
| MAXIMUM RATINGS (Design-Center Values):                                    |          |       |
| Peak Inverse Plate Voltage (Absolute Maximum)*                             | 3850 max | volts |
| Peak Plate Current   | 750 max  | ma    |
| DC Plate Current   | 125 max  | ma    |
| Plate Dissipation  | 3.5 max  | watts |
| Peak Heater-Cathode Voltage:   | •        |       |
| Heater negative with respect to cathode (Absolute Maximum)*                | 2300 max | volts |
| Heater positive with respect to cathode                                    | 300≜max  | volts |
| Heater positive with respect to camoue                                     | Joo max  | 10113 |
| CHARACTERISTICS, Instantaneous Value:                                      |          |       |
| Tube Voltage Drop for plate current of 250 ma                              | 21       | volts |
| And totage Diop for place content of and him                               |          |       |

- \* The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- The dc component must not exceed 500 volts.
- ▲ The dc component must not exceed 100 volts.

### **BEAM POWER TUBE**

6W6GT Related type: 12W6GT

Glass octal type used in the audio output stage of radio and television receivers. Triode-connected, it is used as a vertical deflection amplifier in television receivers. Outline 13D, Outlines section. This type may be supplied



ma

ma

with pin No.1 omitted. Tube requires octal socket and may be mounted in any position. Type 12W6GT is identical with type 6W6GT except for the heater ratings, as shown below.

|   | 6W6GT     | 12W6GT    |         |
|---|-----------|-----------|---------|
| Heater Voltage (ac/dc)                              | 6.3       | 12.6      | volts   |
| Heater Current                                      | 1.2       | 0.6       | ampere  |
| Heater Warm-up Time (Average)                       | _         | 11        | seconds |
| Peak Heater-Cathode Voltage:                        |           |           |         |
| Heater negative with respect to cathode             | 200 max   | 300#max   | volts   |
| Heater positive with respect to cathode             | 200 ■ max | 200 • max | volts   |
| Direct Interelectrode Capacitances (Approx.):       |           |           |         |
| Grid No.1 to Plate                                  |           | 0.8       | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid N | o.3       | 15        | pf      |
| Plate to Cathode, Heater, Grid No.2, and Grid. No.3 |           | 9         | pf      |
| # The dc component must not exceed 200 volts.       |           |           |         |
| . The do component must not exceed 100 volts        |           |           |         |

Peak AF Grid-No.1 Voltage .....

Zero-Signal Plate Current .....

Maximum-Signal Plate Current .....

Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values):

| Plate Voltage Grid-No.2 (Screen-Grid) Voltage Plate Dissipation Grid-No.2 Input |            | 330 max<br>165 max<br>12 max<br>1.35 max | volts<br>volts<br>watts<br>watts |
|---|------------|--|----------------------------------|
| TYPICAL OPERATION:  |            |  |                                  |
| Plate Supply Voltage  | 110        | 200                                      | volts                            |
| Grid-No.2 Supply Voltage  | 110        | 125                                      | volts                            |
| Grid-No.1 (Control-Grid) Voltage  | <b>7.5</b> |  | volts                            |
| Cathode-Bias Resistor   | -          | 180                                      | ohms                             |
| Peak AF Grid-No.1 Voltage   | 7.5        | 8.5                                      | volts                            |

49

50

Pentode

| Zero-Signal Grid-No.2 Current                           | 4       | 2.2     | ma         |
|---|---------|---------|------------|
| Maximum-Signal Grid-No.2 Current                        | 10      | 8.5     | ma         |
| Plate Resistance (Approx.)                              | 13000   | 28000   | ohms       |
| Transconductance  | 8000    | 8000    | $\mu$ mhos |
| Load Resistance   | 2000    | 4000    | ohms       |
| Total Harmonic Distortion (Approx.)                     | 10      | 10      | per cent   |
| Maximum-Signal Power Output                             | 2.1     | 3.8     | watts      |
| CHARACTERISTICS (Triode Connection)*:                   |         |         |            |
| Plate Voltage   |         | 225     | volts      |
| Grid-No.1 Voltage                                       |         | -30     | volts      |
| Amplification Factor                                    |         | 6.2     |            |
| Plate Resistance (Approx.)                              | <b></b> | 1600    | ohms       |
| Transconductance  |         | 3800    | μmhos      |
| Plate Current   |         | 22      | ma         |
| Grid No.1 Voltage (Approx.) for plate current of 0.5 ma |         | -42     | voits      |
| MAXIMUM CIRCUIT VALUES: Grid-No.1 Circuit Resistance:   |         |         |            |
| For fixed-bias operation                                |         | 0.1 max | megohm     |
| For cathode-bias operation                              |         |         | megohm     |

<sup>\*</sup> Grid No. 2 connected to plate.


# Vertical Deflection Amplifier For operation in a 525-line, 30-frame system

For operation in a 525-line, 30-frame system
Triode


| MAXIMUM RATINGS (Design-Maximum Values): | Connection* | Connection |       |
|--|-------------|------------|-------|
| DC Plate Voltage                         | 330 max     | 330 max    | volts |
| Peak Positive-Pulse Plate Voltage†       | 1200 max    | 1500 max   | volts |
| DC Grid No.2 (Screen-Grid) Voltage       | -           | 165 max    | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -275 max    | —275 max   | volts |
| Peak Cathode Current                     | 195 max     | 195 max    | ma    |
| Average Cathode Current                  |             | 65 max     | ma    |
| Plate Dissipation                        | 8.5 max     | 8 max      | watts |
| Grid-No.2 Input                          |             | 1.2 max    | watts |
| MAXIMUM CIRCUIT VALUE:                   |             |            |       |

## Grid-No.1-Circuit Resistance:

† The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.



<sup>\*</sup> Grid No.2 connected to plate.



6W7G

#### SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

#### **FULL-WAVE VACUUM RECTIFIER**

6X4
Related type:

Miniature type used in power supply of automobile and ac-operated radio receivers. Equivalent in performance to larger type 6X5GT. Type 6X4 requires miniature seven-contact socket and may be mounted in any position.



Outline 5D, Outlines section. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. For discussion of Rating Chart and Operation Characteristics, refer to Interpretation of Tube Data. Type 12X4 is identical with type 6X4 except for the heater ratings, as shown below.

| Heater Voltage (ac/dc)   | 6.34    | 12.6    | volts  |
|--|---------|---------|--------|
|  | 0.6     | 0.3     | ampere |
| Heater negative with respect to cathode  Heater positive with respect to cathode | 450 max | 450 max | volts  |
|  | 200=max | 200•max | volts  |

- ▲ When the heater is operated from a 3-cell (nominal-6-volt) storage-battery source, the permissible heater-voltage range is from 5 to 8 volts.
- The dc component must not exceed 100 volts.

#### **Full-Wave Rectifier**


| MAXIMUM RATINGS (Design-Maximum Values):    |                  |
|---|------------------|
| Peak Inverse Plate Voltage                  | 1250 max volts   |
| Steady-State Peak Plate Current (Per Plate) | 245 max ma       |
| AC Plate Supply Voltage (Per Plate, rms)    | See Rating Chart |
| DC Output Voltage (At filter input)†        | 350 max volts    |
| DC Output Current (Each plate)†             | 45 max ma        |
| Hot-Switching Transient Plate Current       | #                |


<sup>†</sup> This rating applies when the 6X4 is used in vibrator operation with a minimum duty cycle of 75 per cent.

<sup>#</sup> If hot-switching is regularly required in operation, the use of choke-input circuits is recommended. Such circuits limit the hot-switching current to a value no higher than that of the peak plate current. When capacitor-input circuits are used, a maximum peak current value per plate of 1.1 amperes during the initial cycles of the hot-switching transient should not be exceeded.

| TYPICAL OPERATION:                             | Sine-Wave | Operation | Vibrator Operation |         |
|--|-----------|-----------|--------------------|---------|
| Filter Input                                   | Capacitor | Choke     | Capacitor          |         |
| AC Plate Supply Voltage (Each plate, rms)      | 325       | 400       | · -                | volts   |
| Filter Input Capacitor                         | 10        | _         | 10                 | μf      |
| Effective Plate Supply Impedance (Each plate)  | 525       | -         |                    | ohms    |
| Filter Input Choke                             |           | 10        | _                  | henries |
| DC Output Current                              |           | 70        | <b>7</b> 0         | ma      |
| DC Output Voltage at Input to Filter (Approx.) |           | 340       | 240                | volts   |

<sup>•</sup> AC plate supply voltage is measured without load.





#### **FULL-WAVE VACUUM RECTIFIER**

**6X5** 

Discontinued type; see chart at end of section for tabulated data.

#### **FULL-WAVE VACUUM RECTIFIER**

6X5GT

Metal type used in power supply of automobile and ac-operated receivers. Outline 13D, Outlines section. This type may be supplied with pin No.1 omitted. Tube requires octal socket and may be operated in any position.



For maximum ratings, and typical operation, refer to type 6X4.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6X8
Related types:
5X8, 19X8

Miniature type used as combined oscillator and mixer tube in television receivers utilizing an intermediate frequency in the order of 40 megacycles per second. In such service, the 6X8 gives performance comparable to that



obtainable with a 6AG5 mixer and an oscillator consisting of one unit of a type 6J6. When used in an AM/FM receiver, the triode unit is used as an oscillator for both sections. In the AM section, the pentode unit is used as a high-gain pentode mixer; in the FM section, the pentode unit is used either as a pentode mixer or as a triode-connected mixer depending on signal-to-noise considerations. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Types 5X8 and 19X8 are identical with type 6X8 except for the heater ratings, as shown below.

|   | 5X8     | 6X8       | 19X8      |         |
|---|---------|-----------|-----------|---------|
| Heater Voltage (ac/dc)                        | 4.7     | 6.3       | 18.4      | volts   |
| Heater Current                                | 0.6     | 0.45      | 0.15      | ampere  |
| Heater Warm-up Time (Average)                 | 11      | -         | -         | seconds |
| Heater negative with respect to cathode       | 200 max | 200 max   | 200 max   | volts   |
| Heater positive with respect to cathode       | 200 max | 200 = max | 200 max   | volts   |
|   |         | Without   | With      |         |
| Direct Interelectrode Capacitances:           |         | External  | External  |         |
| Triode Unit:                                  |         | Shield    | Shield*   |         |
| Grid to Plate                                 |         | 1.5       | 1.5       | pf      |
| Grid to Cathode and Heater                    |         | 2         | 2.4       | pf      |
| Plate to Cathode and Heater                   |         | 0.5       | 1         | pf      |
| Pentode Unit:                                 |         |           |           | •       |
| Grid No.1 to Plate                            |         | 0.09 max  | 0.06 max  | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2       |         |           |           | •       |
| Grid No.3                                     |         | 4.6       | 4.8       | pf      |
| Plate to Cathode, Heater, Grid No.2, and Grid |         | 0.9       | 1.6       | pf      |
| Pentode Grid No.1 to Triode Plate             |         | 0.05 max  | 0.04 max  | pf      |
| Pentode Plate to Triode Plate                 |         | 0.05 max  | 0.008 max | pf      |
| Heater to Cathode                             |         | 6.5       | 6.5•      | pf      |
|   |         |           |           |         |

- The dc component must not exceed 100 volts.
- ▲ With external shield connected to cathode except as noted.
- With external shield connected to pentode plate.


| GI255 A, AIIIPITIEI                      |             |              |
|--|-------------|--------------|
| MAXIMUM RATINGS (Design-Maximum Values): | Triode Unit | Pentode Unit |
| Dista Voltage                            | 275 may     | 275 may      |


 Plate Voltage
 275 max
 275 max
 volts

 Grid No.2 (Screen-Grid) Supply Voltage
 —
 275 max
 volts

 Grid-No.2 Voltage
 —
 See curve page 75

| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  | 0 max         | 0 ma          | x volts      |
|--|---------------|---------------|--------------|
| Plate Dissipation                                      | 1.7 max       | 2.3 ma        | x watts      |
| For grid-No.2 voltages up to 137.5 volts               |               | 0.45 ma       | x watt       |
| For grid-No.2 voltages between 137.5 and 275 volts     |               | See cur       | ve page 75   |
| CHARACTERISTICS:                                       | Triode Unit   | Pentode U     | nit          |
| Plate Voltage  | 125           | 125           | volts        |
| Grid No.3  | Connec        | ted to cathod | ie at socket |
| Grid-No.2 Voltage                                      |               | 125           | volt         |
| Grid-No.1 Voltage                                      | <b>-1</b>     | 1             | volt         |
| Amplification Factor                                   | 40            | _             |              |
| Plate Resistance (Approx.)                             | 6000          | 300000        | ohms         |
| Transconductance                                       | 6500          | 5500          | μmhos        |
| Plate Current  | 12            | 9             | ma           |
| Grid-No.2 Current                                      |               | 2.2           | ma           |
| Grid-No.1 Voltage (Approx.) for plate current of 20 µa | <del></del> 7 | 6.5           | volts        |





# 6**Y**5

#### **FULL-WAVE VACUUM RECTIFIER**

Discontinued type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**

# 6Y6G 6Y6GA

Heater Voltage (ac/dc) ......

Glass octal types used as output amplifier in radio receivers. Also used in rf-operated, high-voltage power supplies in television equipment. Except for envelope size and direct interelectrode capacitances, type 6Y6G and



6.3

volts

type 6Y6GA are identical. Outlines 25 and 19B, respectively, Outlines section. Tubes require octal socket and may be mounted in any position.

| Heater Current                                   |       | 1.25       | amperes    |
|--|-------|------------|------------|
| Peak Heater-Cathode Voltage:                     |       |            |            |
| Heater negative with respect to cathode          |       | 180 max    | volts      |
| Heater positive with respect to cathode          |       | 180 max    |            |
| Direct Interelectrode Capacitances (Approx.):    | 6Y6G  | 6Y6GA      |            |
| Grid No.1 to Plate                               | 0.7   | 0.7        | pf         |
| Grid No.1 to Cathode, Heater, Grid No.2,         | 0     | •          | γ.         |
| and Grid No.3                                    | 15    | 12         | pf         |
| Plate to Cathode, Heater, Grid No.2,             | 15    |            | <i>p</i> - |
| and Grid No.3                                    | 11    | 7.5        | pf         |
| and Ond 140.5                                    | **    | 7.5        | P.         |
| Class A, Amplifier                               |       |            |            |
| MAXIMUM RATINGS (Design-Center Values):          |       |            |            |
| Plate Voltage                                    |       | 200 max    | volts      |
| Grid-No.2 (Screen-Grid) Supply Voltage           |       | 200 max    |            |
| Grid-No.2 Voltage                                |       |            | ve page 75 |
| Grid-No.2 Input:                                 |       | Sec car    | re page 15 |
| For grid-No.2 voltages up to 100 volts           |       | 1.75 max   | watts      |
| For grid-No.2 voltages between 100 and 200 volts |       |            | ve page 75 |
| Plate Dissipation                                |       | 12.5 max   |            |
| Tiate Dissipation                                |       | 12.5 11147 |            |
| TYPICAL OPERATION:                               |       |            |            |
| Plate Voltage                                    | 135   | 200        | volts      |
| Grid-No.2 Voltage                                | 135   | 135        | volts      |
| Grid-No.1 (Control-Grid) Voltage                 | -13.5 | -14        | volts      |
| Peak AF Grid-No.1 Voltage                        | 13.5  | 14         | volts      |
| Zero-Signal Plate Current                        | 58    | 61         | ma         |
| Maximum-Signal Plate Current                     | 60    | 66         | ma         |
| Zero-Signal Grid-No.2 Current                    | 3.5   | 2.2        | ma         |
| Maximum-Signal Grid-No.2 Current                 | 11.5  | 9          | ma         |
| Plate Resistance (Approx.)                       | 9300  | 18300      | ohms       |
| Transconductance                                 | 7000  | 7100       | μmhos      |
| Load Resistance                                  | 2000  | 2600       | ohms       |
| Total Harmonic Distortion                        | 10    | 10         | per cent   |
| Maximum-Signal Power Output                      | 3.6   | 6          | watts      |
| waxintuin-signal tower Output                    | 3.0   | U          | watts      |
| MAXIMUM CIRCUIT VALUES:                          |       |            |            |
| Grid-No.1-Circuit Resistance:                    |       |            |            |
| For fixed-bias operation                         |       | 0.1 max    | megohm     |
| For cathode-bias operation                       |       |            | megohm     |
|  |       | U.J IIIAA  | . mosomii  |

# 6**Y**7G

# HIGH-MU TWIN POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

| Refer to type 84/6Z4.   | 6 <b>Z</b> 4  |
|---|---------------|
| FULL-WAVE VACUUM RECTIFIER Discontinued type; see chart at end of section for tabulated data. | 6 <b>Z</b> 5  |
| HIGH-MU TWIN POWER TRIODE Discontinued type; see chart at end of section for tabulated data.  | 6 <b>Z</b> 7G |
| FULL-WAVE VACUUM RECTIFIER Discontinued type; see chart at end of section for tabulated data. | 6ZY5G         |
| MEDIUM-MU TRIODE  Renewal type; see chart at end of section for tabulated data.               | <b>7A4</b>    |
| BEAM POWER TUBE Renewal type; see chart at end of section for tabulated data.                 | 7 <b>A</b> 5  |
| TWIN DIODE  Renewal type; see chart at end of section for tabulated data.                     | 7 <b>A</b> 6  |
| REMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.           | 7A7           |
| OCTODE CONVERTER Renewal type; see chart at end of section for tabulated data.                | 7 <b>A</b> 8  |
| POWER PENTODE Discontinued type; see chart at end of section for tabulated data.              | 7AD7          |
| MEDIUM-MU TWIN TRIODE Renewal type; see chart at end of section for tabulated data.           | 7AF7          |

SHARP-CUTOFF PENTODE
Renewal type; see chart at end of section for tabulated data.

SHARP-CUTOFF PENTODE
Discontinued type; see chart at end of section for tabulated data.

MEDIUM-MU TWIN TRIODE
Miniature type identical with type 12AU7A except for heater ratings; refer to 12AU7A for data.

HIGH-MU TRIODE

7B4

HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

7B5

POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

7B6
TWIN DIODE—
HIGH-MU TRIODE
Discontinued type; see chart at end of section for tabulated data.

7B7

REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

7B8

PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

7C5

BEAM POWER TUBE

Renewal type; see chart at end of section for tabulated data.

7C6

TWIN DIODE—
HIGH-MU TRIODE
Renewal type; see chart at end of section for tabulated data.

| SHARP-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.                           | <b>7C7</b>   |
|--|--------------|
| TWIN DIODE— MEDIUM-MU TRIODE Discontinued type; see chart at end of section for tabulated data.              | <b>7E</b> 6  |
| TWIN DIODE— REMOTE-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.         | <b>7E7</b>   |
| BEAM POWER TUBE Glass octal type identical with type 6EY6 except for heater ratings; refer to 6EY6 for data. | 7EY6         |
| HIGH-MU TWIN TRIODE Renewal type; see chart at end of section for tabulated data.                            | <b>7F7</b>   |
| MEDIUM-MU TWIN TRIODE Renewal type; see chart at end of section for tabulated data.                          | 7F8          |
| SHARP-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.                      | 7 <b>G</b> 7 |
| SEMIREMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.                      | 7H7          |
| TRIODE—HEPTODE CONVERTER Renewal type; see chart at end of section for tabulated data.                       | <b>7</b> J7  |
| TWIN DIODE— HIGH-MU TRIODE Renewal type; see chart at end of section for tabulated data.                     | 7K7          |

SHARP-CUTOFF PENTODE **7L7** Discontinued type; see chart at end of section for tabulated data. MEDIUM-MU TWIN TRIODE Renewal type: see chart at end of **7N7** section for tabulated data. PENTAGRID CONVERTER Discontinued type; see chart at end **7Q7** of section for tabulated data. TWIN DIODE— REMOTE-CUTOFF PENTODE **7R7** Discontinued type; see chart at end of section for tabulated data. TRIODE—HEPTODE CONVERTER Discontinued type; see chart at end **7S7** of section for tabulated data. SHARP-CUTOFF PENTODE Renewal type; see chart at end of 7V7 section for tabulated data. SHARP-CUTOFF PENTODE Renewal type; see chart at end of 7W7 section for tabulated data.

7X7

TWIN DIODE—
HIGH-MU TRIODE
Renewal type; see chart at end of section for tabulated data.

7Y4 FULL-WAVE VACUUM RECTIFIER
Renewal type; see chart at end of section for tabulated data.

7Z4 FULL-WAVE VACUUM RECTIFIER
Renewal type; see chart at end of section for tabulated data.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6AU8A except for heater ratings; refer to 6AU8A for data.

8AU8

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6AW8A except for heater ratings; refer to 6AW8A for data.

A8WA8

## TWIN DIODE— MEDIUM-MU TWIN TRIODE

Duodecar type identical with type 6B10 except for heater ratings; refer to 6B10 for data.

8B10

#### MEDIUM-MU TRIODE---SHARP-CUTOFF PENTODE

Miniature type identical with type 6BA8A except for heater ratings; see type 6BA8A for data.

8BA8A

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6BH8 except for heater ratings; see type 6BH8 for data.

8BH8

#### TWIN DIODE— HIGH-MU TRIODE

Miniature type identical with type 6BN8 except for heater ratings; refer to 6BN8 for data.

8BN8

## POWER PENTODE

Miniature type identical with type 6BQ5 except for heater ratings; refer to 6BQ5 for data.

8BQ5

## MEDIUM-MU TWIN TRIODE

Miniature type identical with type 6CG7 except for heater ratings; refer to 6CG7 for data.

8**CG**7

#### MEDIUM-MU DUAL TRIODE

8CM7

Miniature type identical with type 6CM7 except for heater ratings; refer to 6CM7 for data.

## TWIN DIODE— HIGH-MU TRIODE

**8CN7** 

Miniature type identical with type 6CN7 except for heater ratings; refer to 6CN7 for data.

## MEDIUM-MU DUAL TRIODE

Miniature type identical with type 6CS7 except for heater ratings; refer to 6CS7 for data.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**8CX8** 

Miniature type identical with type 6CX8 except for heater ratings; refer to 6CX8 for data.

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

**8EB8** 

Miniature type identical with type 6EB8 except for heater ratings; refer to 6EB8 for data.

#### **BEAM POWER TUBE**

8EM5

Miniature type identical with type 6EM5 except for heater ratings; refer to 6EM5 for data.

#### TWIN DIODE— SHARP-CUTOFF PENTODE

**8ET7** 

Miniature type used in television receivers employing series-connected heater strings. The pentode unit is used as a video amplifier and the diodes are used as a horizontal phase inverter. Outline 6E, **Outlines** section.

P<sub>D2</sub> P<sub>P</sub> S<sub>D1</sub> a D<sub>2</sub> P<sub>P</sub>

Tube requires miniature nine-contact socket and may be operated in any position. Heater volts (ac/dc), 8; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Pentode Unit as Class A <sub>1</sub> Amplifier MAXIMUM RATINGS (Design-Maximum Values):  |                         |                |
|--|-------------------------|----------------|
| Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage   | 330 max<br>330 max      | volts<br>volts |
| Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value  | See curve<br>0 max      |                |
| Grid-No.2 Input: For grid-No.2 voltages up to 165 volts  | 1.1 max                 | watts          |
| For grid-No.2 voltages between 165 and 330 volts   | See curve               | page 75        |
| Plate Dissipation  | 5 max                   | watts          |
| CHARACTERISTICS: Plate Supply Voltage  | 200                     | volts          |
| Grid-No.2 Supply Voltage   | 150                     | volts          |
| Grid-No.1 Voltage 0 Cathode-Bias Resistor  | 100                     | volts<br>ohms  |
| Plate Resistance (Approx.)   | 60000                   | ohms           |
| Transconductance —   | 11500                   | μmhos          |
| Plate Current         55*           Grid-No.2 Current         18*  | 25<br>5.5               | ma<br>ma       |
| Grid-No.1 Voltage (Approx.) for plate current of 100 µa -  | -10                     | volts          |
| MAXIMUM CIRCUIT VALUES:  |                         |                |
| Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation  | 0.1 max r<br>0.25 max r |                |
| • This value can be measured by a method involving a recurrent waveformum ratings of the tube will not be exceeded.              | rm such that th         | e maxi-        |
| Diode Units (Each Unit)  |                         |                |
| MAXIMUM RATINGS (Design-Maximum Values): DC Plate Current  | 3 max                   | ma             |
| CHARACTERISTICS, Instantaneous Value: Tube Voltage Drop for plate current of 1.5 ma  | 10                      | volts          |
| MEDIUM-MU TWIN TRIODE  Miniature type identical with type 6FQ7 except for heater ratings; refer to 6FQ7 for data.                | 8FQ7                    | ,              |
| HIGH-MU TRIODE— SHARP-CUTOFF PENTODE  Miniature type identical with type 6GN8 except for heater ratings; refer to 6GN8 for data. | 8GN8                    | 3              |
| HIGH-MU TRIODE— SHARP-CUTOFF PENTODE Miniature type identical with type 6JV8 except for heater ratings; refer to 6JV8 for data.  | 8JV8                    |                |
| HIGH-MU TRIODE— SHARP-CUTOFF PENTODE Miniature type identical with type 6KA8 except for heater ratings; refer to 6KA8 for data.  | 8KA8                    | <b>}</b>       |

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE


8LC8

Miniature type identical with type 6LC8 except for heater ratings; refer to 6LC8 for data.

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**9A8** 

Miniature type used as combined oscillator and mixer tube in vhf television receivers. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be mounted in any position. Heater volts (ac/dc),



9; amperes, 0.3; peak heater-cathode volts, 200 (heater negative with respect to cathode, dc component must not exceed 120 volts), 100 volts (heater positive with respect to cathode).

| Class A, Amplifier                      |             |             |        |
|---|-------------|-------------|--------|
| MAXIMUM RATINGS (Design-Center Values): | Triode Unit | Pentode Uni | it     |
| Plate Supply Voltage                    | 550 max     | 550 max     | volts  |
| Plate Voltage                           | 250 max     | 250 max     | volts  |
| Grid-No.2 (Screen-Grid) Voltage         | _           | 175 max     | volts  |
| Cathode Current                         | 14 max      | 14 max      | ma     |
| Plate Dissipation                       | 1.5 max     | 1.7 max     | watts  |
| Grid-No.2 Input                         | _           | 0.5 max     | watt   |
| CHARACTERISTICS:                        |             |             |        |
| Plate Voltage                           | 100         | 170         |        |
| Grid-No.2 Voltage                       | -           | 170         | volts  |
| Grid-No.1 Voltage                       | -2          | -2          | volts  |
| Amplification Factor                    | 20          | 47*         |        |
| Plate Resistance (Approx.)              | _           | 0.4         | megohm |
| Transconductance                        | 5000        | 6200        | μmhos  |
| Plate Current                           | 14          | 10          | ma     |
| Grid-No.2 Current                       | _           | 2.8         | ma     |
| MAXIMUM CIRCUIT VALUES:                 |             |             |        |
| Grid-No.1-Circuit Resistance:           |             |             |        |
| For fixed-bias operation                | 0.5 max     | 0.5 max     | megohm |
| For cathode-bias operation              | 0.5 max     |             | megohm |

<sup>\*</sup> Grid No.2 to Grid No.1.


**9AU7** 

#### MEDIUM-MU TWIN TRIODE

Miniature type identical with type 12AU7A except for heater ratings; refer to 12AU7A for data.

#### TWIN DIODE— HIGH-MU TRIODE

9BR7 Renewal type; see chart at end of section for tabulated data.



#### MEDIUM-MU TRIODE— SHARP-CUTOFF TETRODE

O'STR Miniature type used as combined oscillator and mixer in vhf tuners of television receivers employing seriesconnected heater strings. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be

9CL8

mounted in any position. Heater volts (ac/dc), 9.5; amperes, 0.3; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, Amplifier   |             |            | -         |
|--|-------------|------------|-----------|
| MAXIMUM RATINGS (Design-Center Values):                    | Triode Unit | Tetrode Un | it        |
| Plate Voltage  | 300 max     | 300 max    | volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                     |             | 300 max    | volts     |
| Grid-No.2 Voltage  |             |            | e page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value.     | 0 max       | 0 max      | volts     |
| Grid-No.2 Input:   |             |            |           |
| For grid-No.2 voltages up to 150 volts                     | _           | 0.5 max    | watt      |
| For grid-No.2 voltages between 150 and 300 volts           |             |            | e page 75 |
| Plate Dissipation  | 2.7 max     | 2.8 max    |           |
|  |             | -10 211411 | 4015      |
| CHARACTERISTICS:   |             |            |           |
| Plate Supply Voltage                                       | 125         | 125        | volts     |
| Grid-No.2 Supply Voltage                                   |             | 125        | volts     |
| Grid-No.1 Voltage  |             | -1         | volt      |
| Cathode-Bias Resistor                                      | 56          |            | ohms      |
| Amplification Factor                                       | 40          | _          | Omnis     |
| Plate Resistance (Approx.)                                 | 5000        | 100000     | ohms      |
| Transconductance   | 8000        | 5800       | μmhos     |
| Plate Current  | 15          | 12         | ma ma     |
| Grid-No.2 Current  | -           | 4          | ma        |
| Grid-No.1 Voltage (Approx.) for plate current of 10 µa     | -9          | -10        | volts     |
| Otto Front Consider (Esperant) for place desirant of 10 pa | •           |            | 10113     |
| MAXIMUM CIRCUIT VALUES:                                    |             |            |           |
| Grid-No.1-Circuit Resistance:                              |             |            |           |
| For fixed-bias operation                                   | 0.5 max     | 0.25 max   | megohm    |
| For cathode-bias operation                                 | 1 max       | 1 max      | megohm    |
|  | - ******    |            |           |

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6EA8 except for heater ratings; refer to 6EA8 for data.

9EA8

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6U8A except for heater ratings; refer to 6U8A for data.

**9U8A** 

#### POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

10

10AL11

BEAM POWER TUBE— SHARP-CUTOFF PENTODE

Duodecar type identical with type 6AL11 except for heater ratings; refer to 6AL11 for data.

10C8

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

**DUAL TRIODE** 

10**DE7** 

Miniature type identical with type 6DE7 except for heater ratings; refer to 6DE7 for data.

**DUAL TRIODE** 

10DR7

Miniature type identical with type 6DR7 except for heater ratings; refer to 6DR7 for data.

10DX8


HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6DX8 except for heater ratings; refer to 6DX8 for data.

#### **DUAL TRIODE**

10EG7

Glass octal type used as combined vertical-deflection oscillator and vertical-deflection amplifier in television receivers employing series-connected heater strings. Outline 13B, Outlines section. Tube requires octal socket



and may be operated in any position. Heater volts (ac/dc), 9.7; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode). For maximum ratings and characteristics, refer to type 6EW7.

10EM7

**DUAL TRIODE** 

Glass octal type identical with type 6EM7 except for heater ratings; refer to 6EM7 for data.

**DUAL TRIODE** 

10GF7
Novar types identical with types 6GF7 and 6GF7A except for heater ratings; refer to 6GF7 and 6GF7A for data.

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE


Miniature type identical with type 6GN8 except for heater ratings; refer to 6GN8 for data.

10GN8

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6HF8 except for heater ratings; refer to 6HF8 for data.

10HF8



Grid-No.1-Circuit Resistance:

For fixed-bias operation ...

For cathode-bias operation .....

#### HIGH-MU TRIODE— SHARP-CUTOFF TETRODE

Miniature type used in color and black-and-white television receivers employing series-connected heater strings. The triode unit is used as a sync separator, sync clipper, and phase inverter; the tetrode unit is used as a

**10JA8** 

video amplifier. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Heater volts (ac/dc), 10.5; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

| MAXIMUM RATINGS (Design-M Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.1 (Control-Grid) Voltage, Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 1 For grid-No.2 voltages between | Positive-b | ias value . | 3   | ode Unit<br>00 max<br>-<br>0 max<br>1 max | 0 ma<br>5 ma<br>1.5 ma | x volts x volts x volts x volts x volts x watts |
|---|------------|-------------|-----|---|------------------------|---|
| CHARACTERISTICS:  | Triod      | le Unit     | T   | etrode Ur                                 | iit                    |   |
| Plate Voltage   | 135        | 200         | 30  | 135                                       | 200                    | volts   |
| Grid-No.2 Voltage   |            |             | 135 | 135                                       | 135                    | volts   |
| Grid-No.1 Voltage   | -2         | -2          | 0   | -1.5                                      | -1.5                   | volts   |
| Amplification Factor  | 60         | 70          |     | _   | _                      |   |
| Plate Resistance  | 23000      | 17000       |     | 6600                                      | 7000                   | ohms  |
| Transconductance  | 2600       | 4000        |     | 12600                                     | 14000                  | $\mu$ mhos                                      |
| Plate Current   | 2          | 4           | 32• | 17  | 18                     | ma  |
| Grid-No.2 Current   |            | -           | 14. | 4.2                                       | 4                      | ma  |
| Grid-No.1 Voltage (Approx.) for   |            |             |     |   |                        |   |
| plate current of 10 $\mu$ a   | -4.8       | 7           |     | <b>~5</b>                                 | 5                      | volts   |
| MAXIMUM CIRCUIT VALUES:   |            |             |     |   |                        |   |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Triode Unit

0.5 max

1 max

Tetrode Unit


0.25 max megohm

1 max megohm

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

**10JY8** 

Miniature type used in a variety of applications in television receivers. The pentode unit is used as a video amplifier, and the triode unit as a sync separator. Outline 6E, Outlines section. Tube requires miniature nine-



contact socket and may be mounted in any position. Heater volts (ac/dc), 10.5; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when heater is positive with respect to cathode; this value may be 300 volts for the triode unit when heater is negative with respect to cathode, with a maximum peak value of 200 volts).

| Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:                      | Triode Unit 330 max  - 0 max 2 max               | Pentode Unit 330 max volts 330 max volts See curve page 75 0 max volts 5 max watts   |
|--|--|--|
| For grid-No.2 voltages up to 165 volts   | -  | 1.1 max watts  |
| For grid-No.2 voltages between 165 and 330 volts.  | -  | See curve page 75  |
| CHARACTERISTICS: Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µa | 125<br>—<br>68<br>46<br>4400<br>10400<br>15<br>— | 50 200 volts<br>150 150 volts<br>0 — volts<br>— 100 ohms<br>— 55000 ohms<br>— 11000 µmhos<br>60* 24 ma<br>18* 4.8 ma<br>— — 10 volts |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation  | 0.5 max<br>1 max                                 | 0.25 max megohm<br>1 max megohm  |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

77

#### DETECTOR AMPLIFIER

Discontinued type; see chart at end of section for tabulated data.

11AR11

#### SEMIREMOTE-CUTOFF TWIN PENTODE

Duodecar type identical with type 6AR11 except for heater ratings; refer to 6AR11 for data.

DUAL TRIODE

Miniature type identical with type 6CY7 except for heater ratings; refer to 6CY7 for data.

11CY7

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6JE8 except for heater ratings; refer to 6JE8 for data.

11JE8

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6KV8 except for heater ratings; refer to 6KV8 for data.

11KV8

#### DETECTOR AMPLIFIER

Discontinued type; see chart at end of section for tabulated data.

12

#### **POWER PENTODE**

Discontinued type; see chart at end of section for tabulated data.

12A5

#### RECTIFIER—POWER PENTODE


Discontinued type; see chart at end of section for tabulated data.

12A7

## PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

**12A8GT** 



#### **BEAM POWER TUBE**

Miniature type used in the output stage of automobile radio receivers operating from a 12-volt storage battery. Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

12AB5

| Heater-Voltage Range (ac/dc)* Heater Current (Approx.) at 12.6 volts   | 10.0 to 15.9<br>0.2 | volts<br>ampere |
|--|---------------------|-----------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode   | 90 max<br>90 max    | volts<br>volts  |
| Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3 | 0.7 max<br>8<br>8.5 | pf<br>pf<br>pf  |

<sup>•</sup> For longest life, it is recommended that the heater be operated within the voltage range of 11 to 14 volts.


Class A, Amplifier MAXIMUM RATINGS (Design-Center Values):

| Plate Voltage   |       | 315 max | VOILS    |
|---|-------|---------|----------|
| Grid-No.2 (Screen-Grid) Voltage                       |       | 285 max | volts    |
| Plate Dissipation                                     |       | 12 max  | watts    |
| Grid-No.2 Input                                       |       | 2 max   | watts    |
| Bulb Temperature (At hottest point)                   |       | 250 max | •c       |
| TYPICAL OPERATION WITH 12.6 VOLTS ON HEAT             | TER:  |         |          |
| Plate Supply Voltage                                  | 250   | 250     | volts    |
| Grid-No.2 Supply Voltage                              | 200   | 250     | volts    |
| Grid-No.1 (Control-Grid) Voltage                      | _     | -12.5   | volts    |
| Cathode-Bias Resistor                                 | 270   | -       | ohms     |
| Peak AF Grid-No.1 Voltage                             | 10.5  | 12.5    | volts    |
| Zero-Signal Plate Current                             | 33.5  | 45      | ma       |
| Maximum-Signal Plate Current                          | 36    | 47      | ma       |
| Zero-Signal Grid-No.2 Current                         | 1.6   | 4.5     | ma       |
| Maximum-Signal Grid-No.2 Current                      | 3.2   | 7       | ma       |
| Plate Resistance (Approx.)                            | 75000 | 50000   | ohms     |
| Transconductance                                      | 4000  | 4100    | μmhos    |
| Load Resistance                                       | 6000  | 5000    | ohms     |
| Total Harmonic Distortion                             | 8     | 8       | per cent |
| Maximum-Signal Power Output                           | 3.3   | 4.5     | watts    |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: |       |         |          |
| For fixed-bias operation                              |       | 0.1 max | megohm   |
| For cathode-bias operation                            |       | 0.5 max | megohm   |

#### Push-Pull Class AB, Amplifier

MAXIMUM RATINGS: (Same as for single-tube class A1 amplifier)

| TYPICAL OPERATION WITH 12.6 VOLTS ON HEATER (Values are for two tubes): |       |
|---|-------|
| Plate Voltage   | volts |
| Grid-No.2 Voltage   | volts |
| Grid-No.1 Voltage   | volts |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage                                  | volts |
| Zero-Signal Plate Current   | ma    |
| Maximum-Signal Plate Current  | ma    |
| Zero-Signal Grid-No.2 Current   | ma    |
| Maximum-Signal Grid-No.2 Current  | ma    |



| Effective Load Resistance (Plate-to-Plate) | 10000 | ohms     |
|--|-------|----------|
| Total Harmonic Distortion                  | 5     | per cent |
| Maximum-Signal Power Output                | 10    | watts    |

MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

For fixed-bias operation ..... For cathode-bias operation .....

0.1 max megohm 0.5 max megohm

REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

12AC6

PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

12AD6

TWIN DIODE-MEDIUM-MU TRIODE

Discontinued type: see chart at end of section for tabulated data.

12AE6

TWIN DIODE-MEDIUM-MU TRIODE

Renewal type; see chart at end of 12AE6A section for tabulated data.

DUAL TRIODE

Renewal type; see chart at end of section for tabulated data.

**12AE7** 

HALF-WAVE VACUUM RECTIFIER

Miniature type identical with type 6AF3 except for heater ratings; refer to 6AF3 for data.

**12AF3** 

REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

12**A**F6

MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

**12AH7GT** 

TWIN DIODE-HIGH-MU TRIODE

Renewal type; see chart at end of 12AJ6 section for tabulated data.

#### TWIN DIODE

**12AL5** 

Miniature type identical with type 6AL5 except for heater ratings; refer to 6AL5 for data.

12AL8

#### MEDIUM-MU TRIODE— POWER TETRODE

Renewal type; see chart at end of section for tabulated data.

12AL11

#### BEAM POWER TUBE— SHARP-CUTOFF PENTODE

Duodecar type identical with type 6AL11 except for heater ratings; refer to 6AL11 for data.

12AQ5

#### **BEAM POWER TUBE**

Miniature type identical with type 6AQ5A except for heater ratings; refer to 6AQ5A for data.

12AT6


#### TWIN DIODE— HIGH-MU TRIODE

Miniature type identical with type 6AT6 except for heater ratings; refer to 6AT6 for data.

#### HIGH-MU TWIN TRIODE

**12AT7** 


Miniature type used as push-pull cathode-drive amplifier or frequency converter in the FM and television broadcast bands. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be



mounted in any position. Each triode unit is independent of the other except for the common heater. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

| Heater Arrangement:                     | Series | Parallel |        |
|---|--------|----------|--------|
| Heater Voltage (ac/dc)                  | 12.6   | 6.3      | volts  |
| Heater Current                          | 0.15   | 0.3      | ampere |
| Peak Heater-Cathode Voltage:            |        |          |        |
| Heater negative with respect to cathode |        | 90 max   | volts  |
| Heater positive with respect to cathode |        | 90 max   | volts  |
| Direct Interelectrode Capacitances:     |        |          |        |
| Grid-Drive Operation:                   |        |          |        |
| Grid to Plate (Each unit)               |        | 1.5      | pf     |
| Grid to Cathode and Heater (Each unit)  |        | 2.2      | pf     |
| Plate to Cathode and Heater:            |        |          | -      |
| Unit No.1                               |        | 0.5      | pf     |
| Unit No.2                               |        | 0.4      | pf     |

| Cathode to Plate (Each Unit) Cathode to Grid and Heater (Each unit) Plate to Grid and Heater (Each unit) Heater to Cathode (Each unit) | 0.2<br>4.6<br>1.8<br>2.4 | pf<br>pf<br>pf<br>pf |
|--|--------------------------|----------------------|
| Class A, Amplifier (Each Unit)   |                          |                      |
| MAXIMUM RATINGS (Design-Center Values):  |                          |                      |
| Plate Voltage  | 300 max                  | volts                |
| Grid Voltage, Negative-bias value  | —50 max                  | volts                |
| Plate Dissipation  | 2.5 max                  | watts                |
| CHARACTERISTICS:   |                          |                      |
| Plate Supply Voltage   | 250                      | volts                |
| Cathode-Bias Resistor  | 200                      | ohms                 |
| Amplification Factor   | 60                       | VIII.                |
| Plate Resistance (Approx.)   | 10900                    | ohms                 |
| Transconductance   | 5500                     | μmhos                |
| Grid Voltage (Approx.) for plate current of 10 µa5   | -12                      | volts                |
| Plate Current  | 10                       | ma                   |
|  |                          |                      |



#### SHARP-CUTOFF PENTODE


Miniature type identical with type 6AU6A except for heater ratings; refer to 6AU6A for data.

12AU6

## MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.

**12AU7** 



## MEDIUM-MU TWIN TRIODE

Miniature type used as phase inverter or push-pull amplifier in ac/dc radio equipment and in diversified applications such as multivibrators or oscillators in industrial control devices. Also used as combined vertical oscil-

12AU7A
Related types:
7AU7, 9AU7

330 max

1200 max

-275 max

66 max

volts

volts

volts

ma

lator and vertical deflection amplifier, and as horizontal deflection oscillator, in television receivers. This type is also useful in applications critical as to microphonics. Outline 6B, Outlines section. Tubes require miniature nine-contact socket and may be mounted in any position. Each triode unit is independent of the other except for the common heater. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Types 7AU7 and 9AU7 are identical with type 12AU7A except for the heater ratings, as shown below.

| are identical with type 12110/11 except in        | or the     | neater rating                           | 55, as silowi | i ociow. |
|---|------------|---|---------------|----------|
| Heater Voltage (ac/dc):                           | 7AU7       | 9AU7                                    | 12AU7A        |          |
| Series  | 7          | 9.4                                     | 12.6          | volts    |
| Parallel  | 3.5        | 4.7                                     | 6.3           | volts    |
| Heater Current:                                   | • • • •    | ***                                     | 0.0           | , , , ,  |
| Series  | 0.3        | 0.225                                   | 0.15          | ampere   |
| Parallel  | 0.6        | 0.45                                    | 0.3           | ampere   |
| Heater Warm-up Time (Parallel, Average)           | 11         | 11                                      | - U.S         | seconds  |
| Peak Heater-Cathode Voltage:                      | **         |   |               | seconds  |
| Heater negative with respect to cathode           | 200 m      | ax 200 max                              | 200 max       | volts    |
| Heater positive with respect to cathode           | 200 m      |   | 200 max       |          |
| Direct Interelectrode Capacitances (Approx.):     | 200-111    | Unit No.1                               | Unit No.2     | VOICS    |
| Grid to Plate                                     |            | 1.5                                     | 1.5           |          |
| Grid to Cathode and Heater                        |            | 1.6                                     | 1.6           | pf       |
| Plate to Cathode and Heater                       | • • • • •  | 0.5                                     | 0.35          | pf       |
| Trace to Cathode and Heater                       | • • • • •  | 0.5                                     | 0.33          | pf       |
| • The dc component must not exceed 100 volts.     |            |   |               |          |
| Class A. Amplifier (Each Unit                     | Unless     | Otherwise 5                             | Specified)    |          |
| MAXIMUM RATINGS (Design-Maximum Values)           | ١٠.٠٠٠     | • | poomou,       |          |
| Plate Voltage                                     | •          |   | 330 max       | volts    |
| Plate Dissipation:                                |            |   | JJU IIIAA     | VOILS    |
| Each Plate  |            |   | 2.75 max      | watts    |
| Both Plates (Both units operating)                |            |   | 5.5 max       | watts    |
| Cathode Current                                   |            |   | 22 max        |          |
| Cathode Current                                   |            |   | 22 max        | ma       |
| CHARACTERISTICS:                                  |            |   |               |          |
| Plate Voltage                                     |            | 100                                     | 250           | volts    |
| Grid Voltage                                      |            | 0                                       | -8.5          | volts    |
| Amplification Factor                              |            | 19.5                                    | 17            | •        |
| Plate Resistance (Approx.)                        |            | 6250                                    | 7700          | ohms     |
| Transconductance                                  |            | 3100                                    | 2200          | umhos    |
| Plate Current                                     |            | 11.8                                    | 10.5          | ma       |
| Grid Voltage (Approx.) for plate current of 10 µa |            | -                                       | -24           | volts    |
| MAXIMUM CIRCUIT VALUES:                           |            |   |               |          |
| Grid-Circuit Resistance:                          |            |   |               |          |
| For fixed-bias operation                          |            |   | 0.25 max      | mecohm   |
| For cathode-bias operation                        |            |   |               | megohm   |
|   |            |   |               | megomu   |
| Oscillator (Each Unit Unle                        | ss Othe    | erwise Speci                            | fied)         |          |
| For operation in a 525-li                         | ne, 30-fra | ame system                              |               |          |
|   | •          | Vertical-                               | Horizontal-   |          |
|   |            | Deflection                              | Deflection    |          |
| MAXIMUM RATINGS (Design-Maximum Values)           | :          | Oscillator                              | Oscillator    |          |
| DC Plate Voltage                                  |            | 330 max                                 | 330 max       | volts    |
| Peak Negative-Pulse Grid Voltage                  |            | -440 max                                | -660 max      | volts    |
| Peak Cathode Current                              |            | 66 max                                  | 330 max       | ma       |
| Average Cathode Current                           |            | 22 max                                  | 22 max        | ma       |
| Plate Dissipation:                                |            |   |               |          |
| Each Plate  |            | 2.75 max                                | 2.75 max      | watts    |
| Both Plates (Both units operating)                |            | 5.5 max                                 | 5.5 max       | watts    |
| •   | <b></b>    | ···                                     | un            |          |
| MAXIMUM CIRCUIT VALUE:                            |            |   |               |          |
| Grid-Circuit Resistance                           |            | 2.2 max                                 | 2.2 max :     | megohms  |
| 10 10 10 10 10 10 10 10 10 10 10 10 10 1          |            |   |               | •        |
| Vertical-Deflection Amplifier (Each               |            |   | wise Specifi  | ed)      |
| For operation in a 525-li                         | ne, 30-fra | ime system                              |               |          |

MAXIMUM RATINGS (Design-Maximum Values):

DC Plate Voltage .....

Peak Positive-Pulse Plate Voltage# .....

Peak Negative-Pulse Grid Voltage .....


Peak Cathode Current .....

For cathode-bias operation ......

2.2 max megohms

| Average Cathode Current                          | 22 | max        | ma             |
|--|----|------------|----------------|
| Each Plate Both Plates (Both units operating)    |    | max<br>max | watts<br>watts |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance: |    |            |                |

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.



#### BEAM POWER TUBE

Glass octal type identical with type 6AV5GA except for heater ratings; 12AV5GA refer to 6AV5GA for data.

#### TWIN DIODE— HIGH-MU TRIODE

Miniature type identical with type 6AV6 except for heater ratings; refer to 6AV6 for data.

12AV6

#### MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

12**AV**7



#### SHARP-CUTOFF PENTODE

Miniature type used as an rf or if amplifier up to 400 megacycles in compact ac/dc FM receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket. Heater volts (ac/dc), 12.6; amperes, 0.15. Ex-

12AW6

cept for heater ratings and terminal connections, this type is identical with miniature type 6AG5.

**12AX3** 

#### HALF-WAVE VACUUM RECTIFIER

Duodecar type identical with type 6AX3 except for heater ratings; refer to 6AX3 for data.

#### HALF-WAVE VACUUM RECTIFIER

12AX4GTA

12AX4GT Discontinued types; see chart at end of section for tabulated data.

#### HALF-WAVE VACUUM RECTIFIER

12AX4GTB Miniature type identical with type 6AX4GTB except for heater ratings; refer to 6AX4GTB for data.

12**AX**7


#### HIGH-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

#### HIGH-MU TWIN TRIODE

12AX7A

Miniature type used as phase inverter or twin resistance-coupled amplifier in radio equipment. This type has controlled hum and noise characteristics and is used in high-fidelity audio-amplifier applications. Outline



6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. Each triode unit is independent of the other except for common heater. For characteristics and curves, refer to type 6AV6. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

| `   |           |           |        |
|---|-----------|-----------|--------|
| Heater Arrangement:                           | Series    | Parallel  |        |
| Heater Voltage (ac/dc)                        | 12.6      | 6.3       | volts  |
| Heater Current                                | 0.15      | 0.3       | ampere |
| Peak Heater-Cathode Voltage:                  |           |           | •      |
| Heater negative with respect to cathode       |           | 200 max   | volts  |
| Heater positive with respect to cathode       |           | 200 max   | volts  |
| Direct Interelectrode Capacitances (Approx.): | Unit No.1 | Unit No.2 |        |
| Grid to Plate (Each unit)                     | 1.7       | 1.7       | pf     |
| Grid to Cathode and Heater (Each unit)        | 1.6       | 1.6       | pf     |
| Plate to Cathode and Heater                   | 0.46      | 0.34      | pf     |
| The do component must not avoid 100 males.    |           |           |        |

The dc component must not exceed 100 volts:

Class A, Amplifier (Each Unit) MAXIMUM RATINGS (Design-Maximum Values):


| Plate Voltage Plate Dissipation Grid Voltage: | 330 max<br>1.2 max | volts<br>watts |
|---|--------------------|----------------|
| Negative-bias value Positive-bias value       | -55 max<br>0 max   | volts<br>volts |

• Measured in "true rms" units under the following conditions: Heater voltage (parallel connection), 6.3 volts ac; center tap of heater transformer grounded; plate supply voltage, 250 volts dc; plate load resistor, 100000 ohms; cathode resistor, 2700 ohms bypassed by 100-µf capacitor; grid resistor, 0 ohms; and amplifier covering frequency range between 25 and 10000 cps.

#### HALF-WAVE VACUUM RECTIFIER

Novar types identical with types 6AY3 and 6AY3A except for heater ratings; refer to 6AY3 and 6AY3A for data.

12AY3 12AY3A



Heater Arrangement:

#### **MEDIUM-MU TWIN TRIODE**

Miniature type used in the first stages of high-gain audio-frequency amplifiers where reduction of microphonics, leakage noise, and hum are primary considerations. Outline 6B, Outlines section. Tube requires miniature nine-

**12AY7** 

Parallel

contact socket and may be mounted in any position. Each triode unit is independent of the other except for the common heater. Use of the 12.6-volt connection with an ac heater supply is not recommended for applications involving low hum. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

Sarian

| ricater Arrangement.                                  | Series                                  | Paranei |        |
|---|---|---------|--------|
| Heater Voltage (ac/dc)                                | 12.6                                    | 6.3     | volts  |
| Heater Current  | 0.15                                    | 0.3     | ampere |
| Peak Heater-Cathode Voltage:                          |   |         |        |
| Heater negative with respect to cathode               |   | 90 max  | volts  |
| Heater positive with respect to cathode               |   | 90 max  | volts  |
| Amplification Factor (Each unit)*                     |   | 44      | 10113  |
| Plate Resistance (Each unit, approx.)*                | • | 25000   | ohms   |
| Transconductance*                                     |   | 1750    |        |
| Transconductance                                      |   | 1730    | μmhos  |
| * For plate volts, 250; grid volts, -4; plate ma., 3. |   |         |        |
| Class A, Amplifier (Eac                               | h Unit)                                 |         |        |
| MAXIMUM RATINGS (Design-Center Values):               | •                                       |         |        |
| Plate Voltage   |   | 300 max | volts  |
| Grid Voltage:   |   | Jou mux | 10103  |
| Negative bias value                                   |   | -50 max | volts  |
| Positive bias value                                   |   | 0 max   | volts  |
| Plate Dissipation                                     |   |         |        |
| Plate Dissipation                                     |   | 1.5 max | watts  |
| Cathode Current                                       | • • • • • • • • • •                     | 10 max  | ma     |
|   |   |         |        |

## HIGH-MU TWIN TRIODE


Discontinued type; see chart at end of section for tabulated data.

12AZ7

#### HIGH-MU TWIN TRIODE

# **12AZ7A**

Miniature type used in direct-coupled cathode-drive rf amplifier circuits of vhf television tuners. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For char-



acteristics, class A1 amplifier, refer to miniature type 12AT7.

| Heater Voltage (ac/dc):                                      |          |          |         |
|--|----------|----------|---------|
| Series   |          | 12.6     | volts   |
| Parallel   |          | 6.3      | volts   |
| Heater Current:  |          |          |         |
| Series   |          | 0.225    | ampere  |
| Parallel   |          | 0.45     | ampere  |
| Heater Warm-up Time (Average)                                |          | 11       | seconds |
| Peak Heater-Cathode Voltage:                                 |          |          |         |
| Heater negative with respect to cathode                      |          | 200 max  | volts   |
| Heater positive with respect to cathode                      |          | 200°max  | volts   |
|  | Without  | With     |         |
|  | External | External |         |
| Direct Interelectrode Capacitance (Approx.):                 | Shield   | Shield*  |         |
| Grid to Plate (Each unit)                                    | 2        | 1.9      | pf      |
| Grid to Cathode and Heater (Each unit)                       | 2.6      | 2.8      | pf      |
| Plate to Cathode and Heater:                                 |          |          |         |
| Unit No.1  | 0.44     | 1.4      | pf      |
| Unit No.2  | 0.36     | 1.6      | pf      |
| * The dc component must not exceed 100 volts.                |          |          |         |
| With external shield connected to cathode of unit under te   | et       |          |         |
| With external sinesa connected to eathour of ant under to    | .st.     |          |         |
| Class A, Amplifier (Eac                                      | h Unit)  |          |         |
| MAXIMUM RATINGS (Design-Maximum Values):                     |          |          | _       |
| Plate Voltage  |          | 330 max  | volts   |
| Grid Voltage, Negative-bias value                            |          | —55 max  | volts   |
| Plate Dissipation  |          | 2.5 max  | watts   |
| MAXIMUM CIRCUIT VALUES (Each Unit): Grid-Circuit Resistance: |          |          |         |
| Oliu-Circuit ixcolotalice.                                   |          |          |         |

#### LOW-MU TRIODE

# 12B4A

For fixed-bias operation ...

For cathode-bias operation ......

Miniature type having high perveance used as vertical deflection amplifier in television receivers. This type has a controlled heater warm-up time for use in series-connected heater strings. Outline 6E, Outlines section.



0.25 max megohm

1 max megohm

Tube requires miniature nine-contact socket and may be mounted in any position. Heater volts (ac/dc), 12.6 (series), 6.3 (parallel); amperes, 0.3 (series), 0.6 (parallel); warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Class A, Amplifier

| MAXIMUM RATINGS (Design-Center Values): |         |       |
|---|---------|-------|
| Plate Voltage                           | 550 max | volts |
| Grid Voltage, Negative-bias value       | —50 max | volts |
| Plate Dissipation                       | 5.5 max | watts |

| CHARACTERISTICS:   |                                  |                |
|--|----------------------------------|----------------|
| Plate Voltage  | 150                              | volts          |
| Grid Voltage Amplification Factor  | 17.5<br>6.5                      | volts          |
| Plate Resistance (Approx.)   | 1030                             | ohms           |
| Transconductance   |                                  | umhos          |
| Plate Current  | 34<br>32                         | ma<br>volts    |
| Plate Current for grid voltage of -23 volts  | 9.6                              | ma             |
| MAXIMUM CIRCUIT VALUES:  |                                  |                |
| Grid-Circuit Resistance:   |                                  |                |
| For fixed-bias operation  For cathode-bias operation   | 0.47 max meg                     | gohm           |
| For cathode-bias operation   | 2.2 max meg                      | gonns          |
| Vertical Deflection Amplifier  |                                  |                |
| For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Center Values):   |                                  |                |
| DC Plate Voltage   | 550 max                          | volts          |
| Peak Positive-Pulse Plate Voltage# (Absolute Maximum)  | 1000†max                         | volts<br>volts |
| Peak Negative-Pulse Grid Voltage   | -250 max<br>105 max              | ma             |
| Average Cathode Current  | 30 max                           | ma             |
| Plate Dissipation  | 5.5 max                          | watts          |
| MAXIMUM CIRCUIT VALUE:   |                                  |                |
| Grid-Circuit Resistance:  For cathode-bias operation   | 2.2 max meg                      | ohms           |
|  | _                                |                |
| # The duration of the voltage pulse must not exceed 15 per cent of one In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is   | 2.5 milliseconds.                | cycle.         |
| † Under no circumstances should this absolute value be exceeded.   |                                  |                |
|  |                                  |                |
| TRIODE-PENTODE   |                                  | _              |
|  | 190001                           |                |
| Discontinued type: see chart at end  |                                  | •              |
| Discontinued type; see chart at end of section for tabulated data.   | 12B8G1                           |                |
|  | 120001                           |                |
| of section for tabulated data.   | 120001                           |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  |                                  |                |
| of section for tabulated data.   | 12BA6                            |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type  |                                  |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer  |                                  | İ              |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer  |                                  | İ              |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER   | 12BA6                            |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  |                                  |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of  | 12BA6                            |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  | 12BA6                            |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE   | 12BA6<br>12BA7                   |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  | 12BA6                            |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE  Renewal type; see chart at end of  | 12BA6<br>12BA7                   |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE  Renewal type; see chart at end of section for tabulated data.  | 12BA6<br>12BA7                   |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE  Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER  | 12BA6<br>12BA7                   |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE  Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER  Duodecar type identical with type   | 12BA6<br>12BA7<br>12BD6          |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE  Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER  Duodecar type identical with type 6BE3 except for heater ratings; refer                                       | 12BA6<br>12BA7                   |                |
| of section for tabulated data.  REMOTE-CUTOFF PENTODE  Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER  Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE  Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER  Duodecar type identical with type   | 12BA6<br>12BA7<br>12BD6          |                |
| REMOTE-CUTOFF PENTODE Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER Duodecar type identical with type 6BE3 except for heater ratings; refer to 6BE3 for data.   | 12BA6<br>12BA7<br>12BD6          |                |
| REMOTE-CUTOFF PENTODE Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER Duodecar type identical with type 6BE3 except for heater ratings; refer to 6BE3 for data.  PENTAGRID CONVERTER                                    | 12BA6<br>12BA7<br>12BD6<br>12BE3 |                |
| REMOTE-CUTOFF PENTODE Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER Duodecar type identical with type 6BE3 except for heater ratings; refer to 6BE3 for data.  PENTAGRID CONVERTER Miniature type identical with type | 12BA6<br>12BA7<br>12BD6<br>12BE3 |                |
| REMOTE-CUTOFF PENTODE Miniature type identical with type 6BA6 except for heater ratings; refer to 6BA6 for data.  PENTAGRID CONVERTER Renewal type; see chart at end of section for tabulated data.  REMOTE-CUTOFF PENTODE Renewal type; see chart at end of section for tabulated data.  HALF-WAVE VACUUM RECTIFIER Duodecar type identical with type 6BE3 except for heater ratings; refer to 6BE3 for data.  PENTAGRID CONVERTER                                    | 12BA6<br>12BA7<br>12BD6          |                |

# 12BF6

#### TWIN DIODE— MEDIUM-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

# 12BH7

#### MEDIUM-MU TWIN TRIODE


Discontinued type; see chart at end of section for tabulated data.

## MEDIUM-MU TWIN TRIODE

# **12BH7A**

Grid-Circuit Resistance: For fixed-bias operation

Miniature type used as combined vertical deflection amplifier and vertical KT2(3) oscillator, and as horizontal deflection oscillator, in television receivers. This type has a controlled heater warm-up time for use in series-connected heater



0.25 max megohm

1.0 max megohm

strings. Tube is also used in other applications including phase-inverter circuits and multivibrator circuits. Outline 6E, Outlines section. This tube requires miniature nine-contact socket and may be mounted in any position. Each triode unit is independent of the other except for the common heater.

| Heater Arrangement:                           | Series    | Parallel  |         |
|---|-----------|-----------|---------|
| Heater Voltage (ac/dc)                        | 12.6      | 6.3       | volts   |
| Heater Current                                | 0.3       | 0.6       | ampere  |
| Heater Warm-up Time (Average)                 | ·         | 11        | seconds |
| Peak Heater-Cathode Voltage:                  |           |           |         |
| Heater negative with respect to cathode       |           | 200 max   | volts   |
| Heater positive with respect to cathode       |           | 200 max   | volts   |
| Direct Interelectrode Capacitances (Approx.): | Unit No.1 | Unit No.2 |         |
| Grid to Plate                                 | 2.6       | 2.6       | pf      |
| Grid to Cathode and Heater                    | 3.2       | 3.2       | pf      |
| Plate to Cathode and Heater                   | 0.5       | 0.4       | pf      |
| Plate of Unit No.1 to Plate of Unit No.2      | 0.        | 8         | pf      |

| • The dc component must not exceed 100 volts.          |          |            |
|--|----------|------------|
| Class A, Amplifier (Each Unit)                         |          |            |
| MAXIMUM RATINGS (Design-Center Values):                |          |            |
| Plate Voltage  | 300 max  | volts      |
| Grid Voltage:  |          |            |
| Negative-bias value                                    | -50 max  | volts      |
| Positive-bias value                                    | 0 max    | volts      |
| Cathode Current  | 20 max   | ma         |
| Plate Dissipation:                                     | 20 Illan | IIIa       |
| Each Plate   | 25       |            |
|  | 3.5 max  | watts      |
| Both plates (Both units operating)                     | 7 max    | watts      |
| CHARACTERISTICS:                                       |          |            |
| Plate Voltage  | 250      | volts      |
|  | -10.5    | volts      |
| Grid Voltage   |          | voits      |
| Amplification Factor                                   | 16.5     | _          |
| Plate Resistance (Approx.)                             | 5300     | ohms       |
| Transconductance                                       | 3100     | $\mu$ mhos |
| Grid Voltage (Approx.) for plate current of 50 $\mu a$ | 23       | volts      |
| Plate Current  | 11.5     | ma         |
| Plate Current for grid voltage of -14 volts            | 4        | ma         |
| MAXIMUM CIRCUIT VALUES:                                |          |            |

For cathode-bias operation .....

Horizontal

70 max

20 max

3.5 max

7 max

ma

ma

watts

watts

#### Oscillator (Each Unit)

For operation in a 525-line, 30-frame system

Vertical

|   | Deflection  | Deflection |         |
|---|-------------|------------|---------|
| MAXIMUM RATINGS (Design-Center Values):               | Oscillator  | Oscillator |         |
| DC Plate Voltage                                      | 450 max     | 450 max    | volts   |
| Peak Negative-Pulse Grid Voltage                      | -400 max    | -600 max   | volts   |
| Peak Cathode Current                                  | 70 max      | 300 max    | ma      |
| Average Cathode Current                               | 20 max      | 20 max     | ma      |
| Plate Dissipation:                                    | 20 111111   | 20 111211  |         |
| Each Plate  | 3.5 max     | 3.5 max    | watts   |
| Both Plates (Both units operating)                    | 7 max       | 7 max      | watts   |
| woll rate (woll will operating)                       |             |            |         |
| MAXIMUM CIRCUIT VALUES:                               |             |            |         |
| Grid-Circuit Resistance                               | 2.2 max     | 2.2 max    | megohms |
| Vertical Deflection Amplifier                         | (Each Unit) |            |         |
| •   | •           |            |         |
| For operation in a 525-line, 30-f                     | rame system |            |         |
| MAXIMUM RATINGS (Design-Center Values):               |             |            |         |
| DC Plate Voltage                                      |             | 450 max    | volts   |
| Peak Positive-Pulse Plate Voltage# (Absolute maximum) |             | 1500*max   | volts   |
| Peak Negative-Pulse Grid Voltage                      |             | -250 max   | volts   |
|   |             |            |         |

#### MAXIMUM CIRCUIT VALUE:

Plate Dissipation: Each Plate .

Grid-Circuit Resistance: For cathode-bias operation ..... 2.2 max megohms


# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

\* Under no circumstances should this absolute value be exceeded.

Peak Cathode Current .....

Average Cathode Current .....

Both Plates (Both units operating) .....



#### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

12BK5

12BL6

#### REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

/12CU6

#### **BEAM POWER TUBE**

12BQ6GTB Glass octal type identical with type 6BO6GTB/6CU6 except for heater ratings; refer to 6BO6GTB/6CU6 for data.

**12BR7** 

#### TWIN DIODE-HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

12BS3 **12BS3A** 

#### HALF-WAVE VACUUM RECTIFIER

Novar types identical with types 6BS3 and 6BS3A except for heater ratings; refer to 6BS3 and 6BS3A for data

#### HALF-WAVE VACUUM RECTIFIER

12BT3

Duodecar type used as damper tube in horizontal-deflection circuits of television receivers. Outline 8C, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted in any position. Heater volts (ac/dc), 12.6; amperes, 0.45.



21

volts

Damper Service

For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values):

| Peak Inverse Plate Voltage#             | 3300 max | volts |
|---|----------|-------|
| Peak Plate Current                      | 1000 max | ma    |
| DC Plate Current                        | 165 max  | ma    |
| Plate Dissipation                       | 5.3 max  | watts |
| Peak Heater-Cathode Voltage:            |          |       |
| Heater negative with respect to cathode | 3300°max | volts |
| Heater positive with respect to cathode | 300 max  | volts |

CHARACTERISTICS, Instantaneous Value: Tube Voltage Drop for plate current of 250 max ...

# The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 1 micro-

- seconds. • The dc component must not exceed 600 volts.
  - The dc component must not exceed 100 volts.

12BV7

#### SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

#### **FULL-WAVE VACUUM RECTIFIER**


Miniature type identical with type 6BW4 except for heater ratings; refer to 6BW4 for data.

12BW4

#### SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

**12BY7** 




## SHARP-CUTOFF PENTODE

Miniature type used as video amplifier in television receivers. This type has a controlled heater warm-up time for use in series-connected heater strings. Outline 6E, Outlines section. Tubes require miniature nine-contact socket and may be mounted in any position.

**12BY7A** 

| Heater Arrangement:                                 | Series | Parallel  |         |
|---|--------|-----------|---------|
| Heater Voltage (ac/dc)                              | 12.6   | 6.3       | volts   |
| Heater Current                                      | 0,3    | 0.6       | ampere  |
| Heater Warm-up Time (Average)                       | _      | 11        | seconds |
| Peak Heater-Cathode Voltage:                        |        |           |         |
| Heater negative with respect to cathode             |        | 200 max   | volts   |
| Heater positive with respect to cathode             |        | 200° max  | volts   |
| Direct Interelectrode Capacitances:                 |        |           |         |
| Grid No.1 to Plate                                  |        | 0.063     | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3  |        |           | • -     |
| and Internal Shield                                 |        | 10.2      | pf      |
| Plate to Cathode, Heater, Grid No.2, and Internal   |        | 3.5       | pf      |
| * The dc component must not exceed 100 volts.       |        |           | -       |
| MAXIMUM RATINGS (Design-Maximum Values):            |        |           |         |
| Plate Supply Voltage                                |        | 330 max   | volts   |
| Grid-No.3 (Suppressor-Grid) Voltage, Positive value |        | 0 max     | volts   |
| Grid-No.2 (Screen-Grid) Voltage                     |        | 190 max   | volts   |
| Grid-No.1 (Control-Grid) Voltage                    |        | 170 Illax | VOICS   |
| Negative-bias value                                 |        | -55 max   | volts   |
| Positive-bias value                                 |        | 0 max     | volts   |
| A COMMITTO-CHAS TRIME                               | •••••  | U IIIAA   | VOILS   |



| Grid-No.2 Input   | 1.2 max  | watts  |
|---|----------|--------|
| Plate Dissipation   | 6.5 max  | watts  |
| CHARACTERISTICS:  |          |        |
| Plate Supply Voltage  | 250      | volts  |
| Grid No.3 Conn  |          |        |
| Grid-No.2 Supply Voltage                                    | 180      | volts  |
| Cathode-Bias Resistor                                       | 100      | ohms   |
| Plate Resistance (Approx.)                                  | 93000    | ohms   |
| Transconductance  | 11000    | μmhos  |
| Plate Current   | 26       | ma     |
| Grid-No.2 Current   | 5.75     | ma     |
| Grid-No.1 Voltage (Approx.) for plate current of 20 $\mu$ a | -11.6    | volts  |
| MAXIMUM CIRCUIT VALUES:                                     |          |        |
| Grid-No.1-Circuit Resistance:                               |          |        |
| For fixed-bias operation                                    | 0.25 max | megohm |
| For cathode-bias operation                                  |          | megohm |

## SEMIREMOTE-CUTOFF PENTODE

12BZ6

Miniature type identical with type 6BZ6 except for heater ratings; refer to 6BZ6 for data.

#### HIGH-MU TWIN TRIODE

12BZ7

Miniature type used in sync-separator and sync-amplifier circuits of television receivers. This tube is also used in clipping circuits and in general-organizations. Outline 6E, Outlines section. Tube re-

5 max megohms

quires miniature nine-contact socket and may be mounted in any position. Heater volts (ac/dc), 12.6 (series), 6.3 (parallel); amperes, 0.3 (series), 0.6 (parallel); peak heater-cathode volts, 180.

Class A Amplifier (Each Unit)

| Class A Ampinici (Lacii Cilit)          |         |       |  |  |  |  |  |
|---|---------|-------|--|--|--|--|--|
| MAXIMUM RATINGS (Design-Center Values): |         |       |  |  |  |  |  |
| Plate Voltage                           | 300 max | volts |  |  |  |  |  |
| Grid Voltage:                           |         |       |  |  |  |  |  |
| Negative-bias value                     | -50 max | volts |  |  |  |  |  |
| Positive-bias value                     | 0 max   | volts |  |  |  |  |  |
| Plate Dissipation                       | 1.5 max | watts |  |  |  |  |  |
| CHARACTERISTICS:                        |         |       |  |  |  |  |  |
| Plate Voltage                           | 250     | volts |  |  |  |  |  |
| Grid Voltage                            | 2       | volts |  |  |  |  |  |
| Amplification Factor                    | 100     |       |  |  |  |  |  |
| Plate Resistance (Approx.)              | 31800   | ohms  |  |  |  |  |  |
| Transconductance                        | 3200    | umhos |  |  |  |  |  |
| Plate Current                           | 2.5     | ma    |  |  |  |  |  |
| MAXIMUM CIRCUIT VALUE.                  |         |       |  |  |  |  |  |

Grid-Circuit Resistance:

For contact-potential-bias operation .....

# TWIN DIODE— SEMIREMOTE-CUTOFF PENTODE Discontinued type: see chart at end

Discontinued type; see chart at end of section for tabulated data.

12C8

#### **BEAM POWER TUBE**

Miniature type identical with type 6CA5 except for heater ratings; refer to 6CA5 for data.

12CA5

#### **REMOTE-CUTOFF PENTODE**

Renewal type; see chart at end of section for tabulated data.

12CN5

# DIODE--REMOTE-CUTOFF PENTODE

Miniature type identical with type 6CR6 except for heater ratings; refer to 6CR6 for data.

12CR6

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

**12CT8** 

#### BEAM POWER TUBE

Miniature type identical with type 6CU5 except for heater ratings; refer to 6CU5 for data.

12CU5/ 12C5

Refer to type 12BQ6GTB/12CU6.

12CU6

#### REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

12CX6



#### HALF-WAVE VACUUM RECTIFIER

Glass octal type used as damper diode in horizontal-deflection circuits of television receivers employing seriesconnected heater strings. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any

12D4

position. Socket terminals 1, 2, 4, and 6 should not be used as tie points. This type

may be supplied with pin 1 omitted. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 12.6; amperes, 0.6; warm-up time (average), 11 seconds.

#### **Damper Service**

| For | operation | in a 525-line, | 30-frame system |
|-----|-----------|----------------|-----------------|
|     |           |                |                 |

| Peak Inverse Plate Voltage#   | 4400 max | volts          |
|---|----------|----------------|
| Peak Plate Current  | 900 max  | ma             |
| DC Plate Current  | 155 max  | ma             |
| Plate Dissipation   | 5.5 max  | watts          |
| Heater negative with respect to cathode#  Heater positive with respect to cathode |          | volts<br>volts |

<sup>#</sup> The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

#### **BEAM POWER TUBE**

12DB5

Miniature type identical with type 6DB5 except for heater ratings; refer to 6DB5 for data.

**12DE8** 

#### DIODE— REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

12DK6

#### SHARP-CUTOFF PENTODE

Miniature type identical with type 6DK6 except for heater ratings; refer to 6DK6 for data.

12DK7

# TWIN DIODE—POWER TETRODE

Renewal type; see chart at end of section for tabulated data.

12DL8

#### TWIN DIODE— POWER TETRODE

Renewal type; see chart at end of section for tabulated data.

12DM4

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

A The dc component must not exceed 900 volts.

<sup>•</sup> The dc component must not exceed 100 volts.

#### HALF-WAVE VACUUM RECTIFIER

Glass octal type identical with type 6DM4A except for heater ratings; refer to 6DM4A for data.

**12DM4A** 

#### **BEAM POWER TUBE**

Glass octal types identical with type 6DQ6A and type 6DQ6B except for heater ratings; refer to 6DO6A and 6DO6B for data.

12DQ6A 12DQ6B

#### POWER PENTODE

Renewal type; see chart at end of section for tabulated data.

12DQ7

#### TWIN DIODE-**POWER TETRODE**

Renewal type; see chart at end of 12DS7 section for tabulated data.

#### TWIN DIODE— **POWER TETRODE**

Discontinued type; see chart at end of section for tabulated data.

12**DS7A** 

## **BEAM POWER TUBE**

Miniature type identical with type 6DT5 except for heater ratings: refer to 6DT5 for data.

12DT5

## HIGH-MU TWIN TRIODE

Miniature type identical with type 6DT8 except for heater ratings: refer to 6DT8 for data.

12DT8

#### TWIN DIODE-**POWER TETRODE**

Renewal type; see chart at end of section for tabulated data.

**12DU7** 

## TWIN DIODE-POWER TETRODE


Renewal type; see chart at end of section for tabulated data.

12DV8

### DUAL TRIODE

## 12DW7

Miniature type containing high-mu and medium-mu triodes; used as \*72(3) amplifier and phase inverter in audio equipment. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be operated in



any position. Heater volts (ac/dc), 12.6 (series), 6.3 (parallel); amperes, 0.15 (series), 0.3 (parallel); peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Cla  | ss A.         | Amplifier       |           |           |            |
|--|---------------|-----------------|-----------|-----------|------------|
| MAXIMUM RATINGS (Design-Maximu                   | ım Val        | lues):          | Unit No.1 | Unit No.2 |            |
| Plate Voltage                                    | • • • • • • • | · · · · · · · · | 330 max   | 330 max   | volts      |
| Negative-bias value                              |               |                 | 55 max    |           | volts      |
| Positive-bias value                              |               |                 | 0 max     |           | volts      |
| Cathode Current                                  |               |                 |           | 22 max    | ma         |
| Plate Dissipation                                |               |                 | 1.2 max   | 3.3 max   | watts      |
| CHARACTERISTICS:                                 | Uni           | t No.1          | Unit      | No.2      |            |
| Plate Voltage                                    | 100           | 250             | 100       | 250       | volts      |
| Grid Voltage                                     | 1             | 2               | 0         | 8.5       | volts      |
| Amplification Factor                             | 100           | 100             | 20        | 17        |            |
| Plate Resistance (Approx.)                       | 80000         | 62500           | 6500      | 7700      | ohms       |
| Transconductance                                 | 1250          | 1600            | 3100      | 2200      | $\mu$ mhos |
| Plate Current                                    | 0.5           | 1.2             | 11.8      | 10.5      | ma         |
| of 10 μa   |               | -               | _         | -24       | volts      |
| MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance: |               |                 | Unit No.1 | Unit No.2 |            |
| For fixed-bias operation                         |               |                 | 0.25 max  | 0.25 max  | megohm     |
| For cathode-bias operation                       |               |                 | 1 max     | 1 max     | megohm     |

# 12DY8


#### MEDIUM-MU TRIODE— REMOTE-CUTOFF TETRODE

Renewal type; see chart at end of section for tabulated data.

## REMOTE-CUTOFF PENTODE

12DZ6


Miniature type used as rf and if amplifier in low B+ voltage automobile radio receivers operating directly from 12-volt storage-battery systems. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.



| Heater-Voltage Range (ac/dc).                           | 10.0 to 15.9 | volts  |
|---|--------------|--------|
| Heater Current (Approx.) at 12.6 volts                  | 0.19         | ampere |
| Peak Heater-Cathode Voltage:                            |              | •      |
| Heater negative with respect to cathode                 | 16 max       | voits  |
| Heater positive with respect to cathode                 | 16 max       | volts  |
| Direct Interelectrode Capacitances:                     |              |        |
| Grid No.1 to Plate                                      | 0.05 max     | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and |              | -      |
| Internal Shield   | 9.5          | рf     |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and     |              |        |
| Internal Shield   | 4            | pf     |
|   |              |        |

For longest life, it is recommended that the heater be operated within the voltage range of 11 to 14 volts.

| MAXIMUM RATINGS (Design-Maximum Values):                           |            |            |
|--|------------|------------|
| Plate Voltage  | 16 max     | volts      |
| Grid-No.2 (Screen-Grid) Voltage                                    | 16 max     | volts      |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value              | 0 max      | volts      |
| CHARACTERISTICS WITH 12.6 VOLTS ON HEATER:                         |            |            |
| Plate Voltage  | 12.6       | volts      |
| Grid No.3 Connected  | to cathode | at socket  |
| Grid-No.2 Voltage  | 12.6       | volts      |
| Grid-No.1 Supply Voltage   | 0          | volts      |
| Grid-No.1 Resistor (Bypassed)                                      | 10         | megohms    |
| Grid-No.3 Resistor (Bypassed)                                      | 10         | megohms    |
| Plate Resistance (Approx.)   | 25000      | ohms       |
| Transconductance   | 3800       | $\mu$ mhos |
| Grids No.1 and No.3 Supply Voltage (Approx.) for transconductance, |            |            |
| grid No.1 to plate, of 10 µmhos                                    | -10        | volts      |
| Plate Current  | 4.5        | ma         |
| Grid-No.2 Current  | 2.2        | ma         |
| MAXIMUM CIRCUIT VALUES:  |            |            |
| Grid-No.1-Circuit Resistance                                       | 10 max     | megohms    |
| Grid-No.3-Circuit Resistance                                       | 10 max     | megohms    |



## REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

12EA6

## MEDIUM-MU TRIODE— SEMIREMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

12EC8

#### BEAM POWER TUBE

## 12ED5

Miniature type used as audio-output amplifier in radio and television receivers employing series-connected heater strings. Outline 5D, Outlines section. Tube requires miniature sevencontact socket and may be mounted in



any position. Heater volts (ac/dc), 12.6; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 300 (heater negative with respect to cathode, dc component must not exceed 200 volts), 200 (heater positive with respect to cathode, dc component must not exceed 100 volts).

| Class A, Amplifie                                     |       |          |          |
|---|-------|----------|----------|
| MAXIMUM RATINGS (Design-Maximum Values):              |       |          |          |
| Plate Voltage   |       | 150 max  | volts    |
| Grid-No.2 (Screen-Grid) Voltage                       |       | 150 max  | volts    |
| Grid-No.2 Input                                       |       | 1.5 max  | watts    |
| Plate Dissipation                                     |       | 6.25 max | watts    |
| TYPICAL OPERATION:                                    |       |          |          |
| Plate Voltage   | 110   | 125      | volts    |
| Grid-No.2 Voltage                                     | 110   | 125      | volts    |
| Grid-No.1 (Control-Grid) Voltage                      | -4    | 4,5      | volts    |
| Peak AF Grid-No.1 Voltage                             | 4     | 4.5      | volts    |
| Zero-Signal Plate Current                             | 32    | 37       | ma       |
| Maximum-Signal Plate Current                          | 31    | 36       | ma       |
| Zero-Signal Grid-No.2 Current                         | 4     | 7        | ma       |
| Maximum-Signal Grid-No.2 Current                      | 8     | 11       | ma       |
| Plate Resistance (Approx.)                            | 14000 | 14000    | ohms     |
| Transconductance                                      | 8100  | 8500     | µmhos    |
| Load Resistance                                       | 4500  | 4500     | ohms     |
| Total Harmonic Distortion                             | 5     | 5        | per cent |
| Maximum-Signal Power Output                           | 1.1   | 1.5      | watts    |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: |       |          |          |
| For fixed-bias operation                              |       | 0.1 max  | megohm   |
| For cathode-bias operation                            |       | 0.5 max  | megohm   |

# 12EG6

## PENTAGRID AMPLIFIER

Renewal type; see chart at end of section for tabulated data.

# 12EH5

## **POWER PENTODE**

Miniature type identical with type 6EH5 except for heater ratings; refer to 6EH5 for data.

# 12EK6

## REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

# 12EL6

#### TWIN DIODE-HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

| ומ | an | E | PΩ | WER | <b>TETR</b> | ODE |
|----|----|---|----|-----|-------------|-----|
|    |    |   |    |     |             |     |

Discontinued type; see chart at end of section for tabulated data.

12EM6

#### BEAM POWER TUBE

Renewal type; see chart at end of section for tabulated data.

12EN6

#### DIODE-**REMOTE-CUTOFF PENTODE**

Miniature type identical with type 6EQ7 except for heater ratings: refer to 6EQ7 for data.

12EQ7

#### HIGH-MU TRIODE

Discontinued type: see chart at end of section for tabulated data.


**12F5GT** 

#### TWIN DIODE-**REMOTE-CUTOFF PENTODE**

Renewal type; see chart at end of section for tabulated data.

12F8

## TWIN DIODE— LOW-MU TRIODE



Miniature type used as combined detector and af amplifier in low B+ voltage automobile radio receivers operating directly from 12-volt storagebattery systems. Outline 5C, Outlines section. Tube requires miniature

12FK6

seven-contact socket and may be mounted in any position.

| Heater-Voltage Range (ac/dc).                        | 10.0 to 15.9 | volts   |
|--|--------------|---------|
| Heater Current (Approx.) at 12.6 volts               |              | ampere  |
| Peak Heater-Cathode Voltage:                         |              |         |
| Heater negative with respect to cathode              | . 16 ma      | x volts |
| Heater positive with respect to cathode              | 16 ma        | x volts |
| Direct Interelectrode Capacitances (Approx.):        |              |         |
| Triode Grid to Triode Plate                          | 1.6          | pf      |
| Triode Grid to Cathode and Heater                    | 1.8          | pf      |
| Triode Plate to Cathode and Heater                   | 0.7          | pf      |
| Plate of Diode Unit No.1 to Plate of Diode Unit No.2 | 0.9          | pf      |
|  |              |         |

<sup>·</sup> For longest life, it is recommended that the heater be operated within the voltage range of 11 to 14 volts.

|   | Triode | Unit | as Class                                | : A, | Amplifier |
|---|--------|------|---|------|-----------|
| - |        |      | • |      |           |

| Triode Unit as Class A, Amplifier                                   |                  |                |
|---|------------------|----------------|
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage Grid Voltage: | 16 max           | volts          |
| Positive-bias value<br>Negative-bias value                          | 0 max<br>—16 max | volts<br>volts |

| Plate Voltage                                     | 12.6 | volts   |
|---|------|---------|
| Grid-Supply Voltage                               | 12.0 | volts   |
| Grid Resistor (Bypassed)                          | 2.2  | megohms |
| Plate Resistance (Approx.)                        | 6200 | ohms    |
| Transconductance                                  | 1200 | μmhos   |
| Amplification Factor                              | 7.4  | •       |
| Plate Current                                     | 1.3  | ma      |
| Grid Voltage (Approx.) for plate current of 10 µa | -4   | volts   |

#### Diode Units

MAXIMUM RATINGS (Design-Center Values):


Grid-Circuit Resistance ......

Plate Current (Each unit) ......

1 max

10 max megohms

ma



# 12FM6


## TWIN DIODE— MEDIUM-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

#### HIGH-MU TWIN DOUBLE-PLATE TRIODE

12FQ8

Miniature type used in frequencydivider and complex-wave-generator circuits of electronic musical instruments. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any




position. Heater volts (ac/dc), 12.6; amperes, 0.15; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Class A. Amplifier (Each Unit)

| CHARACTERISTICS: |      |       |
|------------------|------|-------|
| Plate Voltage    | 250  | volts |
| Grid Voltage     | -1.5 | volts |

|  |   | 137  |
|--|---|--|
| Amplification Factor  Plate Resistance (Approx.)  Transconductance  Plate Current  | 95<br>76000<br>1250<br>1.5                        | ohms<br>µmhos<br>ma                            |
| • Using either plate A or plate B, with plate not in use connected to ground.  |   |  |
| Frequency-Divider and Complex-Wave Generator (Ea   | ch Unit)  |  |
| MAXIMUM RATINGS (Design-Maximum Values): Plate A Voltage Plate B Voltage Grid Voltage, Positive-bias value Plate A Dissipation Plate B Dissipation   | 330 max<br>330 max<br>0 max<br>0.5 max<br>0.5 max | volts<br>volts<br>watt                         |
| DIODE  |   |  |
| MEDIUM-MU TRIODE— REMOTE-CUTOFF PENTODE Discontinued type; see chart at end of section for tabulated data.   | 12FF  | 88   |
| 『 うまれる MEDIUM-MU TWIN TRIODE   |   |  |
| Miniature type used in relay-control tuning units of television receivers.  Outline 6E, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.  | 12FV  | <b>17</b>                                      |
| Heater Arrangement:         Series           Heater Voltage (ac/dc)         12.6           Heater Current         0.45           Peak Heater-Cathode Voltage:         0.45   | Parallel<br>6.3<br>0.9                            | volts<br>ampere                                |
| Heater negataive with respect to cathode Heater positive with respect to cathode Direct Interelectrode Capacitances (Each Unit, Approx.):  | 200 max<br>200 max                                | volts  |
| Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater   | 6<br>0.6<br>5.5                                   | pf<br>pf<br>pf                                 |
| • The dc component must not exceed 100 volts,  |   |  |
| Class A. Amplifier (Each Unit)   |   |  |
| CHARACTERISTICS: Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.) for plate current of 100 µa  | 100<br>-2<br>21.5<br>2250<br>9600<br>16<br>-10    | volts<br>volts<br>ohms<br>µmhos<br>ma<br>volts |
| Relay Control (Each Unit)  MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage, Positive-bias value Cathode Current Plate Dissipation: Plate Dissipations up to 20 seconds in any 2 minute interval   | 300 max<br>0 max<br>30 max                        | volts<br>volts<br>ma                           |
| For ON times exceeding 30 seconds in any 2-minute interval   | 2.5 max   | watts  |
| TYPICAL OPERATION WITH 5000-OHM RELAY LOAD:  ON Time Up to 30 Seconds in Any 2-Minute Interval Plate-Supply Voltage Zero-Bias Plate Current Grid Resistor Grid Voltage (Approx.) for plate current of 2 ma   | 270<br>36<br>2.2<br>—13                           | volts<br>ma<br>megohms<br>volts                |
| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage, Positive-bias value Cathode Current Plate Dissipation: For ON times up to 30 seconds in any 2-minute interval For ON times exceeding 30 seconds in any 2-minute interval  TYPICAL OPERATION WITH 5000-OHM RELAY LOAD:  ON Time Up to 30 Seconds in Any 2-Minute Interval | 0 max<br>30 max<br>4.5 max<br>2.5 max             | watt<br>watt                                   |

MAXIMUM CIRCUIT VALUES:



#### **POWER PENTODE**

12FX5
Related type:
60FX5

TYPICAL OPERATION: Plate Supply Voltage .....

Grid-No.2 Supply Voltage

Miniature type used in output stages of audio amplifiers employing seriesconnected heater strings. Outline 5D, Outlines section. Type 60FX5 is identical with type 12FX5 except for the heater ratings, as shown below.



110

115

62

3

36

35

10

volts

volts

ohms

volts

ma

ma

ma

ma

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage:                                | 12FX5<br>12.6<br>0.45<br>11 | 60FX5<br>60<br>0.1 | volts<br>ampere<br>seconds |
|---|-----------------------------|--------------------|----------------------------|
| Heater negative with respect to cathode  Heater positive with respect to cathode  Direct Interelectrode Capacitances (Approx.): | 200 max<br>200*max          | 200 max<br>200*max | volts<br>volts             |
| Grid No.1 to Plate  |                             | 0.65<br>17         | pf<br>pf                   |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3  |                             | 9                  | pf                         |
| * The dc component must not exceed 100 volts.   |                             |                    |                            |
| Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values):   | -                           |                    |                            |
| Plate Voltage   |                             | 150 max            | volts                      |
| Grid-No.2 (Screen-Grid) Voltage   |                             | 130 max            | volts                      |
| Plate Dissipation Grid-No.2 Input   |                             | 5.5 max            | watts                      |
| Bulb Temperature (At hottest point)   |                             | 2 max<br>225 max   | watts<br>°C                |

Cathode-Bias Resistor .....

Peak AF Grid-No.1 Voltage .....

Zero-Signal Plate Current .....

Maximum-Signal Plate Current .....

Zero-Signal Grid No.2 Current .....

Maximum-Signal Grid No.2 Current .....

For cathode-bias operation ......

Plate Resistance

| Transconductance Load Resistance Total Harmonic Distortion Maximum-Signal Power Output | 3000<br>8 | μmhos<br>ohms<br>per cent<br>watts |
|--|-----------|------------------------------------|
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation         | 0.1 ma    | x megohm                           |


#### MEDIUM-MU TRIODE— PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

12FX8

0.5 max megohm

17500



## MEDIUM-MU TRIODE— PENTAGRID CONVERTER

Miniature type used as combined rf amplifier and frequency converter in low B+ voltage automobile radio receivers operating directly from 12-volt storage-battery systems. Outline 6D, Outlines section. Tube requires minia-

12FX8A

ture nine-contact socket and may be operated in any position. Heater-voltage range (dc), 10 to 15.9; amperes at 12.6 volts, 0.27; peak heater-cathode volts, 16.

Heptode Unit as Converter

| MAXIMUM RATINGS (Design-Center Values):                          |          |             |
|--|----------|-------------|
| Plate Voltage  | 16 max   | volts       |
| Grid-No.3 (Control-Grid) Voltage:                                | 20 11111 | 10113       |
| Negative-bias value  | —16 max  | voits       |
| Positive-bias value  | 0 max    | volts       |
| Grids-No.2 and No.4 (Screen-Grid) Voltage                        | 16 max   | volts       |
| TYPICAL OPERATION AND CHARACTERISTICS WITH 12.6 VOLTS ON HEATER: |          |             |
| Plate Voltage  | 12.6     | volts       |
| Grid-No.3 Voltage•   | -0.5     | volt        |
| Grids-No.2 and No.4 Voltage                                      | 12.6     | volts       |
| RMS Grid-No.1 (Oscillator-Grid) Voltage                          | 1.6      | volts       |
| Grid-No.1 Resistor   | 33000    | ohms        |
| Plate Resistance (Approx.)                                       | 0.5      | megohm      |
| Conversion Transconductance                                      | 300      | μmhos       |
| For conversion transconductance of 10 µmhos                      | -3       | volts       |
| For conversion transconductance of 1 µmho                        | 3<br>8   | voits       |
| Plate Current  | 290      | νοιις<br>μ2 |
| Grids-No.2 and No.4 Current                                      | 1.25     | ma          |
|  | 1.25     | 1114        |
| OSCILLATOR CHARACTERISTICS (Not Oscillating):*                   |          |             |
| Plate and Grids-No.2 and No.4 Voltage                            | 12.6     | volts       |
| Grids-No.3 Voltage   | 0        | volts       |
| Grid-No.1 Voltage  | 0        | volts       |
| No.4 connected to plate)   | 9        |             |
| Transconductance (between grid No.1 and grids No.2 and           | ,        |             |
| No.4 connected to plate)   | 3600     | umhos       |
| Cathode Current  | 4.4      | ma ma       |
| Grid-No.1 Voltage (Approx.) for plate current of 10 µa           | -4.5     | volts       |
| MAXIMUM CIRCUIT VALUES:  |          | 70.00       |
|  | 40       |             |
| Grid-No.3-Circuit Resistance                                     |          | megohms     |
|  |          |             |

- With self-excitation.
- Developed across a 2.2-megohm grid-No.3 resistor.
- \* With grids No.2 and No.4 connected to plate and with 12.6 volts on heater.

#### Triode Unit as Class A. Amplifier

| MAXIMUM RATINGS (Design-Center Values): Plate Voltage | 16 max | volts |
|---|--------|-------|
| CHARACTERISTICS WITH 12.6 VOLTS ON HEATER:            |        |       |
| Plate Voltage   | 12.6   | volts |
| Grid Voltage <sup>D</sup>                             | -0.8   | volt  |
| Amplification Factor                                  | 10     |       |
| Plate Resistance (Approx.)                            | 7150   | ohms  |
| Transconductance                                      | 1400   | μmhos |
| Plate Current   | 1.3    | ma    |
| Grid Voltage (Approx.) for plate current of 10 µa     | -3.2   | volts |

Developed across a 2.2-megohm grid resistor.

# 12GA6

#### PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**

12GC6

CUADACTEDISTICS.

Glass octal type used as horizontaldeflection amplifier in television receivers employing series-connected heater strings. Outline 20, **Outlines** section. Tube requires octal socket and may be operated in any position.



Heater volts (ac/dc), 12.6; amperes, 0.6; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

## Class A, Amplifier

| CHARACTERISTICS:                                      |      |               |            |
|---|------|---------------|------------|
| Plate Voltage   | 60   | 250           | volts      |
| Grid-No.2 (Screen-Grid) Voltage                       | 150  | 150           | volts      |
| Grid-No.1 (Control-Grid) Voltage                      | 0    | -22.5         | volts      |
| Triode Amplification Factor for plate and             |      |               |            |
| grid-No.2 voltages of 150 volts                       | _    | 4.1           |            |
| Plate Resistance (Approx.)                            |      | 20000         | ohms       |
| Transconductance                                      | _    | 6600          | $\mu$ mhos |
| Plate Current   | 345° | 75            | ma         |
| Grid-No.2 Current                                     | 30°  | 2.4           | ma         |
| Grid-No.1 Voltage (Approx.) for plate current of 1 ma | _    | <del>46</del> | volts      |
|   |      |               |            |

\* This value can be measured by a method involving a recurrent waveform such that the maximum ratings will not be exceeded.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|--|-----------|-------|
| DC Plate Voltage                         | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage        | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage        | -1500 max | volts |
| DC Grid-No.2 Voltage                     | 220 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | —330 max  | volts |
| Peak Cathode Current                     | 550 max   | ma    |
| Average Cathode Current                  | 175 max   | ma    |
| Plate Dissipation•                       | 17.5 max  | watts |
| Grid-No.2 Input                          | 4.5 max   | watts |
| Bulb Temperature (At hottest point)      | 220 max   | °C    |
|  |           |       |

## MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance ......

1 max megohm

- This rating is applicable where the duration of the voltage pulse does not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

#### **BEAM POWER TUBE**

Duodecar type identical with type 6GE5 except for heater ratings; refer to 6GE5 for data,

**12GE5** 

#### **BEAM POWER TUBE**

Novar types identical with type 6GJ5 and type 6GJ5A except for heater ratings; refer to 6GJ5 and 6GJ5A for data.

12GJ5 12GJ5A



### SHARP-CUTOFF PENTODE

Miniature type with frame grid used as video amplifier tube in television receivers employing series-connected heater strings. Outline 6E, Outlines section. Tube requires miniature ninecontact socket and may be mounted

12**GN**7

in any position. Heater volts, 6.3 (series), 12.6 (parallel); amperes, 0.6 (series), 0.3 (parallel); warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):              |             |         |
|---|-------------|---------|
| Plate Voltage   | 400 max     | volts   |
| Grid-No.2 (Screen-Grid) Supply Voltage                | 330 max     | volts   |
| Grid-No.2 Voltage                                     | See curv    | page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max       | volts   |
| Plate Dissipation                                     | 7.5 max     | watts   |
| Grid-No.2 Input:                                      |             |         |
| For grid-No.2 voltages up to 165 volts                | 1.5 max     | watts   |
| For grid-No.2 voltages between 165 and 330 volts      | See curve   | page 75 |
| CHARACTERISTICS:                                      |             |         |
| Plate Supply Voltage                                  | 250         | volts   |
| Grid-No.2 Supply Voltage                              | 150         | volts   |
|   | 150         | volts   |
|   | 56          | ohms    |
| Cathode-Bias Resistor                                 |             |         |
| Plate Resistance (Approx.)                            | 0.05        | megohm  |
| Transconductance                                      | 36000       | μmhos   |
| Plate Current 70•                                     | 28          | ma      |
| Grid-No.2 Current                                     | 6.5         | ma      |
| Grid-No.1 Voltage (Approx.) for plate current of      |             |         |
| 100 μa —  | <b>-5.7</b> | volts   |
| MAXIMUM CIRCUIT VALUES:                               |             |         |
| Grid-No.1-Circuit Resistance                          | 0.25 max    | megohm  |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

### **BEAM POWER TUBE**

Novar types identical with type 6GT5 and 6GT5A except for heater ratings; refer to 6GT5 and 6GT5A for data.

12GT5 12GT5A 12GW6

**BEAM POWER TUBE** 

Glass octal type identical with type 6GW6 except for heater ratings; refer to 6GW6 for data.

12H6

TWIN DIODE

Metal type identical with type 6H6 except for heater ratings; refer to 6H6 for data.

12J5GT

MEDIUM-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

12J7GT

SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

**12J8** 

TWIN DIODE— POWER TETRODE

Renewal type; see chart at end of section for tabulated data.

12JB6 12JB6A BEAM POWER TUBE

Novar types identical with type 6JB6 and type 6JB6A except for heater ratings; refer to 6JB6 and 6JB6A for data.

12JT6 12JT6A BEAM POWER TUBE

Novar types identical with type 6JT6 and type 6JT6A except for heater ratings; refer to 6JT6 and 6JT6A for data.

12K5

**POWER TETRODE** 

Renewal type; see chart at end of section for tabulated data.

**12K7GT** 

**REMOTE-CUTOFF PENTODE** 

Renewal type; see chart at end of section for tabulated data.

12K8

TRIODE—HEXODE CONVERTER
Discontinued type; see chart at end
of section for tabulated data.

#### DIODE— SHARP-CUTOFF PENTODE

Miniature type identical with type 6KL8 except for heater ratings; refer to 6KL8 for data.

**12KL8** 

#### **BEAM POWER TUBE**


Renewal type; see chart at end of section for tabulated data.

**12L6GT** 

## TWIN DIODE— HIGH-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

**12Q7GT** 



#### **BEAM POWER TUBE**

Miniature type used as a vertical deflection amplifier in television receivers employing series-connected heater strings. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.

12**R**5

| Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) | 0.6       | volts<br>ampere<br>seconds |
|---|-----------|----------------------------|
| Peak Heater-Cathode Voltage:  | 11        | seconas                    |
| Heater negative with respect to cathode                             |           | volts                      |
| Heater positive with respect to cathode                             | 200 • max | volts                      |
| Plate Resistance (Approx.)*   | 13000     | ohms                       |
| Transconductance*   | 7000      | μmhos                      |

- The dc component must not exceed 100 volts.
- \* For plate and grid-No.2 volts, 110; grid-No.1 volts, -8.5, plate ma., 40; grid-No.2 ma., 3.3.

#### Vertical Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Center Values):               |          |       |
|---|----------|-------|
| DC Plate Voltage                                      | 150 max  | volts |
| Peak Positive-Pulse Plate Voltage† (Absolute Maximum) | 1500*max | volts |
| Grid-No.2 (Screen-Grid) Voltage                       | 150 max  | volts |
| Peak Negative-Pulse Grid No.1 (Control-Grid) Voltage  | —150 max | volts |
| Peak Cathode Current                                  | 155 max  | ma    |
| Average Cathode Current                               | 45 max   | ma    |
| Plate Dissipation                                     | 4.5 max  | watts |
| Grid-No.2 Input                                       | 1 max    | watt  |
|   |          |       |

#### MAXIMUM CIRCUIT VALUE:

Grid-No.1-Circuit Resistance:
For cathode-bias operation

2.2 max megohms

<sup>†</sup> The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

A Under no circumstances should this absolute value be exceeded.

12**S**8**G**T

#### TRIPLE DIODE ... HIGH-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

12SA7

PENTAGRID CONVERTER Metal type identical with type 6SA7

except for heater ratings; refer to 6SA7 for data.

**12SA7GT** 

PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

12SC7

HIGH-MU TWIN POWER TRIODE

Renewal type; see chart at end of section for tabulated data.

12SF5

HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

12SF5GT

HIGH-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

12**SF**7

DIODE-REMOTE-CUTOFF PENTODE

Renewal type: see chart at end of section for tabulated data.

12SG7

SEMIREMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

12**SH7** 

SHARP-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

SHARP-CUTOFF PENTODE **125.17** 

Metal type identical with type 6SJ7 except for heater ratings; refer to 6SI7 for data

SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

**12SJ7GT** 

REMOTE-CUTOFF PENTODE

Renewal types; see chart at end of section for tabulated data.

12SK7 12SK7GT

HIGH-MU TWIN TRIODE

Glass octal type identical with type 6SL7GT except for heater ratings; refer to 6SL7GT for data.

12SL7GT

MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.

**12SN7GT** 

MEDIUM-MU TWIN TRIODE

Glass octal type identical with type 6SN7GTB except for heater ratings; 12SN7GTA refer to 6SN7GTB for data.

> TWIN DIODE-HIGH-MU TRIODE

Metal type identical with type 6SQ7 except for heater ratings; refer to 6SO7 for data.

12SQ7

TWIN DIODE— HIGH-MU TRIODE

Renewal type; see chart at end of 12SQ7GT section for tabulated data.

TWIN DIODE-MEDIUM-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

12**SR**7

TWIN DIODE— **MEDIUM-MU TRIODE** 

Discontinued type; see chart at end 12SR7GT of section for tabulated data.

12**U**7

MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

12V6GT

**BEAM POWER TUBE** 

Glass octal type identical with type 6V6GTA except for heater ratings; refer to 6V6GTA for data.

12W6GT

**BEAM POWER TUBE** 

Glass octal type identical with type 6W6GT except for heater ratings; refer to 6W6GT for data.

12X4

**FULL-WAVE VACUUM RECTIFIER** 

Miniature type identical with type 6X4 except for heater ratings; refer to 6X4 for data.

12**Z**3

HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

13CW4

HIGH-MU TRIODE

Nuvistor type identical with type 6CW4 except for heater ratings; refer to 6CW4 for data.

13DE7

**DUAL TRIODE** 

Miniature type identical with type 6DE7 except for heater ratings; refer to 6DE7 for data.

13DR7

**DUAL TRIODE** 

Miniature type identical with type 6DR7 except for heater ratings; refer to 6DR7 for data.

13EM7

DUAL TRIODE

Glass octal type identical with type 6EM7 except for heater ratings; refer to 6EM7 for data.

| n | 11 | IΔ |   | T | R | ı | n | n | Ľ |
|---|----|----|---|---|---|---|---|---|---|
| u | u  |    | _ |   | к |   | u | u | £ |

Glass type identical with type 6FD7 except for heater ratings; refer to 6FD7 for data.

13FD7

## DUAL TRIODE

Duodecar type identical with type 6FM7 except for heater ratings; refer to 6FM7 for data.

13FM7

## **BEAM POWER TUBE**

Neonoval type identical with type 6GB5 except for heater ratings; refer to 6GB5 for data.

13GB5

## **DUAL TRIODE**

Novar types identical with type 6GF7 and type 6GF7A except for heater ratings; refer to 6GF7 and 6GF7A for data. 13**GF7** 13**GF7A** 

### POWER PENTODE— BEAM POWER TUBE

Duodecar type identical with type 6J10 except for heater ratings; refer to 6J10 for data.

13J10

## MEDIUM-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

**14A4** 

## BEAM POWER TUBE

Discontinued type; see chart at end of section for tabulated data.

14**A**5

## REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

14A7

## MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

14AF7

#### TWIN DIODE-HIGH-MU TRIODE 14**B**6

Discontinued type; see chart at end of section for tabulated data.

PENTAGRID CONVERTER 14B8 Discontinued type; see chart at end of section for tabulated data.

**BEAM POWER TUBE** 14C5 Discontinued type; see chart at end of section for tabulated data.

SHARP-CUTOFF PENTODE 14C7 Renewal type; see chart at end of section for tabulated data.

TWIN DIODE— MEDIUM-MU TRIODE 14E6 Discontinued type; see chart at end of section for tabulated data.


TWIN DIODE-REMOTE-CUTOFF PENTODE 14E7 Discontinued type; see chart at end of section for tabulated data.

HIGH-MU TWIN TRIODE 14F7 Renewal type; see chart at end of section for tabulated data.

MEDIUM-MU TWIN TRIODE 14F8 Renewal type; see chart at end of section for tabulated data.

# TWIN DIODE— HIGH-MU TRIODE

Miniature type used as combined detector and af voltage amplifier in radio receivers. Outline 6B, Outlines **14GT8** section. Tube requires miniature ninecontact socket and may be operated in any position.




volta

volts

Tube Voltage Drop for plate current of 18 ma ...

| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode  Heater positive with respect to cathode  Amplification Factor°  Plate Resistance (Approx.)° | 200 max<br>200=max<br>72<br>72000 | volts<br>volts<br>ohms  |
|--|-----------------------------------|-------------------------|
| Transconductance Transconductance  | 1000                              | μmhos                   |
| • The dc component must not exceed 100 volts. • For triode unit; plate volts, 250; grid volts, -3; plate ma., 0.7.   |                                   |                         |
| Triode Unit as Class A, Amplifier MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation                       | 330 max<br>0 max<br>1.1 max       | volts<br>volts<br>watts |
| Diode Units (Each Unit)  MAXIMUM RATINGS (Design-Maximum Values):  Plate Current   | 5 max                             | ma                      |
| CHARACTERISTICS. Instantaneous Value:  |                                   |                         |



## SEMIREMOTE-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

14H7

## TRIODE—HEPTODE CONVERTER

Discontinued type; see chart at end of section for tabulated data.

14**J**7

## MEDIUM-MU TWIN TRIODE

Discontinued type; see chart at end of section for tabulated data.

14N7

## PENTAGRID CONVERTER

Renewal type; see chart at end of section for tabulated data.

14Q7

14R7

TWIN DIODE— REMOTE-CUTOFF PENTODE

Renewal type; see chart at end of section for tabulated data.

15

SHARP-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

15AF11

DUAL TRIODE— SHARP-CUTOFF PENTODE

Duodecar type identical with type 6AF11 except for heater ratings; refer to 6AF11 for data.

15BD11

DUAL TRIODE— SHARP-CUTOFF PENTODE

Duodecar type identical with type 6BD11 except for heater ratings; refer to 6BD11 for data.

15FM7

**DUAL TRIODE** 

Duodecar type identical with type 6FM7 except for heater ratings; refer to 6FM7 for data.

15FY7

**DUAL TRIODE** 

Duodecar type identical with type 6FY7 except for heater ratings; refer to 6FY7 for data.


15HB6

**POWER PENTODE** 

Miniature type identical with type 6HB6 except for heater ratings; refer to 6HB6 for data.

15KY8 15KY8A HIGH-MU TRIODE— BEAM POWER TUBE

Novar types identical with type 6KY8 and type 6KY8A except for heater ratings; refer to 6KY8 and 6KY8A for data.



#### DIODE

Miniature type used as booster diode in line-time-base circuits of transformerless television receivers. Outline, 7D, Outlines section. Tube requires miniature nine-contact socket and may

**16AQ3** 

be mounted in any position. Heater volts (ac/dc), 16.4; amperes, 0.6; peak heater-cathode volts, 6600 (the pulse duration must not exceed 22 per cent of a cycle, or a maximum of 18 microseconds).

| MAXIMUM RATINGS (Design-Center Values): |         |       |
|---|---------|-------|
| Supply Voltage at zero current          | 550 max | volts |
| Supply Voltage                          | 250 max | volts |
| Peak Plate Current                      | 550 max | ma    |
| Average Plate Current                   |         | ma    |
| Plate Dissipation                       | 5 max   | watts |
| Peak Negative-Pulse Plate Voltage       |         | volts |

- Under no conditions should an absolute maximum value of 7500 volts be exceeded.
- The pulse duration must not exceed 22 per cent of a cycle, or a maximum of 18 microseconds.

#### POWER PENTODE

Miniature type identical with type 6GK6 except for heater ratings; refer to 6GK6 for data.

16**G**K6

#### HALF-WAVE VACUUM RECTIFIER

Duodecar type identical with type 6AX3 except for heater ratings; refer to 6AX3 for data.

17AX3

## HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

## HALF-WAVE VACUUM RECTIFIER

Glass octal type identical with type 6AX4GTB except for heater ratings; 17AX4GTA refer to 6AX4GTB for data.

## HALF-WAVE VACUUM RECTIFIER

Novar types identical with type 6AY3 and type 6AY3A except for heater ratings; refer to 6AY3 and 6AY3A for data. 17AY3 17AY3A

## HALF-WAVE VACUUM RECTIFIER

Duodecar type identical with type 6BE3 except for heater ratings; refer to 6BE3 for data.

17BE3

# 17BF11

#### BEAM POWER TUBE-SHARP-CUTOFF PENTODE

Duodecar type identical with type 6BF11 except for heater ratings; refer to 6BF11 for data.

# 17BH3 17BH3A

#### HALF-WAVE VACUUM RECTIFIER

Novar types identical with type 6BH3 and type 6BH3A except for heater ratings; refer to 6BH3 and 6BH3A for data.

## **BEAM POWER TUBE**

Glass octal type identical with type 17BQ6GTB 6BQ6GTB/6CU6 except for heater ratings; refer to 6BQ6GTB/6CU6 for data.

# 17**BS**3 17BS3A

#### HALF-WAVE VACUUM RECTIFIER

Novar types identical with type 6BS3 and type 6BS3A except for heater ratings; refer to 6BS3 and 6BS3A for data.

# 17C9

## SHARP-CUTOFF DUAL TETRODE

Miniature type identical with type 6C9 except for heater ratings; refer to 6C9 for data.

# 17CU5

## **BEAM POWER TUBE**

Miniature type identical with type 6CU5 except for heater ratings; refer to 6CU5 for data.

# 17D4

## HALF-WAVE VACUUM RECTIFIER

Glass octal type identical with type 6DA4 except for heater ratings; refer to 6DA4 for data.

# 17DE4

### HALF-WAVE VACUUM RECTIFIER

Glass octal type identical with type 6DE4 except for heater ratings; refer to 6DE4 for data.

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

17DM4

## HALF-WAVE VACUUM RECTIFIER

Glass octal type identical with type 6DM4A except for heater ratings; refer to 6DM4A for data.

17DM4A

## **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

17DQ6A

## **BEAM POWER TUBE**

Glass octal type identical with type 6DQ6B except for heater ratings; refer to 6DQ6B for data.

17DQ6B

#### **BEAM POWER TUBE**

Duodecar type identical with type 6GE5 except for heater ratings; refer to 6GE5 for data.

17**GE**5

## **BEAM POWER TUBE**

Novar types identical with type 6GJ5 and type 6GJ5A except for heater ratings; refer to 6GJ5 and 6GJ5A for data.

17GJ5 17GJ5A

## **BEAM POWER TUBE**

Novar types identical with type 6GT5 and type 6GT5A except for heater ratings; refer to 6GT5 and 6GT5A for data. 17GT5 17GT5A

## **BEAM POWER TUBE**

Duodecar type identical with type 6GV5 except for heater ratings; refer to 6GV5 for data.

17GV5

## **BEAM POWER TUBE**

Glass octal type identical with type 6GW6 except for heater ratings; refer to 6GW6 for data.

17GW6

## 17H3

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

# 17JB6 17JB6A

#### **BEAM POWER TUBE**

Novar types identical with types 6JB6 and 6JB6A except for heater ratings; refer to 6JB6 and 6JB6A for data.

# 17JG6 17JG6A

#### **BEAM POWER TUBE**

Novar types identical with types 6JG6 and 6JG6A except for heater ratings; refer to 6JG6 and 6JG6A for data.

# 17JT6 17JT6A


#### **BEAM POWER TUBE**

Novar types identical with types 6JT6 and 6JT6A except for heater ratings; refer to 6JT6 and 6JT6A for data.

#### MEDIUM-MU TRIODE— POWER PENTODE

17JZ8

Duodecar type used as combined vertical-deflection-oscillator and vertical-deflection-amplifier tube in television necesivers employing series-connected heater strings Outline 8B, Outlines section. Tube requires duodecar twelve-



contact socket and may be mounted in any postion. Heater volts (ac/dc), 16.8; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

## Class A, Amplifier

| Triode Pentode                                |       |
|---|-------|
| CHARACTERISTICS: Unit Unit                    |       |
| Plate Voltage                                 | volts |
| Grid-No.2 (Screen-Grid) Voltage – 110 110     | volts |
| Grid-No.1 (Control-Grid) Voltage              | volts |
| Amplification Factor                          |       |
| Plate Resistance (Approx.)                    | ohms  |
| Transconductance                              | μmhos |
| Plate Current                                 | ma    |
| Grid-No.2 Current — 17° 4                     | ma    |
| Grid-No.1 Voltage (Approx.) for plate current |       |
| of 100 $\mu$ a                                | volts |
| Grid-No.1 Voltage (Approx.) for plate current |       |
| of 10 μa —10 — —                              | volts |

<sup>•</sup> This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.


Vertical-Deflection Oscillator and Amplifier

| For operation in a 525-line, 30-fi       | rame system |           |       |
|--|-------------|-----------|-------|
|  | Triode      | Pentode   |       |
|  | Unit        | Unit      |       |
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator  | Amplifier |       |
| DC Plate Voltage                         | 250 max     | 250 max   | volts |
| Peak Positive-Pulse Plate Voltage#       | _           | 2000 max  | volts |
| Grid-No.2 Voltage                        |             | 200 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -400 max    | -150 max  | volts |
| Peak Cathode Current                     | 70 max      | 245 max   | ma    |
| Average Cathode Current                  | 20 max      | 70 max    | ma    |
| Plate Dissipation†                       | 1 max       | 7 max     | watts |
| Grid-No.2 Input                          | _           | 1.8 max   | watts |
| MAXIMUM CIRCUIT VALUES:                  |             |           |       |

#### MAXIMUM CIRCUIT VALUES: Grid-No 1-Circuit Resistance:

| GIIG I TOTT CHICARE RESISTANCES |         |                 |
|---------------------------------|---------|-----------------|
| For fixed-bias operation        | 1 max   | 1 max megohm    |
| For cathode-bias operation      | 2.2 max | 2.2 max megohms |

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds. † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.



## MEDIUM-MU TRIODE— REMOTE-CUTOFF PENTODE

Neonoval type used as combined vertical-deflection-oscillator and vertical-deflection-amplifier in television receivers employing series-connected heater strings. Outline 10F, Outlines section. Tube requires neonoval nine-

17LD8

contact socket and may be mounted in any position. Heater volts (ac/dc), 16.8; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode.

Class A, Amplifier

| CHARACTERISTICS:                 | Triode Unit | Pento | de Unit    |            |
|----------------------------------|-------------|-------|------------|------------|
| Plate Voltage                    | 150         | 45    | 120        | volts      |
| Grid-No.2 (Screen-Grid) Voltage  |             | 110   | 110        | volts      |
| Grid-No.1 (Control-Grid) Voltage | <b>-</b> 5  | 0     | <b>—</b> 8 | volts      |
| Amplification Factor             | 21.5        |       |            |            |
| Plate Resistance (Approx.)       | 11300       | _     | 11700      | ohms       |
| Transconductance                 | 1900        | _     | 7100       | $\mu$ mhos |
| Plate Current                    | 3.3         | 122 - | 46         | ma         |
| Grid-No.2 Current                |             | 17=   | 4          | ma         |
| Grid-No.1 Voltage (Approx.):     |             |       |            |            |
| For plate current of 10 $\mu$ a  | 10          | _     | _          | volts      |
| For plate current of 100 $\mu a$ | _           |       | <b>—25</b> | volts      |

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

## Vertical-Deflection Oscillator and Amplifier

| For operation in a 323-inc, 30-in        | anic system |              |       |
|--|-------------|--------------|-------|
| •  | Triode Unit | Pentode Unit |       |
| MAXIMUM RATINGS (Design-Maximum Values): | Oscillator  | Amplifier    |       |
| DC Plate Voltage                         | 250 max     | 250 max      | volts |
| Peak Positive-Pulse Plate Voltage#       | -           | 2000 max     | volts |
| DC Grid-No.2 Voltage                     | _           | 200 max      | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -400 max    | —150 max     | volts |
| Peak Cathode Current                     | 70 max      | 245 max      | ma    |
| Average Cathode Current                  | 20 max      | 70 max       | ma    |
| Plate Dissipation                        | 1 max       | 7 max        | watts |
| Grid-No.2 Input                          | _           | 1.8 max      | watts |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:

# The duration of the voltage pulse must not exceed 15 per cent of one vertical scanning cycle. In a 525-line, 30-frame system, 15 per cent of one vertical scanning cycle is 2.5 milliseconds.

18**A**5

#### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

18FW6

### REMOTE-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

## REMOTE-CUTOFF PENTODE

**18FW6A** 

Miniature type used as rf- and ifamplifier tube in ac/dc radio receivers. Outline 5C, **Outlines** section. Tube requires miniature seven-contact socket and may be mounted in any position. Heater volts (ac/dc), 18; amperes, 0.1;



warm-up time (average), 20 seconds; peak heater-cathode volts, 100.

Class A, Amplifier
MAXIMUM RATINGS (Design-Maximum Values):

| THE LITTLE OF ACTUAL CONTROL OF ALLES                 |                   |
|---|-------------------|
| Plate Voltage   | 150 max volts     |
| Grid-No.2 (Screen-Grid) Supply Voltage                | 150 max volts     |
| Grid-No.2 Voltage                                     | See curve page 75 |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max volts       |
| Grid-No.2 Input:                                      |                   |
| For grid-No.2 voltages up to 75 volts                 | 0.6 max watt      |
| For grid-No.2 voltages between 75 and 150 volts       | See curve page 75 |
| Plate Dissipation                                     | 2.5 max watts     |
| CUADACTEDISTICS.                                      |                   |

| CHARACIERISTICS:   |           |            |           |
|--|-----------|------------|-----------|
| Plate Supply Voltage   |           | 100        | volts     |
| Grid No.3 C  | Connected | to cathode | at socket |
| Grid-No.2 Supply Voltage                                     |           | 100        | volts     |
| Cathode-Bias Resistor  |           | 68         | ohms      |
| Plate Resistance (Approx.)                                   |           | 0.25       | megohm    |
| Transconductance   |           | 4400       | μmhos.    |
| Plate Current  |           | 11         | ma        |
| Grid-No.2 Current  |           | 4.4        | ma        |
| Grid-No.1 Voltage (Approx.) for transconductance of 25 µmhos |           | 20         | volts     |

18FX6

#### PENTAGRID CONVERTER

Discontinued type; see chart at end of section for tabulated data.

### PENTAGRID CONVERTER

18**F**X6**A** 

Miniature type used for converter applications in ac/dc radio receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Heater volts (ac/dc), 18; amperes, 0.1;



warm-up time (average), 20 seconds; peak heater-cathode volts, 100.

#### Converter

| Controller   |         |        |
|--|---------|--------|
| MAXIMUM RATINGS (Design-Maximum Values):                       |         |        |
| Plate Voltage  | 150 max | volts  |
| Grids-No.2-and-No.4 (Screen-Grid) Supply Voltage               | 150 max | volts  |
| Grids-No.2-and-No.4 Voltage                                    | 110 max | volts  |
| Grids-No.2-and-No.4 Input                                      | 1.2 max | watts  |
| Plate Dissipation  | 1 max   | watt   |
| TYPICAL OPERATION (Separate Excitation);*                      |         |        |
| Plate Voltage  | 100     | volts  |
| Grids-No.2-and-No.4 (Screen-Grid) Voltage                      | 100     | volts  |
| Grid-No.3 (Control-Grid) Voltage                               | -1.5    | volts  |
| Grid-No.1 (Oscillator-Grid) Resistor                           | 20000   | ohms   |
| Plate Resistance (Approx.)                                     | 0.4     | megohm |
| Conversion Transconductance                                    | 480     | μmhos  |
| Grid-No.3 Voltage (Approx.) for conversion transconductance of |         |        |
| 10 μmhos   | -21     | volts  |
| Plate Current  | 2.3     | ma     |
| Grids-No.2-and-No.4 Current                                    | 6.2     | ma     |
| Grid-No.1 Current  | 0.5     | ma     |
| Total Cathode Current  | 9       | ma     |
|  |         |        |


NOTE: The transconductance between grid No.1 and grids No.2 and No.4 connected to plate (not oscillating) is approximately 7000  $\mu$ mhos under the following conditions: grids No.1 and No.3 at 0 volts; grids No.2 and No.4 and plate at 100 volts. Under the same conditions, the plate current is 24 ma., and the amplification factor is 22.

\* The characteristics shown with separate excitation correspond very closely with those obtained in a self-excited oscillator circuit operating with zero bias,

#### TWIN DIODE— HIGH-MU TRIODE

Discontinued type; see chart at end of section for tabulated data.

18FY6



#### TWIN DIODE— HIGH-MU TRIODE

Miniature type used for combined detector, amplifier, and ave tube in compact ac/de radio receivers. Out line 5C, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.

**18FY6A** 

Heater volts (ac/dc), 18; amperes, 0.1; warm-up time (average), 20 seconds; peak heater-cathode volts, 100.

Triode Unit as Class A, Amplifier


| MAXIMUM RATINGS (Design-Maximum Values): |         |       |
|--|---------|-------|
| Piate Voltage                            | 150 max | volts |
| Grid Voltage, Positive-bias value        | 0 max   | volts |
| Plate Dissipation                        | 0.5 max | watt  |
| CHARACTERISTICS:                         |         |       |
| Plate Voltage                            | 100     | volts |
| Grid Voltage                             | -1      | volt  |
| Amplification Factor                     | 100     |       |
| Plate Resistance (Approx.)               | 77000   | ohms  |
| Transconductance                         | 1300    | umhos |
| Plate Current                            | 0.6     | ma    |
| Diode Units (Fach Unit)                  |         |       |

MAXIMUM RATINGS (Design-Maximum Values):

### SHARP-CUTOFF PENTODE

## **18GD6A**

Miniature type used in the if, rf, and converter stages of ac/dc AM radio receivers. Outline 5C, Outlines section. Tube requires miniature seven-contact socket and may be operated in any position.



| Heater Voltage (ac/dc)   | 18      | volts   |
|--|---------|---------|
| Heater Current   | 0.1     | ampere  |
| Warm-up Time (Average)   | 20      | seconds |
| Peak Heater-Cathode Voltage:   |         |         |
| Heater negative with respect to cathode                                  | 100 max | volts   |
| Heater positive with respect to cathode                                  | 100 max | volts   |
| Direct Interelectrode Capacitances:°                                     |         |         |
| Grid-No.1 to Plate   | 0.0035  | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and                  |         | -       |
| Internal Shield  | 6.0     | pf      |
| Plate to Cathode, Heater, Grid No.2, Grid No.3 and Internal              |         | _       |
| Shield   | 5.0     | pf      |
| 9 Malyan and some mishous automal shield on with automal shield assessed |         |         |

Values are same without external shield, or with external shield connected to cathode.

#### Class A. Amplifier

| Class A, Amplitier                                      |           |            |           |
|---|-----------|------------|-----------|
| CHARACTERISTICS:  |           |            |           |
| Plate Supply Voltage                                    |           | 100        | volts     |
| Grid No.3 (Suppressor Grid)                             | Connected | to cathode | at socket |
| Grid-No.2 (Screen-Grid) Voltage                         |           | 100        | volts     |
| Cathode-Bias Resistor                                   |           | 150        | ohms      |
| Plate Resistance (Approx.)                              |           | 0.5        | megohm    |
| Transconductance  |           | 4300       | µmhos.    |
| Plate Current   |           | 5          | ma        |
| Grid-No.2 Current                                       |           | 2          | ma        |
| Grid-No.1 Voltage (Approx.), for plate current of 10 µa | • • • •   | -4.7       | volts     |
| RF Amplifier and Converter                              |           |            |           |
| MAXIMUM RATINGS (Design-Maximum Values):                |           |            |           |
| Plate Voltage   |           | 150 max    | volts     |
| Caid No 2 Symply Voltage                                |           | 160        | trolto    |

Grid-No.2 Supply Voltage 150 max volts
Grid-No.2 Voltage See curve page 75
Plate Dissipation 2.5 max watts
Grid-No.2 Input:
For grid-No.2 voltages up to 75 volts 0.6 max watt
For grid-No.2 voltages between 75 and 150 volts See curve page 75

19

#### HIGH-MU TWIN POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

## HALF-WAVE VACUUM RECTIFIER

19AU4

Glass octal type used as damper diode in horizontal-deflection circuits of black-and-white television receivers employing series-connected heater strings. Outline 13G, Outlines section. Tube requires octal socket and may



be mounted in any position. This type may be supplied with pin 1 omitted. Socket terminals 1, 2, 4, and 6 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater volts (ac/dc), 18.9; amperes, 0.6; warm-up time (average), 11 seconds.

Damper Service

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Center Values): |           |       |
|---|-----------|-------|
| Peak Inverse Plate Voltage#             | 4500°max  | volts |
| Peak Plate Current                      | 1050 max  | ma    |
| DC Plate Current                        | 175 max   | ma    |
| Plate Dissipation                       | 6 max     | watts |
| Peak Heater-Cathode Voltage:            |           |       |
| Heater negative with respect to cathode | 4500°†max | volts |
| Heater positive with respect to cathode | 3004max   | volts |

<sup>#</sup> The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal cycle is 10 microseconds.

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of 19AU4GTA section for tabulated data.

#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

19BG6G

#### **BEAM POWER TUBE**

Renewal type; see chart at end of 19BG6GA section for tabulated data.

#### MEDIUM-MU TRIODE.... SHARP-CUTOFF TETRODE

Miniature type identical with type 6CL8A except for heater ratings; refer to 6CL8A for data.

**19CL8A** 

#### MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE

Miniature type identical with type 6EA8 except for heater ratings; refer to 6EA8 for data.

19EA8

## SEMIREMOTE-CUTOFF PENTODE

Miniature type identical with type 6HR6 except for heater ratings; refer to 6HR6 for data.

19HR6

## SHARP-CUTOFF PENTODE

Miniature type identical with type 6HS6 except for heater ratings; refer to 6HS6 for data.

19HS6

Under no circumstances should this absolute value be exceeded.

<sup>†</sup> The dc component must not exceed 900 volts.


<sup>▲</sup> The dc component must not exceed 100 volts.

Triode

## HIGH-MU TRIODE SHARP-CUTOFF PENTODE

## 19HV8

Miniature type used as if-amplifier and af voltage-amplifier tube in radio receivers employing series-connected PT(2 heater strings. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be mounted



Pentode

ma

volts

volts

in any position. Heater volts (ac/dc), 18.9; amperes, 0.15; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A. Amplifier

| MAXIMUM RATINGS (Design-Maximum Values): Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation | Unit 330 max — 0 max 0.55 max | Unit 330 max 330 max See curv 0 max 3 max | volts volts page 75 volts |
|---|-------------------------------|---|---------------------------|
| Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts  | Ξ                             | 0.55 max<br>See curv                      | watt<br>e page 75         |
| CHARACTERISTICS: Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor   | 100<br><br>1<br>70            | 125<br>125<br>—1                          | volts<br>volts<br>volt    |
| Plate Resistance (Approx.) Transconductance Plate Current   | 54000<br>1300<br>0.8          | 200000<br>6500<br>12                      | ohms<br>µmhos<br>ma       |

**MAXIMUM CIRCUIT VALUES:** 

Grid-No.1 Voltage (Approx.) for plate current of 50 µa

Grid-No.1 Voltage (Approx.) for plate current of 20 µa

Grid-No.2 Current ......

Grid-No.1-Circuit Resistance: For fixed-bias operation .... 0.5 max 0.25 max megohm For cathode-bias operation ..... 1 max 1 max megohm

**19J6** 

## MEDIUM-MU TWIN TRIODE

Renewal type; see chart at end of section for tabulated data.

**19JN8** 

## MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE

Miniature type identical with type except for heater ratings: 6JN8 refer to 6JN8 for data.

TRIPLE DIODE— HIGH-MU TRIODE 19T8

Renewal type; see chart at end of section for tabulated data.

#### MEDIUM-MU TRIODE.... SHARP-CUTOFF PENTODE

Miniature type identical with type 6X8 except for heater ratings; refer to 6X8 for data.

19X8

#### POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

20

### DIODE-REMOTE-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

**20EQ7** 



#### HIGH-MU TWIN TRIODE

Miniature type used in high-gain, resistance-coupled, low-level audio amplifiers operating at low-signal levels. such as preamplifiers for stereo phonographs. Outline 6B, Outlines section. For typical operation as resistance-

**20EZ7** 

330 max

volts

coupled amplifier, refer to Resistance-Coupled Amplifier section. Tube requires miniature nine-contact socket and may be operated in any position.


| Heater Volts (ac/dc)                    |           | 20        | volts   |
|---|-----------|-----------|---------|
| Heater Current                          |           | 0.1       | ampere  |
| Heater Warm-up Time (Average)           |           | 20        | seconds |
| Peak Heater-Cathode Voltage:            |           |           |         |
| Heater negative with respect to cathode |           | 200 max   | volts   |
| Heater positive with respect to cathode |           | 200=max   | volts   |
| Direct Interelectrode Capacitances:     | Unit No.1 | Unit No.2 |         |
| Grid to Plate                           | 1.5       | 1.5       | pf      |
| Grid to Cathode and Heater              | 1.6       | 1.6       | pf      |
| Plate to Cathode and Heater             | 0.2       | 0.3       | pf      |
|   |           |           |         |

- The dc component must not exceed 100 volts.
- ° Without external shield.

Plate Voltage .....

#### Class A, Amplifier (Each Unit) MAXIMUM RATINGS (Design-Maximum Values):

| volts<br>volts<br>watts |
|-------------------------|
| volts                   |
|                         |
| watts                   |
|                         |
|                         |
| volts                   |
| volts                   |
|                         |
| ohms                    |
| μmhos                   |
| ma                      |
|                         |



## **BEAM POWER TUBE**


21EX6

Discontinued type; see chart at end of section for tabulated data.

## **BEAM POWER TUBE**

21GY5

Duodecar type used as horizontal-deflection-amplifier tube in television receivers employing series-connected heater strings. Outline 16A, Outlines section. Tube requires duodecar twelve-contact socket and may be mounted



in any position. Heater volts (ac/dc), 21; amperes, 0.45; warm-up time (average), 11 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

#### Class A, Amplifier CHARACTERISTICS: 60 130 volts Plate Voltage ..... Grid-No.2 (Screen-Grid) Voltage ..... 130 130 volts Grid-No.1 (Control-Grid) Voltage -20 volts Triode Amplification Factor\* ..... 4.7 11000 ohms Plate Resistance (Approx.) 9100 μmhos Transconductance ...... 410• 50 ma Plate Current ... 24• 1.75 ma Grid-No.2 Current ..... Grid-No.1 Voltage (Approx.) for plate current of 1 ma --33 volts

#### Horizontal-Deflection Amplifier

| For operation in a 525-line, 30-frame system |           |       |
|--|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum Values):     |           |       |
| DC Plate Supply Voltage                      | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage#           | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage            | -1500 max | volts |
| Grid-No.2 Voltage                            | 220 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage        | -330 max  | volts |

<sup>\*</sup> Triode connection, grid No.2 connected to plate.

<sup>•</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

| DC Grid-No.1 Voltage                    | max | volts |
|---|-----|-------|
|   | max | ma    |
| Average Canioge Current                 | max | ma    |
| Tiate Dissipation                       | max | watts |
| Glid 110.2 Input                        | max | watts |
| Bulb Temperature (At hottest point) 220 | max | °C    |

MAXIMUM CIRCUIT VALUES:
Grid-No.-1-Circuit Resistance .....

1 max megohm

# The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds. † An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

#### **BEAM POWER TUBE**

Duodecar type identical with type 6HJ5 except for heater ratings; refer to 6HJ5 for data.

21HJ5

#### SHARP-CUTOFF TETRODE

Discontinued type; see chart at end of section for tabulated data.

22

#### HALF-WAVE VACUUM RECTIFIER

Novar types identical with type 6BH3 and type 6BH3A except for heater ratings; refer to type 6BH3 and 6BH3A for data.

22BH3A

## HALF-WAVE VACUUM RECTIFIER


Glass octal type identical with type 6DE4 except for heater ratings; refer to 6DE4 for data.

22DE4

## **BEAM POWER TUBE**

Novar types identical with type 6JG6 and type 6JG6A except for heater ratings; refer to 6JG6 and 6JG6A for data.

22JG6 22JG6A



## BEAM POWER TUBE

Novar type used as horizontal deflection amplifier in low-B+ black-and-white television receivers employing series-connected heater strings. Outline 17D, Outlines section. Tube requires novar nine-contact socket and may be mounted in any position.

**22JU6** 

Dontada

| Heater Voltage (ac/dc)   | 22<br>0.45<br>11 | volts<br>ampere<br>seconds |
|--|------------------|----------------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode        | 200 max          | volts                      |
| Heater positive with respect to cathode  Direct Interelectrode Capacitances: | 200•max          | volts                      |
| Grid No.1 to Plate   | 1.2              | pf                         |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3                       | 22               | pf                         |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3                           | 9                | pf                         |

<sup>•</sup> The dc component must not exceed 100 volts.

| Class | A, | Amplifier |  |
|-------|----|-----------|--|
|       |    | cr · ·    |  |

|                                       | 1 riode      |     | Pentode           |       |
|---------------------------------------|--------------|-----|-------------------|-------|
| CHARACTERISTICS:                      | Connection*  |     | Connection        |       |
| Plate Voltage                         | . 125        | 50  | 130               | volts |
| Grid No.3 (Suppressor Grid)           | Connected    | to  | cathode at socket |       |
| Grid-No.2 (Screen-Grid) Voltage       |              | 125 | 125               | volts |
| Grid-No.1 (Control-Grid) Voltage      | . —20        | 0   | -20               | volts |
| Amplification Factor                  | . 5          | _   | -                 |       |
| Plate Resistance (Approx.)            |              |     | 18000             | ohms  |
| Transconductance                      | . <b>–</b>   | -   | 7000              | μmhos |
| Plate Current                         |              | 470 | 45                | ma    |
| Grid-No.2 Current                     | <del>-</del> | 28  | 1.5               | ma    |
| Grid-No.1 Voltage (Approx.) for plate |              |     |                   |       |
| current of 1 ma                       | . –          | _   | 32                | volts |
|                                       |              |     |                   |       |

<sup>\*</sup> Grid No.2 connected to plate.

## Horizontal-Deflection Amplifier For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): |           |       |
|--|-----------|-------|
| DC Plate Supply Voltage                  | 770 max   | volts |
| Peak Positive-Pulse Plate Voltage#       | 6500 max  | volts |
| Peak Negative-Pulse Plate Voltage        | -1500 max | volts |
| DC Grid-No.3 Voltage <sup>A</sup>        | 75 max    | volts |
| DC Grid-No.2 Voltage                     | 220 max   | volts |
| DC Grid-No.1 Voltage                     | —55 max   | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | —330 max  | volts |
| Peak Cathode Current                     | 850 max   | ma    |
| Average Cathode Current                  | 245 max   | ma    |
| Plate Dissipation†                       | 17 max    | watts |
| Grid-No.2 Input                          | 3.5 max   | watts |
| Bulb Temperature (At hottest point)      | 220 max   | °C    |

#### **MAXIMUM CIRCUIT VALUE:**

Grid-No.1-Circuit Resistance:

For grid-No.1-resistor-bias operation .....

2.2 max megohms

24A

#### SHARP-CUTOFF TETRODE

Discontinued type; see chart at end of section for tabulated data.

# 25A6 25A6GT

#### POWER PENTODE

Discontinued types; see chart at end of section for tabulated data.

<sup>•</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

<sup>#</sup> The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

<sup>▲</sup> In this service, a positive voltage may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 30 volts.

<sup>†</sup> An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

### RECTIFIER—POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

**25A7GT** 

## HIGH-MU POWER TRIODE

Discontinued type; see chart at end 25AC5GT

#### **BEAM POWER TUBE**

Glass octal type identical with type 6AV5GA except for heater ratings; 25AV5GA refer to 6AV5GA for data.

## HALF-WAVE VACUUM RECTIFIER

Glass octal type identical with type 6AX4GTB except for heater ratings; 25AX4GT refer to 6AX4GTB for data.

#### DIRECT-COUPLED POWER AMPLIFIER

Discontinued type; see chart at end of section for tabulated data.

25B5

## POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

25B6G

## POWER PENTODE

Discontinued type; see chart at end of section for tabulated data.

25B8GT

## **BEAM POWER TUBE**

Miniature type identical with type 6BK5 except for heater ratings; refer to 6BK5 for data.

25BK5

## **BEAM POWER TUBE**

Discontinued type; see chart at end 25BQ6GT

### **BEAM POWER TUBE**

Glass octal type identical with type 25BQ6GTB 6BQ6GTB/6CU6 except for heater ratings; refer to 6BO6GTB/6CU6 for /25CU6 data.

#### **BEAM POWER TUBE**

25C5

Miniature type identical with type 50C5 except for heater ratings; refer to 50C5 for data.

25C6G

**BEAM POWER TUBE** Discontinued type; see chart at end

of section for tabulated data.

25CA5

**BEAM POWER TUBE** Miniature type identical with type 6CA5 except for heater ratings; refer to 6CA5 for data.

25CD6GA

**BEAM POWER TUBE** 

Discontinued type; see chart at end of section for tabulated data.

**BEAM POWER TUBE** 

**25CD6GB** 

Glass octal type identical with type 6CD6GA except for heater ratings; refer to 6CD6GA for data.


25CU6

Refer to type 25BQ6GTB/25CU6.

## **BEAM POWER TUBE**

25DN6

Glass octal type used as horizontaldeflection amplifier in television receivers employing series-connected heater strings. Outline 21B, Outlines section. Tube requires octal socket. Vertical tube mounting is preferred



but horizontal operation is permissible if pins 1 and 3 are in vertical plane.

| Heater Voltage (ac/dc)                  | 25      | volts    |
|---|---------|----------|
| Heater Current                          | 0.6     | ampere   |
| Heater Warm-up Time (Average)           | 11      | seconds  |
| Peak Heater-Cathode Voltage:            |         | 24401143 |
| Heater negative with respect to cathode | 200 max | volts    |
| Heater positive with respect to cathode | 200 max | volts    |
| Plate Resistance (Approx.)†             | 4000    | ohms     |
| Transconductance†                       | 9000    | μmhos    |
| Mu-Factor,† Grid No.2 to Grid No.1      | 4.35    |          |

• The dc component must not exceed 100 volts.

† For plate and grid-No.2 volts, 125; grid-No.1 volts, -18; plate ma., 70; grid-No.2 ma., 6.3.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM KATINGS (Design-Center Values):               |           |       |
|---|-----------|-------|
| DC Plate Voltage                                      | 700 max   | volts |
| Peak Positive-Pulse Plate Voltage# (Absolute Maximum) | 6600□max  | volts |
| Peak Negative-Pulse Plate Voltage                     | -1500 max | volts |


| DC Grid-No.2 (Screen-Grid) Voltage Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage Peak Cathode Current Average Cathode Current Grid-No.2 Input Plate Dissipation† | -200 max<br>700 max<br>200 max<br>3 max<br>15 max | volts volts ma ma watts watts |
|---|---|-------------------------------|
| Bulb Temperature (At hottest point)   |   | °C                            |

MAXIMUM CIRCUIT VALUE:
Grid-No.1-Circuit Resistance

Gild-No.1-Circuit Resistance

0.47 max megohm

- # The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.
- Under no circumstances should this absolute value be exceeded.
- $\dagger$  An adequate bias resistor or other means is required to protect the tube in the absence of excitation.



#### **BEAM POWER TUBE**

Glass octal type used as horizontal deflection amplifier in television receivers employing series-connected heater strings. Outline 21A, Outlines section. Tube requires octal socket and may be operated in any position.

25EC6

| Heater Voltage (ac/dc)                                 | 25      | volts   |
|--|---------|---------|
| Heater Current   | 0.6     | ampere  |
| Heater Warm-up Time (Average)                          | 11      | seconds |
| Peak Heater-Cathode Voltage:                           |         |         |
| Heater negative with respect to cathode                | 200 max | volts   |
| Heater positive with respect to cathode                | 200*max | volts   |
| Direct Interelectrode Capacitances:                    |         |         |
| Grid No.1 to Plate                                     | 0.6     | pf      |
| Grid No.1 to Cathode, Heater, Grid No.3, and Grid No.2 | 24      | pf      |
| Plate to Cathode, Heater, Grid No.3, and Grid No.2     | 10      | pf      |

<sup>\*</sup> The dc component must not exceed 100 volts.

#### Class A<sub>1</sub> Amplifier

| CHARACTERISTICS:                                      |      |      |            |
|---|------|------|------------|
| Plate Voltage   | 60   | 135  | volts      |
| Grid-No.2 (Screen-Grid) Voltage                       | 135  | 135  | volts      |
| Grid-No.1 (Control-Grid) Voltage                      | 0    | 22.5 | volts      |
| Triode Amplification Factor                           | _    | 3.8  |            |
| Plate Resistance (Approx)                             | _    | 4700 | ohms       |
| Transconductance                                      | _    | 7500 | $\mu$ mhos |
| Plate Current   | 350= | 70   | ma         |
| Grid-No.2 Current                                     | 40=  | 4.5  | ma         |
| Grid-No.1 Voltage (Approx.) for plate current of 1 ma | _    | -42  | volts      |

<sup>•</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

## Horizontal-Deflection Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values): DC Plate Supply Voltage 700 max volts Peak Positive-Pulse Plate Voltage. 7000 max volts Peak Negative-Pulse Plate Voltage ..... -1500 max volts DC Grid-No.2 Voltage 175 max volts Peak Negative-Pulse Grid-No.1 Voltage ..... -300 max volts Peak Cathode Current ...... 700 max ma Average Cathode Current 200 max ma Grid-No.2 Input 4 max watts Plate Dissipation ..... 10 max watts Bulb Temperature (at hottest point) ..... 225 max

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

For grid-resistor-bias operation .....

1.5 max megohms

• The duration of the voltage pulse must not exceed 15 per cent of horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds. □ An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

#### POWER PENTODE

25EH5

Miniature type identical with type 6EH5 except for heater ratings; refer to 6EH5 for data.


#### **BEAM POWER TUBE**

25F5A

Heater Current .....

Miniature type used in audio-output stage of ac/dc radio receivers employing series-connected heater strings. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.

Heater Voltage (ac/dc) .....



0.15

volts

ampere


| Heater Warm-up Time (Average)   | 17                 | seconds           |
|---|--------------------|-------------------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode | 200                | 14-               |
| Heater positive with respect to cathode                               | 200 max<br>200 max | volts<br>volts    |
| Direct Interelectrode Capacitances (Approx.):                         | 200 max            | voits             |
| Grid No.1 to Plate  | 0.44               | pf                |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3                | 12                 | pf                |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3                    | 8                  | pf                |
| • The dc component must not exceed 100 volts.                         |                    |                   |
| Class A, Amplifier  |                    |                   |
| MAXIMUM RATINGS (Design-Maximum Values):                              |                    |                   |
| Plate Voltage   | 150 max            | volts             |
| Grid-No.2 (Screen-Grid) Voltage                                       | 130 max            | volts             |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value                 | 0 max              | volts             |
| Plate Dissipation   | 5.5 max            | watts             |
| Grid-No.2 Input   | 1.1 max            | watts             |
| Bulb Temperature (at hottest point)                                   | 220 max            | °C                |
| TYPICAL OPERATION AND CHARACTERISTICS:                                |                    |                   |
| Plate Voltage   | 110                | volts             |
| Grid-No.2 Voltage   | 110                | volts             |
| Grid-No.1 Voltage   | <b>7.5</b>         | volts             |
| Peak AF Grid-No.1 Voltage   | <b>—7.5</b>        | volts             |
| Plate Resistance (Approx.)  | 13000              | ohms              |
| Transconductance  | 6400               | $\mu$ mhos        |
| Zero-Signal Plate Current   | 43                 | ma                |
| Maximum-Signal Plate Current  | 45                 | ma                |
| Zero-Signal Grid-No.2 Current   | 3.8                | ma                |
| Maximum-Signal Grid-No.2 Current  Effective Load Resistance           | 7.3<br>2500        | ma                |
| Total Harmonic Distortion   | 2300<br>7          | ohms              |
| Maximum-Signal Power Output   | 1.5                | per cent<br>watts |
| Maximum-bignat Tower Output   | 1.5                | watts             |
| MAXIMUM CIRCUIT VALUES:   |                    |                   |
| Grid-No.1-Circuit Resistance:   |                    |                   |
| For fixed-bias operation  |                    | megohm            |
| For cathode-bias operation  | 0.5 max            | megohm            |
|   |                    |                   |

Push-Pull Class AB, Amplifier MAXIMUM RATINGS: (Same as for class AB1 amplifier)

| TYPICAL OPERATION (Values are for two tubes): | 440  |          |
|---|------|----------|
| Plate Voltage                                 | 110  | volts    |
| Grid-No.2 Voltage                             | 110  | volts    |
| Grid-No.1 Voltage                             | 8    | volts    |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage        | 14.4 | volts    |
| Zero-Signal Plate Current                     | 82   | ma       |
| Maximum-Signal Plate Current                  | 88   | ma       |
| Zero-Signal Grid-No.2 Current                 | 7.2  | ma       |
| Maximum-Signal Grid-No.2 Current              | 12.5 | ma       |
| Effective Load Resistance (Plate-to-plate)    | 4500 | ohms     |
| Total Harmonic Distortion                     | 2.6  | per cent |
| Maximum-Signal Power Output                   | 2.9  | watts    |







#### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

25L6

#### **BEAM POWER TUBE**

Glass octal type identical with type 50L6GT except for heater ratings; refer to 50L6GT for data.

**25L6GT** 

# DIRECT-COUPLED TWIN POWER AMPLIFIER

Discontinued type; see chart at end of section for tabulated data.

25N6G

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

25W4GT

VACUUM RECTIFIER-DOUBLER 25Y5 Discontinued type; see chart at end of section for tabulated data. VACUUM RECTIFIER-DOUBLER Renewal type; see chart at end of 25**Z**5 section for tabulated data. VACUUM RECTIFIER-DOUBLER Discontinued type; see chart at end 25**Z**6 of section for tabulated data. VACUUM RECTIFIER-DOUBLER Renewal type; see chart at end of 25**Z**6**G**T section for tabulated data. **MEDIUM-MU TRIODE** Discontinued type; see chart at end 26 of section for tabulated data. LOW-MU TRIODE Discontinued type; see chart at end 27 of section for tabulated data. MEDIUM-MU TRIODE Discontinued type; see chart at end 30 of section for tabulated data. POWER TRIODE Discontinued type; see chart at end 31

## POWER PENTODE 32ET5 Discontinued type; see chart at end

**32** 

of section for tabulated data.

SHARP-CUTOFF TETRODE Discontinued type; see chart at end

of section for tabulated data.

of section for tabulated data.

# H 3 0°2 C 2 0°2

#### **POWER PENTODE**

Miniature type used in audio output stage of compact ac/dc radio receivers. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Heater volts (ac/dc), 32; amperes, 0.1;

**32ET5A** 

warm-up time (average), 20 seconds; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

|                              | Class | $A_i$ | Amplifier |  |
|------------------------------|-------|-------|-----------|--|
| TERRYINA ON A THIRD PARK CON |       |       |           |  |

| MAXIMUM RATINGS (Design-Maximum Values); |          |          |
|--|----------|----------|
| Plate Voltage                            | 150 max  | volts    |
| Grid-No.2 (Screen-Grid) Voltage          | 130 max  | volts    |
| Grid-No.2 Input                          | 1.2 max  | watts    |
| Plate Dissipation                        | 5.4 max  | watts    |
| TYPICAL OPERATION AND CHARACTERISTICS:   |          |          |
| Plate Voltage                            | 110      | volts    |
| Grid-No.2 Voltage                        | 110      | volts    |
| Grid-No.1 (Control-Grid) Voltage         | -7.5     | volts    |
| Peak AF Grid-No.1 Voltage                | 7.5      | volts    |
| Zero-Signal Plate Current                | 30       | ma       |
| Zero-Signal Grid-No.2 Current            | 2.8      | ma       |
| Plate Resistance (Approx.)               | 21500    | ohms     |
| Transconductance                         | 5500     | μmhos    |
| Load Resistance                          | 2800     | ohms     |
| Total Harmonic Distortion                |          |          |
|  | 10       | per cent |
| Maximum-Signal Power Output              | 1.2      | watts    |
| MAXIMUM CIRCUIT VALUES:                  |          |          |
| Grid-No.1-Circuit Resistance:            |          |          |
| For fixed-bias operation                 | 0.1 **** | megohm   |
| For cathode-bias operation               |          |          |
| Tot camoue-olas operation                | U.5 max  | megohm   |

#### RECTIFIER— BEAM POWER TUBE


Discontinued type; see chart at end of section for tabulated data.

32L7GT

#### **POWER PENTODE**

Discontinued type; see chart at end of section for tabulated data.

33



### DIODE—BEAM POWER TUBE

Duodecar type used as combined damper diode and horizontal deflection amplifier in televison receivers employing series-connected heater strings. Outline 15A, Outlines section. Tube requires duodecar twelve-contact sock-

33**GY**7

et and may be mounted in any position. Heater volts (ac/dc), 33.6; amperes, 0.45; warm-up time (average), 11 seconds.

#### Beam Power Unit as Class A. Amplifier

| CHARACTERISTICS:                              |      |      |       |            |
|---|------|------|-------|------------|
| Plate Voltage                                 | 5000 | 60   | 130   | volts      |
| Grid-No.2 (Screen-Grid) Voltage               | 130  | 130  | 130   | volts      |
| Grid-No.1 (Control-Grid) Voltage              |      | 0    | -22.5 | volts      |
| Triode Amplification Factor                   | _    |      | 4*    |            |
| Plate Resistance (Approx.)                    |      |      | 10000 | ohms       |
| Transconductance                              | _    |      | 6500  | $\mu$ mhos |
| Plate Current                                 | _    | 320= | 48    | ma         |
| Grid-No.2 Current                             |      | 22=  | 2.9   | ma         |
| Grid-No.1 Voltage (Approx.) for plate current |      |      |       |            |
| of 1 ma                                       | -80  |      | 40    | volts      |

<sup>\*</sup> Grid No.2 tied to plate.

#### Beam Power Unit as Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

| MAXIMUM RATINGS (Design-Maximum Values): | Power Beam Un | nit   |
|--|---------------|-------|
| DC Plate Supply Voltage                  | 400 max       | volts |
| Peak Positive-Pulse Plate Voltage#       | 5000 max      | volts |
| Peak Negative-Pulse Plate Voltage        | 0 max         | volts |
| DC Grid-No.2 Voltage                     | 150 max       | volts |
| DC Grid-No.1 Voltage                     | −55 max       | volts |
| Peak Negative-Pulse Grid-No.1 Voltage    | -330 max      | volts |
| Peak Cathode Current                     | 540 max       | ma    |
| Average Cathode Current                  | 155 max       | ma    |
| Plate Dissipation†                       | 9 max         | watts |
| Grid-No.2 Input                          | 3 max         | watts |
| Peak Heater-Cathode Voltage:             |               |       |
| Heater negative with respect to cathode  | 200 max       | volts |
| Heater positive with respect to cathode  | 200•max       | volts |

#### MAXIMUM CIRCUIT VALUE:

Grid-No.1-Circuit Resistance 1 max megohm

# The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

#### Damper Service (Diode Unit)

For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values): Diode Unit Peak Inverse Plate Voltage# ..... 4200 max volts Peak Plate Current ..... 810 max ma DC Plate Current ..... 135 max ma Plate Dissipation 3.8 max watts Peak Heater-Cathode Voltages: 4200\*max Heater negative with respect to cathode ..... volts Heater positive with respect to cathode ...... 200 • max volts Bulb Temperature (At hottest point) ..... 200 max °C CHARACTERISTICS, Instantaneous Value: Tube Voltage Drop for plate current of 250 ma ..... 21 volts

#### REMOTE-CUTOFF PENTODE

Discontinued type; see chart at end of section for tabulated data.

<sup>•</sup> This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

<sup>†</sup> An adequate bias resistor or other means is required to protect the tube in the absence of excitation.

<sup>•</sup> The dc component must not exceed 100 volts.

<sup>#</sup> The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

<sup>▲</sup> The dc component must not exceed 400 volts.

The dc component must not exceed 100 volts.

#### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

34GD5



#### **BEAM POWER TUBE**

Miniature type used in audio output stages of compact ac/dc radio receivers. Outline 5D, **Outlines** section. Tube requires miniature seven-contact socket and may be operated in any position.


**34GD5A** 

| Heater Voltage (ac/dc)                                 | 34         | volts   |
|--|------------|---------|
| Heater Current   | 0.1        | ampere  |
| Heater Warm-up Time (Average)                          | 20         | seconds |
| Peak Heater-Cathode Voltage:                           |            |         |
| Heater negative with respect to cathode                | 200 max    | volts   |
| Heater positive with respect to cathode                | 200 max    | volts   |
| Direct Interelectrode Capacitances (Approx.):          | 200 111111 |         |
| Grid No.1 to Plate                                     | 0.6        | pf      |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 12         | pf      |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 19         | pf      |

#### \* The dc component must not exceed 100 volts.

#### Class A, Amplifier

| - · · · · · · · · · · · · · · · · · · ·  |         |       |
|--|---------|-------|
| MAXIMUM RATINGS (Design-Maximum Values): |         |       |
| Plate Voltage                            | 150 max | volts |
| Grid-No.2 (Screen-Grid) Voltage          | 130 max | volts |
| Grid-No.1 (Control-Grid) Voltage:        |         |       |
| Negative-bias value                      | 50 max  | volts |
| Positive-bias value                      | 0 max   | volts |
| Grid-No.2 Input                          | 1.1 max | watts |
| Plate Dissipation                        | 5 max   | watts |
| Bulb Temperature (At hottest point)      | 250 max | °C    |



| TYPICAL OPERATION AND CHARACTERISTICS: |             |            |
|--|-------------|------------|
| Plate Voltage                          | 110         | volts      |
| Grid-No.2 Voltage                      | 110         | volts      |
| Grid-No.1 Voltage                      | <b>←7.5</b> | volts      |
| Peak AF Grid-No.1 Voltage              | 7.5         | volts      |
| Zero-Signal Plate Current              | 35          | ma         |
| Zero-Signal Grid-No.2 Current          | 3           | ma         |
| Plate Resistance (Approx.)             | 13000       | ohms       |
| Transconductance                       | 5700        | $\mu$ mhos |
| Load Resistance                        | 2500        | ohms       |
| Total Harmonic Distortion              | 10          | per cent   |
| Maximum-Signal Power Output            | 1.4         | watts      |
| MAXIMUM CIRCUIT VALUES:                |             |            |
| Grid-No.1-Circuit Resistance:          |             |            |
| For fixed-bias operation               | 0.1 max     | megohm     |
| For cathode-bias operation             | 0.5 max     | megohm     |

35

#### REMOTE-CUTOFF TETRODE

Discontinued type; see chart at end of section for tabulated data.

35A5


#### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**

35B5

Miniature type used in output stage of compact, ac/dc radio receivers. Because of its high power sensitivity at plate and screen-grid voltages available in ac/dc receivers, it is capable of providing a relatively high power output.



Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Within its maximum rating, this type is equivalent in performance to glass-octal type 35L6GT, and miniature type 35C5. Refer to type 35C5 for typical operation, maximum circuit values, installation, application information, and curves.

| Heater Voltage (ac/dc)                                 | 35      | volts  |
|--|---------|--------|
| Heater Current   | 0.15    | ampere |
| Peak Heater-Cathode Voltage:                           |         | •      |
| Heater negative with respect to cathode                | 150 max | volts  |
| Heater positive with respect to cathode                | 150 max | volts  |
| Direct Interelectrode Capacitances (Approx.):          |         |        |
| Grid No.1 to Plate                                     | 0.6     | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 12      | pf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 9       | pf     |
|  |         |        |

#### Class $\mathbf{A}_{\scriptscriptstyle L}$ Amplifier

| * •                                     |                    |       |
|---|--------------------|-------|
| MAXIMUM RATINGS (Design-Center Values): |                    |       |
| Plate Voltage                           | 117 max            | volts |
| Grid-No.2 (Screen-Grid) Voltage         | 117 max            | volts |
| Plate Dissipation                       | 4.5 max<br>1.0 max | watts |
| Grid-No.2 Input                         | 1.0 max            | watt  |

volts

ma

mnere

#### **BEAM POWER TUBE**



Heater Voltage (ac/dc) .....


Zero-Signal Grid-No.2 Current ..........

Miniature type used in output stage of compact, ac/dc radio receivers. Because of its high power sensitivity and high efficiency at plate and screen-grid voltages available in ac/dc receivers, the 35C5 is capable of providing a

35C5

relatively high power output. Except for terminal connections and slightly higher ratings, type 35C5 is equivalent in performance to miniature type 35B5 and, within its maximum ratings, to glass octal type 35L6GT. The basing arrangement of the 35C5 simplifies the problem of meeting Underwriters' Laboratories requirements in the design of ac/dc receivers.

| Heater Current  | 0.15      | ampere |
|---|-----------|--------|
| Peak Heater-Cathode Voltage:  Heater negative with respect to cathode | 200 max   | voits  |
| Heater positive with respect to cathode                               | 200 max   | volts  |
| Direct Interelectrode Capacitances (Approx.):                         | 200-IIIax | VOICS  |
|   | 0.6       | pf     |
| Grid No.1 to Plate  | 12        | pf     |
|   | 9         |        |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3                    | 9         | pf     |
| • The dc component must not exceed 100 volts.                         |           |        |
| Class A, Amplifier  |           |        |
| MAXIMUM RATINGS (Design-Maximum Values):                              |           |        |
| Plate Voltage   | 150 max   | volts  |
| Grid-No.2 (Screen-Grid) Voltage                                       | 130 max   | volts  |
| Plate Dissipation   | 5.2 max   | watts  |
| Grid-No.2 Input   | 1.1 max   | watt   |
| Bulb Temperature (At hottest point)                                   | 250 max   | °C     |
| buto Temperature (Ite notices point)                                  | 250 IIIda | v      |
| TYPICAL OPERATION:  |           |        |
| Plate Voltage   | 110       | volts  |
| Grid-No.2 Voltage   | 110       | volts  |
| Grid-No.1 (Control-Grid) Voltage                                      | -7.5      | volts  |
| Peak AF Grid-No.1 Voltage   | 7.5       | volts  |
| Zero-Signal Plate Current   | 40        | ma     |
| Maximum-Signal Plate Current  | 41        | ma     |
| Transmining organic and Contents                                      | -T A      | 1110   |



| Plate Resistance (Approx.)    | 13000   | ohms       |
|-------------------------------|---------|------------|
| Transconductance              | 5800    | $\mu$ mhos |
| Load Resistance               | 2500    | ohms       |
| Total Harmonic Distortion     | 10      | per cent   |
| Maximum-Signal Power Output   |         | watts      |
| MAXIMUM CIRCUIT VALUES:       |         |            |
| Grid-No.1-Circuit Resistance: |         |            |
| For fixed-bias operation      | 0.1 max | megohm     |
| For cathode-bias operation    |         |            |

Installation and Application

Type 35C5 requires miniature seven-contact socket and may be mounted in any position. Outline 5D, Outlines section. It is especially important that this tube, like other power-handling tubes, should be adequately ventilated.

The 35-volt heater is designed to operate under the normal conditions of line-voltage variation without materially affecting the performance or serviceability of the 35C5. For operation of the 35C5 in series with other types having 0.15-ampere rating, the current in the heater circuit should be adjusted to 0.15 ampere for the normal supply voltage.

In a series-heater circuit of the "dc-power line" type employing several 0.15-ampere types and one or two 35C5s, the heater(s) of the 35C5(s) should be placed on the positive side of the line. Under these conditions, heater-cathode voltage of the 35C5 must not exceed the value given under maximum ratings. In a series-heater circuit of the "universal" type employing rectifier tube 35W4, one or two 35C5s and several 0.15-ampere types, it is recommended that the heater(s) of the 35C5(s) be placed in the circuit so that the higher values of heater-cathode bias will be impressed on the 35C5(s) rather than on the other 0.15-ampere types. This is accomplished by arranging the 35C5(s) on the side of the supply line which is connected to the cathode of the rectifier, i.e., the positive terminal of the rectified voltage supply. Between this side of the line and the 35C5(s), any necessary auxiliary resistance and the heater of the 35W4 are connected in series.


As a power amplifier (class A<sub>1</sub>), the 35C5 is recommended for use either singly or in push-pull combination in the power-output stage of ac/dc receivers. The operating values shown under typical operation have been determined on the basis that grid-No.1 current does not flow during any part of the input cycle.

# HIGH-MU TRIODE—POWER PENTODE

35DZ8

Miniature type used as two-stage af amplifier where plate supply voltage is obtained from single half-wave rectifier connected directly to 120-volt ac line. Outline 6H, Outlines section.

Tube requires miniature nine-contact



socket and may be operated in any position. Heater volts (ac/dc), 35; amperes, 0.15; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier MAXIMUM RATINGS (Design-Center Values): Triode Unit Pentode Unit 150 max 150 max volts Plate Voltage ..... Grid-No.2 (Screen-Grid) Voltage ..... 135 max volts Cathode Current ..... 5 max 60 max ma 6.5 max Plate Dissipation ..... 0.75 max watts 1.5 max Grid-No.2 Input ..... watts

| TYPICAL OPERATION AND CHARACTERISTICS:                  | Triode Unit | Pentode Unit |            |
|---|-------------|--------------|------------|
| Plate Supply Voltage                                    | 120         | 145          | volts      |
| Grid-No.2 Supply Voltage                                | -           | 120          | voits      |
| Cathode-Bias Resistor                                   | 1500        | 180          | ohms       |
| Amplification Factor                                    | 100         |              |            |
| Plate Current   | 0.8         | 45           | ma         |
| Grid-No.2 Current                                       |             | 6            | ma         |
| Transconductance  | 1400        | 7500         | $\mu$ mhos |
| Load Resistance   |             | 2500         | ohms       |
| Power Output  | -           | 2            | watts      |
| Grid Voltage (Approx.), for plate current of 20 $\mu$ a | 2.5         | _            | volts      |
| MAXIMUM CIRCUIT VALUES:                                 |             |              |            |
| Grid-No.1-Circuit Resistance                            | 5 max       | 0.5 max r    | negohms    |



MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:

#### **POWER PENTODE**

Miniature type used in the audio output stage of radio and television receivers and in phonographs. This type has unusually high power sensitivity and is capable of providing relatively high power output at low plate and

35EH5

35

0.15

volts

amperes

0.1 max megohm

0.5 max megohm


screen-grid voltages with a low af grid-No.1 driving voltage. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position.

Heater Voltage (ac/dc) .....

For fixed-bias operation ......

For cathode-bias operation .....

| Peak Heater-Cathode Voltage:                           |            |          |
|--|------------|----------|
| Heater negative with respect to cathode                | 200 max    | volts    |
| Heater positive with respect to cathode                | 200 max    | volts    |
| Direct Interelectrode Capacitances (Approx.):          | 200-Illax  | TOILS    |
|  | 0.65       | _£       |
| Grid No.1 to Plate                                     |            | pf       |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 17         | pf       |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 9          | pf       |
| ■ The dc component must not exceed 100 volts.          |            |          |
| Class A, Amplifier                                     |            |          |
| MAXIMUM RATINGS (Design-Maximum Values):               |            |          |
| Plate Voltage  | 150 max    | volts    |
| Grid-No.2 (Screen-Grid) Voltage                        | 130 max    | volts    |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  | 0 max      | voits    |
| Plate Dissipation                                      | 5 max      | watts    |
| Grid-No.2 Input  | 1.75 max   | watts    |
| Bulb Temperature (At hottest point)                    | 225 max    | °C       |
| buto remperature (se notical point)                    | 225 111111 | •        |
| TYPICAL OPERATION:                                     |            |          |
| Plate Supply Voltage                                   | 110        | voits    |
| Grid-No.2 Supply Voltage                               | 115        | volts    |
| Cathode-Bias Resistor                                  | 62         | ohms     |
| Peak AF Grid-No.1 Voltage                              | 3          | volts    |
| Zero-Signal Plate Current                              | 32         | ma       |
| Maximum-Signal Plate Current                           | 32         | ma       |
| Zero-Signal Grid-No.2 Current                          | 7.2        | ma       |
| Maximum-Signal Grid-No.2 Current                       | 12         | ma       |
| Plate Resistance (Approx.)                             | 14000      | ohms     |
| Transconductance                                       | 3000       | μmhos    |
| Load Resistance  | 3000       | ohms     |
| Total Harmonic Distortion                              | 8          | per cent |
| Maximum-Signal Power Output                            | 1.2        | watts    |
| Manufilletti pillitti z ouer Orchar                    | ***        | 4113     |



#### **BEAM POWER TUBE**

## 35GL6

Miniature type used in af power-output stage of radio receivers. Outline 5D, Outlines section. Tube has heater tap which may be used for operating a 6.3-volt, 150-ma. panel lamp in equipment using semiconductor rectifiers.



For dc output currents greater than 70 ma., a resistor shunting the panel lamp is required. Tube requires miniature seven-contact socket and may be operated in any position.

| Heater Voltage (ac/dc):                       | Without<br>Panel<br>Lamp | With No.40<br>or 47 Panel<br>Lamp |        |
|---|--------------------------|-----------------------------------|--------|
|   | 35                       | 32                                | volts  |
| Entire Heater (pins 3 and 4)                  | 7                        | 5.5                               | volts  |
| Panel Lamp Section (pins 4 and 6)             | ,                        | 3.3                               | 70163  |
| Heater Current:                               | 0.15                     |                                   | ampere |
| Between Pins 3 and 4                          | 0.15                     | ^ <del>-</del>                    |        |
| Between Pins 3 and 6                          |                          | 0.15                              | ampere |
| Peak-Heater-Cathode Voltage:                  |                          |                                   | ••     |
| Heater negative with respect to cathode       |                          | 200 max                           | volts  |
| Heater positive with respect to cathode       |                          | 200 max                           | volts  |
| Class A, Amplifier                            |                          |                                   |        |
|   | •                        |                                   |        |
| MAXIMUM RATINGS (Design-Maximum Values):      |                          | 14                                | volts  |
| RMS Heater-Tap Voltage, when panel lamp fails |                          | 14 max                            | volts  |
| Plate Voltage                                 |                          | 150 max                           |        |
| Grid-No.2 (Screen-Grid) Voltage               |                          | 130 max                           | volts  |
| Plate Dissipation                             |                          | 5.5 max                           | watts  |
| Grid-No.2 Input                               |                          | 1.1 max                           | watts  |
| Bulb Temperature (At hottest point)           |                          | 225 max                           | °C     |
| TYPICAL OPERATION AND CHARACTERISTICS:        |                          |                                   |        |
| Plate Voltage                                 |                          | 110                               | volts  |
| Grid-No.2 Voltage                             |                          | 110                               | volts  |
| Grid-No.1 (Control-Grid) Voltage              |                          | -7.5                              | volts  |
| Peak AF Grid-No.1 Voltage                     |                          | 7.5                               | volts  |
| Zero-Signal Plate Current                     |                          | 45                                | ma     |
| Maximum-Signal Plate Current                  |                          | 47.                               | ma     |
|   |                          | 3                                 | ma     |
| Zero-Signal Grid-No.2 Current                 |                          | 9                                 | ma     |
| Maximum-Signal Grid-No.2 Current              |                          | ,                                 | ща     |

| Plate Resistance (Approx.)    | 12000   | onms       |
|-------------------------------|---------|------------|
| Transconductance              | 7500    | $\mu$ mhos |
| Load Resistance               | 2500    | ohms       |
| Total Harmonic Distortion     | 8       | per cent   |
| Maximum-Signal Power Output   |         | watts      |
| MAXIMUM CIRCUIT VALUES:       |         |            |
| Grid-No.1-Circuit Resistance: |         |            |
| For fixed-bias operation      | 0.1 max | megohm     |
| For cathode-bias operation    |         | megohm     |




#### **BEAM POWER TUBE**

Glass octal type used in output stage of ac/dc radio receivers. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any position. This type may be supplied with pin No.1 omitted. Refer to minia-

35L6GT

ture type 35C5 for installation, application information, and curves.

| , ,  | •                       |                  |                 |
|--|-------------------------|------------------|-----------------|
| Heater Voltage (ac/dc) Heater Current  |                         | 35<br>0.15       | volts<br>ampere |
| Peak Heater-Cathode Voltage:   |                         |                  |                 |
| Heater negative with respect to cathode  Heater positive with respect to cathode |                         | 90 max<br>90 max | voits<br>voits  |
| Direct Interelectrode Capacitances (Approx.):                                    |                         | 90 max           | VOILS           |
| Grid No.1 to Plate   |                         | 0.6              | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid                                | No.3                    | 13               | pf              |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3                               | • • • • • • • • • • • • | 9.5              | pf              |
| Class & Amulifi  | •                       |                  |                 |
| Class A, Amplifi MAXIMUM RATINGS (Design-Center Values):                         | er                      |                  |                 |
| Plate Voltage  |                         | 200 max          | volts           |
| Grid-No.2 (Screen-Grid) Voltage  |                         | 125 max          | volts           |
| Plate Dissipation  |                         | 8.5 max          | watts           |
| Grid-No.2 İnput  |                         | 1.0 max          | watt            |
| TYPICAL OPERATION:   | Fixed Bias              | Cathode Bias     |                 |
| Plate Supply Voltage   | 110                     | 200              | volts           |
| Grid-No.2 Supply Voltage   | 110                     | 125              | volts           |
| Grid-No.1 (Control-Grid) Voltage   | 7.5                     |                  | volts           |
| Cathode-Bias Resistor  | _                       | 180              | ohms            |
| Peak AF Grid-No.1 Voltage  | 7.5                     | . 8              | volts           |
| Zero-Signal Plate Current  | 40                      | 43               | ma              |
| Maximum-Signal Plate Current   | 41                      | 43               | ma              |
| Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current                   | 3<br>7                  | 2                | ma              |
| Plate Resistance (Approx.)   | 14000                   | 5.5<br>34000     | ma<br>ohms      |
| Transconductance   | 5800                    | 6100             | umhos           |
| Load Resistance  | 2500                    | 5000             | ohms            |
| Total Harmonic Distortion  | 10                      | 10               | per cent        |
| Maximum-Signal Power Output  | 1.5                     | 3.0              | watts           |
| MAXIMUM CIRCUIT VALUES:  |                         |                  |                 |
| Grid-No1-Circuit Resistance:   |                         |                  |                 |
| For fixed-bias operation   |                         | 0.1 max          | megohm          |
| For cathode-bias operation   |                         | 0.5 max          |                 |



#### HALF-WAVE VACUUM RECTIFIER

Miniature type used in power supply of ac/dc receivers. Equivalent in performance to glass-octal type 35Z5-GT. The heater is provided with a tap for operation of a panel lamp,

35W4


| Heater Voltage (ac/dc):                 | *    | **      |        |
|---|------|---------|--------|
| Entire Heater (pins 3 and 4)            | 35   | 32      | volts  |
| Panel Lamp Section (pins 4 and 6)       | 7.5  | 5.5     | volts  |
| Heater Current:                         |      |         |        |
| Between Pins 3 and 4                    | 0.15 |         | ampere |
| Between Pins 3 and 6                    |      | 0.15    | ampere |
| Peak Heater-Cathode Voltage:            |      |         |        |
| Heater negative with respect to cathode |      | 360 max | volts  |
| Heater positive with respect to cathode |      | 360 max | volts  |
| * Without panel lamp.                   |      |         |        |

\*\* With No.40 or No.47 panel lamp.

#### Half-Wave Rectifier MAXIMUM RATINGS (Design-Maximum Values): Peak Inverse Plate Voltage .....

| Peak Plate Current                                      | 660 max           | ma       |
|---|-------------------|----------|
| With Panel Lamp and Shunting Resistor Shunting Resistor | 66 max<br>100 max | ma       |
| without ranci Lamp                                      | 110 max           | ma<br>ma |
| Panel-Lamp-Section Voltage: When Panel Lamp Fails       | 17 max            | volts    |

Installation and Application




Tube requires miniature seven-contact socket and may be mounted in any position. Outline 5D. Outlines section. For heater considerations, refer to miniature type 35C5.

360 max

volts

With the panel lamp connected as shown in the diagram, the drop across R and all heaters (with panel lamp) should equal 117 volts at 0.15 ampere. The shunting resistor R<sub>s</sub> is required when dc output current exceeds 60 milliamperes. Values of Rs for dc output currents greater than 60 milliamperes are given in tabulated data.



15

volts

| TYPICAL OPERATION WITH PANEL LAMP:             |     |     |     |     |       |
|--|-----|-----|-----|-----|-------|
| AC Plate-Supply Voltage (rms)                  | 117 | 117 | 117 | 117 | volts |
| Filter-Input Capacitor                         | 40  | 40  | 40  | 40  | μf    |
| Minimum Total Effective Plate-Supply Impedance | 15  | 15  | 15  | 15  | ohms  |
| Panel-Lamp Shunting Resistor                   |     | 300 | 150 | 100 | ohms  |
| DC Output Current                              | 60  | 70  | 80  | 90  | ma    |

† No.40 or No.47 panel lamp used in circuit given below with capacitor-input filter.

Half-load to full-load current .....

| TYPICAL OPERATION WITHOUT PANEL LAMP:           |     |       |
|---|-----|-------|
| AC Plate-Supply Voltage (rms)                   | 117 | volts |
| Filter-Input Capacitor                          | 40  | μf    |
| Minimum Total Effective Plate-Supply Impedance  | 15  | ohms  |
| DC Output Current                               | 100 | ma    |
| DC Output Voltage at Input to Filter (Approx.): |     |       |
| At half-load current (50 ma.)                   | 135 | volts |
| At full-load current (100 ma.)                  | 120 | volts |
| Voltage Regulation (Approx.):                   |     |       |

#### MAXIMUM CIRCUIT VALUES:

| Panel-I | amp | Shunting | Resistor:* |  |
|---------|-----|----------|------------|--|

| nei-Lamp Snunting Resistor: | •     |         |      |
|-----------------------------|-------|---------|------|
| •                           | 70 ma | 800 max | ohms |
| For de output current of .  | 80 ma | 400 max | ohms |
|                             | 90 ma | 250 max | ohms |

<sup>\*</sup> Required when do output current is greater than 60 milliamperes.

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

35**Y**4

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

**35Z3** 

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

35**Z4GT** 



#### HALF-WAVE VACUUM RECTIFIER

Glass octal type used in power supply of ac/dc receivers. The heater is provided with a tap for operation of a panel lamp. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any position. This

35**Z**5**G**T

шf

type may be supplied with pin No.1 omitted. For installation and application considerations, refer to miniature type 35W4.

| Heater Voltage (ac/dc):                 | *    | **        |        |
|---|------|-----------|--------|
| Entire Heater (pins 2 and 7)            | 35   | 32        | volts  |
| Panel Lamp Section (pins 2 and 3)       | 7.5  | 5.5       | volts  |
| Heater Current:                         |      |           |        |
| Between Pins 2 and 7                    | 0.15 |           | ampere |
| Between Pins 3 and 7                    | _    | 0.15      | ampere |
| Peak Heater-Cathode Voltage:            |      |           |        |
| Heater negative with respect to cathode |      | 350 · max | volts  |
| Heater positive with respect to cathode |      | 350 max   | volts  |
| * Without panel lamp.                   |      |           |        |

Filter-Input Capacitor .....

<sup>\*\*</sup> With No.40 or No.47 panel lamp.

| Half-                                | Wave R   | ectifier |          |     |       |       |
|--------------------------------------|----------|----------|----------|-----|-------|-------|
| MAXIMUM RATINGS (Design-Center       | Values): |          |          |     |       |       |
| Peak Inverse Plate Voltage           |          |          |          | 700 | ) max | volts |
| Peak Plate Current                   |          |          |          | 600 | ) max | ma    |
| DC Output Current:                   |          |          |          |     |       |       |
| With Banel Lamp and No Shunting      | Resistor |          |          | 60  | ) max | ma    |
| With Panel Lamp and   No Shunting Re | sistor   |          | <b>.</b> | 90  | max   | ma    |
| Without Panel Lamp                   |          |          |          | 100 | ) max | ma    |
| Panel-Lamp-Section Voltage (rms):    |          |          |          |     |       |       |
| When Panel Lamp Fails                |          |          |          | 15  | max   | volts |
| TYPICAL OPERATION WITH PANEL L       | AMP:÷    |          |          |     |       |       |
| AC Plate-Supply Voltage (rms) 1      |          | 117      | 117      | 117 | 235   | volts |

**4**0

| Minimum Total Effective Plate-                         |           |             |                |                |           |       |
|--|-----------|-------------|----------------|----------------|-----------|-------|
| Supply Impedance                                       | 15        | 15          | 15             | 15             | 100       | ohms  |
| Panel-Lamp Shunting Resistor                           |           | 300         | 150            | 100            | _         | ohms  |
| DC Output Current                                      | 60        | 70          | 80             | <del>9</del> 0 | 60        | ma    |
| † No.40 or No.47 panel lamp used in                    | circuit w | ith capacit | or-input filte | er given u     | nder type | 35W4. |
| TYPICAL OPERATION WITHOUT P                            | ANEL I    | AMP:        |                |                |           |       |
| AC Plate-Supply Voltage (rms)                          |           |             | 117            | 2              | 35        | volts |
| Filter-Input Capacitor                                 |           |             | 40             |                | 40        | μf    |
| Minimum Total Effective Plate-Supply                   | Impeda    | 1ce ,       | 15             | 1              | 00        | ohms  |
| DC Output Current                                      |           |             | 100            | 1              | 00        | ma    |
| DC Output Voltage at Input to Filter                   | (Approx   | c.):        |                |                |           |       |
| At half-load current (50) ma.)                         |           |             | 140            | 2              | 80        | volts |
| At full-load current (100 ma.)                         |           |             | 120            | 2              | 35        | volts |
| Voltage Regulation (Approx.):                          |           |             |                |                |           |       |
| Half-load to full-load current                         |           |             | 20             |                | 45        | volts |
| MAXIMUM CIRCUIT VALUES: Panel-Lamp Shunting Resistor*: |           |             |                |                |           |       |
| 70 ma  |           |             |                | . 80           | 00 max    | ohms  |
| For dc output current of \$80 ma                       |           |             |                | 46             | M max     | ohms  |

<sup>·</sup> Required when dc output current is greater than 60 milliamperes.

80 ma

#### SHARP-CUTOFF TETRODE

36

For dc output current of

Discontinued type; see chart at end of section for tabulated data.

36AM3

#### HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

**36AM3A** 


## HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

#### HALF-WAVE VACUUM RECTIFIER

**36AM3B** 

Miniature type used in power supply of ac/dc receivers. This type has a tapped heater so that the heater section between pins 4 and 6 can be used as a limiting resistance in the rectifier plate circuit. This heater section is not to be



250 max

ohms

used as a panel-lamp shunt. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be operated in any position.

| Heater Voltage (ac/dc): Entire Heater (Pins 3 and 4)                 | 36                 | volts          |
|--|--------------------|----------------|
| Tap Section (Pins 3 and 6)   | 32                 | volts          |
| Heater Current (Pins 3 and 6)  | 0.1                | ampere         |
| Heater Warm-up Time (Average)  | 20                 | seconds        |
| Peak Heater-Cathode Voltage: Heater negative with respect to cathode | 2500               |                |
| Heater positive with respect to cathode                              | 350°max<br>200°max | volts<br>volts |

The dc component must not exceed 350 volts.

The dc component must not exceed 100 volts.

#### Half-Wave Rectifier

|   | Hall-Wave Rectifie   |           |         |         |
|---|--|-----------|---------|---------|
| MAXIMUM RATINGS (De                             | sign-Maximum Values):  |           |         |         |
| Peak Inverse Plate Voltage                      |  |           | 365 max | volts   |
|   |  |           | 580 max | ma      |
| DC Output Current                               |  |           | 82 max  | ma      |
|   |  |           |         |         |
| TYPICAL OPERATION WI                            | TH CAPACITOR INPUT TO  | FILTER:   |         |         |
| AC Plate-Supply Voltage (rr                     |  | 120       | 117     | volts   |
| Filter-Input Capacitor                          | 113)   | 40        | 40      | μf      |
| Total Effective Plate Supply                    | Decistance   | 70        |         | t above |
|   |  | 75        | 75      | ma      |
| DC Output Current                               |  | 118       | 105     | volts   |
| DC Output Voltage                               |  | 110       | 103     | VOILS   |
| CHARACTERISTICS:<br>Tube Voltage Drop for plate | e current of 150 ma  | 16        | 20      | volts   |
| D   | MEDIUM-MU TRIC<br>iscontinued type; see cha<br>section for tabulated of    | rt at end | 37      |         |
| D   | POWER PENTOD<br>iscontinued type; see cha<br>of section for tabulated      | rt at end | 38      |         |
|   | REMOTE-CUTOFF PEI<br>iscontinued type; see cha<br>of section for tabulated | rt at end | 39/44   | ļ       |
| D   | MEDIUM-MU TRIO<br>iscontinued type; see cha<br>of section for tabulated    | rt at end | 40      |         |
| D   | POWER PENTOD<br>iscontinued type; see cha<br>of section for tabulated      | rt at end | 41      |         |
| Re  | POWER PENTOD<br>enewal type; see chart a<br>section for tabulated d        | t end of  | 42      |         |
| R   | POWER PENTOD<br>enewal type; see chart a<br>section for tabulated of       | t end of  | 43      |         |
| D   | POWER TRIODE<br>iscontinued type; see cha<br>of section for tabulated      | rt at end | 45      |         |

45**Z**3

#### HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

45**Z**5GT

#### HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

46

#### **DUAL-GRID POWER AMPLIFIER**

Discontinued type; see chart at end of section for tabulated data.

47

#### **POWER PENTODE**

Discontinued type; see chart at end of section for tabulated data.

48

#### POWER TETRODE

Discontinued type; see chart at end of section for tabulated data.

49

#### DUAL-GRID POWER AMPLIFIER

Discontinued type; see chart at end of section for tabulated data.

50

#### POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

50A5

#### **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**

50B5

Miniature type used in output stage of compact ac/dc receivers. Because of its high power sensitivity at plate and screen-grid voltages available in ac/dc receivers, it is capable of providing a relatively high power output. Outline



5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. Except for basing arrangement, type 50B5 is identical with miniature type 50C5.



#### **BEAM POWER TUBE**


Miniature type used in output stage of compact, ac/dc radio receivers. Because of its high power sensitivity and high efficiency at plate and screengrid voltages available in ac/dc receivers, the 50C5 is capable of provid-

50C5
Related type: 25C5

ing a relatively high power output. Within its maximum ratings, type 50C5 is equivalent in performance to glass octal type 50L6GT. The basing arrangement of the 50C5 simplifies the problem of meeting Underwriters' Laboratories requirements in the design of ac/dc receivers. Type 25C5 is identical with type 50C5 except for the heater ratings, as shown below.

25C5
50C5

| Heater Voltage (ac/dc)                                | 25      | 50        | volts  |
|---|---------|-----------|--------|
| Heater Current  | 0.3     | 0.15      | атреге |
| Peak Heater-Cathode Voltage:                          |         |           | _      |
| Heater negative with respect to cathode               | 200 max | 200 max   | volts  |
| Heater positive with respect to cathode               | 200 max | 200 = max | volts  |
| Direct Interelectrode Capacitances (Approx.):         |         |           |        |
| Grid No.1 to Plate                                    |         | 0.6       | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid N   | Vo.3    | 13        | pf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3.   |         | 8.5       | pf     |
| The dc component must not exceed 100 volts.           |         |           | -      |
| Class A, Amplifier                                    |         |           |        |
|   |         |           |        |
| MAXIMUM RATINGS (Design-Maximum Values):              |         | 150       | volts  |
| Plate Voltage   |         | 150 max   |        |
| Grid-No.2 (Screen-Grid) Voltage                       |         | 130 max   | volts  |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value |         | 0 max     | volts  |
| Plate Dissipation                                     |         | 7 max     | watts  |
| Grid-No.2 Input                                       |         | 1.4 max   | watts  |
| Bulb Temperature (At hottest point)                   |         | 220 max   | °C     |
| TYPICAL OPERATION:                                    |         |           |        |
| Plate Voltage   |         | 120       | volts  |
| Grid-No.2 Voltage                                     |         | 110       | volts  |
| Grid-No.1 (Control-Grid) Voltage                      |         | 8         | volts  |
| Peak AF Grid-No.1 Voltage                             |         | 8         | volts  |
| Zero-Signal Plate Current                             |         | 49        | ma     |
| Maximum-Signal Plate Current                          |         | 50        | ma     |
| Zero-Signal Grid-No.2 Current                         |         | 4         | ma     |
| Maximum-Signal Grid-No.2 Current                      |         | 8.5       | ma     |
| Plate Resistance (Approx.)                            |         | 10000     | ohms   |
| Transconductance                                      |         | 7500      | µmhos  |
|   |         |           |        |



| Load Resistance Total Harmonic Distortion Maximum-Signal Power Output                                     | ohms<br>per cent<br>watts |
|---|---------------------------|
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation | megohm<br>megohm          |

#### Installation and Application

Type 50C5 requires miniature seven-contact socket and may be mounted in any position. Outline 5D, **Outlines** section. It is especially important that this tube, like other power-handling tubes, be adequately ventilated.

The 50-volt heater is designed to operate under the normal conditions of line-voltage variation without materially affecting the performance or serviceability of the 50C5. For operation of the 50C5 in series with other types having 0.15-ampere rating, the current in the heater circuit should be adjusted to 0.15 ampere for the normal supply voltage.

In a series-heater circuit of the "dc power line" type employing several 0.15-ampere types and one or two 50C5s, the heater (s) of the 50C5(s) should be placed on the positive side of the line. Under these conditions, heater-cathode voltage of the 50C5 must not exceed the value given under maximum ratings. In a series-heater circuit of the "universal" type employing rectifier tube 35W4, one or two 50C5s, and several 0.15-ampere types, it is recommended that the heater(s) of the 50C5(s) be placed in the circuit so that the higher values of heater-cathode bias will be impressed on the 50C5(s) rather than on the other 0.15-ampere types. This is accomplished by arranging the 50C5(s) on the side of the supply line which is connected to the cathode of the rectifier, i.e., the positive terminal of the rectified voltage supply. Between this side of the line and the 50C5(s), any necessary auxiliary resistance and the heater of the 35W4 are connected in series.

As a power amplifier (class  $A_i$ ), the 50C5 is recommended for use either singly or in push-pull combination in the power-output stage of "ac/dc" receivers. The operating values shown under typical operation have been determined on the basis that grid-No.1 current does not flow during any part of the input cycle.

## 50C6G


#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

#### HALF-WAVE VACUUM RECTIFIER

50DC4

Miniature type used in power supply of ac/dc radio receivers. The heater is provided with a tap for operation of a panel lamp. For typical circuit, refer to type 35W4. Outline 5D, Outlines section. Tube requires seven-contact



socket and may be mounted in any position.

| Heater Voltage (ac/dc): Entire Heater (Pins 3 and 4) Panel-Lamp Section (Pins 4 and 6) Heater Current: | *    | **   | volts            |
|--|------|------|------------------|
|  | 50   | 45   | volts            |
|  | 7.5  | 5.5  | volts            |
| Between Pins 3 and 4   | 0.15 | 0.15 | ampere<br>ampere |

Peak Heater-Cathode Voltage:

| Heater negative with respect to ca<br>Heater positive with respect to ca | athode            |                         |                                 |            | max<br>max | volts<br>volts |
|--|-------------------|-------------------------|---------------------------------|------------|------------|----------------|
| * Without panel lamp.  |                   |                         |                                 |            |            |                |
| **With No.40 or No.47 panel lamp.  |                   |                         |                                 |            |            |                |
| - 11   | -16 18/           | D1:0-                   | _                               |            |            |                |
| MAXIMUM RATINGS (Design-Maxin  |                   | Rectifie                | r                               |            |            |                |
| Peak Inverse Plate Voltage   |                   |                         |                                 | 320        | max        | volts          |
| Peak Plate Current   |                   |                         |                                 |            | max        | ma             |
| DC Output Current:   |                   |                         |                                 | 740        | max        | 1114           |
| No Shunti  | ng Resist         | or                      |                                 | 70         | max        | ma             |
| With Panel Lamp and { No Shunti Shunting F                               | <b>lesistor</b> ● |                         |                                 | 110        | max        | ma             |
| Without Panel Lamp   |                   |                         |                                 | 120        | max        | ma             |
| Panel-Lamp-Section Voltage (rms):  |                   |                         |                                 |            |            | _              |
| When Panel Lamp Fails  |                   | • • • • • • • • • •     | · · · · · · · · · · · · · · · · | 16.5       | max        | volts          |
| TYPICAL OPERATION WITH PANE  | L LAMP            | :*                      |                                 |            |            |                |
| AC Plate-Supply Voltage (rms)  | 117               | 117                     | 117                             | 117        |            | volts          |
| Filter-Input Capacitor   | 40                | 40                      | 40                              | 40         |            | $\mu$ f        |
| Minimum Total Effective Plate-   |                   |                         |                                 |            |            | •              |
| Supply Impedance   | 15                | 15                      | 15                              | 15         |            | ohms           |
| Panel-Lamp Shunting Resistor   | 450               | 200                     | 100                             | 75         |            | ohms           |
| DC Output Current  | 70                | 80                      | 90                              | 100        |            | ma             |
| TYPICAL OPERATION WITHOUT P.   | ANEL LA           | AMP:                    |                                 |            |            |                |
| AC Plate-Supply Voltage (rms)  |                   |                         |                                 | 117        |            | volts          |
| Filter-Input Capacitor   |                   |                         |                                 | 40         |            | μf             |
| Minimum Total Effective Plate-Supply                                     |                   |                         |                                 | 15         |            | ohms           |
| DC Output Current  |                   |                         |                                 | 110        |            | ma             |
| DC Output Voltage at Input to Filter (A                                  |                   |                         |                                 | 400        |            | •.             |
| At half-load current (55 ma.)<br>At full-load current (110 ma.)          |                   |                         |                                 | 130<br>110 |            | volts          |
| Voltage Regulation (Approx.):  |                   | · · · · · · · · · · · · | • • • • • • • • • •             | 110        |            | volts          |
| Half-load to full-load current   |                   |                         |                                 | 20         |            | volts          |
| † No.40 or No.47 panel lamp used in a                                    | circuit wi        | th capacito             | r-input filter                  | given und  | er type    | 35W4.          |

#### **POWER PENTODE**

• Required when dc output current is greater than 70 milliamperers.


Miniature type identical with type 6EH5 except for heater ratings; refer to 6EH5 for data.

50EH5

#### **BEAM POWER TUBE**

Glass octal type identical with type 6FE5 except for heater ratings; refer to 6FE5 for data.

**50FE5** 



#### **POWER PENTODE**


Miniature type used as audio output amplifier in ac/dc radio receivers. Outline 5D, Outlines section. Tube requires seven-contact socket and may be operated in any position.

50FK5

| Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage:              | 50<br>0.1          | volts<br>ampere |
|---|--------------------|-----------------|
| Heater negative with respect to cathode Heater positive with respect to cathode | 200 max<br>200•max | volts<br>volts  |

Direct Interelectrode Capacitances:

| Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3  Plate to Cathode, Heater, Grid No.2, and Grid No.3 | 17                                      | pf<br>pf<br>pf |
|--|---|----------------|
| <ul> <li>The dc component must not exceed 100 volts.</li> </ul>  |   |                |
| Class A <sub>1</sub> Amplifier MAXIMUM RATINGS (Design-Maximum Values):  |   |                |
| Plate Voltage  | 150 max                                 | volts          |
| Grid-No.2 (Screen-Grid) Voltage  | 130 max                                 | volts<br>volts |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value  | 0 max<br>5 max                          | watts          |
| Plate Dissipation  |   | watts          |
| Grid-No.2 Input  |   | °C             |
| Bulb Temperature (At hottest point)  | 225 max                                 | ·              |
| TYPICAL OPERATION AND CHARACTERISTICS:   |   |                |
| Plate Supply Voltage   | 110                                     | volts          |
| Grid-No.2 Supply Voltage   | 115                                     | volts          |
| Cathode-Bias Resistor  |   | ohms           |
| Peak AF Grid-No.1 Voltage  | 3                                       | volts          |
| Zero-Signal Plate Current  |   | ma             |
| Maximum-Signal Plate Current   |   | ma             |
| Zero-Signal Grid-No.2 Current  |   | ma             |
| Maximum-Signal Grid-No.2 Current   |   | ma<br>ohms     |
| Plate Resistance (Approx.)   |   | umhos          |
| Transconductance   | • | ohms           |
| Load Resistance  |   | per cent       |
| Total Harmonic Distortion  |   | watts          |
| Maximum-Signal Power Output  | 1.2                                     | watt3          |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:  |   | . •            |
| For fixed-bias operation   |   | megohm         |
|  |   |                |



#### **POWER PENTODE**

50HK6

Miniature type used in audio-frequency power-output stage of radio receivers. Outline 5D, Outlines section. Tube requires miniature seven-contact socket and may be mounted in any position. The heater is provided with a tap for



operation of a panel lamp. Heater volts (ac/dc), 50; amperes, 0.15; tap volts (without panel lamp), 7; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

| Class A, Amplifier                           |         |            |
|--|---------|------------|
| MAXIMUM RATINGS (Design-Maximum Values):     |         |            |
| Plate Voltage                                | 150 max | voits      |
| Grid-No.2 (Screen-Grid) Voltage              | 130 max | volts      |
| Plate Dissipation                            | 5.5 max | watts      |
| Grid-No.2 Input                              | 1.1 max | watts      |
| RMS Heater-Tap Voltage When Panel Lamp Fails | 14 max  | volts      |
| TYPICAL OPERATION AND CHARACTERISTICS:       |         |            |
| Plate Voltage                                | 110     | volts      |
| Grid-No.2 Voltage                            | 110     | volts      |
| Grid-No.1 (Control-Grid) Voltage             | -7.5    | volts      |
| Peak AF Grid-No.1 Voltage                    | 7.5     | volts      |
| Zero-Signal Plate Current                    | 49      | ma         |
| Maximum-Signal Plate Current                 | 50      | ma         |
| Zero-Signal Grid-No.2 Current                | 4       | ma         |
| Maximum-Signal Grid-No.2 Current             | 8.5     | ma         |
| Plate Resistance (Approx.)                   | 10000   | ohms       |
| Transconductance                             | 7500    | $\mu$ mhos |
| Load Resistance                              | 2500    | ohms       |
| Total Harmonic Distortion (Approx.)          | 9       | per cent   |
| Maximum-Signal Power Output                  | 1.9     | watts      |
| MAXIMUM CIRCUIT VALUES:                      |         |            |
| Grid-No.1-Circuit Resistance:                |         |            |
| For fixed-bias operation                     | 0.1 max | megohm     |
| For cathode-bias operation                   | 0.5 max | megohm     |



#### **BEAM POWER TUBE**

Glass octal type used in output stage of ac/dc radio receivers. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any position. This type may be supplied with pin No.1 omitted. Refer to mini-

50L6GT

Related type: 25L6GT

volts

volts

ature type 50C5 for installation and application information. Type 25L6GT is identical with type 50L6GT except for the heater ratings, as shown below.

|   | 25L6GT     | 50L6GT       |        |
|---|------------|--------------|--------|
| Heater Voltage (ac/dc)                              | 25         | 50           | volts  |
| Heater Current                                      | 0.3        | 0.15         | ampere |
| Peak Heater-Cathode Voltage:                        |            |              | •      |
| Heater negative with respect to cathode             | 90 max     | 90 max       | volts  |
| Heater positive with respect to cathode             | 90 max     | 90 max       | volts  |
| Direct Interelectrode Capacitances (Approx.):       |            |              |        |
| Grid No.1 to Plate                                  |            | 0.6          | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid   |            | 15           | pf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3  |            | 9.5          | pf     |
| Tiate to Camoue, Heater, Olio 110.2, and Olio 110.5 |            | 7.5          | pı     |
| Class A. Amplifier                                  |            |              |        |
| MAXIMUM RATINGS (Design-Center Values):             |            |              |        |
| Plate Voltage                                       |            | 200 max      | volts  |
| Grid-No.2 (Screen-Grid) Voltage                     |            | 125 max      | volts  |
| Plate Dissipation                                   |            | 10 max       | watts  |
| Grid-No.2 Input                                     |            | 1.25 max     | watts  |
|   |            | 2125 111411  |        |
| TYPICAL OPERATION:                                  | Fixed Bias | Cathode Bias |        |
| Plate Supply Voltage                                | 110        | 200          | volts  |
| Grid-No.2 Supply Voltage                            | 110        | 125          | volts  |

7.5

Grid-No.1 (Control-Grid) Voltage .....

Peak AF Grid-No.1 Voltage .....

| TYPICAL OPERATION AND CHARACTERISTICS: | Fixed Bias | Cathode Bias |          |
|--|------------|--------------|----------|
| Cathode-Bias Resistor                  | _          | 180          | ohms     |
| Zero-Signal Plate Current              | 49         | 46           | ma       |
| Maximum-Signal Plate Current           | 50         | 47           | ma       |
| Zero-Signal Grid-No.2 Current          | 4          | 2.2          | ma       |
| Maximum-Signal Grid-No.2 Current       | 10         | 8.5          | ma       |
| Plate Resistance (Approx.)             | 13000      | 28000        | ohms     |
| Transconductance                       | 8000       | 8000         | μmhos    |
| Load Resistance                        | 2000       | 4000         | ohms     |
| Total Harmonic Distortion              | 10         | 10           | per cent |
| Maximum-Signal Power Output            | 2.1        | 3.8          | watts    |

50X6

VACUUM RECTIFIER-DOUBLER

Renewal type; see chart at end of section for tabulated data.

50Y6GT

VACUUM RECTIFIER-DOUBLER

Renewal type; see chart at end of section for tabulated data.

**50Y7GT** 

VACUUM RECTIFIER-DOUBLER

Renewal type; see chart at end of section for tabulated data.

50**Z**7G

VACUUM RECTIFIER-DOUBLER

Discontinued type; see chart at end of section for tabulated data.

**53** 

HIGH-MU TWIN POWER TRIODE

Discontinued type; see chart at end of section for tabulated data.

60FX5

POWER PENTODE

Miniature type identical with type 12FX5 except for heater ratings; refer to 12FX5 for data.

70L7GT

RECTIFIER— BEAM POWER TUBE

Discontinued type; see chart at end of section for tabulated data.

**75** 

TWIN DIODE— HIGH-MU TRIODE

Renewal type; see chart at end of section for tabulated data.

**78** 

REMOTE-CUTOFF PENTODE
Discontinued type; see chart at end

Discontinued type; see chart at end of section for tabulated data.

#### FULL-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

80

#### FULL-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

84/6**Z**4

#### RECTIFIER— **BEAM POWER TUBE**

Renewal type; see chart at end of section for tabulated data.

117L7/ M7GT

#### RECTIFIER— BEAM POWER TUBE

Renewal type; see chart at end of 117N7GT section for tabulated data.

#### RECTIFIER— **BEAM POWER TUBE**

Renewal type; see chart at end of 117P7GT section for tabulated data.

#### HALF-WAVE VACUUM RECTIFIER

Renewal type; see chart at end of section for tabulated data.

117**Z**3

#### HALF-WAVE VACUUM RECTIFIER

Discontinued type; see chart at end of section for tabulated data.

117Z4GT

#### VACUUM RECTIFIER-DOUBLER

Renewal type; see chart at end of section for tabulated data.

117**Z**6GT



#### SHARP-CUTOFF PENTODE

Miniature type used as audio amplifier in applications requiring reduced microphonics, leakage noise, and hum. Especially useful in the input stages of medium-gain public-address systems, home sound recorders, and general-

5879

purpose audio systems. Outline 6B, Outlines section. Tube requires miniature ninecontact socket and may be mounted in any position. For operation as resistancecoupled amplifier, refer to Resistance-Coupled Amplifier section.

| Heater Voltage (ac/dc)  Heater Current  Peak Heater-Cathode Voltage:                                 |             | 6.3<br>0.15     | volts<br>ampere |
|--|-------------|-----------------|-----------------|
| Heater negative with respect to cathode  |             | 100 max         | volts           |
| Heater positive with respect to cathode  |             | 100 max         | volts           |
| Direct Interelectrode Capacitances:  |             |                 |                 |
| Pentode Connection:  |             | 0.11            | ¢               |
| Grid No.1 to Plate   |             | 0.11 max<br>2.7 | pf              |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid Plate to Cathode, Heater, Grid No.2, and Grid No.3 |             | 2.4             | pf<br>pf        |
| Triode Connection*:  |             | 2.4             | pι              |
| Grid No.1 to Plate   |             | 1.4             | pf              |
| Grid No.1 to Cathode and Heater  |             | 1.4             | pf              |
| Plate to Cathode and Heater  |             | 0.85            | pf              |
| * Grid No.2 and grid No.3 connected to plate.  |             |                 | •               |
| Class A, Amplifier   | r           |                 |                 |
|  | Triode      | Pentode         |                 |
| MAXIMUM RATINGS (Design-Maximum Values):   | Connection* | Connection      |                 |
| Plate Voltage  | 275 max     | 330 max         | volts           |
| Grid-No.2 (Screen-Grid) Voltage  | _           | See curve       |                 |
| Grid-No.2 Supply Voltage   | _           | 330 max         | volts           |
| Negative-bias value  | 55          | -55 max         | volts           |
| Positive-bias value  | 0 max       | 0 max           | volts           |
| Plate Dissipation  | 1.7 max     | 1.25 max        | watts           |
| Grid-No.2 Input:   |             |                 |                 |
| For grid-No.2 voltages up to 165 volts   | _           | 0.25 max        | watt            |
| For grid-No.2 voltages between 165 and 330 volts   | _           | See curve       | page 75         |

#### CHARACTERISTICS: Plate Voltage

| -    | <ul> <li>Connected to cathode at sock</li> </ul> |   |  |  |
|------|--|---|--|--|
|      |  | 100   | volts  |  |
| -3   | -8   | -3  | volts  |  |
|      | 21   | _   |  |  |
|      | 0.0137   | 2   | megohms  |  |
| 1240 | 1530   | 1000  | umhos  |  |
|      |  |   | •  |  |
|      | _  | 8   | volts  |  |
| 2.2  | 5.5  | 1.8   | ma   |  |
| _    |  | 0.4   | ma   |  |
|      |  | -3 -8<br>21 21<br>0.017 0.0137<br>1240 1530 | 100<br>-3 -8 -3<br>21 21<br>0.017 0.0137 2<br>1240 1530 1000<br>8<br>2.2 5.5 1.8 |  |

.100


#### MAXIMUM CIRCUIT VALUE:


Grid-No.1-Circuit Resistance ..... 2.2 max megohms \* Grid No.2 and grid No.3 connected to plate.

250

250

volts







#### **BEAM POWER TUBE**

Glass octal type used in the output stages of radio receivers and audio amplifiers, particularly in the push-pull stages of high-fidelity audio amplifiers. Outline 29M, **Outlines** section. Tube requires octal socket and may be

5881

mounted in any position. For typical operation as push-pull class  $A_1$ , class  $AB_1$  (within maximum ratings), and class  $AB_2$  amplifier, and for curves of average plate characteristics, refer to type 6L6GC. Heater volts (ac/dc), 6.3; amperes, 0.9; peak heater-cathode volts, 200 max.

Class A. Amplifier


| Class A, Ampiner                        |      |         |       |        |            |
|---|------|---------|-------|--------|------------|
|   |      | iode    |       | tode   |            |
| MAXIMUM RATINGS (Design-Center Values): |      | ection* |       | ection |            |
| Plate Voltage                           | 400  | max     |       | max    | volts      |
| Grid-No.2 (Screen-Grid) Voltage         |      | •       | 400   | max    | volts      |
| Plate Dissipation                       | 26   | max     | 23    | max    | watts      |
| Grid-No.2 Input                         | _    |         | 3     | max    | watts      |
| TYPICAL OPERATION                       |      |         |       |        |            |
| AND CHARACTERISTICS:                    |      |         |       |        |            |
| Plate Voltage                           | 250  | 300     | 250   | 350    | volts      |
| Grid-No.2 Voltage                       |      |         | 250   | 250    | volts      |
| Grid-No.1 (Control-Grid) Voltage        | -18  | -20     | 14    | 18     | volts      |
| Peak AF Grid-No.1 Voltage               | 18   | 20      | 14    | 18     | volts      |
| Zero-Signal Plate Current               | 52   | 78      | 75    | 53     | ma         |
| Maximum-Signal Plate Current            | 58   | 85      | 80    | 65     | ma         |
| Zero-Signal Grid-No.2 Current           | _    | _       | 4.3   | 2.5    | ma         |
| Maximum-Signal Grid-No.2 Current        |      | _       | 7.6   | 8.5    | ma         |
| Amplification Factor                    | 8    |         |       | _      |            |
| Plate Resistance (Approx.)              | _    |         | 30000 | 48000  | ohms       |
| Transconductance                        | 5250 |         | 6100  | 5200   | $\mu$ mhos |
| Load Resistance                         | 4000 | 4000    | 2500  | 4200   | ohms       |
| Total Harmonic Distortion               | 6    | 5.5     | 10    | 13     | per cent   |
| Maximum-Signal Power Output             | 1.4  | 1.8     | 6.7   | 11.3   | watts      |
| MAXIMUM CIRCUIT VALUES:                 |      |         |       |        |            |
| Grid-No.1-Circuit Resistance:           |      |         |       |        |            |
| For fixed-bias operation                |      |         | 0.1   | max ı  | negohm     |
| For cathode-bias operation              |      |         |       |        | negohm     |
| Tot camous official,                    |      |         | 0.5   | may 1  | u. Poum    |

<sup>\*</sup> Grid No.2 connected to plate.

#### **BEAM POWER TUBE**


6973

Miniature type used as power amplifier in compact high-fidelity audio equipment. Tube features linear operation over a wide range of power, high power sensitivity, high stability, and low heater power, and is capable of



delivering high power output at low distortion. Double base-pin connections for both grid No.1 and grid No.2 provide cool operation of grids and thus minimize grid emission and permit use of high values of grid-circuit resistance to reduce driving power. Outline 6G, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position.

| Heater Voltage (ac/dc)  | 6.3            | volts  |
|---|----------------|--------|
| Heater Current  | 0.45           | ampere |
| Peak Heater-Cathode Voltage:                                    |                | -      |
| Heater negative with respect to cathode                         | 200 max        | volts  |
| Heater positive with respect to cathode                         | 200 max        | volts  |
| Direct Interelectrode Capacitances:                             |                |        |
| Grid-No.1 to Plate  | 0.4 max        | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3          | 9              | pf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3              | 6              | pf     |
| <ul> <li>The dc component must not exceed 100 volts.</li> </ul> |                | •      |
| Class A, Amplifier  |                |        |
| CHARACTERISTICS:  |                |        |
| Plate Voltage   | 250            | volts  |
| Grid-No.2 (Screen-Grid) Voltage                                 | 250            | volts  |
| Grid-No.1 (Control-Grid) Votlage                                | <del>-15</del> | volts  |
| Plate Resistance (Approx.)                                      | 73000          | ohms   |
| Transconductance  | 4800           | μmhos  |
| Plate Current   | 46             | ma     |
| Grid-No.2 Current   | 3.5            | ma     |
| Grid-No.1 Voltage (Approx.) for plate current of 100 $\mu$ a    | -40            | volts  |
|   | -40            | 10113  |
| Push-Pull Class AB, Amplifier                                   |                |        |
| MAXIMUM RATINGS (Design-Maximum Values):                        |                |        |
| Plate Voltage   | 440 max        | volts  |
| Grid-No.2 Voltage   | 330 max        | volts  |
| Plate Dissipation   | 12 max         | watts  |
| Grid-No.2 Input   | 2 max          | watts  |
| Bulb Temperature (At hottest point)                             | 250 max        | °C     |



ohms

watts

per cent

| TYPICAL OPERATION                |     |        |      |       |         |       |
|----------------------------------|-----|--------|------|-------|---------|-------|
| (Values are for two tubes):      | F   | ixed B | ias  | Catho | de Bias |       |
| Plate Supply Voltage             | 250 | 350    | 400  | 300   | 310     | volts |
| Grid-No.2 Supply Voltage         | 250 | 280    | 290  | 300   | 310     | volts |
| Grid-No.1 Voltage                | -15 | -22    | 25   |       | _       | volts |
| Cathode-Bias Resistor            | _   |        |      | 230   | 270     | ohms  |
| Peak AF Grid-No.1-to-            |     |        |      |       |         |       |
| Grid-No.1 Voltage                | 30  | 44     | 50   | 48    | 55      | volts |
| Zero-Signal Plate Current        | 92  | 58     | 50   | 80    | 77      | ma    |
| Maximum-Signal Plate Current     | 105 | 106    | 107  | 96    | 92      | ma    |
| Zero-Signal Grid-No.2 Current    | 7   | 3.5    | 2.5  | 6     | 5       | ma    |
| Maximum-Signal Grid-No.2 Current | 16  | 14     | 13.7 | 14    | 14      | ma    |
| Effective Load Resistance        |     |        |      |       | - •     |       |

8000 7500

1.5

20

8000

5500 6000

17

2

#### **MAXIMUM CIRCUIT VALUES:**


(Plate-to-plate) .....

Total Harmonic Distortion .....

Maximum-Signal Power Output .....

Grid-No.1-Circuit Resistance:

For fixed-bias operation 0.5 max megohm For cathode-bias operation ..... 1 max meghom



| Plate and Grid-No.2 Supply Voltage            |            | 410 max    | volts    |
|---|------------|------------|----------|
| Plate Dissipation                             |            | 12 max     | watts    |
| Grid-No.2 Input                               |            | 1.75 max   | watts    |
| Bulb Temperature (At hottest point)           |            | 250 max    | °C       |
| TYPICAL OPERATION (Values are for two tubes): | Fixed Bias | Cathode Bi | as       |
| Plate Supply Voltage                          | 375        | 370        | volts    |
| Grid-No.2 Supply Voltage                      | *          | #          | volts    |
| Grid-No.1 Voltage•                            | 33.5       | _          | volts    |
| Cathode-Bias Resistor                         | _          | 355        | ohms     |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage        | 67         | 62         | volts    |
| Zero-Signal Cathode Current                   | 62         | 74         | ma       |
| Maximum-Signal Cathode Current                | 95         | 84         | ma       |
| Effective Load Resistance (Plate-to-plate)    | 12500      | 13000      | ohms     |
| Total Harmonic Distortion                     | 1.5        | 1.2        | per cent |
| Maximum-Signal Power Output                   | 18.5       | 15         | watts    |
|   |            |            |          |

#### MAXIMUM CIRCUIT VALUES: •

Grid-No.1-Circuit Resistance:


| For fixed-bias operation   | 0.5 max | megohm |
|----------------------------|---------|--------|
| For cathode-bias operation | 1 max   | megohm |

- \* Obtained from taps on the primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to apply 50 per cent of the plate signal voltage to grid No.2 of each output tube.
- # Obtained from taps on the primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to supply 43 per cent of the plate signal voltage to grid No.2 of each output tube.
- The type of input-coupling network used should not introduce too much resistance in the grid-No.1 circuit. Transformer- or impedance-coupling devices are recommended.

#### HIGH-MU TWIN TRIODE

7025

Miniature type used as phase inverter or resistance-coupled amplifier in high-quality, high-fidelity audio amplifiers where low noise and hum are primary considerations. Outline 6B, Outlines section. This type is identical with



miniature type 12AX7A except that it has a controlled equivalent noise and hum characteristic. For operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

#### EQUIVALENT-NOISE AND HUM VOLTAGE

| REFERENCE TO GRID (Each Unit):             |          |                  |
|--|----------|------------------|
| Average Value (rms)†  Maximum Value (rms)• | 1.8<br>7 | μvolts<br>μvolts |

- † Measured in "true rms" units under following conditions: heater volts (ac), 6.3 (parallel connection); center tap of heater transformer connected to ground; plate supply volts, 250; plate load resistor, 2700 ohms; cathode-bypass capacitor, 100  $\mu$ f; grid resistor, 0 ohms; and amplifier covering frequency range between 25 to 10000 cycles per second.
- Same conditions as for "Average Value" except: cathode resistor is unbypassed and grid resistor, 0.05 megohm.

7027

#### **BEAM POWER TUBE**

Discontinued type; see chart at end of section for tabulated data.

#### **BEAM POWER TUBE**

7027A

Glass octal type used in push-pull power amplifier circuits of high-fidelity audio equipment. Tube provides high power sensitivity and high stability and is capable of delivering high power output at low distortion. Double base-



pin connections for both grid No.1 and grid No.2 provide for flexibility of circuit arrangement and also cool operation of the grids with the result that reverse grid current is minimized. Outline 19F, Outlines section. Tube requires octal socket and may be mounted in any position. It is especially important that this tube, like other power-handling tubes, be adequately ventilated.

| Heater Voltage (ac/dc)                                 | 6.3       | volts  |
|--|-----------|--------|
| Heater Current   | 0.9       | ampere |
| Peak Heater-Cathode Voltage:                           |           |        |
| Heater negative with respect to cathode                | 200 max   | volts  |
| Heater positive with respect to cathode                | 200 • max | volts  |
| Direct Interelectrode Capacitances (Approx.):          |           |        |
| Grid No.1 to Plate                                     | 1.5       | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 10        | pf     |
| Plate to Cathode, Heater, Grid No.2 and Grid No.3      | 7.5       | pf     |
|  |           |        |

<sup>\*</sup> The dc-component must not exceed 100 volts.

250

CHARACTERISTICS:

#### Class A. Amplifier


| Plate Voltage                             |             |              | <b></b>             |         | 250     | volts                                   |
|---|-------------|--------------|---------------------|---------|---------|---|
| Grid-No.2 (Screen-Grid) Voltage           |             | <b></b>      | . <i></i>           |         | 250     | volts                                   |
| Grid-No.1 (Control-Grid) Voltage          |             |              | <i></i> .           |         | -14     | volts                                   |
| Plate Resistance (Approx.)                |             |              |                     |         | 2500    | ohms                                    |
| Transconductance                          |             |              |                     | _       | 5000    | μmhos                                   |
| Plate Current                             |             |              |                     |         | 72      | ma                                      |
| Grid-No.2 Current                         |             |              |                     |         | 5       | ma                                      |
| Push-Pull Cia                             | ss AB       | . Ampl       | lifier              |         |         |   |
| MAXIMUM RATINGS (Design-Maximum Val       |             | 1            |                     |         |         |   |
| Plate Voltage                             |             |              |                     |         | 600 max | volts                                   |
| Grid-No.2 Voltage                         |             |              |                     |         | 500 max | volts                                   |
| Plate Dissipation                         |             |              |                     |         | 35 max  | watts                                   |
| Grid-No.2 Input                           |             |              |                     |         | 5 max   | watts                                   |
| Glid-140.2 Input                          |             |              | · · · · · · · · · · |         | Julium  | *************************************** |
| TYPICAL OPERATION (Values are for two tu  |             |              |                     |         |         |   |
| I   | ixed B      | ias          |                     | thode : |         |   |
| Plate Supply Voltage                      | 450         | 540          | 400                 | 380     | 425     | volts                                   |
| Grid-No.2 Supply Voltage 300              | 350         | 400          | 300                 | 380     | 415     | volts                                   |
| Grid-No.1 Voltage                         | <b>−30•</b> | <b>−38</b> • | _                   | _       |         | volts                                   |
| Cathode-Bias Resistor                     | _           | _            | 200                 | 180     | 200     | ohms                                    |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage 50 | 60          | 76           | 57                  | 68.5    | 86      | volts                                   |
| Zero-Signal Plate Current 102             | 95          | 100          | 112                 | 138     | 150     | ma                                      |
| Maximum-Signal Plate Current 152          | 194         | 220          | 128                 | 170     | 196     | ma                                      |
| Zero-Signal Grid-No.2 Current 6           | 3.4         | 5            | 7                   | 5.6     | 8       | ma                                      |
| Maximum-Signal Grid-No.2 Current 17       | 19.2        | 21.4         | 16                  | 20      | 20      | ma                                      |
| Effective Load Resistance (Plate-to-      |             |              |                     |         |         |   |
| Plate)                                    | 6000        | 6500         | 6600                | 4500    | 3800    | ohms                                    |
| Total Harmonic Distortion                 | 1.5         | 2            | 2                   | 3.5     | 4       | per cent                                |
| Maximum-Signal Power Output 34            | 50          | 76           | 32                  | 36      | 44      | watts                                   |
| 1. Zanimiani Digital Zoniti Output        | • •         | . •          |                     |         |         |   |

#### **MAXIMUM CIRCUIT VALUES:**

Grid-No.1-Circuit Resistance:

For fixed-bias operation 0.1 max megohm
For cathode-bias operation 0.5 max megohm

• The type of input coupling network used should not introduce too much resistance in the grid-No.1 circuit. Transformer- or impedance-coupling devices are recommended.




Push-Pull Class AB, Amplifier

Grid No.2 of Each Tube Connected to Tap on Plate Winding of Output Transformer MAXIMUM RATINGS (Design-Maximum Values):

Plate and Grid-No.2 Supply Voltage 600 max volts
Plate Dissipation 35 max watts


| Grid-No.2 Input                               | 4.5 max | watts    |
|---|---------|----------|
| TYPICAL OPERATION (Values are for two tubes): |         |          |
| Plate Supply Voltage                          | 410     | volts    |
| Grid-No.2 Supply Voltage                      | *       | volts    |
| Cathode-Bias Resistor                         | 220     | ohms     |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage        | 68      | volts    |
| Zero-Signal Cathode Current                   | 134     | ma       |
| Maximum-Signal Cathode Current                | 155     | ma       |
| Effective Load Resistance (Plate to plate)    | 8000    | ohms     |
| Total Harmonic Distortion                     | 1.6     | per cent |
| Maximum-Signal Power Output                   | 24      | watts    |
| MAXIMUM CIRCUIT VALUES:                       |         |          |
| Grid-No.1-Circuit Resistance:                 |         |          |



#### **POWER PENTODE**

7189

Miniature type used as power amplifier tube in high-fidelity audio equipment. Outline 6G, **Outlines** section. Tube requires miniature nine-contact socket and may be mounted in any position. Heater volts (ac/dc), 6.3;



volts

amperes, 0.76; peak heater-cathode volts, 100 max.

| Class | A, | <b>Amplifier</b> |  |
|-------|----|------------------|--|
|-------|----|------------------|--|

| CHARACTERISTICS:                  |       |       |
|-----------------------------------|-------|-------|
| Plate Voltage                     | 250   | volts |
| Grid-No.2 (Screen-Grid) Voltage   | 250   | volts |
| Grid-No.1 (Control-Grid) Voltage  | 7.3   | volts |
| Mu-Factor, Grid No.2 to Grid No.1 | 19.5  |       |
| Plate Resistance (Approx.)        | 40000 | ohms  |
| Transconductance                  | 11300 | μmhos |
| Plate Current                     | 48    | ma    |
| Grid-No.2 Current                 | 5.5   | ma    |
| Push Puli Clase AD Amplifica      |       |       |

#### Push-Pull Class AB, Amplifier


|   | ,       | Grid-No.2<br>Special   |
|---|---------|------------------------|
| MAXIMUM RATINGS (Design-Center Values): Plate Voltage | 400 max | Connection•<br>375 max |

|   |            | Grid-No.2           |          |
|---|------------|---------------------|----------|
|   | •          | Special Connection• | •        |
| Grid-No.2 Voltage                             | 300 max    | Connections         | volts    |
| Cathode Current                               | 65 max     | 65 max              | ma       |
| Plate Dissipation                             | 12 max     | 12 max              | watts    |
| Zero-Signal Grid-No.2 Input                   | 2 max      | 2 max               | watts    |
| Maximum-Signal Grid-No.2 Input                | 4 max      | 4 max               | watts    |
| TYPICAL OPERATION (Values are for two tubes): |            |                     |          |
| Plate Supply Voltage                          | -          | 375                 | volts    |
| Plate Voltage                                 | 400        | _                   | volts    |
| Grid-No.2 Supply Voltage                      | _          |                     |          |
| Grid-No.2 Voltage                             | 300        | •                   | volts    |
| Grid-No.1 Voltage                             | <b>—15</b> | _                   | volts    |
| Cathode-Bias Resistor                         | -          | 220                 | ohms     |
| Peak AF Grid-No.1 Voltage                     | 14.8       | 17.7                | volts    |
| Zero-Signal Plate Current                     | 15         | 70                  | ma       |
| Maximum-Signal Plate Current                  | 105        | 81                  | ma       |
| Zero-Signal Grid-No.2 Current                 | 1.6        | •                   | ma       |
| Maximum-Signal Grid-No.2 Current              | 25         | •                   | ma       |
| Effective Load Resistance (Plate-to-plate)    | 8000       | 11000               | ohms     |
| Total Harmonic Distortion                     | 4          | 3                   | per cent |
| Maximum-Signal Power Output                   | 24         | 16.5                | watts    |
| MAXIMUM CIRCUIT VALUES:                       | Fixed Bias | Cathode B           | ias      |

• Grid No.2 of each tube connected to tap on plate winding of output transformer.

• Obtained from taps on primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to supply 43 per cent of the plate signal voltage to grid No.2 of each output tube.

0.3 max



Grid-No.1-Circuit - Resistance

#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in a wide variety of applications in high-quality, highfidelity audio equipment, particularly in phase-splitters, tone-control amplifiers, and high-gain voltage amplifiers in which low hum and reduced noise

7199

1 max megohm

are required. Outline 6B, Outlines section. Tube requires miniature nine-contact socket and may be mounted in any position. For operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. In direct-coupled voltage-amplifier phase-splitter circuits, the pentode unit should drive the triode unit.


| Heater Voltage (ac/dc)                                  | 6.3       | volts  |
|---|-----------|--------|
| Heater Current  | 0.45      | ampere |
| Peak Heater-Cathode Voltage:                            |           | -      |
| Heater positive with respect to cathode                 | 200 max   | volts  |
| Heater negative with respect to cathode                 | 200 • max | volts  |
| Direct Interelectrode Capacitances:                     |           |        |
| Triode Unit:  |           |        |
| Grid to Plate   | 2         | pf     |
| Grid to Cathode and Heater                              | 2.3       | pf     |
| Plate to Cathode and Heater                             | 0.3       | pf     |
| Pentode Unit:   |           | •      |
| Grid No.1 to Plate                                      | 0.06 max  | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and |           | -      |
| Internal Shield   | 5         | pf     |
| Plate to Cathode, Heater, Grid No.2, Grid No.3, and     |           | -      |
| Internal Shield   | 2         | pf     |
| • The dc component must not exceed 100 volts.           |           | -      |


| EQUIVALENT-NOISE AND HUM VOLTAGE REFEREN | CED TO GR   | ID:          |             |
|--|-------------|--------------|-------------|
|  | Triode Unit | Pentode Unit |             |
| Median Value (rms)                       | 10†         | 35●          | $\mu$ volts |
| Maximum Value (rms)                      | 150†        | 100•         | μvolts      |

- † Measured in "true rms" units under the following conditions: heater volts (ac), 6.3; center tap of heater transformer connected to ground; plate-supply volts, 250; plate load resistor, 0.1 megohm; cathode resistor, 1500 ohms; grid resistor, 0.05 megohm; and amplifier covering frequency range between 25 and 10000 cycles per second.
- Same conditions as for triode unit except: grid-No.2 supply volts, 250; grid-No.2 resistor, 0.33 megohm; grid-No.2-bypass capacitor, 0.22  $\mu$ f; cathode resistor, 1200 ohms; and grid-No.1 resistor, 0.05 megohm.

Class A. Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):              | Triode Unit | Pentode Unit      |
|---|-------------|-------------------|
| Plate Voltage   | 330 max     | 330 max volts     |
| Grid-No.2 (Screen-Grid) Voltage                       |             | See curve page 75 |
| Grid-No.2 Supply Voltage                              | _           | 330 max volts     |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value | 0 max       | 0 max volts       |
| Plate Dissipation                                     | 2.4 max     | 3 max watts       |
| Grid-No.2 Input:                                      |             |                   |
| For grid-No.2 voltages up to 165 volts                |             | 0.6 max watt      |
| For grid-No 2 voltages between 165 and 330 volts      |             | See curve page 75 |






| CHARACTERISTICS:                              | Triode Unit | Pento | de Unit |        |
|---|-------------|-------|---------|--------|
| Plate Supply Voltage                          | 215         | 100   | 220     | volts  |
| Grid-No.2 Supply Voltage                      |             | 50    | 130     | volts  |
| Grid-No.1 Voltage                             | 8.5         |       | _       | volts  |
| Cathode-Bias Resistor                         |             | 1000  | 62      | ohms   |
| Amplification Factor                          | 17          | _     |         |        |
| Plate Resistance (Approx.)                    | 0.0081      | 1     | 0.4     | megohm |
| Transconductance                              | 2100        | 1500  | 7000    | μmhos  |
| Grid-No.1 Voltage (Approx.) for plate current |             |       |         |        |
| of 10 μa                                      | 40          | -4    |         | volts  |
| Plate Current                                 | 9           | 1.1   | 12.5    | ma     |
| Grid-No.2 Current                             | _           | 0.35  | 3.5     | ma     |

| Grid-No.2 Current  | _ | 0.35                              | 3.5                                     | ma     |
|--|---|-----------------------------------|---|--------|
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance:* For fixed-bias operation For cathode-bias operation |   | Triode Unit<br>0.5 max<br>1.0 max | Pentode Unit<br>0.25 max 1<br>1.0 max 1 | megohm |

\* If either unit is operated at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated value.



#### DUAL TRIODE

Miniature type used for combined firstand second-stage audio preamplification in high-fidelity phonograph or kT, tape equipment. Tube has high-mu unit and medium-mu unit. Outline 6B, Outlines section. Tube requires minia-

7247

ture nine-contact socket and may be operated in any position. Heater volts (ac/dc), 12.6 (series), 6.3 (parallel); amperes, 0.15 (series), 0.3 (parallel); peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A. Amplifier MAXIMUM RATINGS (Design-Maximum Values): Unit No.1 Unit No.2 Plate Voltage ..... 330 max 330 max volts Grid Voltage 55 max 55 max volts Negative-bias value ..... 0 max volts Positive-bias value ..... 0 max 22 max Cathode Current ..... ma 1.2 max 3 max Plate Dissipation ..... watts CHARACTERISTICS: Unit No.1 Unit No. 2 100 100 250 250 volts Plate Voltage ..... Grid Voltage -20 -8.5volts -1 100 100 20 17 Amplification Factor ..... Plate Resistance (Approx.) ...... 80000 62500 6500 7700 ohms Transconductance ..... 1250 1600 3100 2200 *u*mhos Plate Current ...... 0.51.2 11.8 10.5 ma Grid Voltage (Approx.) for plate current -24 volts of 10 μa ...... MAXIMUM CIRCUIT VALUES: Grid-Circuit Resistance: Unit No.1 Unit No.2 For fixed-bias operation ..... 15 max 0.5 max megohms 1 max megohm For cathode-bias operation ..... HUM OUTPUT VOLTAGE: Average Value (rms, cathode bypassed)...... 1.8 µvolts Maximum Value (rms, cathode unbypassed)..... uvolts · Measured in "true rms" units under the following conditions: heater volts (ac), 6.3 (parallel


Measured in "true rms" units under the following conditions: heater volts (ac), 6.3 (parallel connection); center tap of heater transformer connected to ground; dc plate supply volts, 250; plate load resistor, 0.1 megohm; cathode resistor, 2700 ohms; cathode-bypass capacitor, 100 μf; grid resistor, 0 ohms; amplifier covering frequency range of 25 to 10000 cps.

Same conditions as above, except that cathode resistor is unbypassed and grid resistor is 0.05 megohm.

#### POWER PENTODE

7355

Glass octal type used in the poweroutput stage of high-fidelity audiofrequency amplifier systems. Outline, 13F, Outlines section. Tube requires octal socket and may be mounted in any position. Heater volts (ac/dc), 6.3;



amperes, 0.8; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values):  | ••            |                |                  |
|---|---------------|----------------|------------------|
| Plate Voltage   |               | 500 max        | volts            |
| Grid-No.2 (Screen-Grid) Voltage   |               | 400 max        | volts            |
| Grid-No.1 (Control-Grid) Voltage, Positive-bias value   |               | 0 max          | volts            |
| Plate Dissipation   |               | 18 max         | watts            |
| DC Grid-No.2 Input  |               | 3.5 max        | volts            |
| Average Cathode Current   |               | 100 max        | ma               |
|   |               |                |                  |
| TYPICAL OPERATION AND CHARACTERISTICS:  |               | 250            | volts            |
| Plate Voltage Grid-No.2 Voltage   |               | 225            | volts            |
| Grid-No.1 Voltage   |               | -15            | volts            |
| Peak AF Grid-No.1 Voltage   |               | 15             | volts            |
| Plate Resistance (Approx.)  |               | 42000          | ohms             |
| Transconductance  |               | 7600           | μmhos            |
| Zero-Signal Plate Current   |               | 62             | ma               |
| Maximum Signal Plate Current  |               | 74             | ma               |
| Zero-Signal Grid-No.2 Current   |               | 3.2            | ma               |
| Maximum-Signal Grid-No.2 Current  |               | 16.5           | ma               |
| Load Resistance   |               | 2500           | ohms             |
| Total Harmonic Distortion (Approx.)   |               | 15             | per cent         |
| Maximum-Signal Power Output   |               | 9              | watts            |
| Grid-No.1 Voltage (Approx.) for plate current of 500 µs   |               | -35            | volts            |
| MAXIMUM CIRCUIT VALUES: Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation |               |                | megohm<br>megohm |
| • Grid-No.2 input may reach 7 watts during peak levels of   | of speech and | music signals. |                  |
| Push-Pull Class AB, Ar  | nnlifiar      |                |                  |
| MAXIMUM RATINGS:  | upunei        |                |                  |
| (Same as for Class A <sub>1</sub> Amplifier)  |               |                |                  |
| TYPICAL OPERATION (Values are for two tubes):   |               |                |                  |
| Plate Voltage   | 300           | 400            | volts            |
| Grid-No.2 Voltage   | 250           | 300            | volts            |
| Grid-No.1 Voltage   | -21           | -34            | volts            |
| Peak AF Grid-No.1 Voltage   | 42            | 60             | volts            |
| Zero-Signal Plate Current   | 100           | 56             | ma               |
| Maximum-Signal Plate Current  | 185           | 175            | ma               |
| Zero-Signal Grid-No.2 Current   | 5.5           | 3.5            | ma               |
| Maximum-Signal Grid-No.2 Current  | 24            | 24             | ma               |
| Effective Load Resistance (Plate-to-plate)  | 4000          | 5000           | ohms             |

#### **BEAM POWER TUBE**


2 28.5

7408

Total Harmonic Distortion . . .

Maximum-Signal Power Output

Glass octal type used as output amplifier tube in high-quality sound systems. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any position. Heater volts (ac/dc), 6.3; amperes, 0.45; peak




per cent

watts

heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A Amplifias

| Class A, Amplitiei                       | Í    |         |          |
|--|------|---------|----------|
| MAXIMUM RATINGS (Design-Maximum Values): |      |         |          |
| Plate Voltage                            |      | 350 max | volts    |
| Grid-No.2 (Screen-Grid) Voltage          |      | 315 max | volts    |
| Grid-No.2 Input                          |      | 2.2 max | watts    |
| Plate Dissipation                        |      | 14 max  | watts    |
| TYPICAL OPERATION AND CHARACTERISTICS:   |      |         |          |
| Plate Voltage                            | 60   | 250     | volts    |
| Grid-No.2 Voltage                        | 250  | 250     | volts    |
| Grid-No.1 (Control-Grid) Voltage         | 0    | -12.5   | volts    |
| Peak AF Grid-No.1 Voltage                | _    | 12.5    | volts    |
| Zero-Signal Plate Current                | 100● | 45      | ma       |
| Maximum-Signal Plate Current             | _    | 47      | ma       |
| Zero-Signal Grid-No.2 Current            | 22•  | 4.5     | ma       |
| Maximum-Signal Grid-No.2 Current         | _    | 7       | ma       |
| Plate Resistance (Approx.)               | _    | 50000   | ohms     |
| Transconductance                         |      | 4100    | μmhos    |
| Load Resistance                          | _    | 5000    | ohms     |
| Total Harmonic Distortion                | _    | 7       | per cent |
| Maximum-Signal Power Output              | _    | 4.5     | watts    |
| MAXIMUM CIRCUIT VALUES:                  |      |         |          |
| Grid-No.1-Circuit Resistance:            |      |         |          |
| For fixed-bias operation                 |      | 0.1 max | megohm   |
| For cathode-bias operation               |      |         | megohm   |
|  |      |         |          |



#### SHARP-CUTOFF PENTODE

• This value can be measured by a method involving a recurrent waveform such that the

G2 Miniature type used in compact audio equipment, especially in low-hum, low-microphonic, high-gain, resistance-coupled-amplifier applications. Outline 5C, Outlines section. This type is identical with miniature type 6AU6A

**7543** 

except that it has a controlled hum characteristic.

maximum ratings of the tube will not be exceeded.

#### HUM OUTPUT VOLTAGE:

| Average Value (rms, cathode bypassed)   | 1.2† | millivolts |
|---|------|------------|
| Average Value (rms, cathode unbypassed) | 0.9• | millivolt  |

† Measured in "true rms" units under the following conditions: heater volts (ac), 6.3; center tap of heater transformer connected to ground; plate and grid-No.2 supply volts, 250; plate load resistor, 0.27 megohm; grid No.3 and internal shield connected to cathode at socket; grid-No.2 resistor, 0.68 megohm; grid-No.1 resistor, 0.1 megohm; cathode resistor, 1000 ohms; grid resistor of following stage, 10 megohms; and stage gain, 340.

• Same conditions as above except cathode resistor is unbypassed and stage gain is 110.



#### **POWER PENTODE**

Glass octal type used as audio-frequency power-output tube in high-quality audio applications. Outline 13D, Outlines section. Tube requires octal socket and may be mounted in any position. Heater volts (ac/de), 6.3;

**7591** 

amperes, 0.8; peak heater-cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A. Amplifier

| MAXIMUM RATINGS (Design-Maximum Values): |         |          |
|--|---------|----------|
| Plate Voltage                            | 550 max | volts    |
| Grid-No.2 (Screen-Grid) Voltage          | 440 max | volts    |
| Cathode Current                          | 85 max  | ma       |
| Plate Dissipation                        | 19 max  | watts    |
| Grid-No.2 Input                          | 3.3 max | watts    |
| TYPICAL OPERATION AND CHARACTERISTICS:   |         |          |
| Plate Voltage                            | 300     | volts    |
| Grid-No.2 Voltage                        | 300     | volts    |
| Grid-No.1 (Control-Grid) Voltage         | -10     | volts    |
| Peak AF Grid-No.1 Voltage                | 10      | volts    |
| Zero-Signal Plate Current                | 60      | ma       |
| Maximum-Signal Plate Current             | 75      | ma       |
| Zero-Signal Grid-No.2 Current            | 8       | ma       |
| Maximum-Signal Grid-No.2 Current         | 15      | ma       |
| Triode Amplification Factor*             | 16.8    |          |
| Plate Resistance (Approx.)               | 29000   | ohms     |
| Transconductance                         | 10200   | μmhos    |
| Load Resistance                          | 3000    | ohms     |
| Total Harmonic Distortion                |         | per cent |
| Maximum-Signal Power Output              | 11      | watts    |
| MAXIMUM CIRCUIT VALUES:                  |         |          |

Grid-No.1-Circuit Resistance:

For fixed-bias operation 0.3 max megohm For cathode-bias operation ..... 1 max megohm

- Grid-No.2 input may reach 6 watts during peak levels of speech and music signals.
- \* Triode connection, grid No.2 connected to plate.

#### Push-Pull Class AB, Amplifier

#### **MAXIMUM RATINGS:**

(Same as for Class A1 Amplifier)


#### TYPICAL OPERATION

(Values are for two tubes): Plate Supply Voltage ..... Cathode Bias Fixed Bias 450 450 Grid-No.2 Supply Voltage 350 volts Grid-No.1 Supply Voltage 350 400 400 volts -15.5-21 Cathode-Bias Resistor volts 200 (Common to both cathodes) ... ohms Peak AF Grid-No.1-to-Grid-No.1 Voltage .... 31 42 28 volts Zero-Signal Plate Current ..... 92 66 82 ma Maximum-Signal Plate Current ..... 130 94 144 ma Zero-Signal Grid-No.2 Current ..... 9.4 13 11.5 ma 28.6 Maximum-Signal Grid-No.2 Current ...... 30 22 ma Effective Load Resistance (Plate-to-plate) .... 6600 6600 9000 ohms 2 1.5 2 per cent Total Harmonic Distortion ..... Maximum-Signal Power Output ...... 45 watts

#### BEAM POWER TUBE

7695

Neonoval type used as af poweramplifier tube. Outline 13D, Outlines section. Tube requires neonoval ninecontact socket and may be mounted in any position. Heater volts (ac/dc), amperes, 0.15; peak heater-50;



cathode volts, 200 (the dc component must not exceed 100 volts when the heater is positive with respect to the cathode).

Class A, Amplifier

| MAXIMUM RATINGS (Design-Maximum Values): |         |       |
|--|---------|-------|
| Plate Voltage                            | 150 max | volts |
| Grid-No.2 (Screen-Grid) Voltage          | 150 max | volts |
| Grid-No.2 Input                          | 2.5 max | watts |
| Plate Dissipation                        | 16 max  | watts |

|   | Fixed      | Cathode            |                  |
|---|------------|--------------------|------------------|
| TYPICAL OPERATION AND CHARACTERISTICS:  | Bias       | Bias               |                  |
| Plate Supply Voltage  | 130        | 140                | volts            |
| Grid-No.2 Supply Voltage  | 130        | 140                | volts            |
| Grid-No.1 (Control-Grid) Voltage  | -11        | _                  | volts            |
| Cathode-Bias Resistor   | -          | 100                | ohms             |
| Peak AF Grid-No.1 Voltage   | 11         | 11.3               | volts            |
| Zero-Signal Plate Current   | 100        | 100                | ma               |
| Maximum-Signal Plate Current  | 108        | 100                | ma               |
| Zero-Signal Grid-No.2 Current   | 5          | 5                  | ma               |
| Maximum-Signal Grid-No.2 Current  | 15         | 14                 | ma               |
| Plate Resistance (Approx.)  | 7000       | _                  | ohms             |
| Transconductance  | 11000      |                    | μmhos            |
| Load Resistance   | 1100       | 1100               | ohms             |
| Total Harmonic Distortion   | 11         | 11                 | per cent         |
| Maximum-Signal Power Output   | 4.5        | 4.5                | watts            |
| Grid-No.1-Circuit Resistance:  For fixed-bias operation  For cathode-bias operation |            | 0.1 max<br>0.5 max | megohm<br>megohm |
| Push-Pull Class AB, A   | mplifier   |                    |                  |
| MAXIMUM RATINGS: (Same as for Class A <sub>1</sub> Amplifier):                      |            |                    |                  |
| TYPICAL OPERATION (Values are for two tubes):                                       | Fixed Bias | Cathode Bias       |                  |
| Plate Supply Voltage  | 130        | 140                | volts            |
| Grid-No.2 Supply Voltage  | 130        | 140                | volts            |
| Grid-No.1 Voltage   | 12         | _                  | volts            |
| Cathode-Bias Resistor   | _          | 50                 | ohms             |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage  | 22.6       | 22.6               | volts            |
| Zero-Signal Plate Current   | 195        | 210                | ma               |
| Maximum-Signal Plate Current  | 220        | 220                | ma               |
| Zero-Signal Grid-No.2 Current   | 9          | 9                  | ma               |
| Maximum-Signal Grid-No.2 Current  | 24         | 20                 | ma               |
| Effective Load Resistance (Plate-to-plate)  | 1800       | 1500               | ohms             |

### **POWER PENTODE**

10



Total Harmonic Distortion .....

Maximum-Signal Power Output .....

Novar type used in output stages of high-fidelity audio amplifiers or radio receivers; used in applications requiring relatively large power output. Outline 11C or 30D, Outlines section. Tube requires novar nine-contact

**7868** 

per cent

socket and may be operated in any position. It is especially important that this tube, like other power-handling tubes, be adequately ventilated.

| Heater Voltage (ac/dc)                                 | 6.3     | volts  |
|--|---------|--------|
| Heater Current   | 0.8     | ampere |
| Peak Heater-Cathode Voltage:                           |         |        |
| Heater negative with respect to cathode                | 200 max | volts  |
| Heater positive with respect to cathode                | 2000max | volts  |
| Direct Interelectrode Capacitances (Approx.):          |         |        |
| Grid No.1 to Plate                                     | 0.15    | pf     |
| Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 | 11      | pf     |
| Plate to Cathode, Heater, Grid No.2, and Grid No.3     | 4.4     | pf     |
| □ The dc component must not exceed 100 volts.          |         |        |
| Class & Amulitian                                      |         |        |

| Class A, Amplifier                       |           |       |
|--|-----------|-------|
| MAXIMUM RATINGS (Design-Maximum System): |           |       |
| Plate Voltage                            | 550=max   | volts |
| Grid-No.2 (Screen-Grid) Voltage          | 440 max   | volts |
| Plate Dissipation                        | 19 max    | watts |
| Grid-No.2 Input                          | 3.3 • max | watts |
| DC Cathode Current                       | 90 max    | ma    |
| Bulb Temperature (At hottest point)      | 240 max   | •c    |
|  |           |       |

| TVDICAT | OPEDATION | AND | CHARACTERISTICS: |
|---------|-----------|-----|------------------|
| INPICAL | UPERATION | AND | CHARACIERISHUS:  |

| Plate Supply Voltage             | 300   | volts    |
|----------------------------------|-------|----------|
| Grid-No.2 Voltage                | 300   | volts    |
| Grid-No.1 (Control-Grid) Voltage | -10   | volts    |
| Peak AF Grid-No.1 Voltage        | 10    | volts    |
| Zero-Signal Plate Current        | 60    | ma       |
| Maximum-Signal Plate Current     | 75    | ma       |
| Zero-Signal Grid-No.2 Current    | 8     | ma       |
| Maximum-Signal Grid-No.2 Current | 15    | ma       |
| Plate Resistance (Approx.)       | 29000 | ohms     |
| Transconductance                 | 10200 | μmhos    |
| Effective Load Resistance        | 3000  | ohms     |
| Total Harmonic Distortion        | 13    | per cent |
| Maximum-Signal Power Output      | 1 i   | watts    |

#### MAXIMUM CIRCUIT VALUES:

Grid-No.1-Circuit Resistance:

For fixed-bias operation 0.3 max megohm
For cathode-bias operation 1 max megohm


- In push-pull circuits where the grid No.2 of each tube is connected to a tap on the plate winding of the output transformer, this maximum rating is 440 volts.
- Grid No.2 input may reach 6 watts during peak levels of speech and music signals.

#### Push-Pull Class AB, Amplifier

#### **MAXIMUM RATINGS:**

(Same as for Class A1 Amplifier)

TYPICAL OPERATION Cathode (Values are for two tubes): Fixed Bias Rias 300 Plate Supply Voltage ...... 350 400 450 450 450 volts Grid-No.2 Supply Voltage ....... 350 300 350 350 400 400 volts Grid-No.1 Voltage ..... -12.5 - 15.5-16-16.5-21 volts Cathode-Bias Resistor (Common to both cathodes) ..... 170 ohms Peak AF Grid-No.1-to-Grid-No.1 Voltage ..... 25 31 32 33 42 31 volts Zero-Signal Plate Current 74 72 64 60 40 86 ma Maximum-Signal Plate Current . . . . 116 130 135 142 145 94 ma Zero-Signal Grid-No.2 Current .... 10 9.5 8 7.2 5 10 ma Maximum-Signal Grid-No.2 Current 28 32 28 30 26 20 ma Effective Load Resistance 6600 6600 10000 (Plate-to-plate) 6600 6600 6600 ohms Total Harmonic Distortion ...... 5 2.5 2 2.5 2 per cent 28 Maximum-Signal Power Output .... 24 44 watts



ma

ma

ma

Ohms

watts

per cent

#### Push-Pull Class AB, Amplifier

Grid No.2 of Each Tube Connected to Tap on Plate Winding of Output Transformer\*

| MAXIMUM RATINGS:                                |       |         |       |
|---|-------|---------|-------|
| (Same as for Class A <sub>1</sub> Amplifier)    | Fixed | Cathode |       |
| TYPICAL OPERATION (Values are, for two tubes):  | Bias  | Bias    |       |
| Plate Supply Voltage                            | 400   | 425     | volts |
| Grid-No.2 Supply Voltage                        | *     | *       | volts |
| Grid-No.1 Voltage                               | -20.5 | _       | volts |
| Cathode-Bias Resistor (Common to both cathodes) | _     | 185     | ohms  |
| Peak AF Grid-No.1-to-Grid-No.1 Voltage          | 41    | 42      | volts |
| Zero-Signal Plate Current                       | 60    | 88      | ma    |

115

18

6600

Maximum-Signal Plate Current

Zero-Signal Grid-No.2 Current


Maximum-Signal Grid-No.2 Current

Effective Load Resistance (Plate-to-plate)

Total Harmonic Distortion .....

Maximum-Signal Power Output .....

<sup>\*</sup> Grid No.2 supply voltage is obtained from taps on the primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to apply 50 per cent of the plate signal voltage to the grid No.2 of each output tube.



MAXIMUM CIRCUIT VALUE: Triode-Grid-Circuit Resistance

#### **ELECTRON-RAY TUBE**

Miniature type with triode unit used to indicate visually by means of a fluorescent target the effects of changes in a controlling voltage. Tube is used for accurate tuning or modulation control. Outline 6F. Outlines section.

EM84/ 6FG6

3 max megohms

100

12

16

6600

Tube requires nine-contact socket and may be mounted in any position. For additional considerations, refer to Tuning Indication with Electron-Ray Tubes in Electron Tube Application section. Heater volts (ac/dc), 6.3; amperes, 0.27; peak heater-cathode volts, 100.

#### Indicator Service

MAXIMUM AND MINIMUM RATINGS (Design-Center Values):

| Ray-Control-Electrode Voltage:  |          |         |
|---|----------|---------|
| Without current flowing through series triode-plate resistor            | 550 max  | volts   |
| With current flowing through series triode-plate resistor               | 300 max  | volts   |
| Fluorescent-Target Voltage;   |          |         |
| Without current flowing through series triode-plate resistor            | 550 max  | volts   |
|   | (300 max |         |
| With current flowing through series triode-plate resistor               | 150 min  | volts   |
| Cathode Current   | 3 max    |         |
| Triode-Plate Dissipation  | 0.5 max  |         |
| Bulb Temperature (At hottest point)                                     | 120 max  |         |
|   |          |         |
| TYPICAL OPERATION WITH RAY-CONTROL ELECTRODE CONNECTED TO TRIODE PLATE: |          |         |
| Triode-Plate Supply Voltage   | 250      | volts   |
| Fluorescent-Target Voltage 250  | 250      | volts   |
| Series Triode-Plate Resistor 0.47                                       | 0.47     | megohm  |
| Triode-Grid Supply Voltage 0  | -22      | volts   |
| Triode-Grid Resistor 3  | 3        | megohms |
| Triode-Plate Current 0.45   | 0.06     | ma      |
| Fluorescent-Target Current 1.1  | 1.6      | ma      |
| Length of Dark Part of Fluorescent Target 0.83 ± 0.20                   | 0        | inch    |
| Length of Dark Part of Fluorescent Target                               |          |         |
| when triode-grid resistor is 0 ohms $0.94 \pm 0.20$                     | _        | inch    |

# RCA Types for

NOTES For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

| RCA<br>Type    | Name                               | Tube Dimensions and Basing Diagram△ Dim. B.D. |            | Heater or Filament (F) Unless specified all types have heaters.  Heater with controlled warmup time.  Volts Amps. |      | Use Values to right give operating conditions and characteristics for indicated typical use |
|----------------|------------------------------------|---|------------|---|------|---|
| 0 <b>Z</b> 4   | Full-Wave<br>Gas Rectifier         | 24  | 4R         |   |      | Rectifier   |
| 0 <b>Z</b> 4-G | Full-Wave<br>Gas Rectifier         | 290   | 4R         |   |      | Rectifier   |
| 1A3            | Diode                              | 5C  | 5AP        | 1.4   | 0.15 | Rectifier   |
| 1A4-P          | Remote-Cutoff<br>Pentode           | 248   | 4M         | 2.0F  | 0.06 | Class A Amplifier   |
| 1A5-GT         | Power Pentode                      | 130   | 6X         | 1.4F  | 0.05 | Class A Amplifier   |
| 1A6            | Pentagrid<br>Converter o           | 248   | 6L         | 2.0F  | 0.06 | Converter   |
| 1A7-GT         | Pentagrid<br>Converter <b>9</b>    | 14A   | 7Z¥        | 1.4F  | 0.05 | Converter   |
| 1AC5           | Power<br>Pentode                   | 28A   | 8CP        | 1.25F   | 0.04 | Class A Amplifier   |
| 1AD5           | Sharp-Cutoff<br>Pentode            | 29A   | 8CP        | 1.25F   | 0.04 | Class A Amplifier   |
| 1AX2           | Half-Wave<br>Rectifier             | 7A  | 9Y         | 1.4F  | 0.65 | Pulsed Rectifier in<br>TV Receivers   |
| 1B3-GT         | Half-Wave<br>Rectifier             | 14E   | 30         | 1.25F   | 0.2  | Pulsed Rectifier in<br>TV Receivers   |
| 1B4-P          | Sharp-Cutoff<br>Pentode            | 24B   | 4M         | 2.0F  | 0.06 | Class A Amplifier   |
| 1B5/25S        | Twin Diode—<br>Medium-Mu<br>Triode | 22 or<br>13H                                  | 6M         | 2.0F  | 0.06 | Triode Unit as<br>Class A Amplifier   |
| 1B7-GT         | Pentagrid<br>Converter #           | 14A   | 7Z¥        | 1.4F  | 0.10 | Converter   |
| 1C5-GT         | Power Pentode                      | 13D   | 6X         | 1.4F  | 0.10 | Class A Amplifier   |
| 1C6            | Pentagrid<br>Converter ø           | 24B   | 6L         | 2.0F  | 0.12 | Converter   |
| 1C7-G          | Pentagrid<br>Converter #           | 23  | 7Z         | 2.0F  | 0.12 | Converter   |
| 1D5-GP         | Remote-Cutoff<br>Pentode           | 23  | 5Y         | 2.0F  | 0.06 | Class A Amplifier   |
| 1D5-GT         | Remote-Cutoff<br>Tetrode           | 23  | 5R         | 2.0F  | 0.06 | Class A Amplifier   |
| 1D7-G          | Pentagrid<br>Converter &           | 23  | 7 <b>Z</b> | 2.0F  | 0.06 | Converter   |

# Renewal Use

| Plate<br>Sup-<br>ply   | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor | Screen<br>Sup-<br>ply | Screen<br>Cur-<br>rent | Plate<br>Cur-<br>rent | AC Plate<br>Resis-<br>tance | conduc-<br>tance      | Amplifi-<br>cation<br>Factor          | Locad<br>for Stated<br>Power<br>Output | Power<br>Out-<br>put | RGA<br>Type    |  |
|--|---|-----------------------|------------------------|-----------------------|-----------------------------|-----------------------|---------------------------------------|--|----------------------|----------------|--|
| Volts  | Ohms (Ω)  | Volts                 | Ma                     | Ma.                   | Chms                        | Micromhos             | Plate Curre                           | Ohms                                   | Watts                |                |  |
|  | ng-Supply Vutput Curr                               |                       |                        |                       | peak voits.                 | DC O                  | utput Volta                           | agé, 300 r                             | nax. volts.          | 0 <b>Z</b> 4   |  |
|  | ng-Supply Vutput Curr                               |                       |                        |                       | peak volts.                 |                       | Plate Curre<br>utput Volta            |  |                      | 0 <b>Z</b> 4-G |  |
|  | Max. Peak l<br>Max. Peak l                          |                       |                        | з, 330                |                             | DC Outpu<br>Peak Heat |                                       |  | 40                   | 1A3            |  |
|  |   | F                     | or other c             | haracteri             | stics, refer                | to Type 1D            | 5-GP.                                 |  |                      | 1A4-P          |  |
| 85 - 4.5v 85 0.7 3.5 300000 800 25000 0.100<br>90 - 4.5v 90 1.1 4.0 300000 850 25000 0.115   |   |                       |                        |                       |                             |                       |                                       |  |                      |                |  |
| 135<br>1 <b>8</b> 0  |   |                       |                        |                       |                             |                       |                                       |  | 1A6                  |                |  |
| 90   | 0v  | 45                    | 0.7                    | 0.6                   | 600000                      | Oscillator-           | d (#2): 90<br>Grid (#1)<br>1 Transcon | Resistor,                              | 0.2 meg.             | 1A7-GT         |  |
| 45<br>67.5   | - 3v<br>- 4.5v                                      | 45<br>67.5            | 0.2<br>0.4             | 1.0                   | 170000<br>150000            | 600<br>750            |                                       | 40000<br>25000                         | 0.015<br>0.050       | 1AC5           |  |
| 30<br>67.5   | 0v<br>0v  | 30<br>67.5            | 0.16<br>0.75           | 0.45<br>1.85          | 700000<br>700000            | 430<br>735            |                                       |  |                      | 1AD5           |  |
|  | x. Peak Inv<br>x. Peak Pla                          |                       |                        | 5000                  | M                           | lax. Averag           | e Plate Ma                            | a., 0.5                                |                      | 1AX2           |  |
|  | x. Peak Inv<br>x. Peak Pla                          |                       |                        | 6000                  | М                           | ax. Averag            | e Plate Ma                            | ., 0.5                                 |                      | 1B3-GT         |  |
|  |   | F                     | or other c             | haracteri             | stics, refer                | to Type 1E            | 5-GP.                                 |  |                      | 1B4-P          |  |
|  |   | F                     | or other c             | haracteri             | stics, refer                | to Type 1F            | 16-G.                                 |  |                      | 1B5/25S        |  |
|  |   | Fo                    | r other ch             | aracterist            | ics, refer to               | Type 1A7              | -GT.                                  |  |                      | 1B7-GT         |  |
| 90   | 7.5v  | 90                    | 3.5                    | 7.8                   | 115000                      | 1550                  |                                       | 8000                                   | 0.24                 | 1C5-GT         |  |
|  |   | F                     | or other c             | haracteri:            | stics, refer                | to Type 1C            | 7-G.                                  | •                                      | •                    | 1C6            |  |
| 135 - 3v 67.5 2.5 1.3 600000 Anode-Grid (#2): 180 max. volts, 4.0 ma. Oscillator-Grid (#1) Resistor a. Conversion Transcond., 325 micromhos. |   |                       |                        |                       |                             |                       |                                       |  | 1C7-G                |                |  |
| 90 {- 3v   67.5   0.9   2.2   600000   720   180   min.   67.5   0.8   2.3   1.0§   750  |   |                       |                        |                       |                             |                       |                                       |  |                      |                |  |
|  | , ,   |                       |                        | L                     | · · · · · ·                 | Type 1D5              | -GP.                                  |  |                      | 1D5-GT         |  |
|  |   | Fo                    | or other c             | haracteris            | tics, refer t               | о Туре 1А             | 6.                                    |  |                      | 1D7-G          |  |

| RCA<br>Type     | Name                                    | Dime      | ube<br>ensions<br>Basing<br>gram∆ | Filam<br>Unless sp<br>types hav<br>Heater | ent (F)<br>ent (F)<br>ecified all<br>e heaters.<br>with con-<br>raup time. | Use Values to right give eperating conditions and characteristics for indicated typical use |
|-----------------|---|-----------|-----------------------------------|---|--|---|
|                 |   | Dim.      | B. D.                             | Yolts                                     | Amps.  |   |
| 1D8-GT          | Diode-Triode-<br>Power<br>Pentode       | 144       | BAJ                               | 1.4 <b>F</b>                              | 0.10   | Pentode Unit as<br>Class A Amplifier<br>Triode Unit as<br>Class A Amplifier                 |
| 1DN5            | Diode—<br>Semiremote-<br>Cutoff Pentode | 50        | 6BW                               | 1.4F                                      | 0.5  | Pentode Unit as<br>Class A Amplifier  |
| 1E5-GP          | Sharp-Cutoff<br>Pentode                 | 23        | 5Y                                | 2.0F                                      | 0.06   | Class A Amplifier   |
| 1E7-GT          | Twin Power Pentode                      | 13D       | 8C                                | 2.0F                                      | 0.24   | Class A Amplifier   |
| 1E8             | Pentagrid<br>Converter                  | 28A       | 8CN                               | 1.25F                                     | 0.04   | Converter   |
| 1F4             | Power Pentode                           | 28        | 5K                                | 2.0F                                      | 0.12   | Class A Amplifier   |
| 1F5-G           | Power Amplifier<br>Pentode              | 25        | 8X                                | 2.0F                                      | 0.12   | Class A Amplifier   |
| 1 <b>F</b> 6    | Twin Diode—<br>Sharp-Cutoff<br>Pentode  | 23        | 6W                                | 2.0F                                      | 0.06   | Pentode Unit as<br>Class A Amplifier  |
| 1F7-G           | Twin Diode—<br>Sharp-Cutoff<br>Pentode  | 23        | 7AF                               | 2.0F                                      | 0.06   | Pentode Unit as<br>Class A Amplifier  |
| 1G4-GT          | Medium-Mu<br>Triode                     | 130       | 58                                | 1.4F                                      | 0.05   | Class A Amplifier   |
| 1G5-G           | Power Pentode                           | 25        | 6X                                | 2.0F                                      | 0.12   | Class A Amplifier   |
| 1G6-GT          | High-Mu Twin<br>Power Triode            | 13D       | 7AB                               | 1.4F                                      | 0.10   | Class B Amplifier   |
| 1H4-G           | Medium-Mu<br>Triode                     | 22        | 53                                | 2.0F                                      | 0.06   | Class A Amplifier<br>Class B Amplifier  |
| 1H5-GT          | Diode—<br>High-Mu Triode                | 14A       | 823¢                              | 1.4F                                      | 0.05   | Triode Unit as<br>Class A Amplifier   |
| 1H6-G           | Twin Diode—<br>Medium-Mu<br>Triode      | 22        | 7AA                               | 2.0F                                      | 0.06   | Triode Unit as<br>Class A Amplifier   |
| 1J3             | Half-Wave<br>Rectifier                  | 14E       | 3C                                | 1.25F                                     | 0.2  | Pulsed Rectifier in<br>TV Receivers   |
| 1J5-G           | Power<br>Pentode                        | 25        | 8X                                | 2.0F                                      | 0.12   | Class A Amplifier   |
| 1J6-G<br>1J6-GT | Twin-Triode<br>Amplifiers               | 22<br>13F | 7AB                               | 2.0F                                      | 0.24   | Class B Amplifier   |
| 1K3             | Half-Wave<br>Rectifier                  | 148       | 3C                                | 1.25F                                     | 0.2  | Pulsed Rectifier in<br>TV Receivers   |
| 1L6             | Pentagrid<br>Converter <b>9</b>         | 5C        | 7DC                               | 1.4F                                      | 0.05   | Converter   |
| 1LA4            | Power Pentode                           | 128 5AD   |                                   | 1.4F                                      | 0.05   | Amplifier   |
| 1LA6            | Pentagrid<br>Converter 5                | 12B 7AK   |                                   | 1.4F                                      | 0.05   | Converter   |
| 1LB4            | Power Pentode                           | 128       | SAD                               | 1.4F                                      | 0.05   | Class A Amplifier   |

1.4F

0.05

Class A Amplifier

Sharp-Cutoff

Pentode

1LC5

NOTES

For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

| Plate<br>Sup-<br>ply  | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor | Screen<br>Sup-<br>ply | Screen<br>Cur-<br>rent | Plate<br>Cur-<br>rent | AC Plate<br>Resis-<br>tance | Trans-<br>conduc-<br>tance | Amplifi-<br>cation<br>Factor              | Load<br>for Stated<br>Power<br>Output | Power<br>Out-<br>put | RCA<br>Type     |  |
|---|---|-----------------------|------------------------|-----------------------|-----------------------------|----------------------------|---|---------------------------------------|----------------------|-----------------|--|
| Velts   | Ohms (\O)   | Voits                 | Ma                     | Ma_                   | Ohms                        | Micromhes                  |   | Ohms                                  | Walts                |                 |  |
| 90  | - 9v  | 90                    | 1.0                    | 5.0                   |                             | 925                        |   | 12000                                 | 0.200                | 170.05          |  |
| 90  | 0v  | _                     |                        | 1.1                   | 43500                       | 575                        | 25  | _                                     |                      | 1D8-GT          |  |
| 67.5  | 0v  | 67.5                  | 0.55                   | 2.1                   | 600000                      | 630                        |   |                                       |                      | 1DN5            |  |
| 90<br>180   | - 3v<br>- 3v  | 67.5<br>67.5          | 0.7<br>0.6             | 1.6<br>1.7            | 1.0§<br>1.5§                | 600<br>650                 |   |                                       |                      | 1E5-GP          |  |
| 135   | - 7.5v  | 135                   | 3.5                    | 10.5                  |                             |                            |   | 24000                                 | 0.575                | 1E7-GT          |  |
| 45<br>67.5  | 0v<br>0v  | 45<br>67.5            | 1.1<br>1.5             | 0.6<br>1.0            | 400000<br>400000            |                            | Grid (#1)<br>n Transcor                   |                                       |                      | 1E8             |  |
|   |   | F                     | or other o             | haracteri             | stics, refer                | to Type 11                 | F5-G.                                     |                                       |                      | 1F4             |  |
| 90<br>135   | - 3v<br>- 4.5v                                      | 90<br>135             | 1.1<br>2.4             | 4.0<br>8.0            | 240000                      | 1400                       |   | 20000                                 | 0.11<br>0.31         | 1F5-G           |  |
|   |   | F                     | ····                   |                       | stics, refer                | to Type 11                 | F7-G.                                     | _                                     |                      | 1 <b>F</b> 6    |  |
| 180   | - 1.5v  | 67.5                  | 0.7                    | 2.2                   |                             |                            |   |                                       |                      | 1F7-G           |  |
| 90  | 6v  |                       |                        | 2.3                   | 10700                       | 825                        | 8.8                                       |                                       |                      | 1G4-GT          |  |
| 90<br>135   | - 6v<br>-13.5v                                      | 90<br>135             | 2.5<br>2.5             | 8.5<br>9.7            | 133000<br>160000            | 1500<br>1550               |   | 8500<br>9000                          | 0.25<br>0.55         | 1G5-G           |  |
| 90  | 0v  |                       | 11                     |                       |                             |                            |   | 12000                                 | 0.350                | 1G6-GT          |  |
| 180   | -13.5v  | _                     |                        | 3.1                   | 10300                       | 900                        | 9.3                                       |                                       |                      | 1H4-G           |  |
| 157.5   | -15v  |                       |                        | 1.04                  |                             |                            |   | 8000                                  | 2.1†                 | -               |  |
| 90  | 0v  |                       |                        | 0.15                  | 240000                      | 275                        | 65  |                                       |                      | 1H5-GT          |  |
| 135   | - 3v  | _                     |                        | 0.8                   | 35000                       | 575                        | 20  |                                       |                      | 1H6-G           |  |
|   | Max. Peak l<br>Max. Peak l                          |                       |                        | , 26000 (             | Abs.)                       | Max. A                     | verage Pla                                | te Ma., 0                             | .5                   | 1J3             |  |
| 135   | -16.5v  | 135                   | 2.0                    | 7.0                   | 105000                      | 950                        |   | 13500                                 | 0.45                 | 1J5-G           |  |
| 135<br>135  | 0v<br>- 3v  | -                     |                        |                       | ver Output<br>tated plate-  |                            |   | 10000<br>10000                        | 2.1<br>1.9           | 1J6-G<br>1J6-GT |  |
|   | Max. Peak I<br>Max. Peak I                          |                       |                        | , 26000 (             | Abs.)                       | Max. A                     | verage Pla                                | te Ma., 0.                            | 5                    | 1K3             |  |
| 90 0v 45 0.6 0.5 650000 Anode-Grid (#2): 90 max. volts, 1.2 ma. Oscillator Grid (#1) Resistor, 0.2 meg. Conversion Transcond., 300 micromhos. |   |                       |                        |                       |                             |                            |   |                                       |                      |                 |  |
| For other characteristics, refer to Type 1A5-GT.  |   |                       |                        |                       |                             |                            |   |                                       |                      |                 |  |
| 90  | 0 <b>v</b>  | 65                    | 0.6                    | 0.55                  |                             | Conversion                 | hode ma., 4<br>n Transcon<br>l volts), 10 | d. (for gr                            |                      | 1LA6            |  |
| For other characteristics, refer to Pentode Unit of Type 1D8-GT.  |   |                       |                        |                       |                             |                            |   |                                       |                      |                 |  |
| 45<br>90  | 0v<br>0v  | 45<br>45              | 0.35<br>0.30           | 1.10                  | 700000<br>1.0§              | 750<br>775                 |   | =                                     |                      | 1LC5            |  |
| ئئت   |   |                       |                        |                       |                             |                            |   |                                       |                      |                 |  |

For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

| RCA<br>Type | Name                              | Dimer<br>and E | be<br>nsions<br>Basing<br> ram∆ | Filam<br>Unless s<br>types ha<br>• Heater | ter or<br>ent (F)<br>pecified al<br>ve heaters<br>with con-<br>armup time | operating conditions  |
|-------------|-----------------------------------|----------------|---------------------------------|---|---|---|
|             |                                   | Dim.           | B. D.                           | Velts                                     | Amps.   | anakusee sypaan ese   |
| 1LC6        | Pentagrid<br>Converter <b>s</b>   | 128            | 7AK                             | 1.4F                                      | 0.05  | Converter   |
| 1LD5        | Diode—<br>Sharp-Cutoff<br>Pentode | 128            | 8AX                             | 1.4F                                      | 0.05  | Pentode Unit as<br>Class A Amplifier                        |
| 1LE3        | Medium-Mu<br>Triode               | 128            | 444                             | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1LG5        | Remote-Cutoff<br>Pentode          | 128            | 740                             | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1LH4        | Diode—<br>High-Mu Triode          | 128            | 5AG                             | 1.4F                                      | 0.05  | Triode Unit as<br>Class A Amplifier                         |
| 1LN5        | Sharp-Cutoff<br>Pentode           | 12B            | 7A0                             | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1N2-A       | Half-Wave<br>Rectifier            | 18A            | 3C                              | 1.25F                                     | 0.2   | Pulsed Rectifier in<br>TV Receivers                         |
| 1N5-GT      | Sharp-Cutoff<br>Pentode           | 14A            | 5Y×                             | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1N6-G       | Diode—<br>Power Pentode           | 28A            | 7AM                             | 1.4F                                      | 0.05  | Pentode Unit as<br>Class A Amplifier                        |
| 1P5-GT      | Remote-Cutoff<br>Pentode          | 144            | 5Y%                             | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1Q5-GT      | Beam<br>Power Tube                | 13D            | 8AF                             | 1.4F                                      | 0.1   | Class A Amplifier   |
| 1R5         | Pentagrid<br>Converter▲           | 5C             | 7AT                             | 1.4F                                      | 0.05  | Converter   |
| 154         | Power Pentode                     | SC             | 7AV                             | 1.4F                                      | 0.1   | Class A Amplifier   |
| 155         | Diode—<br>Sharp-Cutoff<br>Pentode | 50             | 6AU                             | 1.4F                                      | 0.05  | Pentode Unit as<br>AF Amplifier                             |
| 1T4         | Remote-Cutoff Pentode             | 5C             | 6AR                             | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1T5-GT      | Beam<br>Power Tube                | 130            | 6X                              | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1T6         | Diode—<br>Sharp-Cutoff<br>Pentode | 28A            | 8DA                             | 1.25F                                     | 0.04  | Pentode Unit as<br>Class A Amplifier                        |
| 1U4         | Sharp-Cutoff<br>Pentode           | 5C             | 6AR                             | 1.4F                                      | 0.05  | Class A Amplifier   |
| 1U5         | Diode—<br>Sharp-Cutoff<br>Pentode | 5C             | 68W                             | 1.4F                                      | 0.05  | Pentode Unit as<br>Class A Amplifier                        |
| 1-v         | Half-Wave<br>Rectifier            | 22 or<br>13H   | 4G                              | 6.3                                       | 0.3   | With Capacitive-<br>Input Filter                            |
| 1X2-A       | Half-Wave<br>Rectifier            | 7A             | 97                              | 1.25F                                     | 0.2   | Pulsed Rectifier in<br>TV Receivers                         |
| 2A3         | Power Triode                      | 278            | 4D                              | 2.5F                                      | 2.5   | Class A Amplifier Push-Pull Class AB <sub>1</sub> Amplifier |
| 2A5         | Power Pentode                     | 26             | 68                              | 2.5                                       | 1.75  | Amplifier   |
| 2A6         | Twin Diode—<br>High-Mu Triode     | 248            | 6G                              | 2.5                                       | 0.8   | Triode Unit as<br>Amplifier                                 |
| 2A7         | Pentagrid<br>Converter #          | 248            | 7C                              | 2.5                                       | 0.8   | Converter   |
| 2AF4-A      | Medium-Mu<br>Triode               | <b>530</b>     | 7DK                             | 2.35⊕                                     | 0.6   | Class A Amplifier   |

|   | ···  |                                | ·                      |                       |                               |                            | т                            |                                       |                      |             |  |
|---|--|--------------------------------|------------------------|-----------------------|-------------------------------|----------------------------|------------------------------|---------------------------------------|----------------------|-------------|--|
| Plate<br>Sup-<br>ply<br>Valts                   | Grid Bias Volts (ν) or Cathode Resistor Ohms (Ω) | Screen<br>Sup-<br>ply<br>Valts | Screen<br>Cur-<br>rent | Plate<br>Cur-<br>rent | AC Plate<br>Resis-<br>tance   | Trans-<br>conduc-<br>tance | Amplifi-<br>cation<br>Factor | Load<br>for Stated<br>Power<br>Output | Power<br>Out-<br>put | RCA<br>Type |  |
|   | · · ·  |                                |                        | <del></del>           |                               |                            | <br>rid (# 2): 50            | Ohms                                  | Watts                |             |  |
| 45<br>90  | 0v<br>0v   | 35<br>35                       | 0.75<br>0.70           | 0.70<br>0.75          | 300000<br>650000              | Oscillator                 | Grid (# 1)                   | Resistor,                             | 0.2 meg.             | 1LC6        |  |
| 90  | 0v   | 45                             | 0.1                    | 0.6                   | 750000                        | 575                        | _                            |                                       |                      | 1LD5        |  |
| 90<br>90  | - 3v   |                                | =                      | 4.5<br>1.4            | 11200<br>19000                | 1300<br>760                | 14.5<br>14.5                 |                                       |                      | 1LE3        |  |
| 90<br>90  | 0v<br>- 1.5v                                     | 45<br>90                       | 0.4                    | 1.7<br>3.7            | 1.0§<br>500000                | 800<br>1150                |                              |                                       |                      | 1LG5        |  |
|   |  |                                |                        |                       | tics, refer to                | ·                          | 5-GT.                        | <u> </u>                              | L                    | 1LH4        |  |
| 90  | 0v   | 90                             | 0.35                   | 1.6                   | 1.15                          | 800                        | <b> </b>                     |                                       |                      | 1LN5        |  |
| Max.<br>Max.                                    | Peak Invers<br>Peak Plate                        | e Plate \ Ma., 50              | Volts (To              | tal DC ar             | nd Peak), 28                  | 3000 Ma                    | x. Average                   | Plate M                               | a., 0.5              | 1N2-A       |  |
| 90  | 0v   | 90                             | 0.3                    | 1.2                   | 1.5§                          | 750                        | <u> </u>                     |                                       | _                    | 1N5-GT      |  |
| 90  | - 4.5v   | 90                             | 0.6                    | 3.1                   | 300000                        | 800                        |                              | 25000                                 | 0.1                  | 1N6-G       |  |
| 90  | 0v   | 90                             | 0.7                    | 2.3                   | 800000                        | 750                        | —                            | _                                     |                      | 1P5-GT      |  |
| 110   | - 6.6v   | 110                            | 1.4                    | 10                    | 100000                        | 2200                       |                              | 8000                                  | 0.4                  | 1Q5-GT      |  |
| 45<br>90  | 0v<br>0v   | 45<br>67.5                     | 2.1<br>3.5             | 0.7<br>1.5            | 500000 (<br>400000            | Conversion<br>Conversion   | Transcone<br>Transcone       | i., 210 μπ<br>i., 280 μπ              | nhos.<br>nhos.       | 1R5         |  |
| 45<br>90  | - 4.5v<br>- 7v                                   | 45<br>67.5                     | 0.8<br>1.4             | 3.8<br>7.4            | 100000<br>100000              | 1250<br>1575               |                              | 8000<br>8000                          | 0.065<br>0.27        | 154         |  |
| Plate<br>3.1 me                                 | Supply, 90                                       | v applie<br>Grid Bis           | d through              | n 1 meg.<br>s. Grid R | resistor. So<br>esistor, 10 r | reen Supp<br>negohms.      | ly, 90 v aj<br>Voltage Ga    | oplied thr                            | ough                 | 155         |  |
| 45<br>90  | 0v<br>0v   | 45<br>67.5                     | 0.7<br>1.4             | 1.7<br>3.5            | 350000<br>500000              | 700<br>900                 |                              | _                                     |                      | 1T4         |  |
| 90  | - 6v   | 90                             | 0.8                    | 6.5                   | 250000                        | 1150                       |                              | 14000                                 | 0.17                 | 1T5-GT      |  |
| 45<br>67.5                                      | 0v<br>0v   | 45<br>67.5                     | 0.21<br>0.4            | 0.75<br>1.6           | 500000<br>400000              | 475<br>600                 |                              |                                       | =                    | 1T6         |  |
| 90  | 0v   | 90                             | 0.50                   | 1.1                   | 1.05                          | 900                        |                              |                                       |                      | 1U4         |  |
| 67.5  | 0₩   | 67.5                           | 0.4                    | 1.6                   | 600000                        | 625                        |                              |                                       |                      | 1U5         |  |
| Max. D  | C Plate Vol<br>C Output M                        | ſa., 45                        | 1                      | 70lts, 0 ol           | al Effective<br>hms; at 150   | volts, 30                  | ohms; at 3                   | 25 volts,                             | p to 117<br>75 ohms. | 1-v         |  |
|   | x. Peak Inv<br>x. Peak Pla                       |                                |                        | 0000                  | Max.                          | Average Pl                 | ate Ma., 0                   | .5                                    |                      | 1X2-A       |  |
| 250<br>300                                      | -45v<br>780Ω♠                                    |                                |                        | 60.0<br>80.0          | 800                           | 5250                       | 4.2                          | 2500<br>5000                          | 3.5<br>10.0†         | 2A3         |  |
| 300   | -62v   |                                |                        | 80.0                  |                               |                            |                              | 3000                                  | 15.0                 | 2A3         |  |
| For other characteristics, refer to Type 6F6-G. |  |                                |                        |                       |                               |                            |                              |                                       |                      |             |  |
| For other characteristics, refer to Type 6SQ7.  |  |                                |                        |                       |                               |                            |                              |                                       |                      |             |  |
|   |  | Fo                             | r other cl             | naracteris            | tics, refer to                | Type 6A8                   | 3.<br>                       | · · · · · · · · · · · · · · · · · · · |                      | 2A7         |  |
| 80  | 1500   |                                | _                      | 17.5                  | 2100                          | 6500                       | 13.5                         |                                       |                      | 2AF4-A      |  |

| RCA<br>Type   | Name  | Dime<br>and I | be<br>nsions<br>Basing<br>Iram | Filam<br>Unless sp<br>types has<br>Heater | ent (F) ecified all re heaters. with con- | Use  Values to right give operating conditions and characteristics for indicated typical use |
|---------------|---|---------------|--------------------------------|---|---|--|
| 1,700         |   | Dim.          | 8. D.                          | Volts                                     | Amps.                                     | makules 17pkal ose   |
| 2B7           | Twin Diode—<br>Remote-Cutoff<br>Pentode         | 248           | 7D                             | 2.5                                       | 0.8                                       | Pentode Unit as<br>Amplifier   |
| 2BN4          | Medium-Mu<br>Triode                             | 5C            | 7EG                            | 2.3⊕                                      | 0.6                                       | Class A Amplifier  |
| 2E5           | Electron-Ray<br>Tube                            | 22 or<br>13H  | 8R                             | 2.5                                       | 0.8                                       | Visual<br>Indicator  |
| 2EN5          | Twin Diode                                      | 5C            | 7FL                            | 2.1⊕                                      | 0.45                                      | Horizontal<br>Phase Detector   |
| 3A2           | Half-Wave<br>Rectifier                          | 7A            | 9DT                            | 3.15                                      | 0.22                                      | Pulsed Rectifier in<br>TV Receivers  |
| 3A3           | 3A3 Half-Wave<br>Rectifier                      |               | 8EZ                            | 3.15                                      | 0.22                                      | Pulsed Rectifier in<br>TV Receivers  |
| 3A8-GT        | Diode-Triode-Pentode                            | 29G           | 883                            | 1.4F<br>2.8F                              | 0.1<br>0.05                               | Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier                           |
| 3B2           | Half-Wave<br>Rectifier                          | 21C           | 8GH                            | 3.15                                      | 0.22                                      | Pulsed Rectifier<br>in TV Service  |
| 3BN4          | Medium-Mu<br>Triode                             | 5C            | 7EG                            | 3.0⊕                                      | 0.45                                      | Class A Amplifier  |
| 3DT6          | Sharp-Cutoff<br>Pentode                         | 5C            | 7EN                            | 3.15⊕                                     | 0.6                                       | Class A Amplifier  |
| 3GS8/<br>3BU8 | Sharp-Cutoff<br>Twin Pentode                    | 8E            | 9LW                            | 3.15⊕                                     | 0.6                                       | Class A Amplifier (With both sections operating)   |
| 3LF4          | Beam<br>Power Tube                              | 12B           | 68A                            | 1.4F<br>2.8F                              | 0.1<br>0.05                               | Class A Amplifier  |
| 3Q4           | Power Pentode                                   | 5C            | 7BA                            | 1.4F<br>2.8F                              | 0.1                                       | Class A Amplifier  |
| 3Q5-GT        | Beam<br>Power Tube                              | 13D           | 7AP                            | 1.4F<br>2.8F                              | 0.1<br>0.05                               | Class A Amplifier  |
| 354           | Power Pentode                                   | 5C            | 7BA                            | 1.4F<br>2.8F                              | 0.1<br>0.05                               | Class A Amplifier  |
| 3V4           | Power Pentode                                   | 5C            | 6BX                            | 1.4F<br>2.8F                              | 0.1<br>0.05                               | Class A Amplifier  |
| 4BC5          | Sharp-Cutoff<br>Pentode                         | 5C            | 7BD                            | 4.2⊕                                      | 0.45                                      | Class A Amplifier  |
| 4DT6          | Sharp-Cutoff<br>Pentode                         | SC            | 7EN                            | 4.2⊕                                      | 0.45                                      | Class A Amplifier  |
| 4G58          | Sharp-Cutoff<br>Pentode                         | \$E           | 7EN                            | 4.2⊕                                      | 0.45                                      | Class A Amplifier  |
| 4GS8/<br>4BU8 | Sharp-Cutoff<br>Twin Pentode                    | 6E            | 9LW                            | 4.2⊕                                      | 0.45                                      | Class A Amplifier (With both sections operating)   |
| 5AS4          | Full-Wave<br>Rectifiers                         | 27A           | 57;                            | 5.0F                                      | 3.0                                       | With Capacitive-<br>Input Filter   |
| 5AW4          | Full-Wave<br>Rectifier                          | 19H           | 5T                             | 5.0F                                      | 3.7                                       | Rectifier  |
| 5AZ4          | Full-Wave<br>Rectifier                          | 12C           | 61                             | 5.0F                                      | 2.0                                       |  |
| SBE8          | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 68            | 9EG                            | 4.7⊕                                      | 0.6                                       | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                  |
| 5BT8          | Twin-Diode—<br>Sharp-Cutoff                     | 6B            | 9FE                            | 4.7⊕                                      | 0.6                                       | Class A Amplifier  |

Pentode

#### NOTES

For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

| Plate<br>Sup-<br>ply<br>Yelts                                    | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor<br>Ohms (Ω)                          | Screen<br>Sup-<br>ply<br>Yets | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent<br>Ms. | AC Plate<br>Resis-<br>tance<br>Ohms | Trans-<br>conduc-<br>tance<br>Micromhes | Amplifi-<br>cation<br>Factor | Load<br>for Stated<br>Power<br>Output<br>Ohms | Power<br>Out-<br>put<br>Watts | RCA<br>Type  |  |  |
|--|--|-------------------------------|------------------------------|------------------------------|-------------------------------------|---|------------------------------|---|-------------------------------|--------------|--|--|
|  |  | F                             | or other                     | character                    | istics, refer t                     | o Type 6I                               | 38-G.                        |   |                               | 2B7          |  |  |
| 150  | 220a   |                               |                              | 9                            | 6300                                | 6800                                    | 43                           |   |                               | 2BN4         |  |  |
| •  |  | Fo                            | r other c                    | haracteri                    | stics, refer to                     | Туре 6Е                                 | 5.                           |   |                               | 2E5          |  |  |
| ∑DC V  | Peak Heate<br>olts Not to  | Exceed -                      | -100                         |                              |                                     |   | Max.                         | DC Plate                                      | e Ma., 5                      | 2EN5         |  |  |
| Max.   | Max. Peak Inverse Plate Volts, 18000 Max. Peak Plate Ma., 80 Max. Average Plate Ma., 1.5 |                               |                              |                              |                                     |   |                              |   |                               |              |  |  |
|  | Max. Peak Inverse Plate Volts, 30000 Max. Peak Plate Ma., 88 Max. Average Plate Ma., 1.7 |                               |                              |                              |                                     |   |                              |   |                               |              |  |  |
| 90   | 0v   | _                             | _                            | 0.2                          | 200000                              | 325                                     | 65                           |   |                               | ***          |  |  |
| 90   | 0v   | 90                            | 0.5                          | 1.5                          | 800000                              | 750                                     |                              |   |                               | 3A8-GT       |  |  |
|  | Peak Plate I<br>Total DC &   |                               | verse Pla                    | ate Volts                    | Max. Do<br>35000 (Aba               |   | Plate Volts                  |   | Ma., 1.1                      | 3 <b>B</b> 2 |  |  |
|  |  |                               |                              |                              | tics, refer to                      |   |                              |   |                               | 3BN4         |  |  |
| 150  | 56Ω  | 100                           | 2.1                          | 1.1                          | 150000                              | 515                                     |                              |   |                               | 3DT6         |  |  |
|  | For other characteristics, refer to Type 4GS8/4BU8.                                      |                               |                              |                              |                                     |   |                              |   |                               |              |  |  |
|  |  | For                           | other ch                     | aracterist                   | ics, refer to                       | Type 3Q5                                | -GT.                         |   |                               | 3LF4         |  |  |
|  |  | F                             | or other                     | haracter                     | istics, refer t                     | o Type 3\                               | 74                           |   |                               | 3Q4          |  |  |
| 110<br>110   | - 6.6v<br>- 6.6v   | 110<br>110                    | 1.4                          | 10.0                         | 100000<br>110000                    | 2200<br>2000                            |                              | 8000<br>8000                                  | 0.40                          | 3Q5-GT       |  |  |
| 90   | - 7v<br>- 7v   | 67.5<br>67.5                  | 1.4                          | 7.4                          | 100000                              | 1575<br>1425                            |                              | 8000  | 0.27<br>0.235                 | 354          |  |  |
| 90   | - 4.5v   | 90                            | 2.1                          | 9.5                          | 100000                              | 2150                                    |                              | 10000   | 0.27                          | 3V4          |  |  |
| 90<br>250  | 4.5v<br>180Ω   | 90<br>150                     | 2.1                          | 7.7                          | 120000<br>800000                    | 2000<br>5700                            |                              | 10000   | 0.24                          | 4BC5         |  |  |
| 150  | 56Ω  | 100                           | 2.1                          | 1.1                          | 150000                              | 515                                     |                              |   |                               | 4DT6         |  |  |
|  |  | For                           | other cha                    | racterist                    | ics, refer to                       | Type 4GS                                | 8/4BU8.                      |   |                               | 4G58/        |  |  |
| 100  | :  | 67.5                          | 6.0                          |                              |                                     |   | ch section,                  |   |                               | 4GS8/        |  |  |
| 100  | :  | 67.5<br>: Gri                 | 3.6<br>d curren              | 2.0<br>t adjuste             | d for 100 mi                        |   | ch section,<br>s DC          | 0   |                               | 4BU8         |  |  |
| Max. I   | AC Volts pe<br>Peak Inverse  | r Plate (I<br>Volts, 1        | RMS), 55<br>550              | 0 Max.<br>Max.               | DC Output<br>Peak Plate l           | Ma., 300<br>Ma., 1000                   | Min. Tota<br>Imped. pe       |   |                               | 5AS4         |  |  |
| Max. Peak Inverse Volts, 1550 Max. Peak Plate Ma. per Plate, 750 |  |                               |                              |                              |                                     |   |                              |   |                               |              |  |  |
|  |  | For rat                       | ings and                     | characte                     | ristics, refer                      | to Type 5                               | Y3-GT.                       |   |                               | 5AZ4         |  |  |
| 150  | 56Ω  |                               |                              | 18                           | 5000                                | 8500                                    | 40                           |   |                               | EPF0         |  |  |
| 250  | 68Ω  | 110                           | 3.5                          | 10                           | 400000                              | 5200                                    |                              |   |                               | 5BE8         |  |  |
| 200  | 180Ω   | 150                           | 2.8                          | 9.5                          | 300000                              | 6200                                    |                              |   |                               | 5BT8         |  |  |

| RCA<br>Type            | Name                         | Dime<br>and    | be<br>ensions<br>Basing<br>gram | Filam<br>Unless sp<br>types hav<br>Heater | ent (F) ecified all re heaters. with con- | Use  Values to right give operating conditions and characteristics for indicated typical use |
|------------------------|------------------------------|----------------|---------------------------------|---|---|--|
|                        |                              | Dia.           | B. D.                           | Valts                                     | Amps.                                     | ,  |
| 5CL8                   | Medium-Mu<br>Triode          | 68             | 9FX                             | 4.7⊕                                      | 0.6                                       | Triode Unit as<br>Class A Amplific   |
| 5T4                    | Full-Wave<br>Rectifier       | 4              | 51                              | 5.0 <b>F</b>                              | 2.0                                       | With Capacitive-<br>Input Filter<br>With Inductive-<br>Input Filter                          |
| 5U4-G                  | Full-Wave<br>Rectifier       | 278            | ST:                             | 5.0F                                      | 3.0                                       | With Capacitive-<br>Input Filter   |
| 5V3                    | Full-Wave                    | 100            | 5T                              | 5.0F                                      | 3.8                                       | With Capacitive<br>Input Filter  |
|                        | Rectifier                    |                |                                 |   |   | With Inductive<br>Input Filter   |
| 5W4<br>5W4-GT          | 4-GT Rectifier               |                | ST<br>ST;                       | 5.0F                                      | 1.5                                       | With Capacitive<br>Input Filter  |
| 5X4-G                  | Full-Wave<br>Rectifier       | 278            | 5Q                              | 5.0F                                      | 3.0                                       |  |
| 5Y3-G                  | Full-Wave<br>Rectifier       | 28             | 5T;                             | 5.0F                                      | 2.0                                       | With Capacitive<br>Input Filter  |
| 5Y4-G                  | Full-Wave<br>Rectifier       | 28             | 5Q                              | 5.0F                                      | 2.0                                       |  |
| 5 <b>Z</b> 3           | Full-Wave<br>Rectifier       | 278            | 4C                              | 5.0F                                      | 3.0                                       |  |
| 6A3                    | Power Triode                 | 278            | 4D                              | 6.3F                                      | 1.0                                       | Amplifier  |
| 6A6                    | High-Mu Twin<br>Power Triode | 28             | 78                              | 6.3                                       | 0.8                                       | Amplifier  |
| 6A7<br>6A7S            | Pentagrid<br>Converter o     | 248<br>248     | 7C                              | 6.3                                       | 0.3                                       | Converter  |
| 6A8<br>6A8-G<br>6A8-GT | Pentagrid<br>Converter &     | 3<br>23<br>14A | BA<br>BA;                       | 6.3                                       | 0.3                                       | Converter  |
| 6AB5/<br>6N5           | Electron-Ray<br>Tube         | 22 or<br>13H   | 5R                              | 6.3                                       | 0.15                                      | Visual<br>Indicato <del>r</del>  |
| 6AB7                   | Sharp-Cutoff<br>Pentode      | 2A             | 8N                              | 6.3                                       | 0.45                                      | Class A Amplifier  |
| 6AC5-GT                | High-Mu<br>Power Triode      | 130            | 6Q‡                             | 6.3                                       | 0.4                                       | Class B Amplifier Dynamic-Coupled Amplifier With 76 Driver                                   |
| 6AC7                   | Sharp-Cutoff<br>Pentode      | 2A             | 8N                              | 6.3                                       | 0.45                                      | Class A Amplifier  |
| 6AD6-G                 | Electron-Ray<br>Tube         | 202            | 780                             | 6.3                                       | 0.15                                      | Visual<br>Indicator  |
| 6AD7-G                 | Low-My Triode                |                | 8AY                             | 6.3                                       | 0.85                                      | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                  |

13D

6Qt

0.3

Class A Amplifier

NOTES

For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

Types shown in lightface are discontinued.

6AE5-GT Low-Mu Triode

|   | ·  |                                |                              | ,                     |   |   |                                       |  | 1                             | ,                      |
|---|--|--------------------------------|------------------------------|-----------------------|---|---|---------------------------------------|--|-------------------------------|------------------------|
| Plate<br>Sup-<br>ply<br>Volts   | Grid Bias Volts (v) or Cathode Resistor Ohms (Ω) | Screen<br>Sup-<br>ply<br>Volts | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent | AC Plate<br>Resis-<br>tance<br>Owns                             | Trans-<br>conduc-<br>tance<br>Microphes | Amplifi-<br>cation<br>Factor          | Locad<br>for Stated<br>Power<br>Output<br>Okus | Power<br>Out-<br>put<br>Watts | RCA<br>Type            |
| 125   | – 1v   |                                |                              | 14                    | 5000  | 8000                                    | 40                                    |  |                               | 5CL8                   |
| Max.  | AC Volts pe<br>Peak Invers<br>AC Volts pe        | e Volts,<br>r Plate (l         | 1550 .<br>RMS), 55           | Max.                  | DC Output Peak Plate I  | Ma., 675<br>Ma., 225                    |                                       | er Plate,<br>ue of Inpu                        | 150 ohms<br>ut Choke,         | 5T4                    |
| Max.  | Peak Invers<br>AC Volts pe                       | r Plate (                      | RMS), 45                     | 0 Max.                | Peak Plate M<br>DC Output                                       | Ma., 225                                | Min. Tot                              |  | Supply                        | 5U4-G                  |
| Max. Peak Inverse Volts, 1550  Max. Peak Plate Ma., 675  Imped. per Plate, 170 ohms  Max. AC Volts per Plate (RMS), 425  Max. DC Output Ma., 350  Max. Peak Inverse Volts, 1400  Min. Total Effect. Supply Imped. per Plate, 56 ohms  Max. AC Volts per Plate (RMS), 500  Max. Peak Inverse Volts, 1400  Min. Value of Input Choke, 10 henries  Imped. per Plate, 170 ohms  Max. DC Output Ma., 950  Max. Peak Plate Ma. per Plate, 1200  Min. Value of Input Choke, 10 henries |  |                                |                              |                       |   |   |                                       |  |                               | 5V3                    |
| Max.  | Peak Inver                                       | se Volts,                      |                              |                       | C Output Ma   |   | Max. Peal                             | k Plate M                                      | ſa., 300                      | 5W4<br>5W4-GT          |
|   |  | Fo                             | r other re                   | atings, re            | fer to Type   | 5U4-G.                                  |                                       |  |                               | 5X4-G                  |
|   | AC Volts pe<br>Peak Invers                       |                                |                              |                       | DC Output I<br>Peak Plate I                                     |   |                                       | tal Effect<br>er Plate,                        |                               | 5Y3-G                  |
| Max.  | Peak Plate                                       | Ma., 37                        | (5Y4-G)                      | )                     | For other   | ratings, re                             | fer to Typ                            | e 5Y3-G1                                       | г.                            | 5Y4-G                  |
|   |  | Fo                             | r other re                   | tings, re             | fer to Type !   | U4-G.                                   |                                       |  |                               | 5 <b>Z</b> 3           |
|   |  | F                              | or other c                   | haracteri             | stics, refer to   | Туре 6В                                 | 4-G.                                  |  |                               | 6A3                    |
|   |  | F                              | or other c                   | haracteri             | stics, refer to   | Type 6N                                 | 7-GT.                                 |  |                               | 6A6                    |
|   |  | Fo                             | r other cl                   | naracteri             | stics, refer to   | Type 6At                                | в.                                    |  |                               | <b>6A7</b><br>6A7S     |
| 250   | — 3v   | 100                            | 2.7                          | 3.5                   | 360000  | 4.0 ma                                  | Grid (#2)<br>Oscillator<br>sion Trans | -Grid (#                                       | 1) Res                        | 6A8<br>6A8-G<br>6A8-GT |
| Grid<br>Plate   | Bias, — 10.<br>& Target St                       | 0 volts;                       | Shadow A<br>135 volts.       | Ingle, 0°. Triode I   | late Resistor<br>. Bias, 0 vol<br>Plate Resisto<br>Bias, 0 volt | ts; Angle,<br>r = 1.0 me                | 90°; Plate<br>eg. Target              | Current,<br>Current =                          | 0.5 ma.<br>= 1.9 ma.          | 6AB5/<br>6N5           |
| 300   | - 3v   | 200                            | 3.2                          | 12.5                  | 700000  | 5000                                    |                                       |  |                               | 6AB7                   |
| 250   | 0v   |                                |                              | 5.0♠                  |   |   |                                       | 10000  | 8.0†                          |                        |
| Bias for both 6AC5-GT and 76 is developed in coupling circuit.  Average Plate Current of Driver = 5.5 milliamperes.  Average Plate Current of 6AC5-GT = 32 milliamperes.  7000 3.7  |  |                                |                              |                       |   |   |                                       |  |                               |                        |
| 300   | 160Ω   | 150                            | 2.5                          | 10.0                  | 1.05  | 9000                                    | —                                     |  |                               | 6AC7                   |
| Targe   | et Voltage, 1<br>irrent, 1.2 n                   | 50 volts.<br>a. Conti          | Control-<br>ol-Electro       | Electrodo<br>de Volta | e Voltage, —<br>age, 75 volts                                   | 50 volts; \$<br>; Angle, 0°             | Shadow And ; Target C                 | gle, 135°;<br>urrent, 3                        | Target<br>ma.                 | 6AD6-G                 |
| 250   | -25v   |                                |                              | 3.7                   | 19000   | 325                                     | 6                                     |  |                               | 6AD7-G                 |
| 250   | -16.5v   | 250                            | 6.5                          | 34.0                  | 80000   | 2500                                    |                                       | 7000   | 3.2                           | OAD/-G                 |
| 95  | 15v  |                                |                              | 7.0                   | 3500  | 1200                                    | 4.2                                   |  |                               | 6AE5-GT                |
|   |  |                                |                              |                       |   |   |                                       |  |                               |                        |

| 0. |  |
|----|--|
|    |  |
|    |  |
|    |  |

For busing diagrams, see pages 549 to 553.

For explanation of foot notes, see page 541

| RCA<br>Type | Name  | Dime<br>and | ube<br>ensions<br>Basing<br>gram∆<br>B. D. | Filam<br>Unless sp<br>types hav<br>⊕ Heater | ter or nent (F) secified all ve heaters. with constrainty time.  Amps. | Use  Values to right give operating conditions and characteristics for indicated typical use |
|-------------|---|-------------|--|---|--|--|
| 6AE6-G      | Twin-Plate<br>Control Tube                      | 22          | 7AH  | 6.3   | 0.15   | Remote Cutoff Triode Sharp-Cutoff Triode   |
| 6AE7-GT     | Twin-Input<br>Triode                            | 13D         | 7AX  | 6.3   | 0.5  | Class A Amp.AA   |
| 6AH4-GT     | Low-Mu<br>Triode                                | 13D         | 8EL  | 6.3   | 0.75   | Vertical Deflection<br>Amplifier   |
| 6AH6        | Sharp-Cutoff<br>Pentode                         | 5C          | 7BK  | 6.3   | 0.45   | Class A Amplifier  |
| 6AL7-GT     | Electron-Ray<br>Tube                            | 13C 8CH     |  | 6.3   | 0.15   | Visual<br>Indicator  |
| 6AM4        | High-Mu Triode                                  | GA.         | 9BX  | 6.3   | 0.225  | Class A Amplifier  |
| 6AM8        | Diode—<br>Sharp-Cutoff<br>Pentode               | 6B          | 9CY  | 6.3<br>6.3⊕                                 | 0.45   | Diode Unit Pentode Unit as Class A Amplifier   |
| 6AN8        | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 6B          | 9DA  | 6.3<br>6.3⊕                                 | 0.45<br>0.45   | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                  |
| 6AQ5        | Beam Power<br>Tube                              | \$D         | 7BZ  | 6.3<br>6.3⊕                                 | 0.45<br>0.45   | Single Tube<br>Class A Amplifier<br>Push-Pull<br>Class A <sub>1</sub> Amplifier              |
| 6AQ6        | Twin-Diode—<br>High-Mu Triode                   | 5C          | 7BT  | 6.3   | 0.15   | Triode Unit as<br>Class A Amplifier  |
| 6AQ7-GT     | Twin-Diode—<br>High-Mu Triode                   | 130         | 8CK  | 6.3   | 0.3  | Triode Unit as<br>Class A Amplifier  |
| 6AR5        | Power Pentode                                   | 50          | 6CC  | 6.3   | 0.4  | Class A Amplifier  |
| 6AT8        | Medium-Mu<br>Triode—                            | 68          | 8DW  | 6.3   | 0.45   | Triode Unit as<br>Class A Amplifier  |
| 6AU4-GT     | Half-Wave<br>Rectifier                          | 130         | 4CG  | 6.3   | 1.8  | Television<br>Damper Service   |
| 6AU6        | Sharp-Cutoff<br>Pentode                         | 5C          | 78K  | 6.3<br>6.3⊕                                 | 0.3<br>0.3   | Class A Amplifier  |
| 6AU7        | Medium-Mu<br>Twin Triode                        | 68          | 84   | 3.15<br>6.3                                 | 0.6<br>0.3   | Each Unit as<br>Class A Amplifier  |
| 6AU8        | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 6E          | 9DX  | 6.3⊕  | 0.6  | Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier                           |
| 6AV5-GT     | Beam Power<br>Tube                              | 130         | 6CK  | 6.3   | 1.2  | Horizontal Deflec-<br>tion Amplifier   |
| 6AW8        | High-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode   | SE          | 9DX  | 6.3⊕  | 0.6  | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier••                |
| 6AX4-GT     | Half-Wave<br>Rectifier                          | 130 4CG     |  | 6.3   | 1.2  | Television<br>Damper Service   |
| 6B4-G       | Power-Triode                                    | 278 5S      |  | 6.3F  | 1.0  | Class A Amplifier  |
| 6B5         | Direct-Coupled<br>Power Triode                  | 26 EAS      |  | 6.3   | 0.8  | Class A Amplifier  |
| 6B6-G       | Twin-Diode—<br>High-Mu Triode                   | 23          | 7V‡  | 6.3   | 0.3  | Triode Unit as<br>Amplifier  |

| Plate<br>Sup-<br>ply<br>Volts  | Grid Bias<br>Volts (ν)<br>or<br>Cathode<br>Resistor<br>Ohms (Ω)   | Screen<br>Sup-<br>ply<br>Volts | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent<br>Ma | AC Plate<br>Resis-<br>tance<br>Olues | Trans-<br>conduc-<br>tance<br>Micromhes | Amplifi-<br>cation<br>Factor | Load<br>for States<br>Power<br>Output<br>Ohms | Power<br>Out-<br>put<br>Watts | RCA<br>Type     |  |  |
|--|---|--------------------------------|------------------------------|-----------------------------|--------------------------------------|---|------------------------------|---|-------------------------------|-----------------|--|--|
| 250<br>250<br>250<br>250<br>250  | - 1.5v<br>-35v<br>- 1.5v<br>- 9.5v  |                                |                              | 6.5<br>0.01<br>4.5<br>0.01  | 25000<br>35000                       | 950                                     | 33                           |   |                               | 6AE6-G          |  |  |
| 250  | -13.5v  |                                |                              | 10.0                        | 4650                                 | 3000                                    | 14                           |   |                               | 6AE7-GT         |  |  |
|  | Max. DC Plate Volts, 500 Max. DC Cathode Ma., 60 Max. Peak Positive-Pulse Plate Volts, 2000 Max. Plate Dissipation, 7.5 watts |                                |                              |                             |                                      |   |                              |   |                               |                 |  |  |
| <b>-</b>   |   |                                |                              | 10.0                        |                                      | r                                       | sipation, 7                  | 5 watts                                       | ·                             | 6AH4-GT<br>6AH6 |  |  |
|  | 300   1600   150   2.5   10.0   500000   9000   |                                |                              |                             |                                      |   |                              |   |                               |                 |  |  |
| Grid   | Target Voltage, 315 volts Grid Voltage = 0 volts Cathode Bias Res., 3300 ohms approx.  Voltage = 0                            |                                |                              |                             |                                      |   |                              |   |                               |                 |  |  |
| 200  | 100Ω  |                                |                              | 10                          | 8700                                 | 9800                                    | 85                           |   |                               | 6AM4            |  |  |
| <u> </u>   |   | Iax. DC I                      |                              |                             | . Peak Heat                          |   | e Volts, ±2                  | 00  |                               | 6AM8            |  |  |
| 125  | 56 <u>0</u>   | 125                            | 3.2                          | 12.5                        |                                      | 7800                                    |                              |   |                               | 0.2.20          |  |  |
| 150  | - 3v  |                                |                              | 15                          | 4500                                 | 4700                                    | 31                           |   |                               | 6AN8            |  |  |
| 125  | 56a   | 125                            | 3.8                          | 12                          | 170000                               | 7800                                    |                              |   |                               |                 |  |  |
| 180<br>250   | - 8.5v<br>-12.5v  | 180<br>250                     | 3.0<br>4.5                   | 29.0<br>45.0                | 50000<br>50000                       | 3700<br>4100                            |                              | 5500<br>5000                                  | 2.0<br>4.5                    |                 |  |  |
| 250  | -15v  | 250                            | 5.0♠                         | 70.0♠                       | 60000                                |   |                              | 10000   | 10.0†                         | 6AQ5            |  |  |
| 100<br>250   | - 1v<br>- 3v  | _                              |                              | 0.8<br>1.0                  | 61000<br>58000                       | 1150<br>1200                            | 70<br>70                     |   |                               | 6AQ6            |  |  |
| 250  | - 2v  | —                              | —                            | 2.3                         | 44000                                | 1600                                    | 70                           |   |                               | 6AQ7-GT         |  |  |
| 250  | -18v  | 250                            | 5.5                          | 32.0                        | 90000                                | 2300                                    |                              | 7600  | 3.4                           | 6AR5            |  |  |
| 125  | - 1v  |                                |                              | 12                          | 6000                                 | 6500                                    | 40                           | —   |                               | 6AT8            |  |  |
|  | Peak Invers<br>Peak Plate   |                                |                              | ) (Absolu                   | ite)                                 |   | . Average I<br>. Plate Dis   |   |                               | 6AU4-GT         |  |  |
| 100<br>250   | 150Ω<br><b>68</b> Ω   | 100<br>150                     | 2.1<br>4.3                   | 5.0<br>10.6                 | 500000<br>1.0§                       | 3900<br>5200                            |                              |   |                               | 6AU6            |  |  |
| 100<br>250   | 0v<br>8.5v  |                                | _                            | 11.8<br>10.5                | 6250<br>7700                         | 3500<br>2200                            | 19.5<br>17                   |   |                               | 6AU7            |  |  |
| 150  | 150Ω  | _                              |                              | 9                           | 8200                                 | 4900                                    | 40                           | _   |                               | 6AU8            |  |  |
| 200  | 82 <u>0</u>   | 125                            | 3.4                          | 15                          | 150000                               | 7000                                    |                              |   |                               | UAUS            |  |  |
|  | DC Plate V  |                                | 10                           |                             | Max. Peak<br>Max. Plate              |   |                              | olts, 550                                     | 0 (Abs.)                      | 6AV5-GT         |  |  |
| 200  | – 2v  |                                |                              | 4                           |                                      | 4000                                    | 70                           |   |                               | 6AW8            |  |  |
| 150 1500 150 3.5 13 200000 9500 — — — — — • • 6AW8-A Features a plate current characteristic with a controlled knee.   |   |                                |                              |                             |                                      |   |                              |   |                               |                 |  |  |
| Max. Peak Inverse Plate Volts, 4400  Max. Peak Plate Ma., 750  Max. DC Plate Ma., 125  Max. Peak Heater-Cathode Volts:   (-4400**  +300  **DC component must not exceed 900 volts. |   |                                |                              |                             |                                      |   |                              |   |                               |                 |  |  |
| Max.<br>250  | DC Plate N  | da., 125                       |                              | 60                          | **DC comp                            | onent mus                               | 4.2                          | d 900 vol                                     | 3.5                           | 6B4-G           |  |  |
| 200  | 777   |                                | r other ci                   |                             |                                      |   |                              |   |                               | 6B5             |  |  |
|  | For other characteristics, refer to Type 6N6-G.  For other characteristics, refer to Type 6SO7.                               |                                |                              |                             |                                      |   |                              |   |                               |                 |  |  |
|  | For other characteristics, refer to Type 6SQ7.  |                                |                              |                             |                                      |   |                              |   |                               |                 |  |  |

| RCA<br>Type           | Name   | Dime<br>and | ube<br>ensions<br>Basing<br>gram∆ | Filerr<br>Unless sp<br>types ba<br>⊕ Heater | ter or nent (F) pecified all ve heaters. with con- |  |
|-----------------------|--|-------------|-----------------------------------|---|--|--|
|                       |  | Din.        | B. D.                             | Velts                                       | Amps.  |  |
| 6B7<br>6B7S           | Twin-Diode—<br>Remote-Cutoff<br>Pentode      | 248<br>248  | 70                                | 6.3   | 0.3  | Pentode Unit as<br>Amplifier                           |
| 6B8                   | Twin-Diode—<br>Semiremote-<br>Cutoff Pentode | 3           | 8E                                | 6.3   | 0.3  | Pentode Unit a<br>Amplifier                            |
| 6B8-G                 | Twin Diode—<br>Semiremote-<br>Cutoff Pentode | 23          | eE;                               | 6.3   | 0.3  | Pentode Unit as<br>Class A Amplifie                    |
| 6BD4                  | Sharp-Cutoff<br>Beam Triode                  | 210         | 8FU                               | 6.3   | 0.6  | Voltage-Control  |
| 6BD4-A                | Sharp-Cutoff<br>Beam Triode                  | 21C         | 8FU                               | 6.3   | 0.6  | Voltage-Control  |
| 6BD6                  | Remote-Cutoff<br>Pentode                     | SC.         | 78K                               | 6.3   | 0.3  | Class A Amplifie                                       |
| 6BF5                  | Beam Power<br>Tube                           | \$D         | 7BZ                               | 6.3   | 1.2  | Class A Amplific                                       |
| 6BF6                  | Twin-Diode—<br>Medium-Mu<br>Triode           | 8C          | 7BT                               | 6.3   | 0.3  | Triode Unit as<br>Class A Amplific                     |
| 6BG6-G                | Beam Power<br>Tube                           | 285         | 58T                               | 6.3   | 0.9  | Horizontal Deflection Amplifier                        |
| 6BK5                  | Beam<br>Power Tube                           | SEZ.        | 9BQ                               | 6.3   | 1.2  | Class A Amplifier                                      |
| 6BK7-A                | Medium-Mu<br>Twin Triodes                    | u           | 8AJ                               | 6.3<br>6.3⊕                                 | 0.45<br>0.45                                       | Each Unit as<br>Class A Amplifier                      |
| 6BL4                  | Half-Wave<br>Rectifier                       | 1 <b>8F</b> | SGB                               | 6.3   | 3.0  | Television<br>Damper Service                           |
| 6BL7-GT               | Medium-Mu<br>Twin Triode                     | 13D         | 88D                               | 6.3   | 1.5  | Vertical Deflectio<br>Amplifier                        |
| 6BN4                  | Medium-Mu<br>Triode                          | 5C          | 7EG                               | 6.3   | 0.2  | Class A Amplifier                                      |
| 6BQ6-GT               | Beam Power<br>Tube                           | 14D         | BAM                               | 6.3   | 1.2  | Horizontal Deflec-<br>tion Amplifier                   |
| 6BQ7                  | Medium-Mu<br>Twin Triode                     | 68          | 8V)                               | 6.3   | 0.4  | Each Unit as<br>Class A Amplifier                      |
| 6BR8                  | Medium-Mu<br>Triode—<br>Sharp-Cutoff         | 48          | 9FA                               | 6.3<br>6.3⊕                                 | 0.45<br>0.45                                       | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as |
|                       | Pentode                                      |             |                                   |   |  | Class A Amplifier                                      |
| 6BY5~GA               | Full-Wave<br>Rectifier                       | 198         | BCN                               | 6.3   | 1.6  | Television<br>Damper Service                           |
| 6BZ8                  | Medium-Mu<br>Twin Triode                     | 8B          | 9AJ                               | 6.3   | 0.4  | Each Unit as<br>Class A Amplifier                      |
| 6 <b>C5</b><br>6C5-GT | Medium-Mu<br>Triode                          | 2A<br>14A   | € Ó*<br>€ Ó                       | 6.3   | 0.3  | Class A Amplifier                                      |
| 6C6                   | Sharp-Cutoff<br>Pentode                      | 24A         | SF                                | 6.3   | 0.3  | Amplifier<br>Detector                                  |
| 6C7                   | Twin-Diode—<br>Medium-Mu<br>Triode           | 248         | 7 <b>G</b>                        | 6.3   | 0.3  | Triode Unit as<br>Class A Amplifier                    |
| 6C8-G                 | Medium-Mu<br>Twin-Triode                     | 23          | 8G                                | 6.3   | 0.3  | Each Unit as<br>Class A Amplifier                      |

8GD

Horizontal Deflection Amplifier

Beam Power Tube

6CB5

NOTES

For basing diagrams, see pages 549 to 553,

For explanation of foot notes, see page 548

Types shown in light-

|  |  |                                |                              |                             |  |   | ,                            |   | T                             | •             |  |  |
|--|--|--------------------------------|------------------------------|-----------------------------|--|---|------------------------------|---|-------------------------------|---------------|--|--|
| Plate<br>Sup-<br>ply<br>Vets   | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor<br>Ohms (2)  | Screen<br>Sup-<br>ply<br>Volts | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent<br>Ma | AC Plate<br>Resis-<br>tance            | Trans-<br>conduc-<br>tance<br>Micromhos | Amplifi-<br>cation<br>Factor | Locad<br>for Stated<br>Power<br>Output<br>Obnes | Power<br>Out-<br>put<br>Watts | RCA<br>Type   |  |  |
|  | Triode: P  | late Volt                      |                              | x.; Plate                   | Volts, 0; Pla<br>Ma., 45; Pl<br>watts. |   |                              |   |                               | 6B7<br>6B7S   |  |  |
|  |  |                                |                              |                             | istics, refer t                        | o <b>T</b> ype 12                       | C8.                          |   |                               | 6B8           |  |  |
| 250  | - 3v   | 125                            | 2.3                          | 9                           | 600000                                 | 1125                                    |                              |   |                               | oB8-G         |  |  |
|  | Max. DC Plate Volts, 20000 Max. DC Plate Ma., 1.5 Max. Unregulated DC Supply Volts, 40000 Max. Plate Dissipation, 20.0 watts |                                |                              |                             |  |   |                              |   |                               |               |  |  |
| Max.   | Max. DC Plate Volts, 27000 Max. DC Plate Ma., 1.5 Max. Unregulated DC Supply Volts, 55000 Max. Plate Dissipation, 25.0 watts |                                |                              |                             |  |   |                              |   |                               |               |  |  |
| 250  |  |                                |                              |                             |  |   |                              |   |                               |               |  |  |
| 110 - 7.5v 110 4.0 36.0 12000 7500 — 2500 1.9  |  |                                |                              |                             |  |   |                              |   |                               |               |  |  |
| 250  | 250 - 9v - 9.5 8500 1900 16 Power Output, 300 milliwatts   |                                |                              |                             |  |   |                              |   |                               |               |  |  |
|  | DC Plate V<br>DC Cathod  |                                | 10                           |                             | Max. Peak I<br>Max. Plate              |   |                              |   | 0 (Abs.)                      | 6BG6-G        |  |  |
| 250  | - 5v   | 250                            | 3.5                          | 35                          | 100000                                 | 8500                                    |                              | 6500  | 3.5                           | 6BK5          |  |  |
| 150  | 56Ω  |                                |                              | 18                          | 4600                                   | 9300                                    | 43                           | Grid-No<br>for Cuto                             | . 1 Volts<br>off, -11         | 6BK7-A        |  |  |
| Max.   | Peak Invers<br>Peak Plate<br>DC Plate M  | Ma., 1?0                       |                              | 0 (Abs.)                    | Max. Peak                              |   |                              | ts:\+300  |                               | 6BL4          |  |  |
| Max.   | DC Plate V<br>DC Cathod  | olts, 500                      | ach Unit                     |                             | Max. Peak F<br>Max. Plate I            | ositive-Pu                              | lse Plate \                  | olts, 200                                       | 00 (Abs.)                     | 6BL7-GT       |  |  |
| 150  | 220Ω   |                                |                              | 9                           | 6300                                   | 6800                                    | 43                           |   |                               | 6BN4          |  |  |
| Max.   | DC Plate V<br>DC Cathode   | olts, 550                      | 0                            |                             | Max. Peak F<br>Max. Piate I            |   |                              | olts, 5500                                      | (Abs.)                        | 6BQ6-GT       |  |  |
| 150  | 220Ω   |                                |                              | 9.0                         | 5800                                   | 6000                                    | 35                           | Grid-No<br>for Cuto                             | off10                         | 6BQ7          |  |  |
| 125  | - 1v   |                                |                              | 13.5                        | 7500                                   |   | 40                           |   |                               |               |  |  |
| 125  | - 1v   | 110                            | 3.5                          | 9.5                         | 200000                                 | 5000                                    |                              |   |                               | 6BR8          |  |  |
| Max. P   | eak Inverse<br>eak Plate M<br>C Plate Ma   | Ia., 525                       | olts, 3000                   | (Abs.)                      | Маз                                    | . Peak He                               | ater-Catho                   | de Volts:                                       | {-450<br>+100                 | 6BY5-GA       |  |  |
| 125  | 100Ω   | —                              |                              | 10                          | 5600                                   | 8000                                    | 45                           |   |                               | 6BZ8          |  |  |
| 250  | 8v   | _                              |                              | 8.0                         | 10000                                  | 2000                                    | 20                           |   |                               | 6C5<br>6C5-GT |  |  |
|  |  | For                            | other ch                     | aracteris                   | tics, refer to                         | Type 6J7                                | •                            |   |                               | 6C6           |  |  |
| 250  | -9v  | _                              | -                            | 4.5                         | 16000                                  | 1250                                    | 20                           |   |                               | 6C7           |  |  |
| 250  | -4.5v  |                                |                              | 3.2                         | 22500                                  | 1600                                    | 36                           | —   |                               | 6C8-G         |  |  |
| Max. DC Plate Volts, 700 Max. Peak Positive-Pulse Plate Volts, 6800 (Abs.) Max. DC Cathode Ma., 200 Max. Plate Dissipation, 23 Watts |  |                                |                              |                             |  |   |                              |   |                               | 6CB5          |  |  |

| RCA<br>Type          | Name  | Dime<br>and I | rbe<br>nsions<br>Basing<br>gram∆ | Filam            | ecified all<br>s heaters.<br>with con- | Use  Values to right give operating conditions and characteristics for indicated typical use |
|----------------------|---|---------------|----------------------------------|------------------|--|--|
|                      |   | Dim.          | B. D.                            | Volts            | Amps.                                  |  |
| 6CD6-G               | Beam Power<br>Tube                              | 288           | 58T                              | 6.3              | 2.5                                    | Horizontal Deflec-<br>tion Amplifier   |
| 6CG8                 | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 68            | 9GF                              | 6.3<br>6.3⊕      | 0.45<br>0.45                           | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                  |
| 6CK4                 | Low-Mu<br>Triode                                | 13F           | 81B                              | 6.3              | 1.25                                   | Vertical Deflec-<br>tion Amplifier   |
| 6CL8                 | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Tetrode | 88            | 9FX                              | 6.3⊕             | 0.45                                   | Triode Unit as<br>Class A Amplifier<br>Tetrode Unit as<br>Class A Amplifier                  |
| 6D6                  | Remote-Cutoff<br>Pentode                        | 24A           | 8F                               | 6.3              | 0.3                                    | Amplifier<br>Mixer   |
| 6D7                  | Sharp-Cutoff<br>Pentode                         | 24A           | 7H                               | 6.3              | 0.3                                    | Amplifier<br>Detector  |
| 6D8-G                | Pentagrid<br>Converter <b>p</b>                 | 23            | 8A;                              | 6.3              | 0.15                                   | Converter  |
| 6DM4                 | Half-Wave<br>Rectifier                          | 136           | 4CG                              | 6.3 <sup>.</sup> | 1.2                                    | Damper Service   |
| 6DN6                 | Beam Power<br>Tube                              | 21B           | 5BT                              | 6.3              | 2.5                                    | Horizontal Deflec-<br>tion Amplifier   |
| 6DQ6-A               | Beam Power<br>Tube                              | 2B            | 6AM                              | 6.3              | 1.2                                    | Horizontal Deflec-<br>tion Amplifier   |
| 6DT6                 | Sharp-Cutoff<br>Pentode                         | 5C            | 7EN                              | 6.3              | 0.3                                    | Class A Amplifier  |
| 6 <b>E</b> 6         | Twin<br>Power Amplifier                         | 26            | 7B                               | 6.3              | 0.6                                    | Push-Pull<br>Class A Amplifier   |
| 6 <b>E</b> 7         | Remote-Cutoff<br>Pentode                        | 24A           | 7H                               | 6.3              | 0.3                                    | Amplifier  |
| 6ÉH8                 | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 48            | 91G                              | 6.3⊕             | 0.45                                   | Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier                           |
| 6EX6                 | Beam Power<br>Tube                              | 218           | 5BT                              | 6.3⊕             | 2.25                                   | Horizontal Deflec-<br>tion Amplifier   |
| <b>6F5</b><br>6F5-GT | High-Mu<br>Triode                               | 144           | 5M<br>5M‡                        | 6.3              | 0.3                                    | Class A Amplifier  |
| 6F6-G<br>6F6-GT      | Power<br>Pentode                                | 25<br>13F     | 78<br>75;<br>75;                 | 6.3              | 0.7                                    | Pentode Class A Amplifier Triode Class A Amplifier Pentode Push-Pull Class A Amplifier       |
| 6 <b>F</b> 7         | Low-Mu<br>Triode—<br>Remote-Cutoff<br>Pentode   | 248           | 7E                               | 6.3              | 0.3                                    | Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier                           |
| 6F8-G                | Medium-Mu<br>Twin Triode                        | 23            | 8G                               | 6.3              | 0.6                                    | Each Unit as<br>Class A Amplifier  |
| 6FV8                 | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 68            | 9FA                              | 6,3⊕             | 0.45                                   | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                  |

## NOTES

For explanation of foot-

notes, see page 548.

Types shown in light-

|   |   |                                | ,                            | <del></del>                 | τ                                       | ,                                       | ,                            |  | · · · · · · · · · · · · · · · · · · · |                      |
|---|---|--------------------------------|------------------------------|-----------------------------|---|---|------------------------------|--|---------------------------------------|----------------------|
| Plate<br>Sup-<br>ply<br>Velts   | Grid Bias Volts (ν) or Cathode Resistor   | Screen<br>Sup-<br>ply<br>Volts | Screen<br>Cur-<br>rent<br>M1 | Plate<br>Cur-<br>rent<br>M1 | AC Plate<br>Resis-<br>tance             | Trans-<br>conduc-<br>tance<br>Micromhes | Amplifi-<br>cation<br>Factor | Load<br>for Stated<br>Power<br>Output<br>Olens | Power Out- put Watts                  | RCA<br>Type          |
| Max<br>Max  | . DC Plate '  | Volts, 700<br>de Ma., 2        | 00                           |                             | Max. Peak<br>Max. Plate                 |   |                              |  | 00                                    | 6CD6-G               |
| 100   | - 1v  |                                |                              | 12                          | 6000                                    | 6500                                    | 40                           |  |                                       | 6CG8                 |
| 250   | - 1v  | 125                            | 2.2                          | 9                           | 300000                                  | 5500                                    |                              | —  |                                       | ocus                 |
| Max.<br>Max   | DC Plate V<br>Peak Catho  | olts, 550<br>de Ma             | 350                          |                             | Max. Peak l<br>Max. Plate               |   |                              |  | 0 (Abs.)                              | 6CK4                 |
| 125   | - lv  | _                              |                              | 14                          | 5000                                    | 8000                                    | 40                           |  |                                       |                      |
| 125   | - 1v  | 125                            | 4                            | 12                          | 120000                                  | 6000                                    |                              |  | —                                     | 6CL8                 |
|   |   | F                              | or other c                   | haracteri                   | stics, refer t                          | о Туре б                                | 7-G.                         |  |                                       | 6D6                  |
|   |   | Fo                             | or other c                   | haracteri                   | stics, refer t                          | о Туре бЈ?                              | 7.                           |  |                                       | 6D7                  |
| 250   | 250 — 3v 100 2.7 3.5 360000 Anode-Grid (#2): 250 max. volts, 4 ma. Oscillator-Grid (#1) Resistor a. Conversion Transcond., 550 micrombos. |                                |                              |                             |   |   |                              |  | 6D8-G                                 |                      |
| Max. Peak Inverse Plate Volts, 5000 Max. Peak Plate Ma., 1100 Max. DC Plate Ma., 175  Max. Peak Heater—Cathode Volts, -5000 (DC Component Not to Exceed 900 Volts)  Max. Peak Heater—Cathode Volts, +300 (DC Component Not to Exceed 100 Volts) |   |                                |                              |                             |   |   |                              |  | 6DM4                                  |                      |
| Max   | DC Plate V  | olts, 700                      |                              |                             | Max. Peak                               | Positive-P                              | ılse Plate                   | Volts, 660                                     | 0 (Abs.)                              | 6DN6                 |
| Max.  | DC Cathod<br>DC Plate V<br>DC Cathod  | olts, 770                      |                              |                             | Max. Plate<br>Max. Peak I<br>Max. Plate | Positive-Pu                             | lse Plate                    | Volts, 600                                     | 0 (Abs.)                              | 6DQ6-A               |
| 150   | 560Ω  | 100                            | 2.1                          | 1.1                         | 150000                                  | 515                                     |                              |  | I                                     | 6DT6                 |
| 250   | -27.5v  |                                |                              | <del></del>                 |   |   |                              | 14000  | 1.60†                                 | 6E6                  |
|   | 1   | Fo                             | r other cl                   | haracteris                  | tics, refer to                          | Type 6U                                 | 7-G.                         |  | 1                                     | 6E7                  |
| 125   | - 1v  |                                |                              | 13.5                        | <u> </u>                                | 7500                                    | 40                           |  |                                       | <del></del>          |
| 125   | - 1v  | 125                            | 4                            | 12                          | 170000                                  | 6000                                    |                              |  |                                       | 6EH8                 |
| 175   | -30v  | 175                            | 3.3                          | 67                          | 8500                                    | 7700                                    |                              |  |                                       | 6EX6                 |
| 100<br>250  | - 1v<br>- 2v  |                                |                              | 0.4<br>0.9                  | 85000<br>66000                          | 1150<br>1500                            | 100<br>100                   |  |                                       | <b>6F5</b><br>6F5-GT |
| 250<br>285  | -16.5v<br>-20v  | 250<br>285                     | 6.5<br>7.0                   | 34.0<br>38.0                | 80000<br>78000                          | 2500<br>2550                            |                              | 7000<br>7000                                   | 3.2<br>4.8                            |                      |
| 250   | -20v  | -                              |                              | 31.0                        | 2600                                    | 2600                                    | 6.8                          | 4000   | 0.85                                  | 6F6-G                |
| 315   | -24v  | 285                            | 12.0♠                        | 62.0♠                       |   | _                                       |                              | 10000  | 11.0†                                 | 6F6-GT               |
| 100   | - 3v  | _                              | _                            | 3.5                         | 16000                                   | 500                                     | 8                            |  |                                       | 6F7                  |
| 250   | 3v  | 100                            | 1.5                          | 6.5                         | 850000                                  | 1100                                    |                              |  |                                       | VI.                  |
|   |   | Fo                             | r other ch                   | aracteris                   | tics, refer to                          | Type 6J5                                |                              |  |                                       | 6F8-G                |
| 125   | - 1v  | _                              |                              | 14                          | 5000                                    | 8000                                    | 40                           | _  |                                       | CTIVO.               |
| 125   | – 1v  | 125                            | 4                            | 12                          | 200000                                  | 6500                                    |                              |  |                                       | 6FV8                 |
|   |   |                                |                              |                             |   |   |                              |  |                                       |                      |

|   | RCA<br>Type            | Name  | Dime<br>and    | ube<br>Insions<br>Basing<br>gram∆ | Filam<br>Unless sp<br>types bar<br>⊕ Heater | ter or<br>ent (F)<br>ecified all<br>re heaters,<br>with con-<br>rmup time. | Use Values to right give operating conditions and characteristics for indicated typical use |
|---|------------------------|---|----------------|-----------------------------------|---|--|---|
|   |                        |   | Dist.          | B, D.                             | Yolts                                       | Amps.  |   |
|   | 6FW8                   | Medium-Mu<br>Twin Triode                        | 18             | BAJ                               | 6.3   | 0.4  | Each Unit as<br>Class A Amplifier   |
|   | 6G6-G                  | Power Pentode                                   | 22             | 78‡                               | 6.3   | 0.15   | Pentode<br>Class A Amplifier  |
|   | 6GH8                   | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 88             | 9AE                               | 6.3⊕  | 0.45   | Triode Unit as Horiz. Defl. Osc. Pentode Unit as Horiz. Defl. Osc.                          |
|   | 6GJ8                   | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 18             | 9AE                               | 6.3⊕  | 0.6  | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                 |
|   | 6H6-GT                 | Twin Diode                                      | 130            | 7Q<br>7Q11                        | 6.3   | 0.3  | Voltage<br>Doubler<br>Half-Wave<br>Rectifier  |
|   | 6J5<br>6J5-GT          | Medium-Mu<br>Triode                             | 2A<br>13D      | 80%<br>80                         | 6.3   | 0.3  | Class A Amplifier   |
| NOTES   | 6 <b>J</b> 6           | Medium-Mu<br>Twin Triode                        | 5C             | 7BF                               | 6.3<br>6.3⊕                                 | 0.45<br>0.45   | Each Unit as Class A Amplifier Push-Pull Class C Amplifier                                  |
| For basing diagrams,<br>see pages 549 to 553,                           | 6J7<br>6J7-G<br>6J7-GT | Sharp-Cutoff<br>Pentode                         | 3<br>23<br>14A | 7R<br>7R‡‡<br>7R¥                 | 6.3   | 0.3  | Pentode Class A<br>RF Amplifier   |
| For explanation of foot-<br>notes, see page 548.  Types shown in light- | 6J8-G                  | Triode-<br>Heptode<br>Converter                 | 23             | вн                                | 6.3   | 0.3  | Triode Unit as Oscillator Heptode Unit as Mixer   |
| face are discontinued.  | 6K5-GT                 | High-Mu Triode                                  | 144            | 50                                | 6.3   | 0.3  | Class A Amplifier   |
|   | 6K7<br>6K7-G<br>6K7-GT | Remote-Cutoff<br>Pentode                        | 3<br>23<br>14A | 7R<br>7R‡<br>7R¥                  | 6.3   | 0.3  | Class A Amplifier   |
|   | 6K8<br>6K8-G<br>6K8-GT | Triode-Hexode<br>Converter                      | 3<br>23<br>—   | 8K.;<br>8K;                       | 6.3   | 0.3  | Triode Unit as Oscillator Hexode Unit as Mixer  |
|   | 6K11                   | Twin High-Mu<br>Triode—<br>Medium-Mu            | EA.            | 12 <b>BY</b>                      | 6.3⊕  | 0.6  | Twin Unit as<br>Class A Amplifier<br>Class A Amplifier                                      |
|   | 6L5-G                  | Triode<br>Medium-Mu<br>Triode                   | 22             | 6Q;                               | 6.3   | 0.15   | Class A Amplifier   |
|   | 6L6-G<br><b>6L6-GB</b> | Beam Power<br>Tube                              | 27B<br>190     | 7AC<br>7AC;<br>7AC<br>7AC         | 6.3   | 0.9  | Single-Tube Class A Amplifier Push-Pull Class A Amplifier Push-Pull Class AB, Amplifier     |
|   | 6L7<br>6L7-G           | Pentagrid<br>MixerA                             | 3<br>23        | π;                                | 6.3   | 0.3  | Mixer Service   |
|   | 6N6-G                  | Direct-Coupled<br>Power Triode                  | 25             | 7AU                               | 6.3   | 0.8  | Class A Amplifier   |

| ,—   |   | г                              |                              |                             |                                     | ,  | · · · · · · · · · · · · · · · · · · · |   |                               |                        |
|--|---|--------------------------------|------------------------------|-----------------------------|-------------------------------------|--|---------------------------------------|---|-------------------------------|------------------------|
| Plate<br>Sup-<br>ply<br>Volts                                | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor<br>Ohms (Ω) | Screen<br>Sup-<br>ply<br>Yelts | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent<br>Ma | AC Plate<br>Resis-<br>tance<br>Obms | Trans-<br>conduc-<br>tance<br>Micromhos  | Amplifi-<br>cation<br>Factor          | Load<br>for Stated<br>Power<br>Output<br>Ohms | Power<br>Out-<br>put<br>Watts | RCA)<br>Type           |
| 100  | 1.2v  |                                |                              | 15                          | 2500                                | 13000                                    | 33                                    |   |                               | 6FW8                   |
| 180  | ~ 9v  | 180                            | 2.5                          | 15.0                        | 175000                              | 2300                                     |                                       | 10000   | 1.1                           | 6G6-G                  |
| Max.   | DC Plate  | Volts, 330                     | )                            |                             |                                     | Max.                                     | Plate Diss                            | pation, 2                                     | .5 watts                      |                        |
|  | DC Plate V<br>Peak Neg.   |                                |                              |                             | x. Peak Ca<br>x. DC Cati            |  |                                       | Plate<br>pation, 2                            | .5 watts                      | 6GH8                   |
| 125  | - 1v  |                                |                              | 13.5                        | 5000                                | 8500                                     | 40                                    |   |                               | 6GJ8                   |
| 125  | - 1v  | 125                            | 4.5                          | 12                          | 150000                              | 7500                                     |                                       |   |                               | oajs                   |
|  | AC Supply<br>Total Effec  |                                |                              |                             |                                     | wave. 30 o                               | Max. DC C                             | utput M                                       | a., 8. min.                   |                        |
| Max.   | AC Plate V  | olts (RA                       | (S), 150                     |                             | Min. To                             | tal Effectiv                             | e Plate-Su                            | ply Imp                                       | edance: up                    | 6H6-GT                 |
| 90<br>250  | 0v<br>- 8v  | =                              | =                            | 10<br>9                     | 6700<br>7700                        | 3000<br>2600                             | 20<br>20                              | =   | =                             | ียร<br>ยร-GT           |
| 100  | 50α (F  | or both t                      | inits)                       | 8.5                         | 7100                                | 5300                                     | 38                                    |   |                               | 6]6                    |
| 150  | -10v  |                                |                              | 30                          |                                     | rrent, 16 m<br>Power, 0.3                |                                       |   | 3.5                           | 0,10                   |
|  | _   |                                |                              |                             |                                     |  |                                       |   |                               | 6J7                    |
| 100<br>250   | - 3v<br>- 3v  | 100<br>100                     | 0.5<br>0.5                   | 2.0<br>2.0                  | 1.0§<br>1.0§                        | 1185<br>1225                             |                                       |   | _                             | 6J7-G<br>6J7-GT        |
| 100<br>250 =   |   | Grid Res                       |                              | 4 5                         |                                     |  | =                                     | $\equiv$                                      |                               |                        |
| 250  | - 3v  | 100                            | 2.8                          | 1.4                         | 1.5§                                | Conversion                               | Transcond                             | i., 290 mi                                    | cromhos.                      | 6J8-G                  |
| 250  | - 3v  |                                |                              | 1,1                         | 50000                               | 1400                                     | 70                                    |   |                               | 6K5-GT                 |
| 250  | – 3v  | 125                            | 2.6                          | 10.5                        | 600000                              | 1650                                     |                                       |   |                               | 6K7<br>6K7-G<br>6K7-GT |
| 100  | Grid R  | <b>≈.,</b> 50000               | ) ohms                       | 3.8                         | Triode-                             | Grid & Hea                               | code-Grid (                           | Current, C                                    | .15 ma.                       | 6K8                    |
| 100<br>250   | - 3v<br>- 3v  | 100<br>100                     | 6.2<br>6.0                   | 2.3<br>2.5                  | 400000<br>600000                    |  | n Transcon                            |   |                               | 6K8-G<br>6K8-GT        |
| 250  | - 2v  |                                |                              | 1.2                         | 62500                               | 1600                                     | 100                                   |   |                               | CTP11                  |
| 250  | - 8.5v  |                                |                              | 10.5                        | 7700                                | 2200                                     | 17                                    |   |                               | 6K11                   |
| 250  | – 9v  | _=                             |                              | 8.0                         | 9000                                | 1900                                     | 17                                    |   |                               | 6L5-G                  |
| 250<br>250   | −14v<br>168Ω  | 250<br>250                     | 5.0<br>5.4                   | 72.0<br>75.0                | _ == 1                              |  |                                       | 2500<br>2500                                  | 6.5<br>6.5                    |                        |
| 270<br>270   | −17.5v<br>124Ω <b>♠</b>   | 270<br>270                     | 11.04                        | 134.0<br>134.0              | _=                                  | =  |                                       | 5000<br>5000                                  | 17.5†<br>18.5†                | 6L6-GB                 |
| 360<br>360   | 22.5v<br>248Ω♠  | 270<br>270                     | 5.0<br>5.0                   | 88.0<br>88.0                |                                     |  |                                       | 6600<br>9000                                  | 26.5†<br>24.5†                |                        |
| 250  | - 6v  | 150                            | 9.2                          | 2.3                         | Grid-N                              | or-Grid (N<br>o. 3 Peak S<br>sion Transc | wing, 16 v                            | olts minir                                    | num.                          | 6L7<br>6L7-G           |
|  | put Triode:<br>de: Plate V                                      |                                |                              |                             | ., 45; Load                         | , 7000 ohm                               |                                       |   | 4.0                           | 6N6-G                  |
| Triode: Plate Volts, 300; Grid Volts, 0; Input Plate Ma., 8. |   |                                |                              |                             |                                     |  |                                       |   |                               |                        |

For explanation of foot-notes, see page 548. Types shown in light-face are discontinued.

|       | RCA<br>Type                           | Name   | Dime<br>and               | be<br>nsions<br>Basing<br>gram△<br>B.D. | Filam<br>Unless sp<br>types hav<br>⊕ Heater | ent (F) ecified all re heaters. with con- rmup time. Amps. | Values to right give operating conditions and characteristics for indicated typical use |
|-------|---------------------------------------|--|---------------------------|---|---|--|---|
| 61    | 6N7<br>N7-GT                          | Medium-Mu<br>Twin Power<br>Triode              | 2B<br>13D                 | 88<br>8B:                               | 6.3   | 0.8  | Class A Amplifier (as Driver)° Class B Amplifier  |
| 6     | P5-GT                                 | Medium-Mu<br>Triode                            | 13D                       | 8Q;                                     | 6.3   | 0.3  | Amplifier<br>Detector   |
|       | 5P7-G                                 | Low-Mu Triode—<br>Remote-Cutoff<br>Pentode     | 23                        | 70                                      | 6.3   | 0.3  | Amplifier<br>and Converter  |
|       | <b>6Q7</b><br>5Q7-G<br>5Q7-G <b>T</b> | Twin Diode<br>High-Mu<br>Triode                | 3<br>23<br>14A            | 7V<br>7V;<br>7V×                        | 6.3   | 0.3  | Triode Unit as<br>Class A Amplifier   |
|       | 6Q11                                  | Twin High-Mu<br>Triode—<br>Medium-Mu<br>Triode | 6A 12BY                   |   | 6.3⊕  | 0.6  | Twin Unit as<br>Class A Amplifier<br>Class A Amplifier                                  |
|       | 6R7<br>6R7-G<br>R7-GT                 | Twin Diode—<br>Medium-Mu<br>Triode             | 3 7V<br>23 7V:<br>144 7V: |   | 6.3   | 0.3  | Triode Unit as<br>Class A Amplifier   |
|       | 6S4                                   | Medium-Mu<br>Triode                            | SE SAC                    |   | 6.3<br>6.3⊕                                 | 0.6<br>0.6   | Vertical Deflection<br>Amplifier  |
|       | 6S7                                   | Remote-Cutoff<br>Pentode                       | 3<br>23                   | 7R<br>7R‡                               | 6.3   | 0.15   | Class A Amplifier   |
| 6     | S8-GT                                 | Triple Diode<br>High-Mu Triode                 | 14C                       | 8CB                                     | 6.3   | 0.3  | Triode Unit as<br>Class A Amplifier   |
| 65    | A7-GT                                 | Pentagrid<br>Converter▲                        | 13D                       | 8R<br>8AD                               | 6.3   | 0.3  | Mixer   |
| 6     | SB7-Y                                 | Pentagrid<br>Converter▲                        | 2A                        | 8R                                      | 6.3   | 0.3  | Mixer   |
| ~     | 6SC7                                  | High-Mu<br>Twin Triode                         | 2A                        | 85                                      | 6.3   | 0.3  | Each Unit as<br>Amplifier   |
|       | 6SF5<br>F5-GT                         | High-Mu<br>Triode                              | 2A<br>13D                 | 6AB<br>6AB‡                             | 6.3   | 0.3  | Class A Amplifier   |
|       | 6SF7                                  | Diode—<br>Remote-Cutoff<br>Pentode             | 2A                        | 7AZ                                     | 6.3   | 0.3  | Pentode Unit as<br>Class A Amplifier  |
|       | 6SG7                                  | Semiremote-<br>Cutoff Pentode                  | 2A                        | 8BK                                     | 6.3   | 0.3  | Class A Amplifier   |
|       | 6SH7                                  | Sharp-Cutoff<br>Pentode                        | 2A                        | 8BK                                     | 6.3   | 0.3  | Class A Amplifier   |
|       | SJ7-GT                                | Sharp-Cutoff<br>Pentode                        | 13D                       | 8N%<br>8N                               | 6.3   | 0.3  | Class A Amplifier   |
| 963 L | 6SK7<br>K7-GT                         | Remote-Cutoff<br>Pentode                       | 2A 8N<br>13D 8NK          |   | 6.3   | 0.3  | Class A Amplifier   |
|       | N7-GT<br>N7-GTA                       | Medium-Mu<br>Twin Triode                       | 13D<br>13D 8BD            |   | 6.3<br>6.3<br>6.3⊕                          | 0.6<br>0.6<br>0.6  | Each Unit as<br>Class A Amplifier<br>Each Unit as<br>Vertical Amplifier                 |
| 65    | Q7-GT                                 | Twin-Diode<br>High-Mu Triode                   | 13D                       | 8Q<br>%Q8                               | 6.3   | 0.3  | Triode Unit as<br>Class A Amplifier   |
|       | 6SR7                                  | Twin Diode—<br>Medium-Mu<br>Triode             | 2A                        | 8Q                                      | 6.3   | 0.3  | Triode Unit as<br>Class A Amplifier   |

| Plate<br>Sup-<br>ply | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor | Screen<br>Sup-<br>ply | Screen<br>Cur-<br>rent | Plate<br>Cur-<br>rent | AC Plate<br>Resis-<br>tance      | Trans-<br>conduc-<br>tance | Amplifl-<br>cation<br>Factor | Locad<br>for Stated<br>Power<br>Output | Power<br>Out-<br>put | RCA<br>Type            |
|----------------------|---|-----------------------|------------------------|-----------------------|----------------------------------|----------------------------|------------------------------|--|----------------------|------------------------|
| Velts                | Ohms (Ω)  | Velts                 | Ma                     | Ma.                   | Chaes                            | Micrombes                  |                              | Olues                                  | Watts                |                        |
| 250<br>300           | - 5v<br>- 6v  |                       | l                      | 6.0<br>7.0            | 11300<br>11000                   | 3100<br>3200               | 35<br>35                     | 20000<br>or more                       | exceeds<br>0.4       | 6N7                    |
| 300                  | 0v  | Power                 | Output f               |                       | at stated pl                     |                            |                              | 8000                                   | 10.0                 | 6N7-GT                 |
|                      |   | F                     | or other c             | haracteri             | stics, refer to                  | Туре 76.                   |                              |  |                      | 6P5-GT                 |
|                      |   | F                     | or other o             | haracteri             | istics, refer t                  | о Туре 6F                  | 7.                           |  |                      | 6P7-G                  |
| 100<br>250           | - 1v<br>- 3v  | _                     | _                      | 0.8<br>1.1            | 58000<br>58000                   | 1200<br>1200               | 70<br>70                     |  |                      | 6Q7<br>6Q7-G<br>6Q7-GT |
| 250                  | - 2v  |                       |                        | 1.2                   | 62500                            | 1600                       | 100                          |  |                      |                        |
| 150                  | 0v  |                       |                        | 22                    | 7000                             | 2500                       | 18                           |  |                      | 6Q11                   |
| 250                  | – 9v  | _                     |                        | 9.5                   | 8500                             | 1900                       | 16                           |  |                      | 6R7<br>6R7-G<br>6R7-GT |
|                      | C Plate Vol   |                       |                        |                       | Max. Peak<br>Max. Plate          |                            |                              |  | 0                    | 6S4                    |
| 250                  | - 3v  | 100                   | 2.0                    | 8.5                   | 1.05                             | 1750                       |                              |  |                      | 6S7                    |
| 250                  | - 2v  | _                     |                        | 0.9                   | 91000                            | 1100                       | 100                          |  |                      | 6S8-GT                 |
| 250                  | Self-<br>Excited                                    | 100                   | 8.5                    | 3.5                   | 1.0§                             |                            | 1 Resistor                   |  |                      | 6SA7-GT                |
| 100                  | - 1v  | 100                   | 10.2                   | 3.6                   | 500000                           |                            | 1 Resistor                   |  |                      | 6SB7-Y                 |
| 250                  | - 2v  |                       |                        | 2.0                   | 53000                            | 1325                       | 70                           |  |                      | 6SC7                   |
| 250                  | – 2v  |                       |                        | 0.9                   | 66000                            | 1500                       | 100                          | _                                      |                      | 6SF5<br>6SF5-GT        |
| 100<br>250           | - 1v<br>- 1v  | 100<br>100            | 3.4<br>3.3             | 12.0<br>12.4          | 200000<br>700000                 | 1975<br>2050               |                              |  |                      | 6SF7                   |
| 100                  | - lv  | 100                   | 3.2                    | 8.2                   | 250000                           | 4100                       |                              |  |                      | 6SG7                   |
| 250<br>100           | - 2.5v  | 150<br>100            | 3.4<br>2.1             | 9.2<br>5.3            | 1.0§<br>350000                   | 4000<br>4000               |                              |  | -                    | 6SH7                   |
| 250                  | - 1v  | 150                   | 4.1                    | 10.8                  | 900000                           | 4900                       |                              |  |                      | 0311/                  |
| 100<br>250           | - 3v<br>- 3v  | 100<br>100            | 0.9                    | 2.9<br>3.0            | 700000<br>1.0+§                  | 1575<br>1650               |                              |  |                      | 6SJ7-GT                |
| 100<br>250           | - 1v<br>- 3v  | 100<br>100            | 4.0<br>2.6             | 13.0<br>9.2           | 120000<br>800000                 | 2350<br>2000               |                              |  |                      | 6SK7<br>6SK7-GT        |
| 90<br>250            | 0v<br>- 8v  | $\equiv$              |                        | 10.0<br>9.0           | 6700<br>7700                     | 3000<br>2600               | 20<br>20                     |  | =                    | 6SN7-GT                |
| Max.                 | DC Plate V<br>Peak Catho                            |                       |                        | Plate Di              | ssipation: 5 v<br>sitive Pulse I | vatts eithe                | r plate; 7.5                 | watts bot                              | h plates             | 6SN7-GTA               |
| 100<br>250           | - 1v<br>- 2v  | _                     | —                      | 0.5<br>1.1            | 110000<br>85000                  | 925<br>1175                | 100<br>100                   |  |                      | 6SQ7-GT                |
| 250                  | - 9v  |                       |                        | 9.5                   | 8500                             | 1900                       | 16                           |  |                      | 6SR7                   |

|   | RGA<br>Type    | Name  | Dime<br>and I | ube<br>Insions<br>Basing<br>gram∆ |                    | e heaters.<br>with con- | Use Values to right give operating conditions and characteristics for indicated typical use |
|---|----------------|---|---------------|-----------------------------------|--------------------|-------------------------|---|
| L |                |   | Dim.          | 8, D.                             | Volts              | Amps.                   |   |
|   | 6557           | Remote-Cutoff<br>Pentode                        | 2A            | 8N                                | 6.3                | 0.15                    | Class A Amplifier   |
|   | 6ST7           | Twin Diode—<br>Medium-Mu<br>Triode              | 2A            | 8Q                                | 6.3                | 0.15                    | Triode Unit as<br>Amplifier   |
|   | 6SZ7           | Twin Diode—<br>High-Mu Triode                   | 2A            | 8Q                                | 6.3                | 0.15                    | Triode Unit as<br>Class A Amplifier   |
|   | 6T4            | Medium-Mu<br>Triode                             | 60            | 7DK                               | 6.3                | 0.225                   | Oscillator in UHF<br>TV Receivers<br>Class A Amplifier                                      |
|   | 6 <b>T</b> 7-G | Twin Diode—<br>High-Mu Triode                   | 2.            | 7V;                               | 6.3                | 0.15                    | Triode Unit as<br>Class A Amplifier   |
|   | 6T8            | Triple Diode—<br>High-Mu Triode                 | (B            | 9E                                | 6.3<br>6.3⊕        | 0.45<br>0.45            | Triode Unit as<br>Class A Amplifier   |
|   | 6U5            | Electron-Ray<br>Tube                            | 13H           | 6R                                | 6.3                | 0.3                     | Visual<br>Indicator   |
|   | 6U7-G          | Remote-Cutoff<br>Pentode                        | 28.j          | 7R‡                               | 6.3                | 0.3                     | Class A Amplifier   |
|   | 6U8            | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode |               | SAE                               | 6.3<br>6.3⊕        | 0.45<br>0.45            | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                 |
|   | 6V6-GT         | Beam<br>Power Tube                              | 13D           | 7AC<br>7AC‡<br>7AC‡               | 6.3<br>6.3<br>6.3⊕ | 0.45<br>0.45<br>0.45    | Single-Tube Class A Amplifier Push-Pull Class AB <sub>1</sub> Amplifier                     |
|   | 6V7-G          | Twin Diode—<br>Low-Mu Triode                    | 23            | 7V;                               | 6.3                | 0.3                     | Triode Unit as  |
|   | 6W7-G          | Sharp-Cutoff<br>Pentode                         | 23            | 7R‡                               | 6.3                | 0.15                    | Class A Amplifier   |
|   | 6X5            | Full-Wave<br>Rectifier                          | 28            | 6S;                               | 6.3                | 0.6                     | With Capacitive-<br>Input Filter<br>With Inductive-<br>Input Filter                         |
|   | 6¥5            | Full-Wave<br>Rectifier                          | 22 or<br>13H  | 61                                | 6.3                | 0.8                     | With Capacitive-<br>Input Filter  |
|   | 6Y7-G          | High-Mu Twin<br>Power Triode                    | 22            | 8B;                               | 6.3                | 0.6                     | Class B Amplifier   |
|   | 6 <b>2</b> 5   | Full-Wave<br>Rectifier                          | 22            | 6K                                | 6.3<br>12.6        | 0.8<br>0.4              | With Capacitive-<br>Input Filter  |
|   | 6Z7-G          | High-Mu Twin<br>Power Triode                    | 22            | 8B:                               | 6.3                | 0.3                     | Class B Amplifier   |
|   | 6ZY5-G         | Full-Wave<br>Rectifier                          | 22            | 68;                               | 6.3                | 0.3                     | With Capacitive-<br>Input Filter  |
| ۱ | 7A4            | Medium-Mu<br>Triode                             | 128           | BAC                               | 6.3                | 0.3                     | Amplifier   |
| l | 7A5            | Beam<br>Power Tube                              | 12C           | 6AA                               | 6.3                | 0.75                    | Class A Amplifier   |
|   | 7A6            | Twin Diode                                      | 12B           | 7AJ                               | 6.3                | 0.15                    | Detector Rectifier  |
|   | 7A7            | Remote-Cutoff<br>Pentode                        | 128           | 87                                | 6.3                | 0.3                     | Class A Amplifier   |
|   | 7A8            | Octode<br>Converter                             | 128           | 8U                                | 6.3                | 0.15                    | Converter   |
|   | 7AD7           | Power<br>Pentode                                | 12C           | 87                                | 6.3                | 0.6                     | Class A Amplifier   |
|   |                |   |               |                                   |                    |                         |   |

Medium-Mu Twin Triode

**7AF7** 

128

BAC

6.3

0.3

Each Unit as Class A Amplifier

NOTES

For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

|   |   |                       | ,                      |                       |                             |                            |                              |                                       |   |               |
|---|---|-----------------------|------------------------|-----------------------|-----------------------------|----------------------------|------------------------------|---------------------------------------|---|---------------|
| Plate<br>Sup-<br>ply  | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor | Screen<br>Sup-<br>ply | Screen<br>Cur-<br>rent | Plate<br>Cur-<br>rent | AC Plate<br>Resis-<br>tance | Trans-<br>conduc-<br>tance | Amplifi-<br>cation<br>Factor | Load<br>for Stated<br>Power<br>Output | Power<br>Out-<br>put                      | RCA<br>Type   |
| Veits   | Ohms ( $\Omega$ )                                   | Volts                 | Ma                     | Ma.                   | Ohms                        | Micromhos                  |                              | Ohms                                  | Watts                                     |               |
| 250   | - 3v  | 100                   | 2.0                    | 9.0                   | 1.05                        | 1850                       |                              | <u> </u>                              |   | 6SS7          |
|   |   | F                     | or other cl            | naracteria            | stics, refer t              | to Type 68                 | iR7.                         |                                       |   | 6ST7          |
| 100<br>250  | - 1v<br>- 3v  |                       |                        | 0.8                   | 54000<br>58000              | 1300<br>1200               | 70<br>70                     |                                       |   | 6SZ7          |
| Max.  | DC Plate  |                       |                        |                       |                             | Max.                       | Grid Ma.,                    |                                       |   |               |
|   | DC Catho  | ie Ma., 3             | 0                      |                       |                             |                            | Plate Diss                   | ipation, 3                            | .5 watts                                  | 6T4           |
| 80  | 150Ω  | _=                    |                        | 18                    | 62000                       | 7000<br>1050               | 13<br>65                     |                                       | <u> </u>                                  |               |
| 250<br>300 ×  | 3v<br>4580Ω   |                       | H <del></del>          | 1.2<br>Grid R         | esistor,** 0                |                            |                              | in per ste                            | ige = 40                                  | 6T7-G         |
| 100 A   | - 1v  |                       |                        | 0.8                   | 54000                       | 1300                       | 70                           |                                       | - 40                                      |               |
| 250   | - 3v  |                       |                        | 1.0                   | 58000                       | 1200                       | 70                           | === .                                 |   | 6T8           |
| Plate<br>Grid   | ås Target Su<br>Bias, -22                           | ipply = 2             | 50 volts. T            | riode Pla             | ate Resistor                | = 1.0 meg                  | g. Target C                  | urrent =                              | 4.0 ma.<br>24 ma.                         | 6U5           |
| 250   | - 3v  | 100                   | 2.0                    | 8.2                   | 800000                      | 1600                       |                              |                                       |   | 6U7-G         |
| 125   | – 1v  |                       |                        | 13.5                  |                             | 7500                       | 40                           |                                       |   | 6U8           |
| 125   | - 1v  | 110                   | 3.5                    | 9.5                   | 200000                      | 5000                       |                              |                                       |   | -             |
| 250   | -12.5v  | 250                   | 4.5                    | 45.0                  | 50000                       | 4100                       |                              | 5000                                  | 4.5                                       |               |
| 315   | -13v  | 225                   | 2.2                    | 34.0                  | 80000                       | 3750                       |                              | 8500                                  | 5.5                                       | 6V6-GT        |
| 250<br>285  | -15v<br>-19v  | 250<br>285            | 5.0♠<br>4.0♠           | 70.0♠<br>70.0♠        |                             |                            |                              | 10000<br>8000                         | 10.0†<br>14.0†                            |               |
|   |   | F                     | or other cl            | naracteri             | stics, refer t              | to Type 85                 |                              |                                       |   | 6V7-G         |
| 250   | 3v  | 100                   | 0.5                    | 2.0                   | 1.55                        | 1225                       |                              |                                       |   | 6W7-G         |
|   | AC Volts p  |                       |                        |                       | . DC Outp                   |                            |                              | tal Effect                            |   |               |
|   | Peak Inver  |                       |                        |                       | . Peak Plat                 |                            |                              |                                       | out Choke,                                | 6X5           |
|   | AC Volts p  |                       |                        |                       | . DC Outpu<br>. Peak Plat   |                            |                              | or inf<br>O henries                   |   |               |
| Man.  | reak Inve   | ac voica,             | Max. A                 | C Volta               | per Plate (I                |                            |                              |                                       |   | 6Y5           |
|   |   |                       |                        |                       | it Ma., 50                  |                            |                              |                                       |   |               |
|   |   | F                     |                        |                       | stics, refer t              |                            |                              |                                       |   | 6¥7-G         |
|   |   |                       | Max. E                 | C Outpu               | per Plate (l<br>it Ma., 60  | KM(5), 230                 |                              |                                       |   | 6 <b>Z</b> 5  |
| 180   | 0v  | Power C               | Output is f            |                       | be at stated                |                            |                              | 12000                                 | 4.2                                       | 6Z7-G         |
| Max. I  | Peak Invers   | e Volts, 1            | 250                    |                       | C Output I                  |                            | Min. To<br>Imped. p          | tal Effect<br>er Plate,               |   | 6ZY5-G        |
|   |   | F                     | or other cl            | naracteris            | stics, refer t              |                            | 5.                           |                                       |   | 7A4           |
| 110   -7.5v   110   3.0   40.0   16000   5800     2500   1.5   125   -9v   125   3.3   44.0   17000   6000   2700   2.2 |   |                       |                        |                       |                             |                            |                              |                                       |   |               |
| Max   | AC Voltag   |                       | te, 150 Vo             | lts, RM               | S Max                       | x. DC Out                  | put Curren                   | t per plat                            | e, 8 Ma.                                  | 7A6           |
|   |   |                       |                        |                       | stica, refer t              |                            |                              |                                       |   | 7A7           |
| 250   | - 3v  | 100                   | 3.2                    | 3.0                   | 700000                      | Anode-Gr<br>4.2 ma. C      | id (#2):<br>scillator-G      | rid (#1)                              | nax. volts,<br>Resistor • .<br>micromhos. | 7A8           |
| 300   | 68Ω   | 150                   | 7.0                    | 28.0                  | 300000                      | 9500                       |                              |                                       | ,   | 7 <b>A</b> D7 |
| 250   | -10v  |                       |                        | 9.0                   | 7600                        | 2100                       | 16                           |                                       |   | 7AF7          |

| RCA<br>Type   | Name                                    | Dime<br>and I | i <b>be</b><br>nsions<br>Basing<br>jram∆ | Filam<br>Unless sp<br>types har<br># Heater | ent (F)<br>ecified all<br>re heaters.<br>with con-<br>irmup time. | Use  Yalues to right give operating conditions and characteristics for indicated typical use |
|---------------|---|---------------|--|---|---|--|
|               |   | Dim.          | 8. D.                                    | Volts                                       | Amps.   |  |
| 7AG7          | Sharp-Cutoff<br>Pentode                 | 12B           | 8V                                       | 6.3   | 0.15  | Class A Amplifier  |
| 7 <b>AH</b> 7 | Sharp-Cutoff<br>Pentode                 | 128           | 87                                       | 6.3   | 0.15  | Class A Amplifier  |
| 7B4           | High-Mu Triode                          | 128           | 5AC                                      | 6.3   | 0.3   | Amplifier  |
| 7B5           | Power Pentode                           | 12C           | 6AE                                      | 6.3   | 0.4   | Class A Amplifier  |
| 7 <b>B</b> 6  | Twin Diode—<br>High-Mu Triode           | 12 <b>B</b>   | 8W                                       | 6.3   | 0.3   | Triode Unit as Amplifier   |
| 7 <b>B</b> 7  | Remote-Cutoff<br>Pentode                | 128           | 87                                       | 6.3   | 0.15  | Class A Amplifier  |
| 7B8           | Pentagrid<br>Converter                  | 12B           | 8X                                       | 6.3   | 0.3   | Converter  |
| 7C5           | Beam Power<br>Tube                      | 12C           | 6AA                                      | 6.3   | 0.45  | Class A Amplifier  |
| 7C6           | Twin Diode—<br>Aigh-Mu Triode           | 12B           | 8W                                       | 6.3   | 0.15  | Triode Unit as<br>Class A Amplifier  |
| 7C7           | Sharp-Cutoff<br>Pentode                 | 128           | #V                                       | 6.3   | 0.15  | Class A Amplifier  |
| 7 <b>E</b> 6  | Twin Diode—<br>Medium-Mu<br>Triode      | 128           | 8W                                       | 6.3   | 0.3   | Triode Unit as<br>Amplifier  |
| 7E7           | Twin Diode—<br>Remote-Cutoff<br>Pentode | 12 <b>B</b>   | 8AE                                      | 6.3   | 0.3   | Pentode Unit as<br>Class A Amplifier   |
| 7 <b>F</b> 7  | High-Mu<br>Twin Triode                  | 12B           | 8AC                                      | 6.3   | 0.3   | Each Unit as<br>Amplifier  |
| 7F8           | Medium-Mu<br>Twin Triode                | 12A           | 8BW                                      | 6.3   | 0.3   | Each Unit as<br>Class A Amplifier  |
| 7 <b>G</b> 7  | Sharp-Cutoff<br>Pentode                 | 128           | 87                                       | 6.3   | 0.45  | Class A Amplifier  |
| 7H7           | Semiremote-<br>Cutoff Pentode           | 128           | 8V                                       | 6.3   | 0.3   | Class A Amplifier  |
| 737           | Triode-Heptode<br>Converter             | 12 <b>B</b>   | 8BL                                      | 6.3   | 0.3   | Triode Unit as Oscillator Heptode Unit as Mixer  |
| 7K7           | Twin Diode—<br>High-Mu Triode           | 128           | 8BF                                      | 6.3   | 0.3   | Triode Unit as<br>Class A Amplifier  |
| 7L7           | Sharp-Cutoff<br>Pentode                 | 128           | 87                                       | 6.3   | 0.3   | Class A Amplifier  |
| 7N7           | Medium-Mu<br>Twin-Triode                | 12C           | BAC                                      | 6.3   | 0.6   | Each Unit as<br>Class A Amplifier  |
| 7Q7           | Pentagrid<br>Converter                  | 128           | 8AL                                      | 6.3   | 0.3   | Converter  |
| 7R7           | Twin Diode—<br>Remote-Cutoff<br>Pentode | 128           | 8AE                                      | 6.3   | 0.3   | Pentode Unit as<br>Class A Amplifier   |
| 7S7           | Triode-Heptode<br>Converter             | 120           | 8BL                                      | 6.3   | 0.3   | Triode Unit as Oscillator Heptode Unit as Mixer  |
| <b>7V7</b>    | Sharp-Cutoff<br>Pentode                 | 128           | <b>5</b> V                               | 6.3   | 0.45  | Class A Amplifier  |
| 7W7           | Sharp-Cutoff<br>Pentode                 | 128           | 188                                      | 6.3   | 0.45  | Class A Amplifier  |
|               |   |               |  | -   |   |  |

8BZ

Triode Unit as Class A Amplifier

Twin Diode— High-Mu Triode

**7X7** 

NOTES

For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

| Plate   |  | T   |                       |              |              |                 | т                | · —        |                               |             |              |  |
|---|--|---|-----------------------|--------------|--------------|-----------------|------------------|------------|-------------------------------|-------------|--------------|--|
| 250   250a   250   2.0   6.0   1 meg.   4200  | Sup-<br>ply                                    | Volts (v)<br>or<br>Cathode<br>Resistor        | Screen<br>Sup-<br>ply | Cur-<br>rent | Cur-<br>rent | Resis-<br>tance | conduc-<br>tance | cation     | for Stated<br>Power<br>Output | Out-<br>put | RCA<br>Type  |  |
| For other characteristics, refer to Type 6SF5.   7BA  | 250  | 250α  | 250                   | 2.0          | 6.0          | 1 meg.          | 4200             |            | _                             |             | 7AG7         |  |
| For other characteristics, refer to Type 6K6-GT.   7B5   7B6   7B7   7B8    | 250  | 250Ω  | 250                   | 1.9          | 6.8          | 1 meg.          | 3300             |            |                               |             | 7AH7         |  |
| Por other characteristics, refer to Type 6SQ7.   7B6  |  |   |                       |              |              |                 |                  |            |                               | ·           | 7B4          |  |
| For other characteristics, refer to Type 6A8.   788   |  |   |                       |              |              |                 |                  |            |                               |             |              |  |
| For other characteristics, refer to Type 6A8.   768   |  |   | F                     | or other c   | haracteri    | stics, refer to | Type 6S          | Q7.        | ·                             |             | 7B6          |  |
| For other characteristics, refer to Type 6V6.   7C5   | 250  | 3v  | 100                   | 1.7          | 8.5          | 750000          | 1750             |            |                               | <u></u>     | 7B7          |  |
| 250   |  |   | F                     | or other c   | haracteri    | stics, refer to | Туре бА          | 8.         |                               |             | 7B8          |  |
| Test  |  | For other characteristics, refer to Type 6V6. |                       |              |              |                 |                  |            |                               |             |              |  |
| For other characteristics, refer to Type 6BF6.   7E6  | 250  | io – 1v — — 1.3 100000 1000 100 — —           |                       |              |              |                 |                  |            |                               |             |              |  |
| For other characteristics, refer to Type 6SL7-GT.   7F7   | 250  | - 3v  | 100                   | 0.5          | 2.0          | 2.05            | 1300             |            |                               |             | 7 <b>C</b> 7 |  |
| For other characteristics, refer to Type 6SL7-GT.   7F7   250   5000     6.0     3300   48     7F8   250   -2v   100   2.0   6.0   800000   4500     7G7                    | For other characteristics, refer to Type 6BF6. |   |                       |              |              |                 |                  |            |                               |             |              |  |
| 250   5000       6.0     3300   48     7F8     250   -2v   100   2.0   6.0   800000   4500     7G7     100   -1.5v   100   2.6   7.5   350000   4000     7H7     250   180n   150   3.2   10.0   800000   4000     7H7     250   Triode-Grid Resistor, 5.0   Triode-Grid & Heptode-Grid Current, 0.4 ma. 7J7     250   -3v   100   2.8   1.4   1.5  | 250 3300 100 1.6 7.5 700000 1300               |   |                       |              |              |                 |                  |            |                               |             |              |  |
| 250   -2v   100   2.0   6.0   80000   4500     7G7     100   -1.5v   100   2.6   7.5   35000   4000     7H7     250   180α   150   3.2   10.0   800000   4000     7H7     250   Triode-Grid Resistor, 5.0   Triode-Grid & Heptode-Grid Current, 0.4 ma.     250   -3v   100   2.8   1.4   1.5   |  |   | F                     | or other c   | haracteri    | stics, refer to | Type 6S          | L7-GT.     |                               |             | 7 <b>F</b> 7 |  |
| 100   | 250  | 500Ω  |                       |              | 6.0          |                 | 3300             | 48         |                               |             | 7F8          |  |
| Thick-Grid Resistor, Sound  |  |   | 100                   | 2.0          | 6.0          | 800000          | 4500             |            |                               |             | 7G7          |  |
| Those-Grid & Heptode-Grid & Heptode-Grid & Grid & Heptode-Grid & Hept |  | 180Ω  | 150                   | 3.2          |              |                 |                  |            |                               |             | 7H7          |  |
| 250   -3v   100   2.8   1.4   1.5\frac{1}{5}   Conversion Transcond., 290 μmhos.     250   -2v       2.3   44000   1600   70     7K7     100   -1v   100   2.4   5.5   100000   3000     7L7     100   Triode-Grid Resistor, 20000 chms   5.0     7R7     100   Triode-Grid Resistor, 5.0       7R7     100   Triode-Grid Resistor, 5.0       7R7     250   -2v   100   3.0   1.8   1.25\frac{1}{5}   Conversion Transcond., 525 μmhos.     160a   150   3.9   10.0   300000   5800     7V7     To other characteristics, refer to Type 7V7.   7W7  | 250 €  | Triode-                                       | Grid Res              | istor,       | 5.0          | Triode-G        | rid & Hep        | tode-Grid  | Current,                      | 0.4 ma,     | 717          |  |
| 100   | 250  | - 3v  | 100                   | 2.8          | 1.4          | 1.5§            | Conversi         | on Transco | ond., 290                     | μmhos.      | 131          |  |
| 250   -1.5v   100   1.5   4.5   1.0   3100     7L7     For other characteristics, refer to Type 6SN7-GT   7N7     250   -2v   100   8.5   3.5   1.0   Grid #1 Resistor, 20000 ohms. Conversion Transcond., 450 μmhos.   7Q7     250   -1v   100   2.1   5.7   1.0   3200     7R7     100   Triode-Grid Resistor, 50000 ohms   5.0       7S7     250   -2v   100   3.0   1.8   1.25   Conversion Transcond., 525 μmhos.     300   160α   150   3.9   10.0   300000   5800     7V7     For other characteristics, refer to Type 7V7.   7W7  | 250  | 2v  |                       |              | 2.3          | 44000           | 1600             | 70         |                               |             | 7K7          |  |
| 250   -2v   100   8.5   3.5   1.0   Grid #1 Resistor, 20000 ohms.   7Q7   |  |   |                       |              |              |                 |                  |            |                               |             | 7L7          |  |
| 250   -1v   100   2.1   5.7   1.0   3200     7R7  |  |   | For                   | other cha    | racterist    | cs, refer to    | Type 6SN         | 7-GT       |                               |             | 7N7          |  |
| 100 Triode-Grid Resistor, 3.0   | 250  | - 2v  | 100                   | 8.5          | 3.5          | 1.0§            |                  |            |                               |             | 7Q7          |  |
| 250         50000 ohms         5.0         —         —         —         —         7S7           250 a         - 2v         100         3.0         1.8         1.25§         Conversion Transcond., 525 μmhos.         7V7           For other characteristics, refer to Type 7V7.         7W7   | 250  | - 1v  | 100                   | 2.1          | 5.7          | 1.0§            | 3200             |            |                               |             | 7 <b>R</b> 7 |  |
| 250 <b>a</b> - 2 <b>v</b> 100 3.0 1.8 1.25§ Conversion Transcond., 525 μmhos.  300 160α 150 3.9 10.0 300000 5800 — —  |  |   |                       | istor,       |              |                 |                  |            |                               |             |              |  |
| For other characteristics, refer to Type 7V7.   |  |   |                       | 3.0          |              | 1.25§           | Conversi         | on Transco | ond., 525                     | μmhos.      | 787          |  |
|   | 300  | 160Ω  | 150                   | 3.9          | 10.0         | 300000          | 5800             |            |                               |             | 7V7          |  |
| 250 - 1v - 1.9 67000 1500 100 - 7X7   |  |   | F                     | or other o   | haracter     | istics, refer t | o Type 7\        | 77.        |                               |             | 7W7          |  |
|   | 250  | – 1v  |                       |              | 1.9          | 67000           | 1500             | 100        |                               |             | 7X7          |  |

|                            | REA          | Name  | Dime                   | be<br>nsions | Filam<br>Unless sp | ent (F)                        | Use<br>Yalues to right give   |
|----------------------------|--------------|---|------------------------|--------------|--------------------|--------------------------------|---|
|                            | Туре         | Name  | and Basing<br>Diagram∆ |              | trolled wa         | with con-                      | operating conditions<br>and characteristics for<br>indicated typical use    |
|                            |              |   | Dim.                   | B. D.        | Yeits              | Amps.                          |   |
|                            | 7Y4          | Full-Wave<br>Rectifier                        | 128                    | 5AB          | 6.3                | 0.5                            | With Capacitive-<br>Input Filter  |
|                            | 7 <b>Z</b> A | Full-Wave<br>Rectifier                        | 120                    | 5AB          | 6.3                | 0.9                            | With Capacitive-<br>Input Filter  |
|                            | 9BR7         | Twin Diode—<br>High-Mu Triode                 |                        | 9CF          | 4.7⊕<br>9.4        | 0.6<br>0.3                     | Triode Unit as<br>Class A Amplifier   |
|                            | 10           | Power Triode                                  | 278                    | 4D           | 7.5F               | 1.25                           | Class A Amplifier   |
|                            | 10C8         | High-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | 68                     | 9DA          | 10.5⊕              | 0.3                            | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier |
|                            | 11<br>12     | Detector<br>Amplifier                         | 47<br>40               | 4F<br>4D     | 1.1F               | 0.25                           | Class A Amplifier   |
|                            | 12A5         | Power Pentode                                 | 22 or<br>13H           | 78           | 6.3<br>12.6        | 0.6<br>0.3                     | Class A Amplifier   |
| . 22                       | 12A7         | Rectifier—<br>Power Pentode                   | 248                    | 7K           | 12.6               | 0.3                            | Pentode Unit as<br>Class A Amplifier<br>Half-Waye<br>Rectifier              |
|                            | 12A8-GT      | Pentagrid<br>Converter #                      | 144                    | BAJK         | 12.6               | 0.15                           | Converter   |
|                            | 12AC6        | Remote-Cutoff<br>Pentode⊙                     | 5C                     | 7BK          | 10.0<br>to<br>15.9 | 0.15<br>approx.<br>at 12.6 v   | Class A Amplifier   |
| diagrams,<br>149 to 553.   | 12AD6        | Pentagrid<br>Converter⊙                       | SC                     | 7CH          | 10.0<br>to<br>15.9 | 0.15<br>approx.<br>at 12.6 v   | Converter   |
| page 548.                  | 12AE6        | Twin Diode<br>Medium-Mu<br>Triode⊙            | SC .                   | 78T          | 10.0<br>to<br>15.9 | 0.15<br>approx.<br>at 12.6 v   | Triode Unit as<br>Class A Amplifier   |
| n in light-<br>scontinued. | 12AE6-A      | Twin Diode—<br>Medium-Mu<br>Triode⊙           | 5C                     | 78T          | 10.0<br>to<br>15.9 | 0.15<br>approx.<br>at 12.6 v   | Triode Unit as<br>Class A Amplifier   |
| - 2014 P                   | 12AE7        | Dual Triode                                   | 48                     | 8.4          | 10.0<br>to<br>15.9 | 0.45<br>approx.<br>at<br>12.6V | Unit No. 1 as<br>Class A Amplifier<br>Unit No. 2 as<br>Class A Amplifier    |
|                            | 12AF6        | Remote-Cutoff<br>Pentode⊙                     | SC                     | 7BK          | 10.0<br>to<br>15.9 | 0.15<br>approx.<br>at 12.6 v   | Class A Amplifier   |
|                            | 12AH7-GT     | Medium-Mu<br>Twin Triode                      | 13C                    | 8BE          | 12.6               | 0.15                           | Each Unit as<br>Class A Amplifier   |
|                            | 12AJ6        | Twin Diode—<br>Medium-Mu<br>Triode⊙           | 5C                     | 7 <b>B</b> T | 10.0<br>to<br>15.9 | 0.15<br>approx.<br>at 12.6 v   | Triode Unit as<br>Class A Amplifier   |
|                            | 12AL8        | Medium-Mu<br>Triode—<br>Power Tetrode⊙        | SE                     | 9GS          | 10.0<br>to<br>15.9 | 0.55<br>approx.<br>at 12.6 v   | Triode Unit as<br>Class A Amplifier<br>Tetrode Unit as<br>Class A Amplifier |
|                            | 12AU7        | Medium-Mu<br>Twin Triode                      | 48                     | 9A           | 6.3                | 0.3<br>0.15                    | Each Unit As<br>Class A Amplifier   |
|                            | 12AV7        | Medium-Mu<br>Twin-Triode                      | 6B                     | 9A           | 6.3<br>12.6        | 0.45<br>0.225                  | Each Unit as<br>Class A Amplifier   |

| Plate<br>Sup-<br>ply<br>Yots  | Grid Bias Volts (ν) or Cathode Resistor Ohms (Ω) | Screen<br>Sup-<br>ply<br>Yolis     | Screen<br>Cur-<br>rent<br>Ma       | Plate<br>Cur-<br>rent<br>Ma | AC Plate<br>Resis-<br>tance<br>Ohms | Trans-<br>conduc-<br>tance<br>Micromhos | Amplifi-<br>cation<br>Factor             | Load<br>for Stated<br>Power<br>Output<br>Ohms | Power<br>Out-<br>put<br>Watts | RCA<br>Type  |
|---|--|------------------------------------|------------------------------------|-----------------------------|-------------------------------------|---|--|---|-------------------------------|--------------|
| Max. I  | Peak Inverse                                     | Volts, 1                           | 250 1                              | Max. DO                     | Output M                            | [a., 70                                 | Max. Peak                                | Plate M                                       | a., 180                       | 7Y4          |
| Мах. І  | Peak Inverse                                     | Volts, 1                           | 250                                |                             | . DC Outpi                          |   |  | otal Effec.<br>per Plate                      |                               | 7 <b>Z</b> 4 |
| 250   | 200Ω   |                                    | <u> </u>                           | 10                          | 10900                               | 4000                                    | 60                                       |   |                               | 9BR7         |
| 425   | -40v   |                                    |                                    | 18.0                        | - 5000                              | 1600                                    | 8.0                                      | 10200   | 1.6                           | 10           |
| 250   | 390₂   |                                    |                                    | 7.3                         | 12000                               | 4400                                    | 53                                       |   |                               | 10C8         |
| 135   | 100Ω   | 135                                | 3.2                                | 11.5                        | 190000                              | 8000                                    |  |   |                               | 1000         |
| 135   | -10.5v   |                                    |                                    | 3                           | 15500                               | 440                                     |  |   |                               | 11<br>12     |
| 180   | -25v   | 180                                | 8.0                                | 45.0                        | 35000                               | 2400                                    |  | 3300  | 3.4                           | 12A5         |
| 135   | -13.5v   | 135                                | 2.5                                | 9.0                         | 100000                              | 975                                     |  | 13500   | 0.55                          | 12A7         |
| Maximum AC Plate Voltage 125 Volts, RMS Maximum DC Output Current 30 Milliamperes |  |                                    |                                    |                             |                                     |   |  |   | 1211,                         |              |
| For other characteristics, refer to Type 6A8-GT.                                  |  |                                    |                                    |                             |                                     |   |  |   | 12A8-GT                       |              |
| 12.6  |  | 12.6                               | .2                                 | .55                         | 500000                              |   | Grid-No. 1<br>Grid-No. 1                 |   |                               | 12AC6        |
| 12.6  | Self-<br>excited                                 | 12.6                               | 1.5                                | 0.45                        | IŞ                                  |   | 1 Resistor,<br>n Transcon                |   |                               | 12AD6        |
| 12.6  | 0v   |                                    |                                    | 0.75                        | 15000                               | 1000                                    | 15                                       |   |                               | 12AE6        |
| 12.6  | 0v   | _                                  |                                    | 1                           | 13000                               | 1300                                    | 16.7                                     |   |                               | 12AE6-A      |
| 12.6  | Grid Res   | . 1 .5 me                          | zohms                              | 1.9                         | 3150                                | 4000                                    | 13.0                                     |   |                               | 12AE7        |
| 12.6  | Grid Res   | . 1 megol                          | hm                                 | 7.5                         | 985                                 | 6500                                    | 6.4                                      |   |                               | IZAEI        |
| 12.6  |  | 12.6                               | 0.45                               | 1.1                         | 350000                              |   | Grid-No. 1<br>Grid-No. 1                 |   |                               | 12AF6        |
| 180   | - 6.5v   |                                    | :                                  | 7.6                         | 8400                                | 1900                                    | 16                                       |   |                               | 12AH7-GT     |
| 12.6  | Grid-No. 1<br>Grid-No. 1                         |                                    |                                    | s 0.75                      | 45000                               | 1200                                    | 55                                       |   |                               | 12AJ6        |
| 12.6  | - 0.9v<br>(across 2                              | .2 megohm                          | res.)                              | .5                          | 13000                               | 1000                                    | 13                                       |   |                               |              |
|   | Grid-No.<br>(across 2<br>Grid-No.                | 2 (Contr<br>2.2 megohn<br>1 (Space | ol Grid) V<br>1 res.)<br>-Charge C | rid) Vol                    |                                     | Grid-No.                                | ctor (Grid-<br>1 Ma., 75<br>sistance, 48 | Plate   | Plate) 7.2<br>Ma., 40         | 12AL8        |
| 100   | 0v<br>- 8.5v                                     |                                    |                                    | 11.8                        | 6250<br>7700                        | 3100<br>2200                            | 19.5<br>17                               | 7   | _                             | 12AU7        |
| 250   |  |                                    |                                    |                             |                                     |   |  |   |                               |              |

| RCA<br>Type              | Name  | Dime<br>and E | be<br>nsions<br>Basing<br>pram∆ | Filam<br>Unless sp<br>types hav<br>⊕ Heater | er or<br>ent (F)<br>ecified oil<br>re besters.<br>with coe-<br>rance time. | Use Values to right give eperating conditions and characteristics for indicated typical use |  |
|--------------------------|---|---------------|---------------------------------|---|--|---|--|
|                          |   | Dint.         | B, D.                           | Yelts                                       | Amps.  |   |  |
| 2AX4-GT<br>12AX4-<br>GTA | Half-Wave<br>Rectifier                          | 13D<br>13D    | 4CG                             | 12.6<br>12.6⊕                               | 0.6<br>0.6   | Television<br>Damper Service  |  |
| 12AX7                    | High-Mu<br>Twin-Triode                          | 638           | 9A                              | 6.3<br>12.6                                 | 0.3<br>0.15  | Each Unit as<br>Class A Amplifier   |  |
| 12AZ7                    | High-Mu<br>Twin Triode                          | 68            | 9A                              | 6.3<br>12.6                                 | 0.45<br>0.225  | Each Unit as<br>Class A Amplifier   |  |
| 12B8-GT                  | High-Mu Triode—<br>Remote-Cutoff<br>Pentode     | _             | 87                              | 12.6  | 0.3  | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                 |  |
| 12BA7                    | Pentagrid<br>Converter <b>≜</b>                 | OE.           | SCT                             | 12.6  | 0.15   | Converter   |  |
| 12BD6                    | Remote-Cutoff<br>Pentode                        | BC BC         | 7BK                             | 12.6  | 0.15   | Class A Amplifier   |  |
| 12BF6                    | Twin Diode—<br>Medium-Mu<br>Triode              | IC.           | 78T                             | 12.6  | 0.15   | Triode Unit as<br>Class A Amplifier   |  |
| 12BH7                    | Medium-Mu<br>Twin Triode                        | eg.           | 9.4                             | 6.3⊕<br>12.6                                | 0.6<br>0.3   | Vertical Deflec-<br>tion Amplifier  |  |
| 12BK5                    | Beam Power<br>Tube                              | 8E            | 9BQ                             | 12.6⊕                                       | 0.6  | Class A Amplifier   |  |
| 12BL6                    | Remote-Cutoff<br>Pentode⊙                       | SC.           | 78K                             | 10.0<br>to<br>15.9                          | 0.15<br>approx.<br>at 12.6 v   | Class A Amplifier   |  |
| 12BR7                    | Twin Diode—<br>High-Mu Triode                   | 88            | 9CF                             | 6.3<br>12.6                                 | 0.45<br>0.225  | Triode Unit as<br>Class A Amplifier   |  |
| 12BV7                    | Sharp-Cutoff<br>Pentode                         | 98            | 9BF                             | 6.3<br>12.6                                 | 0.6<br>0.3   | Class A Amplifier   |  |
| 12BY7                    | Sharp-Cutoff<br>Pentode                         | 92            | 98F                             | 6.3⊕<br>12.6                                | 0.6<br>0.3   | Class A Amplifier   |  |
| 12C8                     | Twin Diode—<br>Semiremote-<br>Cutoff Pentode    | 3             | 8E                              | 12.6  | 0.15   | Pentode Unit as<br>RF Amplifier   |  |
| 12CN5                    | Remote-Cutoff<br>Pentode⊙                       | 80            | 7CV                             | 10.0<br>to<br>15.9                          | 0.45<br>approx.<br>at 12.6 v   | Class A Amplifier   |  |
| 12CT8                    | Medium-Mu<br>Triode—<br>Sharp-Cutoff<br>Pentode | æ             | 9DA                             | 12.6⊕                                       | 0.3  | Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier                          |  |
| 12CX6                    | Remote-Cutoff<br>Pentode⊙                       | SC SC         | 7BK                             | 10.0<br>to<br>15.9                          | 0.15<br>approx.<br>at 12.6 v   | Class A Amplifier   |  |
| 12DE8                    | Diode—<br>Remote-Cutoff<br>Pentode⊙             | 40            | 9HQ                             | 10.0<br>to<br>15.9                          | 0.2<br>approx.<br>at 12.6V   | Pentode Unit as<br>Class A Amplifier  |  |
| 12DK7                    | Twin Diode—<br>Power Tetrode⊙                   | 82            | 9HZ                             | 10.0<br>to<br>15.9                          | 0.5<br>approx.<br>at 12.6V   | Tetrode Unit as<br>Class A Amplifier  |  |
| 12DL8                    | Twin Diode—<br>Power Tetrode⊙                   | 6E            | 9HR                             | 10.0<br>to<br>15.9                          | 0.55<br>approx.<br>at 12.6 v   | Tetrode Unit as<br>Class A Amplifier  |  |
| 12DQ7                    | Power<br>Pentode                                | SEE .         | 9BF                             | 6.3⊕<br>12.5                                | 0.6  | Class A Amplifier   |  |

For beeing diagrams, see pages 549 to 553,

notes, see page 548.

| 100   | Mex<br>Max<br>100<br>250                       | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor<br>Ohms (Ω)<br>. Peak Inver<br>. Peak Plate<br>. DC Plate<br>. 1v<br>. 2v | Ma., 75           | Cur-<br>rent<br>Ma<br>Volts, 44 | 0.5        | **DC comp<br>80000<br>62500 | 1250<br>1600 | cation<br>Factor         | ( + 300               |                    | Type  12AX4-GT 12AX4-GTA 12AX7 |
|---|--|---|-------------------|---------------------------------|------------|-----------------------------|--------------|--------------------------|-----------------------|--------------------|--------------------------------|
| Por other characteristics, refer to Type 6BA7.   12BA7   12BA7   12BA7   12BA7   12BA7   12BA7   12BA7   12BA7   12BA7   12BA6   12BD6   16   16   16   16   16   16   16   |  |   |                   |                                 |            |                             |              |                          |                       |                    | 12AZ7                          |
| For other characteristics, refer to Type 6BA7.   12BA7   12BA6   12BB6   12BB7   12 |  |   |                   |                                 |            |                             |              | 90                       |                       |                    | 12B8-GT                        |
| Pro other characteristics, refer to Type 6BD6.   12BD6  | 90   | 3v  |                   | L                               |            |                             |              |                          |                       | L                  |                                |
| 250   -9v     9.5   8500   1900   16   Power Output, 300 milliwatts   12BF6   | For other characteristics, refer to Type 6BA7. |   |                   |                                 |            |                             |              |                          |                       | 12BA7              |                                |
| Max. DC Plate Volts, 450 Max. DC Plate Volts, 450 Max. DC Plate Ma., 20         Absolute Max. Peak Positive-Pulse Plate Volts, 1500 Max. Plate Dissipation (Each Unit), 3.5 watts         12BH7           250         - 5v         250         3.5         35         100000         8500         — 6500         3.5         12BK5           12.6         Grid-No. 1 and Grid-No. 3 Volts for transcond. of 10 micromhos, -5         12BL6         126 for transcond. of 10 micromhos, -5         12BL6           100         270α molecal molecular molecular micromhos, -5         10 1990 5500 60         — 12BR7           250         - 8v         180 micromhos, -5         12BV7           250         - 3v         125 micromhos, -75   |  |   | F                 | or other                        | characteri | stics, refer                | to Type 6    | BD6.                     |                       |                    | 12BD6                          |
| Max. DC Plate Ma.,         20         Max. Plate Dissipation (Each Unit), 3.5 watts         12BH7           250         - 5v         250         3.5         35         100000         8500         —         6500         3.5         12BK5           12.6         Grid-No. 1 and Grid-No. 3 Volts for transcond. of 10 micrombos, -5         12BL6         100         2700 —         —         3.7         15000   4000   5000   60         —         12BR7           250         2000 —         —         10         10990   5500   60         —         12BR7           250         68n   150   6   27   85000   13000   —         —         12BV7           250         - 8v   180   -         0.5 x         85000   13000   —         —         12BV7           250         - 8v   180   -         0.5 x         85000   13000   —         —         12BV7           250         - 3v   125   2.3   10   600000   1325   —         —         12C8           12.6         —         12.6   3.5   4.5   40000   3800   Grid-No. 1 Supply Volts, 0 Grid-No. 1 Res., 2.2 megohms}         12CN5           150         150a   -         —         9   8200   4900   40   —         —         12CT8           200         82a   125   3.4   15   150000   7000   —         —         12CT8   | 250  | – 9v  |                   |                                 | 9.5        | 8500                        | 1900         | 16                       |                       |                    | 12BF6                          |
| 12.6   Grid-No. 1   12.6   0.5   1.35   50000   1350   Grid-No. 1 and Grid-No. 3 Volts for transcond. of 10 micromhos, -5   12BL6   |  |   |                   |                                 |            |                             |              |                          |                       | 12BH7              |                                |
| 12.6       Supply Volts, 0       12.6       0.5       1.35       500000       1350       for transcond. of 10 micromhos, -5       12BL6         100       2700       —       —       3.7       15000       4000       60       —       12BR7         250       2000       —       —       10       10900       5500       60       —       12BR7         250       680       150       6       27       85000       13000       —       12BV7         250       1000       180       5.75       26       93000       11000       —       12BY7         250       —       3.5       4.5       40000       3800       Grid-No. 1 Supply Volts, 0 Grid-No. 1 Supply Volts, 0 Grid-No. 1 Res., 2.2 megohms       12CN5         12.6       —       —       9       8200       4900       40       —       —       12CT8         12.6       Supply Volts, 0       12.6       1.4       3       40000       3100       Grid-No. 1 Volts for Plate Current of 10 μa., -4.5       12CX6         12.6       —       12.6       0.5       1.3       300000       1500       Grid-No. 1 Supply Volts, 0 Grid-No. 1 Res., 2.2 megohms       12DE8         12.6   | 250  | - 5v  | 250               | 3.5                             | 35         | 100000                      | 8500         |                          | 6500                  | 3.5                | 12BK5                          |
| 250   200a     10   10900   5500   60     12BK/     250   68a   150   6   27   85000   13000         250   -8v   180     0.5 x   85000   13000         250   100a   180   5.75   26   93000   11000         250   -3v   125   2.3   10   600000   1325         250   -3v   125   2.3   10   600000   1325         12.6     12.6   3.5   4.5   40000   3800   Grid-No. 1 Supply Volts, 0   Grid-No. 1 Res., 2.2 megohms     150   150a       9   8200   4900   40         200   82a   125   3.4   15   150000   7000         12.6   Grid-No. 1   12.6   1.4   3   40000   3100   Grid-No. 1 Volts for Plate Current of 10 μa., -4.5     12.6     12.6   0.5   1.3   300000   1500   Grid-No. 1 Supply Volts, 0   Grid-No. 1 Res., 2.2 megohms     12.6     12.6   1   6   4000   5000     3500   0.010   12DK7     12.6   Grid-No. 2 (Control Grid) Volts, -0.5   Ampl. Factor (Grid-No. 2 to Plate) 7.2   Grid-No. 1 (Space-Charge Grid) Volts, 12.6   Grid-No. 1 Ma., 75   Plate Ma., 40   Plate Resistance, 480 ohms   12DL8   12   | 12.6   | Supply  | 12.6              | 0.5                             | 1.35       | 500000                      | 1350         | for tr                   | of 10                 | 12BL6              |                                |
| 250   |  |   |                   |                                 |            |                             |              |                          |                       |                    | 12BR7                          |
| 250   1000   180   5.75   26   93000   11000   —   —   —   12BY7  | 250  | 68Ω   |                   | 6                               | 27         |                             |              |                          |                       |                    | 12BV7                          |
| 12.6 — 12.6 3.5 4.5 40000 3800 {Grid-No. 1 Supply Volts, 0 Grid-No. 1 Res., 2.2 megohms} 12CN5  150 1500 — 9 8200 4900 40 — 12CT8  200 82α 125 3.4 15 150000 7000 — — 12CT8  12.6 Grid-No. 1 Supply Volts, 0 12.6 1.4 3 40000 3100 Grid-No. 1 Volts for Plate Current of 10 μa., -4.5  12.6 — 12.6 0.5 1.3 300000 1500 Grid-No. 1 Supply Volts, 0 12DE8  12.6 — 12.6 1 6 4000 5000 — 3500 0.010 12DK7  12.6 Grid-No. 2 (Control Grid) Volts, -0.5 Ampl. Factor (Grid-No. 2 to Plate) 7.2 (across 2.2 megohm resistor) Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Transcond. (Grid-No. 2 to Plate), 15000 μmhos Grid-No. 1 Ma., 75 Plate Ma., 40 Plate Resistance, 480 ohms  |  |   |                   | 5.75                            |            | 93000                       | 11000        |                          |                       |                    | 12BY7                          |
| 12.6  | 250  | - 3v  | 125               | 2.3                             | 10         | 600000                      | 1325         |                          |                       |                    | 12C8                           |
| 200 82a 125 3.4 15 150000 7000 — 12CT8  12.6 Grid-No. 1 Supply Volts, 0 12.6 1.4 3 40000 3100 Grid-No. 1 Volts for Plate Current of 10 μa., -4.5 12CX6  12.6 — 12.6 0.5 1.3 300000 1500 Grid-No. 1 Supply Volts, 0 Grid-No. 1 Res., 2.2 megohms 12DE8  12.6 — 12.6 1 6 4000 5000 — 3500 0.010 12DK7  12.6 Grid-No. 2 (Control Grid) Volts, -0.5 (across 2.2 megohm resistor) (across 2.2 megohm resistor) Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Grid-No. 1 Ma., 75 Plate Ma., 40 Plate Resistance, 480 ohms  | 12.6   |   | 12.6              | 3.5                             | 4.5        | 40000                       | 3800 {       | Grid-No. 1<br>Grid-No. 1 | Supply V<br>Res., 2.2 | olts, 0<br>megohms | 12CN5                          |
| 200 82α 125 3.4 15 150000 7000 — — — — — — — — — — — — — — —  | 150  | 150Ω  |                   | -                               | 9          | 8200                        | 4900         | 40                       |                       |                    | 12070                          |
| 12.6 Supply Volts, 0  12.6 1.4 3 40000 3100 Current of 10 μa., -4.5  12.6 - 12.6 0.5 1.3 300000 1500 Grid-No. 1 Supply Volts, 0 Grid-No. 1 Res., 2.2 megohms  12.6 - 12.6 1 6 4000 5000 - 3500 0.010 12DK7  12.6 Grid-No. 2 (Control Grid) Volts, -0.5 (across 2.2 megohm resistor)  Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Transcond. (Grid-No. 2 to Plate), 15000 μmhos Transcond. (Grid-No. 2 to Plate)  | 200  | 82 <b>0</b>   | 125               | 3.4                             | 15         | 150000                      | 7000         |                          |                       |                    | 2010                           |
| 12.6 — 12.6 1 6 4000 5000 — 3500 0.010 12DK7  12.6 — 12.6 1 6 4000 5000 — 3500 0.010 12DK7  12.6 Grid-No. 2 (Control Grid) Volts, -0.5 Ampl. Factor (Grid-No. 2 to Plate) 7.2 (across 2.2 megohm resistor) Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Transcond. (Grid-No. 2 to Plate), 15000 µmhos Plate Resistance, 480 ohms  | 12.6   | Supply  | 12.6              | 1.4                             | 3          | 40000                       | 3100         |                          |                       |                    | 12CX6                          |
| Grid-No. 2 (Control Grid) Volts, -0.5 Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Transcond. (Grid-No. 2 to Plate), 15000 µmhos  Ampl. Factor (Grid-No. 2 to Plate) 7.2 Grid-No. 1 Ma., 75 Plate Ma., 40 Plate Resistance, 480 ohms  | 12.6   |   | 12.6              | 0.5                             | 1.3        | 300000                      | 1500         |                          |                       |                    | 12DE8                          |
| 12.6 (across 2.2 megohm resistor) Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Transcond. (Grid-No. 2 to Plate), 15000 μmhos  Grid-No. 1 Ma., 75 Plate Ma., 40 Plate Resistance, 480 ohms   | 12.6   |   | 12.6              | 1                               | 6          | 4000                        | 5000         |                          | 3500                  | 0.010              | 12DK7                          |
| 200 68n 125 5.6 26 53000 10500 — — 12DQ7  | 12.6   | (across 2.2<br>Grid-No. 1   | megohm<br>(Space- | resistor)<br>Charge C           | irid) Volt | s, 12.6                     | Grid-No.     | . 1 Ma., 75              | Plate                 | •                  | 12DL8                          |
|   | 200  | <b>68</b> Ω   | 125               | 5.6                             | 26         | 53000                       | 10500        |                          |                       |                    | 12DQ7                          |

| RCA<br>Type             | Name   | Di me<br>and | ube<br>ensions<br>Basing<br>gram∆ | Filan<br>Unless s<br>types ho<br>Heate | rter or<br>nent (F)<br>pecified all<br>rve heaters.<br>r with con-<br>armup time. | Use  Values to right give operating conditions and characteristics for indicated typical use |
|-------------------------|--|--------------|-----------------------------------|--|---|--|
|                         |  | Dim.         | B. D.                             | Volts                                  | Amps.   | munuter typical eas  |
| <b>12DS7</b><br>12DS7-A | Twin Diode—<br>Power Tetrode⊙                            | ::           | nre                               | 10.0<br>to<br>15.9                     | 0.4<br>approx.<br>at 12.6 v   | Tetrode Unit as<br>Class A Amplifier<br>Diode Units  |
| 12DU7                   | Twin Diode—<br>Power Tetrode⊙                            | 63           | alX                               | 10.0<br>to<br>15.9                     | 0.25<br>approx.<br>at 12.6V   | Tetrode Unit as<br>Class A Amplifier   |
| 12DV8                   | Twin Diode—<br>Power Tetrode⊙                            | SE.          | 9HR                               | 10.0<br>to<br>15.9                     | 0.375<br>approx.<br>at 12.6 v   | Class A Amplifier  |
| 12DY8                   | Medium-Mu<br>Triode<br>Remote-Cutoff<br>Tetrode⊙         | 68           | 810                               | 10.0<br>to<br>15.9                     | 0.35<br>approx.<br>at 12.6V   | Triode Unit as<br>Class A Amplifier<br>Tetrode Unit as<br>Signal Seeker<br>Relay             |
| 12EA6                   | Remote-Cutoff<br>Pentode⊙                                | 5C           | 7BK                               | 10.0<br>to<br>15.9                     | 0.19<br>approx.<br>at 12.6 v  | Class A Amplifier  |
| 12EC8                   | Medium-Mu<br>Triode—<br>Semiremote-<br>Cutoff Pentode⊙   | <b>#8</b>    | 9FA                               | 10.0<br>to<br>15.9                     | 0.225<br>approx.<br>at 12.6V  | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                  |
| 12EG6                   | Pentagrid<br>Amplifier⊙                                  | BC           | 7CH                               | 10.0<br>to<br>15.9                     | 0.15<br>approx.<br>at 12.6 v  | Class A Amplifier  |
| 12EK6                   | Remote-Cutoff<br>Pentode⊙                                | SC.          | 78K                               | 10.0<br>to<br>15.9                     | 0.19<br>approx.<br>at 12.6 v  | Class A Amplifier  |
| 12EL6                   | Twin Diode—<br>High-Mu<br>Triode⊙                        | 5C           | 7F8                               | 10.0<br>to<br>15.9                     | 0.15<br>approx.<br>at 12.6 v  | Class A Amplifier  |
| 12 <b>EM</b> 6          | Diode—<br>Power Tetrode⊙                                 | 0E           | 9HV                               | 10.0<br>to<br>15.9                     | 0.5<br>approx.<br>at 12.6 v   | Class A Amplifier  |
| 12EN6                   | Beam Power<br>Tube                                       | 130          | 7AC                               | 12.6⊕                                  | 0.6   | Vertical Deflec-<br>tion Amplifier.  |
| 12F5-GT                 | High-Mu Triode   | 14A          | 5M‡                               | 12.6                                   | 0.15  | Amplifier  |
| 12F8                    | Twin Diode—<br>Remote-Cutoff<br>Pentode⊙                 | 68           | 9FH                               | 10.0<br>to<br>15.9                     | 0.15<br>approx.<br>at 12.6 v  | Pentode Unit as<br>Class A Amplifier   |
| 12FM6                   | Twin Diode—<br>Medium-Mu<br>Triode⊙                      | SC           | 7 <b>8</b> T                      | 10.0<br>to<br>15.9                     | 0.15<br>approx.<br>at 12.6 v  | Triode Unit as<br>Class A Amplifier  |
| 12FR8                   | Diode—<br>Medium-Mu<br>Triode—Remote-<br>Cutoff PentodeO | <b>8</b> D   | 9KU                               | 10.0<br>to<br>15.9                     | 0.32<br>approx.<br>at 12.6V   | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                  |
| 12FX8                   | Medium-Mu<br>Triode—<br>Pentagrid<br>Converter⊙          | 8D           | 9KV                               | 10.0<br>to<br>15.9                     | 0.3<br>approx.<br>at 12.6V  | Triode Unit as<br>Class A Amplifier<br>Pentagrid Unit<br>as Converter                        |
| 12GA6                   | Pentagrid<br>Converter⊙                                  | 5C           | 7CH                               | 10.0<br>to<br>15.9                     | 0.15<br>approx.<br>at 12.6V   | Converter  |
|                         | Madian Ma  |              |                                   |  |   |  |

Medium-Mu

Triode

13D

8Q:

12.6

0.15

Amplifier

12J5-GT

NOTES

For basing diagrams, see pages 549 to 553.

For explanation of footnotes, see page 548.

| 1  |   |                                    |                        |                             |                                     |                                       |                              | T   |                               |             |
|--|---|------------------------------------|------------------------|-----------------------------|-------------------------------------|---------------------------------------|------------------------------|---|-------------------------------|-------------|
| Plate<br>Sup-<br>ply<br>Yelts  | Grid Bias Volts (v) or Cathode Resistor Ohms (Ω)  | Screen<br>Sup-<br>ply<br>Volts     | Cur-<br>rent<br>Ma     | Plate<br>Cur-<br>renf<br>Ma | AC Plate<br>Resis-<br>tance<br>Ohms | Trans-<br>conduc<br>fance<br>Micrombo | cation<br>Factor             | Load<br>for Stated<br>Power<br>Output<br>Ohms | Power<br>Out-<br>put<br>Watts | RGA<br>Type |
| 12.6   | 12.6v   | (across 2.2<br>megohm<br>resistor) | 75<br>(Grid-<br>No. 1) | 35                          | 500                                 | (Grid-<br>No. 2<br>to Plate)          | (Grid-<br>No. 2<br>to Plate) |   |                               | 12DS7-A     |
|  |   | Di                                 | ode Flate              | Ma., wi                     | th 10 Volts                         | Applied,                              | 3 Ma.                        |   |                               |             |
| 12.6   |   | 12.6                               | 1.5                    | 12                          | 6000                                | 6200                                  |                              | 2700  | 0.025                         | 12DU7       |
| Grid-No. 2 (Control Grid) Resistor, 4.7 megohms Grid-No. 1 (Space-Charge Grid) Volts, 12.6 Transcond. (Grid-No. 2 to Plate), 8500 µmhos  Ampl. Factor (Grid-No. 2 to Plate) 7.6 Grid-No. 1 Ma., 53 Plate Ma., 9 Plate Resistance, 900 ohms |   |                                    |                        |                             |                                     |                                       |                              |   | 12DV8                         |             |
| 12.6   |   |                                    |                        | 1.2                         | 10000                               | 2000                                  | 20                           |   |                               |             |
| 10   |   | 10                                 |                        | 5 min.                      | Grid No. 1 re                       | esistor 10                            | megohms. 1                   | Plate Load                                    | 1 700 ohms                    | 12DY8       |
| 15   | 6v  | 15                                 |                        | 3 max.                      |                                     |                                       | <del>,</del> -               | 700 ohms                                      |                               |             |
| 12.6   |   | 12.6                               | 1.4                    | 3.2                         | 32000                               | 3800                                  | Grid-No. 1<br>Grid-No. 1     |   |                               | 12EA6       |
| 12.6   | 4700Ω<br>(Grid Res.)  |                                    |                        | 2,4                         | 6000                                | 4700                                  | 25                           |   |                               | 10500       |
| 12.6   |   | 12.6                               | 0.28                   | 0.66                        | 750000                              | 2000                                  | Grid No.                     | 1 Res., 33                                    | 000 ohms.                     | 12EC8       |
| 12.6   | -0.6v†  | 12.6                               | 2.8                    | .55                         | 150000                              | 800‡                                  |                              | 3 & Plate<br>is res.                          | 12EG6                         |             |
| 12.6   |   | 12.6                               | 1.7                    | 4                           | 50000                               | 4200                                  | Grid-No.<br>Grid-No.<br>2.   | ypassed),                                     | 12EK6                         |             |
| 12.6   | 0ν  |                                    |                        | 0.75                        | 45000                               | 1200                                  | 55                           |   |                               | 12EL6       |
| 12.6   |   | 12.6                               | 1                      | 6                           | 4000                                | 5000                                  | Grid-No. 1                   | Res., 2.2                                     | megohms                       | 12EM6       |
| Max.   | Peak PosI<br>Peak NegI<br>Peak Catho  | Pulse Gri                          | id Volts.              | 250                         | <del></del>                         |                                       | ax. Plate Di<br>ax. DC Plat  |   |                               | 12EN6       |
|  |   |                                    |                        | aracteris                   | tics, refer to                      | Type 6F                               | 5-GT.                        |   |                               | 12F5-GT     |
| 12.6   | 0v  | 12.6                               | 0.38                   | 1                           | 330000                              | 1000                                  | Grid-No. 1<br>cond. of 1     |   |                               | 12F8        |
| 12.6   | 0v  |                                    |                        | 1                           | 7700                                | 1300                                  | 10                           |   |                               | 12FM6       |
| 12.6   |   |                                    |                        | 1                           |                                     | 1200                                  | 10                           | Grid I<br>2.2 me                              | Res.,<br>gohms                | 12FR8       |
| 12.6   |   | 12.6                               | 0.7                    | 1.9                         | 0.4                                 | 2700                                  | Grid No. 1                   | Res., 2.2                                     | megohms                       | 122 200     |
| 12.6   |   |                                    |                        | 1.3                         | 7150                                | 1400                                  | 10                           | Grid 2.2 meg                                  | ohms                          | 12FX8       |
|  | 2.6 — 12.6 1.25 0.29 500000 Grid No. 3 Res., 2.2 megohms Conversion Transcond., 300 μmhos |                                    |                        |                             |                                     |                                       |                              | 484   |                               |             |
| 12.6   | 12.6 1.6v 12.6 0.8 0.3 1§ Grid No. 1 Res., 33000 ohms. Conversion. Transcond., 140 μmhos  |                                    |                        |                             |                                     |                                       |                              |   |                               |             |
|  | 1.6v  | 12.6                               | 0.8                    | 0.3                         | 18                                  |                                       |                              |   |                               | 12GA6       |

For explanation of foot-

| RCA<br>Type              | Name                               | Tube Dimensions and Basing Diagram |                         | Filan<br>Unless s<br>types ho<br>⊕ Heater | nent (F) specified all ove heaters, r with con- armup time. | Use Yalves to right give operating conditions and characteristics for indicated typical use |  |
|--------------------------|------------------------------------|------------------------------------|-------------------------|---|---|---|--|
|                          |                                    | Oim.                               | B, D.                   | Volts                                     | Amps.   |   |  |
| 12J7-GT                  | Sharp-Cutoff<br>Pentode            | 144                                | 7R <sub>a</sub> c       | 12.6                                      | 0.15  | Amplifier   |  |
| 12J8                     | Twin Diode—<br>Power Tetrode⊙      | **                                 | 9GC                     | 10.0<br>to<br>15.9                        | 0.325<br>approx.<br>at 12.6 v                               | Tetrode Unit a<br>Class A Amplific  |  |
| 12K5                     | Power<br>Tetrode⊙                  | \$0                                | 7EK                     | 10.0<br>to<br>15.9                        | 0.4<br>approx.<br>at 12.6 v                                 | Class A Amplifi   |  |
| 12K7-GT                  | Remote-Cutoff<br>Pentode           | 144                                | 7R)                     | 12.6                                      | 0.15  | Amplifier   |  |
| 12K8                     | Triode-Hexode<br>Converter         | ,                                  | 8K                      | 12.6                                      | 0.15  | Oscillator<br>Mixer   |  |
| 12L6-GT                  | Beam Power<br>Tube                 | 130                                | 7AC‡                    | 12.6⊕                                     | 0.6   | Class A Amplific  |  |
| 12Q7-GT                  | Twin Diode—<br>High-Mu Triode      | 144                                | 7V×                     | 12.6                                      | 0.15  | Triode Unit as<br>Amplifier   |  |
| 12S8-GT                  | Triple Diode—<br>High-Mu Triode    | 148                                | 8CB                     | 12.6                                      | 0.15  | Triode Unit as<br>Class A Amplific  |  |
| 12SA7-GT                 | Pentagrid<br>Converter▲            | 13D                                | 8R<br>8AD               | 12.6                                      | 0.15  | Converter   |  |
| 12SC7                    | High-Mu<br>Twin Triode             | 2A                                 | 88                      | 12.6                                      | 0.15  | Each Unit as<br>Class A Amplifi   |  |
| <b>12SF5</b><br>12SF5-GT | High-Mu Triode                     | 2A<br>13D                          | 6AB                     | 12.6                                      | 0.15  | Class A Amplific  |  |
| 12SF7                    | Diode—<br>Remote-Cutoff<br>Pentode | 2A                                 | 7AZ                     | 12.6                                      | 0.15  | Pentode Unit a<br>Amplifier   |  |
| 12SG7                    | Semiremote-<br>Cutoff Pentode      | 2A                                 | 8BK                     | 12.6                                      | 0.15  | Class A Amplific  |  |
| 12SH7                    | Remote-Cutoff<br>Pentode           | 3                                  | 8BK                     | 12.6                                      | 0.15  | Class A Amplifi   |  |
| 12SJ7-GT                 | Sharp-Cutoff<br>Pentode            | 1 <b>3</b> D                       | 8N<br>8N <sub>3</sub> c | 12.6                                      | 0.15  | Class A Amplifi   |  |
| 12\$K7<br>12\$K7-GT      | Remote-Cutoff<br>Pentode           | 2A<br>13D                          | 8N<br>8N×               | 12.6                                      | 0.15  | Class A Amplific  |  |
| 12SN7-GT                 | Medium-Mu<br>Twin Triode           | 130                                | 8BD                     | 12.6                                      | 0.3   | Each Unit as<br>Class A Amplific  |  |
| 12\$Q7-GT                | Twin Diode—<br>High-Mu Triode      | 130                                | 80%<br>80%              | 12.6                                      | 0.15  | Triode Unit as<br>Class A Amplific  |  |
| <b>12SR7</b><br>12SR7-GT | Twin Diode—<br>Medium-Mu<br>Triode | 2A<br>13D                          | 86³₹<br>86              | 12.6                                      | 0.15  | Triode Unit as<br>Class A Amplific  |  |
| 12U7                     | Medium-Mu<br>Twin Triode           | 68                                 | 7CK                     | 10.0<br>to<br>15.9                        | 0.15<br>approx.<br>at 12.6 v                                | Each Unit as<br>Class A Amplifi   |  |
| 12 <b>Z</b> 3            | Half-Wave<br>Rectifier             | 22                                 | 4G                      | 12.6                                      | 0.3   | With Capacitive<br>Input Filter   |  |
| 14 <b>A</b> 4            | Medium-Mu<br>Triode                | 12B                                | BAC                     | 12.6                                      | 0.15  | Class A Amplifi   |  |
| 14 <b>A</b> 5            | Beam Power<br>Tube                 | 128                                | 6AA                     | 12.6                                      | 0.15  | Class A Amplifi   |  |
| 14A7                     | Remote-Cutoff<br>Pentode           | 128                                | 8V                      | 12.6                                      | 0.15  | Class A Amplifi   |  |
| 14AF7                    | Medium-Mu<br>Twin-Triode           | 128                                | 8AC                     | 12.6                                      | 0.15  | Each Unit as<br>Class A Amplifi   |  |
|                          | Twin Diada                         |                                    |                         |   |   | Trioda Unit as  |  |

Twin Diode

High-Mu Triode

14B6

Triode Unit as Class A Amplifier

12.6

0.15

| Plate<br>Sup-<br>ply<br>Valts                    | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor<br>Olms (Ω) | Screen<br>Sup-<br>ply<br>Volts | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent<br>M1 | AC Plate<br>Resis-<br>tance<br>Ohms    | Trans-<br>conduc-<br>tance<br>Micromhos | Amplifi-<br>cation<br>Factor              | Load<br>for Stated<br>Power<br>Output<br>Ohms | Power Out- put Watts | RCA<br>Type       |
|--|---|--------------------------------|------------------------------|-----------------------------|--|---|---|---|----------------------|-------------------|
|  |   | Fo                             | r other ch                   | aracteri                    | stics, refer to                        | Type 6J7                                | -GT.                                      |   |                      | 12J7-GT           |
| 12.6   | - 0v  | 12.6                           | 1.5                          | 12                          | 6000                                   | 5500                                    |   | 2700  | 0.02                 | 12J8              |
| Grid-  | late Volts, I<br>No. 1 (Space<br>late Ma., 40                   | -Charge                        |                              | ts, 12.6                    | ol Grid) Volt<br>Amplifica<br>Transcor | ation Fact                              | Plate Resi<br>or, Grid-No<br>No. 2 to Pla | o. 2 to P1                                    | ate, 7.2             | 12K5              |
| For other characteristics, refer to Type 6K7-GT. |   |                                |                              |                             |  |   |   |   |                      |                   |
|  |   |                                |                              |                             | stics, refer to                        |   | 8.  |   |                      | 12K8              |
| 110<br>200                                       | - 7.5v<br>180Ω  | 110<br>125                     | 4.0<br>2.2                   | 49<br>46                    | 13000<br>28000                         | 8000<br>8000                            |   | 2000<br>4000                                  | 2.1<br>3.8           | 12L6-GT           |
|  |   | Fo                             | r other ch                   | aracteri                    | stics, refer to                        | Туре 6Q                                 | 7-GT.                                     |   |                      | 12Q7-GT           |
| 250  | - 2v  |                                |                              | 0.9                         | 91000                                  | 1100                                    | 100                                       |   |                      | 12S8-GT           |
|  |   | For                            | other ch                     | aracteri                    | stics, refer to                        | Type 6SA                                | 17.                                       |   |                      | 125A7-GT          |
| _  |   | For                            | other ch                     | aracteris                   | stics, refer to                        | Type 6SC                                | 27.                                       |   |                      | 12SC7             |
|  | · · · · · · · · · · · · · · · · · · ·                           | For                            | other ch                     | aracteris                   | tics, refer to                         | Type 6SF                                | r5.                                       |   |                      | 12SF5<br>12SF5-GT |
|  |   | For                            | other ch                     | aracteris                   | tics, refer to                         | Type 6SF                                | 77.                                       |   |                      | 12SF7             |
|  | ······  | For                            | other ch                     | aracteris                   | tics, refer to                         | Type 6SC                                | 37.                                       |   |                      | 12SG7             |
|  |   | For                            | other ch                     | aracteris                   | tics, refer to                         | Type 6SF                                | 17.                                       |   |                      | 12SH7             |
|  |   | For                            | other ch                     | aracteris                   | tics, refer to                         | Type 6SJ                                | 7.  |   |                      | 12SJ7-GT          |
|  |   | For                            | other cha                    | aracteris                   | tics, refer to                         | Type 6SE                                | <b></b>                                   |   | -                    | 12SK7<br>12SK7-GT |
|  |   | For                            | other cha                    | racteris                    | tics, refer to                         | Type 6J5.                               |   |   |                      | 12SN7-GT          |
|  |   | For                            | other cha                    | racteris                    | tics, refer to                         | Type 6SQ                                | 7.  |   |                      | 12SQ7-GT          |
|  |   | For                            | other cha                    | aracteris                   | tics, refer to                         | Type 6SR                                | 27.                                       |   |                      | 12SR7<br>12SR7-GT |
| 12.6   | 0v  |                                | ]                            | 1                           | 12500                                  | 1600                                    | 20  |   |                      | 12U7              |
|  |   |                                | Ma                           | x. DC C                     | utput Ma.,                             | 55                                      |   |   |                      | 12 <b>Z</b> 3     |
| For other characteristics, refer to Type 6J5.    |   |                                |                              |                             |  |   |   |   |                      |                   |
| 250  | -12.5v  | 250                            | 5.5                          | 32                          | 70000                                  | 3000                                    |   | 7500  | 2.8                  | 14A5              |
| 100<br>250                                       | - 1v<br>- 3v  | 100<br>100                     | 4.0                          | 13.0<br>9.2                 | 120000<br>800000                       | 2350<br>2000                            |   |   |                      | 14A7              |
|  |   | For                            | other ch                     | aracteris                   | stics, refer to                        | Type 7Al                                | F7.                                       | 1   |                      | 14AF7             |
|  |   | For                            | other ch                     | aracteris                   | tics, refer to                         | Type 6SQ                                | 27.                                       |   |                      | 14B6              |

|   | RCA<br>Type    | Name                                    | Dime<br>and I | be<br>nsions<br>Basing<br>pram△ | Filam         | with con-  | Use Yalues to right give eperating conditions and characteristics for indicated typical use |
|---|----------------|---|---------------|---------------------------------|---------------|------------|---|
|   |                |   | Dim.          | B. D.                           | Valts         | Amps.      |   |
|   | 14B8           | Pentagrid<br>Converter •                | 129           | 8X                              | 12.6          | 0.15       | Converter   |
|   | 14C5           | Beam Power<br>Tube                      | 120           | BAA                             | 12.6          | 0.225      | Class A Amplifier   |
|   | 14C7           | Sharp-Cutoff<br>Pentode                 | 128           | 87                              | 12.6          | 0.15       | Class A Amplifier   |
|   | 14 <b>E</b> 6  | Twin Diode—<br>Medium-Mu<br>Triode      | 128           | 8W                              | 12.6          | 0.15       | Triode Unit as<br>Class A Amplifier   |
| 10 MA   | 14E7           | Twin Diode—<br>Remote-Cutoff<br>Pentode | 128           | 8AE                             | 12.6          | 0.15       | Pentode Unit as<br>Class A Amplifier  |
|   | 14F7           | High-Mu<br>Twin Triode                  | 128           | 8AC                             | 12.6          | 0.15       | Each Unit as<br>Class A Amplifier   |
|   | 14F8           | Medium-Mu<br>Twin Triode                | 12A           | 8BW                             | 12.6          | 0.15       | Each Unit as<br>Class A Amplifier   |
|   | 14H7           | Semiremote-<br>Cutoff Pentode           | 128           | 87                              | 12.6          | 0.15       | Class A Amplifier   |
|   | 14J7           | Triode-Heptode<br>Converter             | 128           | 8BL                             | 12.6          | 0.15       | Converter   |
|   | 14N7           | Medium-Mu<br>Twin Triode                | 12C           | 8AC                             | 12.6          | 0.3        | Each Unit as<br>Class A Amplifier   |
| NOTES   | 14Q7           | Pentagrid<br>Converter                  | 128           | 8AL                             | 12.6          | 0.15       | Converter   |
| For basing diagrams,  | 14R7           | Twin Diode—<br>Remote-Cutoff<br>Pentode | 128           | 8AE                             | 12.6          | 0.15       | Pentode Unit as<br>Class A Amplifier  |
| see pages 549 to 553,   | 15             | Sharp-Cutoff<br>Pentode                 | 248           | 5F                              | 2.0           | 0.22       | Class A Amplifier   |
| For explanation of foot-<br>notes, see page 548.  Types shows in light- | 17AX4-GT       | Half-Wave<br>Rectifier                  | 130           | 4CQ                             | 16.8⊕         | 0.45       | Television<br>Damper Service  |
| face are discontinued.  | 17DM4          | Half-Wave<br>Rectifier                  | 130           | 4CQ                             | 16.8⊕         | 0.45       | Television<br>Damper Service  |
|   | 17DQ6-A        | Beam Power<br>Tube                      | 20            | 6AM                             | 16.8⊕         | 0.45       | Horizontal Deflec-<br>tion Amplifier  |
|   | 17H3           | Half-Wave<br>Rectifier                  | 0E            | 9FK                             | 17.5⊕         | 0.3        | Television<br>Damper Service  |
|   | 18A5           | Beam Power<br>Tube                      | 13F           | 8CK                             | 18.5⊕         | 0.3        | Horizontal Deflec-<br>tion Amplifier  |
|   | 18FW6          | Remote-<br>Cutoff Pentode               | BC            | 7CC<br>7CC                      | 18.0<br>18.0⊕ | 0.1<br>0.1 | Class A Amplifier   |
|   | 18FX6          | Pentagrid<br>Converter▲                 | #C            | 7CH<br>7CH                      | 18.0<br>18.0⊕ | 0.1        | Converter   |
|   | 18FY6          | Twin Diode—                             | 5C            | 7BT                             | 18.0          | 0.1        | Triode Unit as  |
|   | 19             | High-Mu Triode<br>High-Mu Twin          | 22 or<br>13H  | 78T<br>6C                       | 18.0⊕<br>2.0F | 0.1        | Class A Amplifier Amplifier   |
|   | 19AU4-         | Power Triode<br>Half-Wave               | 13H<br>13Q    | 4CG                             |               |            | Television  |
|   | GTA<br>10BG6 G | Rectifier                               |               | 466                             | 18.9⊕         | 0.6        | Damper Service  |
|   | 19BG6-GA       | Beam Power<br>Tube                      | 278           | 58T                             | 18.9          | 0.3        | Horizontal Deflec-<br>tion Amplifier  |
|   | 19J6           | Medium-Mu<br>Twin Triode                | 5C            | 7BF                             | 18.9          | 0.15       | Each Unit as<br>Class A Amplifier   |

Triple Diode— High-Mu Triode

19T8

Triode Unit as Class A Amplifier

18.9

0.15

| Plate<br>Sup-<br>ply<br>Volts  | Grid Bias Volts (v) or Cathode Resistor Ohms (Ω) | Screen<br>Sup-<br>ply<br>Volts | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent<br>M2 | AC Plate<br>Resis-<br>tance | Trans-<br>conduc-<br>tance<br>Micromhos | Amplifi-<br>cation<br>Factor | Load<br>for Stated<br>Power<br>Output<br>Ohms | Power<br>Out-<br>put<br>Walts | RCA<br>Type                |  |
|--|--|--------------------------------|------------------------------|-----------------------------|-----------------------------|---|------------------------------|---|-------------------------------|----------------------------|--|
|  | <del></del>                                      | F                              | or other                     | character                   | ristics, refer              | to Type 6.                              | A8.                          |   |                               | 14B8                       |  |
| 315  | -13v   | 225                            | 2.2                          | 34.0                        | 80000                       | 3750                                    | l                            | 8500  | 5.5                           | 14C5                       |  |
| For other characteristics, refer to Type 6SJ7.   |  |                                |                              |                             |                             |   |                              |   |                               |                            |  |
|  | For other characteristics, refer to Type 6BF6.   |                                |                              |                             |                             |   |                              |   |                               |                            |  |
| 250  | 330Ω   | 100                            | 1.6                          | 7.5                         | 700000                      | 1300                                    |                              |   |                               | 14E7                       |  |
|  | <b>.</b>   | :                              | For other                    | characte                    | ristics, refer              | to Type (                               | SL7-GT.                      |   |                               | 14F7                       |  |
| 250  | 500α   |                                |                              | 6.0                         |                             | 3300                                    | 48                           |   |                               | 14F8                       |  |
|  | <u> </u>   |                                | For other                    | characte                    | ristics, refer              | to Type 7                               | 7H7.                         | <b></b> -                                     |                               | 14H7                       |  |
|  |  |                                | For other                    | characte                    | eristics, refer             | to Type                                 | 7 <b>J</b> 7.                |   |                               | 14J7                       |  |
|  |  |                                | For other                    | characte                    | ristics, refer              | to Type 6                               | SN7-GT.                      |   |                               | 14N7                       |  |
|  |  |                                | For other                    | characte                    | ristics, refer              | to Type 6                               | 5SA7.                        |   |                               | 14Q7                       |  |
|  |  |                                | For other                    | characte                    | ristics, refer              | to Type                                 | 7R7.                         |   |                               | 14R7                       |  |
| 135  | - 1.5v   | 67.5                           | 0.3                          | 1.85                        | 800000                      | 750                                     |                              |   |                               | 15                         |  |
| Max  | . Peak Inver<br>. Peak Plate<br>. DC Plate l     | Ma., 75                        |                              | 00                          |                             |   | er-Cathode                   | Ι.  | -4000 • •<br>+300<br>00 volts | 17AX4-GT                   |  |
|  |  |                                | For oth                      | er rating                   | s, refer to T               |   |                              |   |                               | 17DM4                      |  |
| Max<br>Max   | DC Plate   | Volts, 700<br>de Ma., 1        | 40                           |                             | Max. Peak<br>Max. Plate     |   |                              |   | 00 (Abs.)                     | 17DQ6-A                    |  |
| Max  | . Peak Inver                                     | se Plate                       | Volts, 20                    |                             |                             | Ma                                      | x. Average                   | Plate M                                       |                               | 17H3                       |  |
| Max  | . DC Plate \ . DC Cathor                         | Volts, 350                     | )                            |                             |                             | Max. Peak                               | PosPulse<br>Dissipatio       | Plate Vo                                      | lts, 3000                     | 18A5                       |  |
| 100  | 680  | 100                            | 4.4                          | 11                          | 250000                      | 4400                                    |                              |   |                               | 18FW6                      |  |
| 100  | - 1.5v   | 100                            | 6.2                          | 2.3                         | 400000                      |   | o. 1 Resisto<br>sion Transc  |   |                               | 18FX6                      |  |
| 100  | - 1v   |                                |                              | 0.6                         | 77000                       | 1300                                    | 100                          |   |                               | 18FY6                      |  |
|  |  | F                              | or other o                   | haracteri                   | stics, refer t              | o Type 1J                               | 6-GT.                        |   |                               | 19                         |  |
| For other ratings, refer to Type 6AU4-GTA.   |  |                                |                              |                             |                             |   |                              |   |                               |                            |  |
| Max. DC Plate Volts, 700 Max. Peak Positive-Pulse Plate Volts, 6600 (Abs.) Max. DC Plate Current, 110 ma. Max. Plate Dissipation, 20 watts |  |                                |                              |                             |                             |   |                              |   |                               | 19BG6-G<br><b>19BG6-GA</b> |  |
| 100  |  | r both u                       |                              | 8.5                         | 7100                        | 5300                                    | 38                           |   |                               | 19J6                       |  |
|  |  |                                |                              | character                   | istics, refer               | to Type 6                               | T8-A.                        |   |                               | 19T8                       |  |

NOTES

|            | RCA<br>Type                                   | Name  | Dime<br>and<br>Diag | ube<br>ensions<br>Basing<br>gram Δ | Filam<br>Unless sp<br>types har<br>types har<br>trolled wa | ter or<br>ent (F)<br>secified all<br>we heaters.<br>with con-<br>imoup time. | Use Yalues to right give operating conditions and characteristics for indicated typical use |
|------------|---|---|---------------------|------------------------------------|--|--|---|
|            |   | Power Triode                                | Dine.               | B. D.                              | Velts  | Amps.  |   |
|            | 20<br>20EQ7                                   | Diode                                       | 6E                  | 9LQ                                | 3.3F<br>20.0   | 0.132  | Pentode Unit as<br>Class A Amplifier  |
|            | 21EX6   | Beam Power<br>Tube                          | 21B                 | 58T                                | 21.5⊕  | 0.6  | Horizontal Deflec-<br>tion Amplifier  |
|            | 22  | Sharp-Cutoff<br>Tetrode                     | 29K                 | 4K                                 | 3.3F   | 0.132  | Screen-Grid<br>RF Amplifier   |
|            | 24-A  | Sharp-Cutoff<br>Tetrode                     | 29K                 | 5E                                 | 2.5  | 1.75   | Screen-Grid<br>RF Amplifier   |
|            | 25A6<br>25A6-GT                               | Power Pentode                               | 28<br>130           | 78<br>78‡                          | 25.0   | 0.3  | Class A Amplifier   |
|            | 25A7-GT                                       | Rectifier—<br>Power Pentode                 | 130                 | tF                                 | 25.0   | 0.3  | Pentode Unit as<br>Class A Amplifier<br>Half-Wave<br>Rectifier                              |
|            | 25AC5-GT                                      | High-Mu<br>Power Triode                     | 130                 | 8Q‡                                | 25.0   | 0.3  | Amplifier   |
|            | 25B5  | Direct-Coupled<br>Power Amplifier           |                     | 8D                                 | 25.0   | 0.3  | Amplifier   |
|            | 25B6-G  | Power Pentode                               | 25                  | 78;                                | 25.0   | 0.3  | Class A Amplifier   |
|            | 25B8-GT                                       | High-Mu Triode—<br>Remote-Cutoff<br>Pentode | 130                 | ध                                  | 25.0   | 0.15   | Triode Unit as<br>Class A Amplifier<br>Pentode Unit as<br>Class A Amplifier                 |
| 01-<br>45. | 25BQ6-GT                                      | Beam Power<br>Tube                          | 140                 | SAM                                | 25.0   | 0.3  | Horizontal Deflec-<br>tion Amplifier  |
| he.        | 25C6-G  | Beam Power<br>Tube                          | 25                  | 7AC‡                               | 25.0   | 0.3  | Class A Amplifier   |
|            | 25CD6-GA                                      | Beam Power<br>Tube                          | 218                 | 58T<br>58T                         | 25⊕<br>25⊕   | 0.6  | Horizontal Deflec-<br>tion Amplifier  |
|            | 25L6  | Beam<br>Power Tube                          | 29                  | 7AC                                | 25.0   | 0.3  | Amplifier   |
|            | 25L6-GT                                       | Beam<br>Power Tube                          | 13D                 | 7AC‡                               | 25.0   | 0.3  | Amplifier   |
|            | 25N6-G  | Direct-Coupled<br>Power Amplifier           |                     | TW                                 | 25.0   | 0.3  | Class A Amplifier   |
|            | 25W4-GT                                       | Half-Wave<br>Rectifier                      | 130                 | 40G                                | 25.0   | 0.3  | Television<br>Damper Service  |
|            | 25¥5  | Rectifier-<br>Doubler                       | 22 SF<br>13H        | 6E                                 | 25.0   | 0.3  | Half-Wave<br>Rectifier  |
| 1          | 257.5   | Rectifier-<br>Doubler                       | 22 or<br>13H        | 38                                 | 25.0   | 0.3  | Rectifier-<br>Doubler   |
|            | 25 <b>Z</b> 6<br><b>25<b>Z</b>6-<b>G</b>T</b> | Rectifier-<br>Doubler                       | 28<br>130           | 7Q                                 | 25.0   | 0.3  | Voltage<br>Doubler<br>Half-Wave   |
| L          |   |   |                     | 7Q:                                | 25.0   | 0.3  | Rectifier   |
| 1          | 26  | Medium-Mu<br>Triode                         | 26                  | 40                                 | 1.5F   | 1.05   | Class A Amplifier   |
| L          | 27  | Low-Mu Triode                               | ZZ of<br>13H        | 5A                                 | 2.5  | 1.75   | Class A Amplifier   |
| )          | 30  | Medium-Mu<br>Triode                         | 22 or<br>13H        | 4D ·                               | 2.0F   | 0.06   | Amplifier   |

| Plate<br>Sup-<br>ply<br>Volts   | Grid Bias Volts (v) or Cathode Resistor Ohms (Ω)   | Screen<br>Sup-<br>ply<br>Volts  | Screen<br>Cur-<br>rent<br>Ma  | Plate<br>Cur-<br>rent<br>Ma   | AC Plate<br>Resis-<br>tance<br>Ohms   | Trans-<br>conduc-<br>tance<br>Micromhos   | Amplifi-<br>cation<br>Factor  | Load<br>for Stated<br>Power<br>Output<br>Ohms  | Power Out- put Watts     | RGA<br>Type   |  |  |  |  |
|---|--|---|---|---|---|---|---|--|--------------------------|---|--|--|--|--|
| 135   | -22.5v   |   |   | 6.5   | 6300  | 525 3.3 6500 0.110  |   | 20   |                          |   |  |  |  |  |
|   |  | For   | other ch  | aracteris   | tics, refer to  | Туре 6ЕС  | 27.   |  |                          | 20EQ7   |  |  |  |  |
| For other ratings, refer to Type 6EX6.                                    |  |   |   |   |   |   |   |  |                          |   |  |  |  |  |
| 135 - 1.5v 67.5 1.3 3.7 325000 500  |  |   |   |   |   |   |   |  |                          |   |  |  |  |  |
| 250   | - 3v   | 90  | 1.7<br>(Max.)   | 4.0   | 600000  | 1050  |   |  |                          | 24-A  |  |  |  |  |
| 95  | -15v   | 95  | 4   | 20  | 45000   | 2000  | _   | 4500   | 0.9                      | 25A6<br>25A6-GT   |  |  |  |  |
| 100   | -15v   | 100   | 4.0   | 20.5  | 50000   | 1800  |   | 4500   | 0.77                     |   |  |  |  |  |
| Max.  | AC Plate V   | olts (RM  | IS), 117  | Max.  | DC Output   | Ma., 75   | Max. Pea  | k Plate I  | Ma., 450                 | 25A7-GT   |  |  |  |  |
| 110   | +15v   | (Grid Ma  | ., 7)   | 15  | 15200   | 3800  | 58  | . —  | ī —                      | 25AC5-GT  |  |  |  |  |
|   |  | Fo  | r other cl  | naracteris  | stics, refer to   | Type 251  | <br>N6-G.   |  |                          | 25B5  |  |  |  |  |
| 200   | - 23v  | 135   | 1.8   | 62.0  | 18000   | 5000  |   | 2500   | 7.1                      | 25B6-G  |  |  |  |  |
| 100   | - 1v   |   | ]   | 0.6   | 75000   | 1500  | 112   |  |                          | arna con  |  |  |  |  |
| 100   | - 3v   | 100   | 2.0   | 7.5   | 185000  | 2000  |   |  |                          | 25B8-GT   |  |  |  |  |
|   | DC Plate V<br>DC Cathod  |   |   |   | Max. Peak F<br>e Dissipation  |   |   | olts, 600  | 0 (Abs.)                 | 25BQ6-GT  |  |  |  |  |
|   |  | Fo  | or other cl   | naracteri   | stics, refer to   | Type 6Y   | 6-G.  |  |                          | 25C6-G  |  |  |  |  |
|   |  |   |   |   | For other characteristics, refer to Type 6Y6-G.  Max. DC Plate Volts, 700  Max. Peak Positive-Pulse Plate Volts, 7000  Max. DC Plate May 200  Max. DC Plate May 200 |   |   |  |                          |   |  |  |  |  |
| Man. Flate Dissipation, 20 Watts  |  |   |   |   |   |   |   |  | 25CD6-GA                 |   |  |  |  |  |
| 110   | - 7.5v   | 110   | 4 2   | 49  | 13000   | 9000  | - I   | 2000   | 2.1                      | 25CD6-GA<br>25L6  |  |  |  |  |
|   | - 7.5v<br>- 8v   | 110   | 2   | 49<br>50  |   | 9000<br>9500  |   | 2000<br>3000   | 2.1<br>4.3               |   |  |  |  |  |
| 110<br>200  | - 8v   | Fo  | 2<br>r other ch   | 49<br>50<br>aracteris   | 13000<br>30000<br>stics, refer to   | 9000<br>9500<br>Type 50L  |   | 3000   |                          | 25L6  |  |  |  |  |
| Outp<br>Trioc<br>Max.<br>Max.   | - 8v  out Triode: F de: Plate Vol. Peak Invers Peak Plate  | Fo<br>Plate Volts, 100; G<br>e Plate V<br>Ma., 750  | 2<br>r other ch   | 49<br>50<br>haracteris<br>late Ma.<br>0; A-F Si<br>0 (Abs.)                               | 13000<br>30000<br>stics, refer to<br>, 46; Load, 4<br>gnal Volts (P<br>Max. Peak  | 9000<br>9500<br>Type 50L<br>000 ohms<br>eak), 29.7<br>Heater-Ca   | .6-GT. ; Plate Ma   | 3000<br>a., 5.8.<br>s: {-500<br>+200   | 3.8<br>0 (Abs.)          | 25L6<br>25L6-GT   |  |  |  |  |
| Outp<br>Triox<br>Max.<br>Max.<br>Max.                                     | - 8v   | Fo<br>Plate Volts, 100; G<br>e Plate V<br>Ma., 750<br>Ia., 125  | z rother ch<br>ts, 180; P<br>rid Volts,<br>rolts, 3850  | 49<br>50<br>haracteris<br>late Ma.<br>0; A-F Si<br>0 (Abs.)                               | 13000<br>30000<br>stics, refer to<br>, 46; Load, 4  | 9000<br>9500<br>Type 50L<br>000 ohms<br>eak), 29.7<br>Heater-Ca   | .6-GT. ; Plate Ma   | 3000<br>a., 5.8.<br>s: {-500<br>+200   | 3.8<br>0 (Abs.)          | 25L6<br>25L6-GT<br>25N6-G<br>25W4-GT                                    |  |  |  |  |
| Outp<br>Triox<br>Max.<br>Max.<br>Max.                                     | - 8v out Triode: File: Plate Vol. Peak Invers Peak Plate DC Plate M  | Fo<br>Plate Volits, 100; G<br>e Plate V<br>Ma., 750<br>Ia., 125<br>Ma. per                                | z rother chits, 180; Prid Volts, 3850   | 49<br>50<br>haracteris<br>late Ma.<br>0; A-F Si<br>0 (Abs.)                               | 13000<br>30000<br>stics, refer to<br>, 46; Load, 4<br>gnal Volts (P<br>Max. Peak I  | 9000<br>9500<br>Type 50L<br>0000 ohms.<br>eak), 29.7<br>Heater-Ca   | .6-GT. ; Plate Ma   | 3000<br>a., 5.8.<br>s: {-500<br>+200   | 3.8<br>0 (Abs.)          | 25L6<br>25L6-GT<br>25N6-G   |  |  |  |  |
| Outp<br>Trico<br>Max.<br>Max.<br>Max.                                     | out Triode: I<br>de: Plate Vol<br>Peak Invers<br>Peak Plate<br>DC Plate M<br>DC Output   | Fo<br>Plate Volts, 100; G<br>e Plate V<br>Ma., 750<br>Ia., 125<br>Ma. per<br>Fo<br>Plate (R               | r other ches, 180; Prid Volts, 3850 Plate, 75   | 49<br>50<br>haracteris<br>late Ma.<br>0; A-F Si<br>0 (Abs.)                               | 13000<br>30000 stics, refer to<br>, 46; Load, 4<br>gnal Volts (P<br>Max. Peak I<br>DC Comp  | 9000<br>9500<br>Type 50L<br>0000 ohms.<br>eak), 29.7<br>Heater-Ca<br>onent mus                                    | .6-GT. ; Plate Ma thode Volta t not excee   | 3000<br>a., 5.8.<br>s: \begin{pmatrix} -500 \\ +200 \\ ed 100 \\ volume{0} \end{pmatrix} | 3.8<br>0 (Abs.)          | 25L6<br>25L6-GT<br>25N6-G<br>25W4-GT<br>25Y5<br>25Z5                    |  |  |  |  |
| Outp<br>Trice<br>Max.<br>Max.<br>Max.<br>Max.                             | ut Triode: I<br>de: Plate Vol.<br>Peak Invers<br>Peak Plate DC Plate M<br>DC Output<br>C Volts per<br>DC Output M<br>C Volts per                     | Fo Plate Volts, 100; G e Plate Volts, 100; G e Plate Volta, 125  Ma. per  Fo Plate (R  Ia., 75  Plate (R) | r other ch<br>ts, 180; P<br>rid Volts,<br>7 olts, 3850<br>Plate, 75<br>r other ra<br>MS), 117 | 49<br>50<br>laracteris<br>late Ma.<br>0; A.F.Si<br>0 (Abs.)<br>tings, ret<br>Min.<br>Wav. | 13000 30000  tics, refer to 46; Load, 4 gnal Volts (P Max. Peak 1 DC Comp  Total Effect, 30 ohms; otal Effect.  | 9000<br>9500<br>Type 50I<br>1000 ohms.<br>eak), 29.7<br>Heater-Ca<br>onent mus                                    | te-Supply   | 3000  a., 5.8.  s: \( \ \ -500 \) d 100 vo  Impedar                                      | 3.8<br>0 (Abs.)<br>olts. | 25L6<br>25L6-GT<br>25N6-G<br>25W4-GT                                    |  |  |  |  |
| Outp<br>Trice<br>Max.<br>Max.<br>Max.<br>Max.                             | out Triode: I<br>de: Plate Vol<br>Peak Invers<br>Peak Plate M<br>DC Plate M<br>DC Output   | Fo Plate Volts, 100; G e Plate Volts, 100; G e Plate Volta, 125  Ma. per  Fo Plate (R  Ia., 75  Plate (R) | r other ch<br>ts, 180; P<br>rid Volts,<br>7 olts, 3850<br>Plate, 75<br>r other ra<br>MS), 117 | 49<br>50<br>laracteris<br>late Ma.<br>0; A.F.Si<br>0 (Abs.)<br>tings, ret<br>Min.<br>Wav. | 13000 30000  tics, refer to , 46; Load, 4 gnal Volts (P Max. Peak 1  DC Comp  Total Effee, 30 ohms;   | 9000<br>9500<br>Type 50I<br>1000 ohms.<br>eak), 29.7<br>Heater-Ca<br>onent mus                                    | te-Supply   | 3000  a., 5.8.  s: \( \ \ -500 \) d 100 vo  Impedar                                      | 3.8<br>0 (Abs.)<br>olts. | 25L6<br>25L6-GT<br>25N6-G<br>25W4-GT<br>25Y5<br>25Z5<br>25Z6            |  |  |  |  |
| Outp<br>Triox<br>Max.<br>Max.<br>Max.<br>Max.<br>Max.<br>Max. D<br>Max. A | out Triode: I<br>de: Plate Vol<br>Peak Invers<br>Peak Plate M<br>DC Plate M<br>DC Output<br>C Volts per<br>DC Output M<br>C Volts per<br>DC Output M | Fo Plate Volts, 100; G e Plate Volts, 100; G e Plate Volta, 125  Ma. per  Fo Plate (R  Ia., 75  Plate (R) | r other ch<br>ts, 180; P<br>rid Volts,<br>7 olts, 3850<br>Plate, 75<br>r other ra<br>MS), 117 | 49<br>50<br>laracteris<br>late Ma.<br>0; A.F.Si<br>0 (Abs.)<br>tings, rel<br>Min.<br>Wavy | 13000 30000  tics, refer to 46; Load, 4 gnal Volts (P Max. Peak 1 DC Comp  for to Type 2 Total Effect, 30 ohms; total Effect. s; at 150 v.                          | 9000 9500  Type 50L  1000 ohms. eak), 29.7  Heater-Ca onent mus  25Z6. ective Pla Full-Wave Supply In olts, 40 of | 6-GT.  ; Plate Mathode Volts to not exceed the Supply 1, 15 ohms. aped. per Imms; at 23 | 3000  a., 5.8.  s: \( \ \ -500 \) d 100 vo  Impedar                                      | 3.8<br>0 (Abs.)<br>olts. | 25L6<br>25L6-GT<br>25N6-G<br>25W4-GT<br>25Y5<br>25Z5<br>25Z6<br>25Z6-GT |  |  |  |  |

| J. 9 32   | 9150                            |         |
|-----------|---------------------------------|---------|
| S 9 80    | OTES                            |         |
|           | OIE.                            |         |
| W. 3      | DILU                            |         |
|           | UILU                            |         |
|           | OIEG.                           | ۹       |
|           | 0150                            | 1       |
|           | 0150                            | 1       |
|           | 0150                            |         |
|           | UILU                            |         |
|           | UIEG                            |         |
| ï         | UIEG                            |         |
|           | UILU                            |         |
|           | 0150                            |         |
| Н         | O I E O                         |         |
|           |                                 |         |
|           |                                 |         |
|           |                                 |         |
|           |                                 |         |
|           |                                 |         |
|           |                                 |         |
|           |                                 |         |
|           |                                 |         |
|           |                                 | 5       |
|           |                                 | 5       |
|           |                                 | 5       |
|           |                                 |         |
|           |                                 | 5<br>54 |
|           |                                 | 54      |
|           | r basin                         | 5<br>54 |
|           |                                 | 54      |
| Fe        | r basin<br>: pages              | ä       |
| Fe        | r basin<br>: pages              | ä       |
| Fe        | r basin<br>: pages              | ä       |
| Fe        | r basin<br>: pages              | ä       |
| Fe        | r basin<br>: pages              | ä       |
| Fe        | r basin<br>: pages              | ä       |
| Fe        | r basin<br>: pages              | ä       |
| Fe<br>sec | r hasing<br>: pages<br>rexplant | ıti     |
| Fe<br>sec | r hasing<br>: pages<br>rexplant | ıti     |
| Fe<br>sec | r hasing<br>: pages<br>rexplant | ıti     |
| Fe<br>sec | r hasing<br>: pages<br>rexplant | ıti     |
| Fe<br>sec | r hasing<br>: pages<br>rexplant | ıti     |
| Fe<br>sec | r basin<br>: pages              | ıti     |

|             |  |               |  |  |  | ,   |
|-------------|--|---------------|--|--|--|---|
| RGA<br>Type | Name   | Dime<br>and   | ube<br>ensions<br>Basing<br>gram∆<br>8. D. | Filam<br>Unless sp<br>types ha<br>⊕ Heater | ter or<br>ent (F)<br>ecified all<br>we heaters.<br>with con-<br>imup time. | Values to right give operating conditions and characteristics for indicated typical use |
| 31          | Power Triode                                   | 22 or<br>13H  | 4D   | 2.0F                                       | 0.13   | Class A Amplifier   |
| 32          | Sharp-Cutoff                                   | 13H<br>29K    | 4K   | 2.0F                                       | 0.06   | Class A Amplifier   |
| 32ET5       | Tetrode Power Pentode                          | <del></del> - | 7CV  | 32.0                                       | 0.1  | Class A Amplifier   |
| 32L7-GT     | Rectifier—<br>Beam Power<br>Tube               | 5D<br>14A     | 8Z   | 32.5                                       | 0.3  | Class A Amplifier Half-Wave Rectifier   |
| 33          | Power Pentode                                  | 25            | 5K   | 2.5F                                       | 0.26   | Class A Amplifier   |
| 34          | Remote-Cutoff<br>Pentode                       | 29%           | 4M   | 2.0F                                       | 0.06   | Screen-Grid<br>RF Amplifier   |
| 34GD5       | Beam Power<br>Tube                             | <b>50</b>     | 7CV<br>7CV                                 | 34.0<br>34.0⊕                              | 0.1  | Class A Amplifier   |
| 35          | Remote-Cutoff<br>Tetrode                       | 29K           | 5E   | 2.5  | 1.75   | Screen-Grid<br>RF Amplifier   |
| 35A5        | Beam<br>Power Tube                             | 12C           | BAA  | 35.0                                       | 0.15   | Single-Tube<br>Class A Amplifier  |
| 35Y4        | Half-Wave<br>Rectifier                         | 12C           | 5AL  | 35.0                                       | 0.15   | With Capacitive-<br>Input Filter  |
|             | Heater Tap for Pilot<br>Half-Wave              |               |  | en Pins 1                                  | 1  | With Capacitive-  |
| 35Z3        | Rectifier                                      | 12C           | 4Z   | 35.0                                       | 0.15   | Input Filter  |
| 35Z4-GT     | Half-Wave<br>Rectifier                         | 130           | SAA  | 35.0                                       | 0.15   | With Capacitive-<br>Input Filter  |
| 35Z5-GT     | Half-Wave<br>Rectifier<br>Heater Tap for Pilot | 14C<br>Pilo   | 6AD<br>of Between                          | 35.0<br>en Pins 2                          | 0.15<br>and 3  | With Capacitive-<br>Input Filter  |
| 36          | Sharp-Cutoff<br>Tetrode                        | 248           | 5€   | 6.3  | 0.3  | Screen-Grid<br>RF Amplifier   |
| 36AM3       | Half-Wave<br>Rectifier                         | 8D            | 5BQ  | 36.0                                       | 0.1  | With Capacitive-<br>Input Filter  |
| 36AM3-A     | Half-Wave<br>Rectifier                         | 5D            | 5BQ<br>5BQ                                 | 36.0⊕<br>36.0⊕                             | 0.1  | With Capacitive-<br>Input Filter  |
| 37          | Medium-Mu<br>Triode                            | 22 or<br>13H  | 5A   | 6.3  | 0.3  | Class A Amplifier   |
| 38          | Power Pentode                                  | 248           | 5F   | 6.3  | 0.3  | Class A Amplifier   |
| 39/44       | Remote-Cutoff<br>Pentode                       | 248           | 5F   | 6.3  | 0.3  | Class A Amplifier   |
| 40          | Medium-Mu<br>Triode                            | 26            | 4D   | 5.0F                                       | 0.25   | Class A Amplifier   |
| 41          | Power Pentode                                  | 22 or<br>13H  | 6B   | 6.3  | 0.4  | Amplifier   |
| 42          | Power Pentode                                  | 26            | 68   | 6.3  | 0.7  | Amplifier   |
| 43          | Power Pentode                                  | 28            | 6B   | 25.0                                       | 0.3  | Amplifier   |
| 45          | Power Triode                                   | 28            | 4D   | 2.5F                                       | 1.5  | Class A Amplifier   |
| 45Z3        | Half-Wave<br>Rectifier                         | \$C           | 5AM  | 45.0                                       | 0.075  | Half-Wave<br>Rectifier  |
| 45Z5-GT     | Half-Wave<br>Rectifier<br>Heater Tap for Pilot | 13D<br>Pilo   |  | 45.0<br>n Pins 2                           | 0.15<br>and 3  | With Capacitive-<br>Input Filter  |
| 46          | Dual-Grid<br>Power Amplifier                   | 278           | 5C   | 2.5F                                       | 1.75   | Class A Amplifier   |
| 47          | Power Pentode                                  | 278           | 5B   | 2.5F                                       | 1.75   | Class A Amplifier   |
| 48          | Power Tetrode                                  | 278           | 6A   | 30.0                                       | 0.4  | Class A Amplifier   |
| 49          | Dual-Grid<br>Power Amplifier                   | 26            | 5C   | 2.0F                                       | 0.12   | Class A Amplifier   |

| Plate<br>Sup-<br>ply<br>Volts             | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor<br>Olms (Ω)                                   | Screen<br>Sup-<br>ply<br>Volts            | Screen<br>Cur-<br>rent<br>Ma.  | Plate<br>Cur-<br>rent<br>Ma                        | AC Plate<br>Resis-<br>tance<br>Ohms   | Trans-<br>conduc-<br>tance<br>Micrombos   | Amplifi-<br>cation<br>Factor                   | Load<br>for Stated<br>Power<br>Output<br>Oksas | Power<br>Out-<br>put<br>Walts | RCA<br>Type   |  |  |
|---|---|---|--|--|---|---|--|--|-------------------------------|---|--|--|
| 180                                       | -30v  |   |  | 12.3   | 3600  | 1050  | 3.8  | 5700   | 0.375                         | 31  |  |  |
| 180<br>(Max.)                             | -3v   | 67.5                                      | 0.4  | 1.7  | 1.0+\$  | 650   |  |  |                               | 32  |  |  |
| 110                                       | - 7.5v  | 110                                       | 2.8  | 30   | 21500   | 5500  |  | 2800   | 1.2                           | 32ET5   |  |  |
| 90  | 90 - 7v 90 2.0 27.0 17000 4800 - 2600 1.0  Maximum AC Plate Voltage 125 Volts, RMS                |   |  |  |   |   |  |  |                               | 32L7-GT   |  |  |
| Maximum DC Output Current                 |   |   |  |  |   |   |  |  |                               |   |  |  |
| 180                                       | -18v  | 180                                       | 5.0  | 22.0   | 55000   | 1750  |  | 6000   | 1.4                           | 33  |  |  |
| 180                                       | - 3v<br>min.  | 67.5                                      | 1.0  | 2.8  | 1.0\$   | 620   |  |  |                               | 34  |  |  |
| 110                                       | - 7.5v  | 110                                       | 3  | 35   | 13000   | 5700  |  | 2500   | 1.4                           | 34GD5   |  |  |
| 250                                       | - 3v<br>min.  | 90  | 2.5*   | 6.5  |   | 1050  |  |  |                               | 35  |  |  |
|   |   | F   | or other c   | haracter   | stics, refer t  | o Type 35   | L6-GT.   |  |                               | 35A5  |  |  |
|   | For other characteristics, refer to Type 35L6-GT.  For other characteristics, refer to Type 35W4. |   |  |  |   |   |  |  |                               |   |  |  |
| For other ratings, refer to Type 35Z5-GT. |   |   |  |  |   |   |  |  |                               |   |  |  |
| Max. 1                                    | DC Output   | Ma., 100                                  |  |  | . Total Effe  |   |  |  | Up to 117                     | 35 <b>Z</b> 4-G1  |  |  |
| Min. 1<br>Max.                            | Total Effect<br>DC Output   | : Ma.: V                                  | pply Implith Pilot<br>ith Oith Pilot   | ed.: Up  | to 117 volts<br>Shunt Re  | , 15 ohms;  | at 235 v                                       | olts, 100                                      | ohms.<br>Res., 90;            | 35 <b>Z</b> 5-GT  |  |  |
| 100<br>250                                | - 1.5v<br>- 3v  | 55<br>90                                  | 1.7*   | 1.8  | 550000<br>550000  | 850<br>1080   |  |  |                               | 36  |  |  |
|   | AC Plate 1<br>DC Outpu  |   |  |  | Max. Peak<br>Tube Volta   |   |  | 150  | 20 volte                      | 36AM3   |  |  |
| Max.                                      | AC Plate V  | Volta (RI                                 | TS), 120   |  | Max. Peak<br>Tube Volta   | Inverse V   | olts, 365                                      |  |                               | 36AM3-A   |  |  |
| 250                                       | -18v  |   |  |  |   |   |  |  |                               | JON 11110-7   |  |  |
|   |   |   |  | 7.5  | 8400  | 1100  | 9.2  |  |                               | 37  |  |  |
| 250                                       | -25v  | 250                                       | 3.8  | 22.0   | 100000  | 1100<br>1200  | 9.2  | 10000  | 2.50                          |   |  |  |
| 250<br>250                                | -25v  | 250<br>90                                 | 3.8  |  |   |   | 9.2  | 10000  | 2.50                          | 37  |  |  |
|   | ∫- 3v\  |   |  | 22.0   | 100000  | 1200  | 9.2  | 10000  | 2.50                          | 37<br>38  |  |  |
| 250                                       | {− 3v}<br>min.}   | 90  | 1.4  | 5.8<br>0.2   | 100000  | 1200<br>1050<br>200   | 30   | 10000  | 2.50                          | 37<br>38<br>39/44<br>40<br>41                                   |  |  |
| 250                                       | {− 3v}<br>min.}   | 90<br>——<br>Fo                            | 1.4 or other cor other c   | 5.8<br>0.2<br>haracteri                            | 1.0§<br>1.0§<br>150000<br>stics, refer t  | 1200<br>1050<br>200<br>o Type 6K<br>o Type 6F   | 30<br>C6-GT.                                   | 10000  | 2.50                          | 37<br>38<br>39/44<br>40<br>41<br>42                             |  |  |
| 250<br>180×                               | {- 3v<br>min.}<br>- 3v  | 90<br>——<br>Fo                            | 1.4 or other cor other c   | 5.8 0.2 haracteri                                  | 100000 1.0§ 150000 stics, refer t stics, refer t                                    | 1200<br>1050<br>200<br>o Type 6F<br>o Type 6F<br>o Type 25                                | 30<br>C6-GT.<br>6-G.<br>A6.                    |  |                               | 37<br>38<br>39/44<br>40<br>41<br>42<br>43                       |  |  |
| 250<br>180×<br>275                        | - 3v<br>min 3v<br>- 56v   | 90<br>Fo                                  | 1.4 —— or other cor other cor other cor  | 5.8 0.2 haracteri haracteri 36.0                   | 100000  1.0§  150000 stics, refer t stics, refer t 1700                             | 1200<br>1050<br>200<br>o Type 6K<br>o Type 6F<br>o Type 25<br>2050                        | 30<br>66-GT.<br>6-G.<br>A6.                    | 4600   | 2.00                          | 37<br>38<br>39/44<br>40<br>41<br>42<br>43<br>45                 |  |  |
| 250<br>180×<br>275                        | {- 3v<br>min.}<br>- 3v  | 90 Fo                                     | 1.4 ————————————————————————————————————   | 5.8 0.2 haracteri haracteri 36.0 Max. D            | 100000 1.0§ 150000 stics, refer t stics, refer t                                    | 1200<br>1050<br>200<br>o Type 6K<br>o Type 6F<br>o Type 25<br>2050                        | 30<br>C6-GT.<br>6-G.<br>A6.                    | 4600   | 2.00                          | 37<br>38<br>39/44<br>40<br>41<br>42<br>43                       |  |  |
| 250<br>180×<br>275                        | - 3v<br>min 3v<br>- 56v   | 90 Fo                                     | 1.4 ————————————————————————————————————   | 5.8 0.2 haracteri haracteri 36.0 Max. D            | 100000  1.0§  150000  stics, refer t stics, refer t stics, refer t 2700  C Output M | 1200<br>1050<br>200<br>o Type 6K<br>o Type 6F<br>o Type 25<br>2050                        | 30<br>66-GT.<br>6-G.<br>A6.                    | 4600   | 2.00                          | 37<br>38<br>39/44<br>40<br>41<br>42<br>43<br>45<br>45           |  |  |
| 250<br>180 <sup>×</sup><br>275<br>Max     | - 3v<br>(min.)<br>- 3v<br>- 56v<br>. Peak Inve  | 90 Fo                                     | 1.4 ————————————————————————————————————   | 5.8 0.2 haracteri haracteri 36.0 Max. D atings, re | 100000  1.0 § 150000 stics, refer t stics, refer t 1700 C Output M                  | 1200<br>1050<br>200<br>o Type 6K<br>o Type 6F<br>o Type 25<br>2050<br>Ia., 65<br>35Z5-GT. | 30<br>C6-GT.<br>6-G.<br>A6.<br>3.5<br>Max. Per | 4600<br>ak Plate I                             | 2.00<br>Ma., 390              | 37<br>38<br>39/44<br>40<br>41<br>42<br>43<br>45<br>45Z3         |  |  |
| 250<br>180 <sup>32</sup><br>275<br>Max    | - 3v \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \  | 90 Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr | 1.4 — or other cor 5.8 0.2 haracteri haracteri 36.0 Max. D atings, re | 100000  1.0§  150000  stics, refer t stics, refer t 1700  C Output M  effer to Type | 1200<br>1050<br>200<br>o Type 6K<br>o Type 6F<br>o Type 25<br>2050<br>Ia., 65<br>35Z5-GT. | 30<br>C6-GT.<br>6-G.<br>A6.<br>3.5<br>Max. Per | 4600<br>ak Plate 1                             | 2.00<br>Ma., 390              | 37<br>38<br>39/44<br>40<br>41<br>42<br>43<br>45<br>4523<br>45Z3 |  |  |

|   | RGA<br>Type        | Name   | Dime<br>and E | be<br>nsions<br>Basing<br>pram∆<br>B. D. | Filam                     | with con-     | Use  Values to right give operating conditions and characteristics for indicated typical use |
|---|--------------------|--|---------------|--|---------------------------|---------------|--|
|   | 50                 | Power Triode                                     | 28L           | 4D                                       | 7.5 <b>F</b>              | 1.25          | Class A Amplifier  |
|   | 50A5               | Beam Power<br>Tube                               | 12C           | 6AA                                      | 50.0                      | 0.15          | Class A Amplifier  |
|   | 50C6-G             | Beam Power<br>Tube                               | 25            | 7AC                                      | 50.0                      | 0.15          | Single-Tube<br>Class A Amplifier   |
|   | 50X6               | Rectifier-Doubler                                | 12C           | 7DX                                      | 50.0                      | 0.15          | Rectifier-Doubler  |
|   | 50Y6-GT            | Rectifier-Doubler                                | 130           | 7Q:                                      | 50.0                      | 0.15          | Rectifier-Doubler  |
|   | 50Y7-GT            | Rectifier-<br>Doubler<br>Heater Tap for<br>Pilot | 130<br>Pilot  | 1  | 50.0 0.15<br>Pins 6 and 7 |               | Voltage<br>Doubler<br>Half-Wave<br>Rectifier   |
|   | 50Z7-G             | Rectifier-Doubler<br>Heater Tap for Pilot        | 22<br>Pilot   |  | 50.0<br>Pins 6 a          | 0.15<br>ind 7 | Voltage Doubler<br>Half-Wave Rect.   |
|   | 53                 | High-Mu Twin<br>Power Triode                     | 28            | 7B                                       | 2.5                       | 2.0           | Amplifier  |
|   | 70L7-GT            | Rectifier-Beam<br>Power Tube                     | 137           | 8AA                                      | 70.0                      | 0.15          | Amplifier Unit as<br>Class A Amplifier<br>Half-Wave<br>Rectifier                             |
| NOTES   | 75                 | Twin Diode—<br>High-Mu Triode                    | 24B           | 6G                                       | 6.3                       | 0.3           | Amplifier  |
| For basing diagrams,<br>see pages 549 to 553.                           | 78                 | Remote-Cutoff<br>Pentode                         | 248           | 6F                                       | 6.3                       | 0.3           | Amplifier<br>Mixer   |
| see pages 549 to 553.  For explanation of foot-<br>notes, see page 548. | 80                 | Full-Wave<br>Rectifier                           | 26            | 4C                                       | 5.0F                      | 2.0           | With Capacitive-<br>Input Filter<br>With Inductive-<br>Input Filter                          |
| Types shown in light-<br>face are discontinued.                         | 84/6Z4             | Full-Wave<br>Rectifier                           | 22 or<br>13H  | 5D                                       | 6.3                       | 0.5           | With Capacitive-<br>Input Filter<br>With Inductive-<br>Input Filter                          |
|   | 117L7-GT/<br>M7-GT | Rectifier-Beam<br>Power Tube                     | 13F           | 8AO                                      | 117                       | 0.09          | Amplifier Unit as<br>Class A Amplifier<br>Half-Wave<br>Rectifier                             |
|   | 117N7-GT           | Rectifier-Beam<br>Power Tube                     | 13F           | 8AV                                      | 117                       | 0.09          | Amplifier Unit as<br>Class A Amplifier<br>Half-Wave<br>Rectifier                             |
|   | 117P7-GT           | Rectifier-Beam<br>Power Tube                     | 13F           | 8AV                                      | 117                       | 0.09          |  |
|   | 117 <b>Z</b> 3     | Half-Wave<br>Rectifier                           | 5D            | 4CB                                      | 117                       | 0.04          | With Capacitive-<br>Input Filter   |
|   | 117Z4-GT           | Half-Wave<br>Rectifier                           | 20F           | 5AA                                      | 117                       | 0.04          | With Capacitive-<br>Input Filter   |
|   | 117Z6-GT           | Rectifier-<br>Doubler                            | 13D           | 7Q‡                                      | 117                       | 0.075         | Voltage<br>Doubler<br>Half-Wave<br>Rectifier   |
|   | 7027               | Beam Power<br>Tube                               | 19F           | 8НҮ                                      | 6.3                       | 0.9           | Push-Pull<br>Class AB <sub>1</sub> Amplifier<br>Push-Pull<br>Class AB <sub>1</sub> Amplifier |

| Plate<br>Sup-<br>ply<br>Valls   | Grid Bias<br>Volts (v)<br>or<br>Cathode<br>Resistor<br>Olms (Ω) | Screen<br>Sup-<br>ply<br>Voits | Screen<br>Cur-<br>rent<br>Ma | Plate<br>Cur-<br>rent<br>Ma | AC Plate<br>Resis-<br>tance<br>Olms                           | Trans-<br>conduc-<br>tance<br>Micronhes | Amplifi-<br>cation<br>Factor | Load<br>for Stated<br>Power<br>Output<br>Ohms       | Power<br>Out-<br>put<br>Watts               | RGA<br>Type        |
|---|---|--------------------------------|------------------------------|-----------------------------|---|---|------------------------------|---|---|--------------------|
| 450   | -84v  |                                |                              | 55                          | 1800  | 2100                                    | 3.8                          | 4350  | 4.6   | 50                 |
|   |   | F                              | or other                     | characte                    | eristics, refer   | to Type 5                               | OL6-GT.                      |   |   | 50A5               |
| 135<br>200  | -13.5v<br>-14v  | 135<br>135                     | 3.5                          | 58<br>61                    | 9300<br>18300   | 7000<br>7100                            |                              | 2000<br>2600  | 3.6<br>6                                    | 50C6-G             |
| For other ratings, refer to Type 25Z6-GT.   |   |                                |                              |                             |   |   |                              |   |   |                    |
| For other ratings, refer to Type 25Z6-GT.   |   |                                |                              |                             |   |   |                              |   |   |                    |
| Max. AC Volts per Plate (RMS), 117 Max. DC Output ma., 65 Max. AC Volts per Plate (RMS), 235 Max. AC Volts per Plate (RMS), 235 Max. DC Output Ma. per Plate, 65 Min. Total EffectivePlate-Supply Impedance per Plate; 15 ohms Min. Total EffectivePlate-Supply Impedance per Plate: At 117 Volts, 15 ohms; at 150 volts, 40 ohms; at 235 volts, 100 ohms |   |                                |                              |                             |   |   |                              |   |   |                    |
| Max. DC Output Ma. per Plate, 65  Max. DC Output Ma. per Plate, 65  |   |                                |                              |                             |   |   |                              |   |   |                    |
|   |   | F                              | or other cl                  | naracter                    | istics, refer to  | Type 6N                                 | 17.                          |   |   | 53                 |
| 110   | - 7.5v<br>Peak Inver  | 110                            | 3.0                          | 40.0                        | 15000<br>C Output Ma  | 7500                                    | Max. Peal                    | 2000  | 1.8   | 70L7-GT            |
|   |   |                                |                              |                             | ate-Supply I  |   | ohms                         | K FIRIC M   | 420   |                    |
|   |   | F                              | or other c                   | haracte                     | ristics, refer t  | o Type 68                               | 5Q7.                         |   |   | 75                 |
|   |   | F                              | or other c                   | haracter                    | istics, refer t   | о Туре бК                               | <b>C7.</b>                   |   |   | 78                 |
| Max. F  | lts per Plat<br>Peak Invers<br>Its per Plat<br>Peak Invers      | e Volts, 1<br>e (RMS),         | 400<br>500                   | Ma<br>Ma                    | Output Ma.<br>x. Peak Plate<br>x. DC Output<br>x. Peak Plate  | Ma., 440<br>t Ma., 125                  | Imped.<br>Min. Va            | per Plate   | ct. Supply<br>, 50 ohms<br>put Choke,<br>es |                    |
| Max. P  | its per Plate<br>eak Inverse<br>its per Plate<br>eak Inverse    | Volts, 1<br>(RMS),             | 450<br>450                   | Max<br>Max                  | Output Ma.,<br>L. Peak Plate<br>L. DC Output<br>L. Peak Plate | Ma., 180<br>Ma., 60                     | Imped.                       | al Effect.<br>per Plate,<br>alue of In<br>oke, 10 h | 150 ohms.<br>nput                           | 84/624             |
| 105   | - 5.2v  | 105                            | 4                            | 43                          | 17000   | 5300                                    | Г <u> </u>                   | 4000  |   | 11717 OT/          |
| Max. A  | C Plate Vo  | its (RMS                       |                              |                             | . DC Output<br>. Peak Plate                                   |   |                              | otal Effe<br>Imped.,                                | ct. Plate-                                  | 117L7-GT/<br>M7-GT |
| 100   | - 6v<br>C Plate Vo  | 100                            | 5                            | 51<br>Mar                   | 16000   | 7000                                    |                              | 3000  | 1.2<br>ct. Plate-                           | 117N7-GT           |
|   | eak Inverse   | Volts, 3                       | 50                           | Max                         | . Peak Plate<br>ristics, refer t                              | Ma., 450                                | Supply                       | Impedanc  | e, 15 ohms.                                 | 117P7-GT           |
| Max. P  | eak Inverse   |                                |                              |                             | DC Output   |   |                              | al Effect.  |   | 117Z3              |
|   | eak Inverse   |                                |                              |                             | Peak Plate  |   |                              | mped., 20   |   |                    |
|   |   |                                |                              | Max                         | . Peak Plate  | ma., 540                                | Supply I                     | mped., 30   | ohms  | 117Z4-GT           |
| AC Volts per Plate (RMS), 117 DC Output Ma., 60 Min. Total Effective Plate-Supply Impedance per Plate: Half-Wave, 30 ohms; Full-Wave, 15 ohms. AC Volts per Plate (RMS), 235 Min. Total Effect. Supply Imped. per Plate: At 117 DC Output Ma. per Plate, 60 volts, 15 ohms; at 150 volts, 40 ohms; at 235 volts, 100 ohms.                                |   |                                |                              |                             |   |   |                              |   |   |                    |
| AC VO   |   |                                |                              |                             |   | v vnits. 40 (                           | onus: at 23                  | o voits, li   | NOOTES.                                     |                    |
| DC Ou   | -30v  | er Plate,                      | 3.4                          | 95 🏟                        |   |   |                              | 6000  | 50  |                    |
| DC Ou   |   |                                | 3.4♠                         |                             |   |   |                              |   |   | 7027               |

#### **FOOTNOTES**

- Superseded by 10-Y. See Power and Gas Tubes Booklet PG-101D.
- With tube mounted horizontally and pins No. 4 and No. 8 in a vertical plane (pin No. 4 on top). deflecting electrode No. 1 controls left-hand section of pattern, deflecting electrode No. 2 controls top right-hand section of pattern, deflecting electrode No. 3 controls bottom section of pattern.
- Grid-No. 2 of each tube connected to tap on plate winding of output transformer. This arrangement permits approximately 40% to 50% of the plate signal voltage to be applied to Grid-No. 2 of each output tube.
- \* Applied through plate resistor of 250000 ohms.
- ▶ Supply voltage applied through 20000-ohm voltage-dropping resistor.
- ♥ Applied through plate resistor of 100000 ohms.
- Obtained preferably by using 70000-ohm voltage-dropping resistor in series with a 90-volt supply.
  Note 1: Subscript 1 on class of amplifier service (as AB<sub>1</sub>) indicates that grid current does not
- flow during any part of input cycle.

  ° Applied through plate resistor of 150000 ohms.

Note 2: Subscript 2 on class of amplifier service (as AB<sub>2</sub>) indicates that grid current flows during some part of the input cycle.

§ Megohms.

a 50000 ohms.

+ Each unit.

\* Maximum.

• For two tubes.

➤ Mercury-Vapor Type.

☐ Grid # 2 tied to plate.

- \* Value is for both units operating at the specified conditions.
- AA Both grids connected together; likewise both cathodes.
- ¶ For signal-input control-grid (# 1); control-grid # 3 bias, −3 volts.
- Both grids connected together; likewise, both plates.
- ★ For Grid-leak Detection—plate volts, 45; grid return to + filament or to cathode.

φ For television damper service.

- \*\* For grid of following tube.
- √ With separate excitation and triode unit grounded.
- ■■ Grid # 1 is control grid. Grid # 2 is screen. Grid # 3 tied to cathode.
- ¶ Grid # 1 is control grid. Grids # 2 and # 3 tied to plate.
- A Grids # 2 and # 4 are screen. Grid # 1 is signal-input control grid.
- Grids # 1 and # 2 connected together. Grid # 3 tied to plate.
- F Grids # 2 and # 3 tied to plate.
- ♦ Grids # 1 and # 2 tied together.

Types with octal bases have Miniature Cap; all others have Small Cap.


- For use in automobile receivers which operate directly from 12-volt storage batteries.
- ▲ Grids # 2 and # 4 are screen. Grid # 3 is signal-input control grid.
- o Grids # 3 and # 5 are screen. Grid # 4 is signal-input control grid.
- † Power output is for two tubes at stated plate-to-plate load.
- ‡ This diagram is like the one having the same designation except that Pin No. 1 has no connection.
- This diagram is like the one having the same designation except that base sleeve is connected to Pin No. 1.
- ‡‡ This diagram is like the one having the same designation except that Pin No. 1 is connected to internal shield.


## Basing Diagrams for RCA Renewal and Discontinued Types


#### LEGEND FOR BASE AND ENVELOPE CONNECTION DIAGRAMS


**Bottom Views** 


Subscripts B. D. HP. HX. P. T. and TR indicate, respectively, beam unit, diode unit, heptode unit, hexode unit, pentode unit, triode unit, and tetrode unit in multi-unit types.











### RCA PICTURE TUBE CHARACTERISTICS CHART

Greatest

| 5TP4 <sup>a</sup> Yes    | 6.3/600<br>6.3/600 | ama Ty<br>● G            | nes fo     |          |          |                 |            |                | Required |
|--------------------------|--------------------|--------------------------|------------|----------|----------|-----------------|------------|----------------|----------|
| 5TP4 <sup>d</sup> Yes    | 6.3/600            |                          | , pos 10   | r Blac   | k-and    | l-White         | TV         |                |          |
|                          |                    |                          | 50         | E        | 1.2      | 12.12           | 12C        | 29500          | No       |
| 7.JP4 No                 | 0.07000            | ● G                      | (e)        | E        | 3        | 14.88           | 14R        | 6500           | No       |
| 8DP4 No                  | 6.3/600            | <b>■</b> G               | 90         | E        | 3        | 10.750          | 12AB       | 9000           | Yes      |
| 9QP4A No                 | 4.7/300            | ■ G                      | 70         | Ε        | 3.5      | 13.062          | 12AD       | 7500           | Yes      |
| 10FP4A Yes               |                    | ● G                      | 50         | M        | 10       | 18              | 12N        | 13000          | No       |
| 12KP4A Yes               |                    | • G                      | 54         | M        | 12       | 18              | 12N        | 13000          | , No     |
| 14ATP4 Yes               |                    | ■ G                      | 90         | E        | 8.5      | 13.500          | 12L        | 15500          | No       |
| 14EP4 No                 | 6.3/600            | <b>■</b> G               | 70         | M        | 10       | 16.844          | 12N        | 15500          | Yes      |
| 140P4B Yes               |                    | ■ G                      | 70         | E        | 10       | 16.531          | 12L        | 12000          | No       |
| 14WP4 Yes                | 6.3/600            | <b>=</b> G               | 90         | Ε        | 8.5      | 13.500          | 12L        | 15500          | No       |
| 16AP4A No                | 6.3/600            | <ul><li>M</li></ul>      | 53         | M        | 11       | 22.31           | 12D        | 15500          | Yes      |
| 16AYP4 Yes               | 6.3/450            | <b>≡</b> G               | 114        | E        | 8.5      | 10.563          | 8HR        | 20000          | No       |
| 16DP4A No                | 6.3/600            | • G                      | 60         | M        | 15       | 21              | 12D        | 16500          | Yes      |
| 16GP4B No                | 6.3/600            | • M                      | 70         | M        | 11       | 17.69           | 12D        | 15500          | Yes      |
| 16LP4A No                | 6.3/600            | ● G                      | 52         | M        | 14.5     | 22.625          | 12N        | 15500          | Yes      |
| 16RP4A Yes               | 6.3/600            | ■ G                      | 70         | M        | 16       | 19.125          | 12N        | 17500          | Yes      |
| 16TP4 No<br>16WP4A No    | 6.3/600            | ■ G                      | 70         | М        | 16       | 18.50           | 12N        | 15500          | Yes      |
| 16WP4A No<br>17BJP4 Yes  | 6.3/600<br>6.3/600 | ● G<br>■ G               | 70<br>90   | M        | 16.5     | 18.125          | 12N        | 17500          | Yes      |
| 17BP4D Yes               | 6.3/600            | ■ G                      | 70         | E<br>M   | 15<br>18 | 15<br>19.56     | 12L<br>12N | 17500<br>17500 | No<br>No |
| 17CDP4 Yes               | 8.4/450            | ■ G                      | 110        | E        |          | 12.812          | 8HR        |                |          |
| 17CFP4 Yes               | 6.3/600            | ≖ G                      | 90         | E        | 10<br>10 | 15.38           | 88K<br>12L | 17500<br>17500 | No<br>No |
| 17CP4 No                 | 6.3/600            | <b>=</b> ₩               | 70         | M        | 10       | 19.36           | 12D        | 17500          | Yes      |
| 17CSP4 Yes               | 6.3/600            | ■ G                      | 110        | Ë        | 10       | 12.62           | 7FA        | 17500          | No       |
| 17CYP4 Yes               | 6.3/600            | ≡ Ğ                      | 90         | Ē        | 10       | 14.38           | 12L        | 17500          | No       |
| 17DAP4 Yes               | 2.68/450           | ■ G                      | 110        | E        | 10       | 10.875          | 8JK        | 17500          | No       |
| 17DKP4 Yes               | 6.3/600            | ■ G                      | 110        | Ē        | 10       | 10.94           | 8JR        | 23000          | No       |
| 17DQP4' Yes              | 6.3/450            | <b>≡</b> G               | 110        | E        | 10       | 12.38           | 7FA        | 17500          | No       |
| 17DRP4° Yes              | 2.68/450           | <b>≡</b> G               | 110        | Ε        | 10       | 11              | 8JK        | 17500          | No       |
| 17DSP4 Yes               | 6.3/600            | <b>■</b> G               | 110        | Ε        | 10       | 11.44           | 8HR        | 20000          | No       |
| 17DXP4 Yes               | 6.3/450            | <b>≡</b> G               | 110        | Ε        | 10       | 10.94           | 8JR        | 17500          | No       |
| 17GP4 No                 | 6.3/600            | ■ M                      | 70         | Ε        | 10       | 19.31           | 12M        | 17500          | Yes      |
| 17HP4C Yes               | 6.3/600            | <b>≡</b> G               | 70         | Ε        | 18       | 19.56           | 12L        | 17500          | No       |
| 17LP4B Yes               | 6.3/600            | ■ G <sup>n</sup>         | 70         | E        | 19       | 19.56           | 12L        | 17500          | No       |
| 17QP4B Yes               | 6.3/600            | ■ G <sup>n</sup>         | 70         | M        | 19       | 19.56           | 12N        | 20000          | No       |
| 17TP4 No                 | 6.3/600            | ■ M                      | 70         | E        | 10       | 19.31           | 12M        | 17500          | Yes      |
| 19ABP4 Yes               | 2.68/450           | <b>≡</b> G               | 114        | Ē        | 14       | 11.125          | 8JK        | 20000          | No       |
| 19AHP4 Yes               | 6.3/450            | <b>≡</b> G               | 114        | Ē        | 13.5     | 11.625          | 8HR        | 17500          | No       |
| 19AJP47 Yes<br>19AP4B No | 6.3/450            | <b>≡</b> G               | 114        | E        | 14       | 11.62           | 7FA        | 20000          | No       |
|                          | 6.3/600            | ● M                      | 66         | <u>M</u> | 14       | 22              | 120        | 17500          | Yes      |
| 19AUP4 Yes<br>19AVP4 Yes | 6.3/600            | <b>≡</b> G <sup>jk</sup> | 114        | E        | 18.5     | 11.94           | 8HR        | 20000          | No       |
| 19AVP4 Yes<br>19AYP4 Yes | 6.3/600<br>6.3/450 | ■ G<br>■ G               | 114<br>114 | Ē        | 14       | 11.62           | 8HR        | 23000          | No<br>No |
| 19BDP4' Yes              | 6.3/450<br>6.3/600 | ≡ G<br>≡ G               | 92         | E<br>E   | 14       | 11.62           | 8HR        | 23000          | No<br>No |
| <b>19BTP4</b> Yes        | 6.3/600            | ≡ G                      | 92<br>114  | E<br>E   | 15<br>14 | 15.625<br>11.06 | 12L<br>8JR | 20000          | No<br>No |
| 100117 103               | 0.3/000            | <b>=</b> u               | 114        | <u> </u> | 14       | 11.00           | ЛГО        | 23000          | NU       |

#### RCA PICTURE TUBE CHARACTERISTICS CHART (Cont'd)

| RCA<br>Type      | Aluminized<br>Screen | Heater<br>Volts/Ma | Envelopa                  | Greatest<br>Deflection<br>Angle <sup>b</sup><br>(Approx.)<br>Degrees | 1<br>Focusing<br>Method | Apprex.<br>Tube<br>Weight<br>Pounds | Maximum<br>Over-all<br>Length<br>Inches | Basing     | Design<br>Maximum<br>Anodeo<br>Volts | PM<br>Ion-Trap<br>Magnet<br>Required |
|------------------|----------------------|--------------------|---------------------------|--|-------------------------|-------------------------------------|---|------------|--------------------------------------|--------------------------------------|
|                  |                      | Silvera            | ama T                     | ypes f   | or Blac                 | k-and                               | l-White                                 | TV         |                                      |                                      |
| 19CHP4'          | Yes                  | 6.3/600            | ■ G                       | 114  | E                       | 14                                  | 11.88                                   | 8HR        | 20000                                | No                                   |
| 19CMP4'          | Yes                  | 6.3/450            | <b>■</b> G                | 114  | E                       | 14                                  | 11.88                                   | 8HR        | 20000                                | No                                   |
| 19DQP4           | Yes                  | 6.3/450            | <b>≡</b> G‴               | 114  | E                       | 15                                  | 11.625                                  | 8HR        | 23000                                | No                                   |
| 200P4D           | Yes                  | 6.3/600            | <b>≡</b> G                | 70   | M                       | 30                                  | 22.12                                   | 12N        | 20000                                | No                                   |
| 20HP4E           | Yes                  | 6.3/600            | ■ G                       | 70   | E                       | 30                                  | 22.12                                   | 12L        | 17500                                | No                                   |
| 21AMP4B          | Yes                  | 6.3/600            | ■ G                       | 90   | M                       | 24                                  | 20.375                                  | 12N        | 20000                                | No                                   |
| 21AP4<br>21AVP4C | No<br>Yes            | 6.3/600<br>6.3/600 | ■ M<br>■ G                | 70<br>72   | M<br>E                  | 18<br>24                            | 22.62<br>23.41                          | 12D<br>12L | 20000<br>22000                       | Yes<br>No                            |
| 21AWP4A          | Yes                  | 6.3/600            | ■ G                       | 72   | M                       | 24                                  | 23.41                                   | 12L<br>12N | 20000                                | No                                   |
| 21 CBP4A         | Yes                  | 6.3/600            | ■ G                       | 90   | E                       | 24                                  | 18.375                                  | 12L        | 22000                                | No                                   |
| 21CQP4           | Yes                  | 6.3/600            | ■ G                       | 110  | E                       | 20                                  | 14.81                                   | 7FA        | 20000                                | No                                   |
| 21DEP4A          | Yes                  | 6.3/600            | = G                       | 110  | Ē                       | 20                                  | 15                                      | 8HR        | 22000                                | No                                   |
| 21 DFP4          | Yes                  | 6.3/600            | ≡ Ğ                       | 110  | Ē                       | 24                                  | 14.750                                  | 8HR        | 20000                                | No                                   |
| 210HP4           | Yes                  | 6.3/450            | ■ G                       | 110  | Ē                       | 20                                  | 15                                      | 8HR        | 20000                                | No                                   |
| 21DLP4           | Yes                  | 6.3/600            | ■ G                       | 90   | Ε                       | 24                                  | 17.375                                  | 12L        | 22000                                | No                                   |
| 21DSP41          | Yes                  | 6.3/600            | ■ G                       | 90   | E                       | 24                                  | 18.375                                  | 12L        | 22000                                | No                                   |
| 21 EP4C          | Yes                  | 6.3/600            | <b>≡</b> G*               | 70   | M                       | 29                                  | 23.41                                   | 12N        | 20000                                | No                                   |
| 21 EQP4          | Yes                  | 6.3/600            | <b>■</b> G                | 110  | E                       | 24                                  | 12.88                                   | 8JR        | 20000                                | No                                   |
| 21 EVP4"         | Yes                  | 2.68/450           | ■G                        | 110  | Ε                       | 20                                  | 13.19                                   | 8JK        | 20000                                | No                                   |
| 21FAP4           | Yes                  | 6.3/600            | ■ G                       | 110  | E                       | 20                                  | 13.12                                   | 8JR        | 22000                                | No                                   |
| 21FDP4           | Yes                  | 6.3/600            | ■ G                       | 110  | E                       | 20                                  | 13.38                                   | 8KW        | 20000                                | No                                   |
| 21FP4D           | Yes                  | 6.3/600            | ■ G*                      | 70   | Ē                       | 29                                  | 23.41                                   | 12L        | 20000                                | No                                   |
| 21MP4            | No                   | 6.3/600            | ■ M                       | 70   | Ë                       | 18                                  | 22.62                                   | 12M        | 17500                                | Yes                                  |
| 21WP4A<br>21XP4A | Yes<br>Yes           | 6.3/600<br>6.3/600 | ■ G<br>■ G                | 70<br>70   | M<br>E                  | 24<br>24                            | 22.81<br>22.81                          | 12N<br>12L | 20000<br>20000                       | Yes<br>Yes                           |
| 21YP4B           | Yes                  |                    |                           |  |                         | 24                                  |   |            |                                      |                                      |
| 217P4B<br>21ZP4C | res<br>Yes           | 6.3/600<br>6.3/600 | ■ G<br>■ G                | 70<br>70   | E<br>M                  | 24<br>24                            | 23.41<br>23.41                          | 12L<br>12N | 20000<br>20000                       | No<br>No                             |
| 23AHP4           | Yes                  | 6.3/600            | ■ G                       | 92   | E                       | 25                                  | 18.38                                   | 12 L       | 22000                                | No                                   |
| 23ASP4           | Yes                  | 6.3/600            | ■ G                       | 92   | Ē                       | 25                                  | 17.38                                   | 12L        | 22000                                | No                                   |
| 23BGP4'          | Yes                  | 6.3/600            | <b>≡</b> G <sup>j</sup> k | 110  | Ē                       | 33                                  | 15.56                                   | 8HR        | 22000                                | No                                   |
| 23BJP41          | Yes                  | 6.3/600            | ■ G                       | 92   | E E                     | 25                                  | 18.50                                   | 12L        | 25000                                | No                                   |
| 23BLP41          | Yes                  | 6.3/600            | <b>■</b> G <sup>j</sup> * | 92   | Ĕ                       | 35                                  | 18.88                                   | 12L        | 25000                                | No                                   |
| 23CBP4           | Yes                  | 6.3/450            | <b>■</b> G <sup>j</sup> ≥ | 110  | E                       | 33                                  | 15.56                                   | 8HR        | 23000                                | No                                   |
| 23CP4            | Yes                  | 6.3/600            | <b>≡</b> G <sup>j</sup>   | 110  | E                       | 33                                  | 15.56                                   | 8HR        | 22000                                | No                                   |
| 23CQP4           | Yes                  | 6.3/450            | <b>≡</b> G                | 114  | E                       | 25                                  | 14.062                                  | 8HR        | 23500                                | No                                   |
| 23DAP41          | Yes                  | 6.3/600            | ■ G                       | 94   | E                       | 27                                  | 17.39                                   | 8HR        | 23000                                | No                                   |
| 230BP4'          | Yes                  | 6.3/600            | <b>≡</b> G                | 110  | E                       | 25                                  | 15.156                                  | 8HR        | 22000                                | No                                   |
| 23ENP4           | Yes                  | 6.3/600            | <b>■</b> G"               | 92   | Ē                       | 29                                  | 18.500                                  | 12L        | 25000                                | No                                   |
| 23EP47           | Yes                  | 6.3/600            | <b>■</b> G'               | 110  | Ē                       | 33                                  | 15.562                                  | 8KP        | 22000                                | No                                   |
| 23FBP4           | Yes                  | 6.3/600            | ■ G <sup>km</sup>         | 92   | E                       | 29                                  | 18.500                                  | 12L        | 25000                                | No                                   |
| 23FP4A           | Yes                  | 6.3/600            | ■ G                       | 114  | E                       | 25                                  | 14.062                                  | 8HR        | 23500                                | No                                   |
| 23JP41           | Yes                  | 6.3/450            | ■ G,                      | 110  | E                       | 33                                  | 15.88                                   | 7FA        | 22000                                | No                                   |
| 23NP4            | Yes<br>Yes           | 6.3/600<br>6.3/600 | ≡ G<br>■ G′               | 114<br>92  | E<br>E                  | 25<br>35                            | 14.812<br>18.75                         | 8HR<br>12L | 22000                                | No<br>No                             |
| 23174<br>24AEP4  | Yes                  | 6.3/600            | ■ G                       | 92<br>90   | E                       | აი<br>35                            | 18.75                                   | 12L<br>12L | 22000<br>22000                       | No<br>No                             |
| 47RLFT           | 169                  | 0.0/000            | = 0                       | 30   | L                       | JJ                                  | 13.300                                  | 14L        | 22000                                | 110                                  |

#### RCA PICTURE TUBE CHARACTERISTICS CHART (Cont'd)


| Aluminized<br>Screen | Heater<br>Volts/Ma                      | Envelope <sup>a</sup> | Greatest Deflection Angleb (Approx.) Degrees        | Focusing<br>Method | Approx.<br>Tube<br>Weight<br>Pounds  | Maximum<br>Over-all<br>Length<br>Inches  | Basing      | Design<br>Maximum<br>Anodes<br>Volts | PM<br>Ion-Trap<br>Magnet<br>Required |
|----------------------|---|-----------------------|---|--------------------|--|--|-------------|--------------------------------------|--------------------------------------|
|                      | Silvera                                 | ıma Ty                | pes fo  | r Blac             | k-and  | l-White  | TV          |                                      |                                      |
| Yes                  | 6.3/600                                 | ■ G                   | 110   | E                  | 28   | 16.188   | 8HR         | 22000                                | No                                   |
| Yes                  | 6.3/600                                 | <b>■</b> G            | 90  | E                  | 35   | 19.500   | 12L         | 22000                                | No                                   |
| Yes                  | 6.3/600                                 | <b>■</b> G            | 90  | Ε                  | 35   | 18.50  | 12L         | 22000                                | No                                   |
| Yes                  | 6.3/600                                 | <b>■</b> G            | 110   | Ε                  | 28   | 16.188   | 8HR         | 22000                                | No                                   |
| Yes                  | 6.3/600                                 | <b>≡</b> G            | 110   | Ę                  | 28   | 15.12  | 8KW         | 20000                                | No                                   |
| Yes                  | 6.3/600                                 | ■ G                   | 90  | М                  | 35   | 21.50  | 12N         | 22000                                | No                                   |
| Yes                  | 6.3/600                                 | ■ M                   | 90  | M                  | 30   | 22.19  | 12 <b>D</b> | 20000                                | Yes                                  |
| Yes                  | 6.3/600                                 | <b>■</b> G            | 90  | M                  | 44   | 23.44  | 12N         | 22000                                | No                                   |
|                      |   | Co                    | lor Pic   | ture               | Tubes  |  |             |                                      |                                      |
| Yes                  | 6.3/1800 <sup>p</sup>                   | • G                   | 45  | E                  | 25   | 26.12  | 20A         | 22000                                | No                                   |
| Yes                  | $6.3/1800^{p}$                          | <ul><li>M</li></ul>   | 70  | Ε                  | 28   | 25.31  | 14AH        | 27500                                | No                                   |
| Yes                  | $6.3/1800^{p}$                          | • G                   | 70  | Ε                  | 36.5   | 25.406   | 14AL        | 27500                                | No                                   |
| Yes                  | $6.3/1800^{p}$                          | • G                   | 70  | Ε                  | 36.5   | 25.406   | 14AU        | 27500                                | No                                   |
| Yes                  | $6.3/1800^{p}$                          | $lackbox{G}^{kq}$     | 70  | E                  | 41   | 25.594   | 14AU        | 27500                                | No                                   |
|                      |   | Te                    | est Pic   | ture T             | ubes   |  |             |                                      | -                                    |
| No                   | 6.3/600                                 | • G                   | 53  | Er                 | 1.5  | 11.00  | 128         | 20000                                | No                                   |
| Yes                  | 6.3/600                                 | ■ G                   | 90  | E۳                 | 3  | 11.75  | 128         | 22000                                | No                                   |
| Yes                  | 6.3/600                                 | <b>≡</b> G            | 110   | Ē٢                 | 2  | 9  | 7FG         | 22000                                | No                                   |
|                      | Yes Yes Yes Yes Yes Yes Yes Yes Yes Yes | Screen   Volts/Ma     | Screen Volts/Ma Envelope  Silverama Ty  Yes 6.3/600 | Aluminized Screen  | Aluminized Screen Volts/Ma Envelope Per (Approx.)  Silverama Types for Blace  Yes 6.3/600 ■ G 110 E  Yes 6.3/600 ■ G 90 E  Yes 6.3/600 ■ G 110 E  Yes 6.3/600 ■ G 110 E  Yes 6.3/600 ■ G 90 E  Yes 6.3/600 ■ G 110 E  Yes 6.3/600 ■ G 10 M   Color Picture T  Yes 6.3/1800 ● G 45 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Yes 6.3/1800 ● G 70 E  Test Picture T | Aluminized   Heater   Screen   Volts/Ma   Envelope   Volts/Ma   Types   For   Black-and   Weight   Pounds   Ves   6.3/600   G   90   E   35   35   Yes   6.3/600   G   90   E   35   35   Yes   6.3/600   G   910   E   28   28   Yes   6.3/600   G   90   M   35   35   Yes   6.3/600   G   90   M   30   35   Yes   6.3/600   G   90   M   44   44   Yes   6.3/1800   G   90   M   44   44   Yes   6.3/1800   G   70   E   28   25   Yes   6.3/1800   G   70   E   28   36.5   Yes   6.3/1800   G   70   E   36.5   Yes   6.3/1800   G   70   E   36.5   41   30   30   30   30   30   30   30   3 | No          | No                                   | No                                   |

- G Glass round.
  M Metal round.
- G Glass rectangular. ■ M Metal rectangular. E Electrostatic.
- M Magnetic.
- a Faceplate is spherical, unless otherwise specified.
- b All types utilize magnetic deflection except for type 7JP4 which employs electrostatic deflection.
- c The anode is defined as the electrode, or the electrode in combination with one or more additional electrodes
- connected within the tube to it, to which is applied the highest dc voltage for accelerating the electrons in
- the beam.
  d Projection type.
- deflection factors e Typical (volts dc/in.) for anode voltage of 6000 volts; DJ1 & DJ2 (nearer screen)
  - 186 to 246 DJ3 & DJ4 (nearer base)
  - 150 to 204
  - f Has low grid-No.2 voltage rating: for Cathode-Drive Service.

- g This type has an internal magnetic shield.
- h Cylindrical faceplate.
- j Bipanel type. k Treated to reduce specular
- reflection. m PAN-O-PLY-integral im-
- plosion protection.

  n This type has a flat, aluminized, filterglass phosphor-
- dot screen plate. p Three heaters paralleled in-
- ternally. q This type has an integral
- protective window. r Automatic.


#### BASING DIAGRAMS FOR RCA PICTURE TUBES



ANODE - Gg + Gg + CL POCUSING ELECTRODE - GA



ANODE = G3 + G5 + CL FOCUSING ELECTRODE = G4



ANODE - G + Gs + CL FOCUSING ELECTRODE - 04

#### RCA Picture Tube Characteristics Chart



ANODE = G<sub>3</sub> + G<sub>5</sub> + CL FOCUSING ELECTRODE = G<sub>4</sub>




ANODE = G3 + G5 + CL FOCUSING ELECTRODE = G4



ANODE = G3 + G5 + CL FOCUSING ELECTRODE = G4



ANODE = G4 + G5 + CL + R FOCUSING ELECTRODE = G3



ANODE = G4 + G5 + CL FOCUSING ELECTRODE = G3



ANODE = G3 + G5 + CL AUTOMATIC FOCUSING



ANODE = G<sub>4</sub> + CL FOCUSING ELECTRODE = G<sub>3</sub>



ANODE = G4 + CL FOCUSING ELECTRODE = G2



ANODE = G3 + G5 + CL FOCUSING ELECTRODE = G4




14AL



ANODE = G2 + G4 + CL FOCUSING ELECTRODE = G3



12AD ANODE = G<sub>3</sub> + G<sub>5</sub> + CL FOCUSING ELECTRODE = G<sub>4</sub>



ANODE = G3 + G5 + CL FOCUSING ELECTRODE = GA



ANODE - G<sub>3</sub> + CL



ANODE = G3 + CL

#### (14AL) CAP OVER PIN No. 1 = G4 + G5 CAP OVER PIN No. 2 -ANODE + CL & HIGH-VOLTAGE

TERMINAL. Connect High-Voltage Supply to this Cap and also connect 50,000 - ahm resistor between this Cap and the Cap

FOCUSING ELECTRODE = G3



ANODE = G<sub>5</sub> + G<sub>6</sub> + CL FOCUSING ELECTRODE = G<sub>3</sub>



ANODE = G3 + G5 + CL AUTOMATIC FOCUSING

## RCA VOLTAGE-REGULATOR AND VOLTAGE-REFERENCE TUBES

These tubes are designed for voltage-regulation requiring a relatively constant dc output voltage across a load independent of load and line-voltage variations.

| RCA<br>Type | DC Oper-<br>ating<br>Volts | DC<br>Operating<br>Current<br>Range<br>(ma) | Anode<br>Starting<br>Volts | Anode<br>Starting<br>Ma | Regu-<br>lation<br>Volts | Ambient<br>Operating<br>Temperature<br>Range (°C) | Max<br>Length<br>(in) | Max<br>Diam-<br>eter<br>(in) | Terminal<br>Diagram |
|-------------|----------------------------|---|----------------------------|-------------------------|--------------------------|---|-----------------------|------------------------------|---------------------|
|             |                            | VOLT  | AGE-I                      | REGU                    | LAT0                     | R TUBES   | t                     |                              |                     |
| OA2         | 150                        | 5 to 30                                     | 185                        | 75                      | 6                        | -55 to +90  | 2-5/8                 | 3/4                          | 5B0                 |
| OA3         | 75                         | 5 to 40                                     | 105                        | 100                     | 6.5                      | -55 to +90  | 4-1/8                 | 1-9/16                       | 4AJ                 |
| DASA        | 75                         | 5 to 40                                     | 105                        | 100                     | 6.5                      | -55 to +90  | 3-1/16                | 1-9/32                       | 4AJ                 |
| 0B2         | 105                        | 5 to 30                                     | 133                        | .75                     | 4                        | —55 to +90  | 2-5/8                 | 3/4                          | 5B0                 |
| OC2         | 75                         | 5 to 30                                     | 115                        | 75                      | 4.5                      | -55 to +90  | 2-5/8                 | 3/4                          | 5B0                 |
| OC3         | 105                        | 5 to 40                                     | 133                        | 100                     | 4                        | -55 to +90  | 4-1/8                 | 1-9/16                       | 4AJ                 |
| OC3A        | 105                        | 5 to 40                                     | 127                        | 100                     | 4                        | -55 to +90  | 3-1/16                | 1-9/32                       | 4AJ                 |
| OD3         | 150                        | 5 to 40                                     | 185                        | 100                     | 5.5                      | -55 to +90  | 4-1/8                 | 1-9/16                       | 4Aj                 |
| OD3A        | 150                        | 5 to 40                                     | 180                        | 100                     | 5.5                      | -55 to +90  | 3-1/16                | 1-9/32                       | 4AJ                 |
| 991         | 59                         | 0.4 to 2                                    | 87                         |                         | 8                        | _   | 1-9/16                | 5/8                          | *                   |
| 6073        | 150                        | 5 to 30                                     | 185                        | 75                      | 6                        | -55 to +90  | 2-5/8                 | 3/4                          | 5B0                 |
| 6073/0A2    | 150                        | 5 to 30                                     | 185                        | 75                      | 6                        | -55 to +90  | 2-5/8                 | 3/4                          | 5B0                 |
| 6074        | 105                        | 5 to 30                                     | 133                        | 75                      | 4                        | -55 to $+90$                                      | 2-5/8                 | 3/4                          | 5B0                 |
| 6074/0B2    | 105                        | 5 to 30                                     | 133                        | 75                      | 4                        | -55 to +90  | 2-5/8                 | 3/4                          | 5B0                 |
| 6626/0A2WA  | 150                        | 5 to 30                                     | 165                        | 75                      | 5                        | —55 to +90  | 2-5/8                 | 3/4                          | 5B0                 |

### VOLTAGE-REFERENCE TUBES †

(for exceptional voltage stability)

|       | <br> |                |   |   |                    |       | •   |     |
|-------|------|----------------|---|---|--------------------|-------|-----|-----|
| 5651  | 87   | 1.5 to 3.5 115 | _ | 3 | -55 to +90         | 2-1/8 | 3/4 | 5B0 |
| 5651A | 85.5 | 1.5 to 3.5 115 | - | 3 | <b>−</b> 55 to +90 | 2-1/8 | 3/4 | 5B0 |


#### **SERIES-VOLTAGE-REGULATOR TUBES \*\***

(for high-current applications)


| RCA<br>Type | Heater<br>Volts | Heater<br>Amperes | DC<br>Plate<br>Volts | DC<br>Plate<br>Amperes | Plate Dis-<br>sipation<br>(watts) | Ampli-<br>fication<br>Factor | Plate Re-<br>sistance<br>(ohms) | Max<br>Length<br>(in) | Max<br>Diameter<br>(in) | Terminal<br>Diagram |
|-------------|-----------------|-------------------|----------------------|------------------------|-----------------------------------|------------------------------|---------------------------------|-----------------------|-------------------------|---------------------|
| 6AS7G       | 6.3             | 2.5               | 250                  | 0.125                  | 13                                | 2                            | 280                             | 4-5/8                 | 1-9/16                  | 8BD                 |
| 6080        | 6.3             | 2.5               | 250                  | 0.125                  | 13                                | 2                            | 280                             | 4-1/6                 | 1-23/32                 | 8BD                 |
| 6082        | 26.5            | 0.6               | 250                  | 0.125                  | 13                                | 2                            | 280                             | 4-1/6                 | 1-23/32                 | 8BD                 |
| 6336A       | 6.3             | 5                 | 400                  | 0.4                    | 30                                | 2.7                          | 280                             | 4-3/4                 | 2.07                    | 8BD                 |

<sup>\*\*</sup> Indirectly-heated-cathode, vacuum, low-mu twin triodes.

<sup>†</sup> Cold-cathode, glow-discharge types.







\* Candelabra two-contact socket.

580

## Electron Tube Testing

HE electron-tube user-service man. experimenter, or non-technical radio listener-is interested in knowing the condition of his tubes, since they govern the performance of the device in which they are used. In order to determine the condition of a tube, some method of test is necessary. Because the operating capabilities and design features of a tube are indicated and described by its electrical characteristics, a tube is tested by measuring its characteristics and comparing them with values established as standard for that type. Tubes which read abnormally high with respect to the standard for the type are subject to criticism just the same as tubes which are too low.

Certain practical limitations are placed on the accuracy with which a tube test can be correlated with actual tube performance. These limitations make it impractical for the service man and dealer to employ complex and costly testing equipment having laboratory accuracy. Because the accuracy of the tube-testing device need be no greater than the accuracy of the correlation between test results and receiver performance, and since certain fundamental characteristics are virtually fixed by the manufacturing technique of leading tube manufacturers, it is possible to employ a relatively simple test in order to determine the serviceability of a tube.

In view of these factors, dealers and service men will find it economically expedient to obtain adequate accuracy and simplicity of operation by employing a device which indicates the status of a single characteristic. Whether the tube is satisfactory or unsatisfactory is judged from the test result of this single characteristic. Consequently, it is

very desirable that the characteristic selected for the test be one which is truly representative of the tube's over-all condition.

The following information and circuits are given to describe and illustrate general theoretical and practical tubetester considerations and not to provide information on the construction of a home-made tube tester. In addition to the problem of determining what tube characteristic is most representative of performance capabilities in all types of receivers, the designer of a home-made tester faces the difficult problem of determining satisfactory limits for his particular tester. Getting information of this nature, if it is to be accurate and useful, is a big job. It requires the testing of many tubes of each type, testing of many types, and correlation of the data with performance in many kinds of equipment.

#### Short-Circuit Test

The fundamental circuit of a short-circuit tester is shown in Fig. 99. Although this circuit is suitable for tet-




Fig. 99—Fundamental circuit of a shortcircuit tester.

rodes and types having less than four electrodes, tubes of more electrodes may be tested by adding more indicator lamps to the circuit. Voltages are applied between the various electrodes with lamps in series with the electrode leads. The value of the voltages applied will depend on the type of tube being tested and its maximum ratings. Any two shorted electrodes complete a circuit and light one or more lamps. Since two electrodes may be just touching to give a high-resistance short, it is desirable that the indicating lamps operate on very low current. It is also desirable to maintain the filament or heater of the tube at its operating temperature during the short-circuit test, because shortcircuits in a tube may sometimes occur only when the electrodes are heated. However, a short-circuit tester having too high a sensitivity may indicate veryhigh-resistance shorts that do not adversely affect tube operation.

#### Selection of a Suitable Characteristic for Test

Some characteristics of a tube are far more important in determining its operating worth than are others. The cost of building a device to measure any one of the more important characteristics may be considerably higher than that of a device which measures a less representative characteristic. Consequently, three methods of test will be discussed, ranging from relatively simple and inexpensive equipment to more elaborate, more accurate, and more costly devices.

An emission test is perhaps the simplest method of indicating a tube's condition. (Refer to Diodes, in Electrons, Electrodes, and Electron Tubes section, for a discussion of electron emission.) Since emission falls off as the tube wears out, low emission is indicative of the end of tube serviceability. However, the emission test is subject to limitations because it tests the tube under static conditions and does not take into account the actual operation of the tube. On the one hand, coated filaments, or cathodes,

often develop active spots from which the emission is so great that the relatively small grid area adjacent to these spots cannot control the electron stream. Under these conditions, the total emission may indicate the tube to be normal although the tube is unsatisfactory. On the other hand, coated types of filaments are capable of such large emission that the tube will often operate satisfactorily after the emission has fallen far below the original value.

Fig. 100 shows the fundamental circuit diagram for an emission test. All of the electrodes of the tube, except the cathode, are connected to the plate. The filament, or heater, is operated at rated voltage; after the tube has reached con-




Fig. 100—Fundamental circuit of an emission tester.

stant temperature, a low positive voltage is applied to the plate and the electron emission is read on the meter. Readings which are well below the average for a particular tube type indicate that the total number of available electrons has been so reduced that the tube is no longer able to function properly.

A transconductance test takes into account a fundamental operating principle of the tube. (This fact will be seen from the definition of transconductance in the Section on Electron Tube Characteristics.) It follows that transconductance tests, when properly made, permit better correlation between test results and actual performance than does a straight emission test.

There are two forms of transconductance test which can be utilized in a tube tester. In the first form (illustrated by Fig. 101 giving a fundamental circuit with a tetrode under test), appropriate operating voltages are applied to the electrodes of the tube. A plate current

depending upon the electrode voltages will then be indicated by the meter. If the bias on the grid is then shifted by the application of a different grid voltage, a new plate-current reading is obtained. The difference between the two plate-current readings is indicative of the transconductance of the tube. This




Fig. 101—Fundamental circuit of a transconductance tester using the "grid-shift" method.

method of transconductance testing is commonly called the "grid-shift" method, and depends on readings under static conditions. The fact that this form of test is made under static conditions imposes limitations not encountered in the second form of test made under dynamic conditions.

The dynamic transconductance test illustrated in Fig. 102 gives a fundamental circuit with a tetrode under test. This method is superior to the static transconductance test in that ac voltage




Fig. 102—Fundamental circuit of a dynamic transconductance tester.

is applied to the grid. Thus, the tube is tested under conditions which approximate actual operating conditions. The alternating component of the plate current is read by means of an ac ammeter of the dynamometer type. The transconductance of the tube is equal to the ac plate current divided by the inputsignal voltage. If a one-volt rms signal is applied to the grid, the plate-current-meter reading in milliamperes multiplied by one thousand is the value of transconductance in micrombos.

The power-output test probably gives the best correlation between test results and actual operating performance of a tube. In the case of voltage amplifiers, the power output is indicative of the amplification and output voltages obtainable from the tube. In the case of power-output tubes, the performance of the tube is closely checked. Consequently, although more complicated to set up, the power-output test will give closer correlation with actual performance than any other single test.

Fig. 103 shows the fundamental circuit of a power-output test for class A operation of tubes. The diagram illustrates the method for a pentode. The ac output voltage developed across the




Fig. 103—Fundamental circuit of a power-output tester for class A operation of tubes.

plate-load impedance (L) is indicated by the current meter. The current meter is isolated as far as the dc plate current is concerned by the capacitor (C). The power output can be calculated from the current reading and known load resistance. In this way, it is possible to determine the operating condition of the tube quite accurately.

Fig. 104 shows the fundamental circuit of a power-output test for class B operation of tubes. With ac voltage

applied to the grid of the tube, the current in the plate circuit is read on a dc milliammeter. The power output of the tube is approximately equal to:

$$(I_{b^2} \times R_L)/0.405$$
.

where Po is the power output in watts, In is the dc current in amperes, and R<sub>L</sub> is the load resistance in ohms.




Fig. 104—Fundamental circuit of a power-output tester for class B opera-tion of tubes.

#### **Essential Tube-Tester** Requirements

- 1. The tester should provide for making a short-circuit test before measurement of the tube's characteristics.
- 2. It is important that some means of controlling the voltages applied to the electrodes of the tube be provided. If

the tester is ac operated, a line-voltage control permits the supply of proper electrode voltages.

3. It is essential that the rated voltage applied to the filament or heater be

maintained accurately.

4. It is suggested that the characteristics test follow one of the methods described. The method selected and the quality of the parts used in the test will depend upon the user's requirements.

#### **Tube-Tester Limitations**

A tube-testing device can only indicate the difference between a given tube's characteristics and those which are standard for that particular type. Since the operating conditions imposed upon a tube of a given type may vary within wide limits, it is impossible for a tube-testing device to evaluate tubes in terms of performance capabilities for all applications. The tube tester. therefore, cannot be looked upon as a final authority in determining whether or not a tube is always satisfactory. Actual operating test in the equipment in which the tube is to be used will give the best possible indication of a tube's worth.

# Resistance-Coupled Amplifiers

RESISTANCE-COUPLED, audiofrequency voltage amplifiers utilize simple components and are capable of providing essentially uniform amplification over a relatively wide frequency range.

#### Suitable Tubes

In this section, data are given for over 45 types of tubes suitable for use in resistance-coupled circuits. These types include low- and high-mu triodes, twin triodes, triode-connected pentodes, and pentodes. The accompanying key to tube types will assist in locating the appropriate data chart.

#### Circuit Advantages

For most of the types shown, the data pertain to operation with cathode bias; for all of the pentodes, the data pertain to operation with series screengrid resistor. The use of a cathode-bias resistor where feasible and a series screen-grid resistor where applicable offers several advantages over fixed-voltage operation.

The advantages are: (1) effects of possible tube differences are minimized; (2) operation over a wide range of plate-supply voltages without appreciable change in gain is feasible; (3) the low frequency at which the amplifier cuts off is easily changed; and (4) tendency toward motorboating is minimized.

#### **Number of Stages**

These advantages can be enhanced by the addition of suitable decoupling filters in the plate supply of each stage of a multi-stage amplifier. With proper filters, three or more amplifier stages can be operated from a single powersupply unit of conventional design with-

| Type Cha                                | rt No.                    | Type Chart                                     | No.                   |
|---|---------------------------|--|-----------------------|
| 3AU6<br>3AV6<br>3BC5<br>3CB6<br>3CF6    | 2<br>9<br>11<br>10<br>11  | 6CG7<br>6CN7<br>6EU7<br>6FQ7<br>6SL7GT         | 8<br>5<br>9<br>8<br>5 |
| 4AU6<br>4BQ7A<br>4BZ7<br>4CB6<br>5BK7A  | 2<br>10<br>10<br>11<br>11 | 6SN7GTB<br>6T8A<br>7AU7<br>8CG7<br>12AT6       | 8<br>5<br>3<br>8<br>5 |
| 5BQ7A<br>5T8<br>6AB4<br>6AG5<br>6AT6    | 10<br>5<br>4<br>11<br>5   | 12AT7<br>12AU6<br>12AU7A<br>12AV6<br>12AX7A    | 4<br>2<br>3<br>9      |
| 6AU6A<br>6AV6<br>6BC5<br>6BK7B<br>6BQ7A | 2<br>9<br>11<br>10<br>10  | 12AY7<br>12SL7GT<br>12SN7GTA<br>20EZ7<br>5879P | 1<br>5<br>8<br>9<br>6 |
| 6BZ7<br>6C4<br>6CB6<br>6CB6A<br>6CF6    | 10<br>3<br>11<br>11<br>11 | 5879T<br>7025<br>7199P<br>7199T                | 7<br>9<br>12<br>13    |
| T = Triode U:                           | nit or Ti                 | iode Connection<br>Pentode Connec              | tion                  |

**KEY TO CHARTS** 

out encountering any difficulties due to coupling through the power unit. When decoupling filters are not used, not more than two stages should be operated from a single power-supply unit.

#### Symbols Used in Resistance-Coupled Amplifier Charts

 $C = Blocking Capacitor (\mu f).$ 

 $C_k$  = Cathode Bypass Capacitor ( $\mu$ f).  $C_{g^2}$  = Screen-Grid Bypass Capacitor

 $(\mu f)$ .

E<sub>bb</sub> = Plate-Supply Voltage (volts).

Voltage at plate equals platesupply voltage minus drop in R<sub>p</sub>
and R<sub>k</sub>.

R<sub>k</sub> = Cathode Resistor (ohms).

R<sub>g2</sub> = Screen-Grid Resistor

(megohms).

R<sub>g</sub> = Grid Resistor (megohms) for following stage.

R<sub>p</sub> = Plate Resistor (megohms).

V.G. = Voltage Gain.

E<sub>o</sub> = Output Voltage (peak volts).


This voltage is obtained across
R<sub>g</sub> (for following stage) at any
frequency within the flat region
of the output vs. frequency
curve, and is for the condition
where the signal level is adequate to swing the grid of
the resistance-coupled amplifier
tube to the point where its grid
starts to draw current.

Note: The listed values for E<sub>0</sub> are the peak output voltages available when the grid is driven from a low-impedance source. The listed values for the cathode resistors are optimum for any signal source. With a high-impedance source, protection against severe distortion and loss of gain due to input loading may be obtained by the use of a coupling capacitor connected directly to the input grid and a high-value resistor connected between the grid and ground.

#### **General Circuit Considerations**


In the discussions which follow, the frequency (f<sub>2</sub>) is that value at which the high-frequency response begins to fall off. The frequency (f<sub>1</sub>) is that value at which the low-frequency response drops below a satisfactory value, as discussed below. A variation of 10 per cent in values of resistors and capacitors has only slight effect on perform-

ance. One-half-watt resistors are usually suitable for  $R_{g2}$ ,  $R_g$ ,  $R_p$ , and  $R_k$  resistors. Capacitors C and  $C_{g2}$  should have a working voltage equal to or greater than  $E_{bb}$ . Capacitor  $C_k$  may have a low working voltage in the order of 10 to 25 volts.



#### Triode Amplifier

Heater-Cathode Type
Capacitors C and C<sub>k</sub> have been chosen to give an output voltage equal to 0.8 E<sub>0</sub> for a frequency (f<sub>1</sub>) of 100 cycles. For any other value of f<sub>1</sub>, multiply values of C and C<sub>k</sub> by 100/f<sub>1</sub>. In




the case of capacitor C<sub>k</sub>, the values shown in the charts are for an amplifier with dc heater excitation; when ac is used, depending on the character of the associated circuit, the gain, and the value of f1, it may be necessary to increase the value of Ck to minimize hum disturbances. It may be desirable to operate the heater at a positive voltage of from 15 to 40 volts with respect to the cathode. The voltage output at  $f_1$  of "n" like stages equals  $(0.8)^n \times E_0$ , where E<sub>o</sub> is the peak output voltage of final stage. For an amplifier of typical construction, the value of f2 is well above the audio-frequency range for any value of R<sub>p</sub>.

## Pentode Amplifier Filament-Type

Capacitors C and C<sub>g2</sub> have been chosen to give an output voltage equal

to  $0.8 \times E_0$  for a frequency (f<sub>1</sub>) of 100 cycles. For any other value of f1, multiply values of C and Cg2 by 100/f1. The voltage output at f, for "n" like stages equals  $(0.8)^n \times E_0$  where  $E_n$  is peak output voltage of final stage. For an amplifier of typical construction, and for  $R_p$  values of 0.1, 0.25, and 0.5 megohm, approximate values of f2 are 20000, 10000, and 5000 cps, respec-




tively. Note: The values of inputcoupling capacitor in microfarads and of grid resistor in megohms should be such that their product lies between 0.02 and 0.1. Values commonly used are  $0.005 \mu f$  and 10 megohms.

#### Pentode Amplifier Heater-Cathode Type

Capacitors C, Ck, and Cg2 have been chosen to give an output voltage

equal to  $0.7 \times E_0$  for a frequency (f<sub>1</sub>) of 100 cycles. For any other value of f1, multiply values of C, Ck, and Cg2 by 100/f<sub>1</sub>. In the case of capacitor C<sub>k</sub>, the values shown in the charts are for



an amplifier with dc heater excitation; when ac is used, depending on the character of the associated circuits, the voltage gain, and the value of f1, it may be necessary to increase the value of C<sub>k</sub> to minimize hum disturbances. It may be desirable to operate the heater at a positive voltage of from 15 to 40 volts with respect to the cathode. The voltage output at f, for "n" like stages equals  $(0.7)^n \times E_o$  where E<sub>o</sub> is peak output voltage of final stage. For an amplifier of typical construc-tion, and for R<sub>p</sub> values of 0.1, 0.25, and 0.5 megohm, approximate values of f<sub>2</sub> are 20000, 10000, and 5000 cps, respectively.

| Ebb | Rp                  | Rg                  | R | g2 Rk                | C <sub>g2</sub> | Ck | С | E <sub>o</sub> * | V.G            |
|-----|---------------------|---------------------|---|----------------------|-----------------|----|---|------------------|----------------|
| 90  | 0.1<br>0.24<br>0.51 | 0.24<br>0.51<br>1.0 | - | 1800<br>3700<br>7800 | -               | =  | = | 13<br>14<br>16   | 24<br>26<br>27 |
| 180 | 0.1<br>0.24<br>0.51 | 0.24<br>0.51<br>1.0 | = | 1300<br>2800<br>5700 | =               | -  | = | 31<br>33<br>33   | 27<br>29<br>30 |
| 300 | 0.1<br>0.24<br>0.51 | 0.24<br>0.51<br>1.0 | - | 1200<br>2300<br>4800 | =               |    | = | 58<br>30<br>56   | 28<br>30<br>31 |



12AY7°

One triode unit.

<sup>\*</sup> Peak volts. \* Coupling capacitors should be selected to give desired frequency response. Cathode resistors

should be adequately bypassed.



3AU6 4AU6 6AU6A 12AU6

See Circuit Diagram 3

| $\mathbf{E}_{\mathbf{bb}}$ | Rp   | Rg                  | R <sub>g2</sub>         | Rk                   | C <sub>g2</sub>         | Ck                   | С                          | E <sub>o</sub> * | V.G.              |
|----------------------------|------|---------------------|-------------------------|----------------------|-------------------------|----------------------|----------------------------|------------------|-------------------|
|                            | 0.22 | 0.22<br>0.47<br>1.0 | 0.340<br>0.370<br>0.380 | 2700<br>2900<br>3100 | 0.057<br>0.050<br>0.050 | 5.8<br>5.4<br>5.3    | 0.0081<br>0.0055<br>0.0034 | 16<br>22<br>25   | 79<br>104<br>125  |
| 90                         | 0.47 | 0.47<br>1.0<br>2.2  | 1.00<br>1.00<br>1.00    | 6000<br>6200<br>6300 | 0.027<br>0.023<br>0.027 | 2.8<br>2.7<br>2.8    | 0.0042<br>0.0027<br>0.0019 | 13<br>17<br>25   | 105<br>137<br>161 |
|                            | 1.0  | 1.0<br>2.2          | 1.90<br>2.40            | 10800<br>13100       | 0.017<br>0.017          | 1.7<br>1.7           | 0.0025<br>0.0017           | 10<br>19         | 139<br>184        |
|                            | 0.22 | 0.22<br>0.47<br>1.0 | 0.520<br>0.520<br>0.520 | 1340<br>1390<br>1420 | 0.059<br>0.059<br>0.059 | 8.8<br>8.7<br>8.6    | 0.0081<br>0.0053<br>0.0032 | 31<br>43<br>48   | 143<br>192<br>223 |
| 180                        | 0.47 | 0.47<br>1.0<br>2.2  | 1.05<br>1.15<br>1.20    | 2700<br>2880<br>2960 | 0.039<br>0.037<br>0.036 | 5.5<br>5.4<br>5.4    | 0.0041<br>0.0027<br>0.0019 | 34<br>43<br>50   | 189<br>249<br>294 |
|                            | 1.0  | 1.0<br>2.2          | 2.40<br>2.70            | 5500<br>6000         | 0.028<br>0.022          | 3.2<br>2.8           | 0.0023<br>0.0015           | 33<br>40         | 230<br>323        |
|                            | 0.22 | 0.22<br>0.47<br>1.0 | 0.530<br>0.540<br>0.540 | 780<br>783<br>800    | 0.077<br>0.077<br>0.077 | 13.2<br>13.2<br>13.1 | 0.0082<br>0.0053<br>0.0033 | 53<br>65<br>74   | 200<br>270<br>316 |
| 300                        | 0.47 | 0.47<br>1.0<br>2.2  | 1.15<br>1.22<br>1.31    | 1590<br>1650<br>1720 | 0.057<br>0.049<br>0.045 | 8.4<br>7.4<br>7.2    | 0.0045<br>0.0027<br>0.0017 | 56<br>72<br>82   | 275<br>357<br>418 |
|                            | 1.0  | 1.0<br>2.2          | 2.50<br>2.80            | 3300<br>3500         | 0.036<br>0.031          | 5.3<br>4.2           | 0.0022<br>0.0015           | 57<br>72         | 352<br>466        |



6C4 7AU7' 12AU7A'

|     | 0.047 | 0.047<br>9.1<br>0.22 | -      | 1600<br>1800<br>2000  | - | 3.2<br>2.5<br>2.0   | 0.061<br>0.033<br>0.015   | 9<br>11<br>14  | 10<br>11<br>11 |
|-----|-------|----------------------|--------|-----------------------|---|---------------------|---------------------------|----------------|----------------|
| 90  | 0.1   | 0.1<br>0.22<br>0.47  | -      | 3000<br>3800<br>4500  | = | 1.6<br>1.1<br>1.0   | 0.032<br>0.015<br>0.007   | 10<br>15<br>18 | 11<br>11<br>11 |
|     | 0.22  | 0.22<br>0.47<br>1.0  | -      | 6800<br>9500<br>11500 | = | 0.7<br>0.5<br>0.43  | 0.015<br>0.0065<br>0.0035 | 14<br>20<br>24 | 11<br>11<br>11 |
|     | 0.047 | 0.047<br>0.1<br>0.22 | -<br>- | 920<br>1200<br>1400   | = | 3.9<br>2.9<br>2.5   | 0.062<br>0.037<br>0.016   | 20<br>26<br>29 | 11<br>12<br>12 |
| 180 | 0.1   | 0.1<br>0.22<br>0.47  | -      | 2000<br>2800<br>3600  | - | 1.9<br>1.4<br>1.1   | 0.032<br>0.016<br>0.007   | 24<br>33<br>40 | 12<br>12<br>12 |
|     | 0.22  | 0.22<br>0.47<br>1.0  |        | 5300<br>8300<br>10000 | - | 0.8<br>0.56<br>0.48 | 0.015<br>0.007<br>0.0035  | 31<br>44<br>54 | 12<br>12<br>12 |
|     | 0.047 | 0.047<br>0.1<br>0.22 | -      | 870<br>1200<br>1500   | - | 4.1<br>3.0<br>2.4   | 0.065<br>0.034<br>0.016   | 38<br>52<br>68 | 12<br>12<br>12 |
| 300 | 0.1   | 0.1<br>0.22<br>0.47  | -<br>- | 1900<br>3000<br>4000  | - | 1.9<br>1.3<br>1.1   | 0.032<br>0.016<br>0.007   | 44<br>68<br>80 | 12<br>12<br>12 |
|     | 0.22  | 0.22<br>0.47<br>1.0  |        | 5300<br>8800<br>11000 |   | 0.9<br>0.52<br>0.46 | 0.015<br>0.007<br>0.0035  | 57<br>82<br>92 | 12<br>12<br>12 |

<sup>•</sup> One triode unit.

<sup>\*</sup> Peak volts.

| Ebb | Rp   | Rg                  | R <sub>g2</sub> | Rk                      | C <sub>g2</sub> | Ck                   | С                          | E <sub>o</sub> *  | V.G.           | ] |
|-----|------|---------------------|-----------------|-------------------------|-----------------|----------------------|----------------------------|-------------------|----------------|---|
|     | 0.1  | 0.1<br>0.22<br>0.47 | =               | 2680<br>3060<br>3390    | -               | 2.4<br>2.00<br>1.84  | 0.026<br>0.014<br>0.0074   | 8<br>11<br>13     | 24<br>25<br>28 |   |
| 90  | 0.22 | 0.22<br>0.47<br>1.0 | -               | 5500<br>6300<br>6930    | =               | 1.33<br>1.01<br>0.92 | 0.0136<br>0.0067<br>0.0038 | 10<br>14<br>15    | 25<br>28<br>28 |   |
|     | 0.47 | 0.47<br>1.0<br>2.2  | -<br>-          | 10900<br>12500<br>13500 | -               | 0.63<br>0.52<br>0.47 | 0.007<br>0.0043<br>0.0031  | 13<br>14<br>18    | 26<br>28<br>28 |   |
|     | 0.1  | 0.1<br>0.22<br>0.47 | =               | 1407<br>1674<br>1786    | 1 1 1           | 3.6<br>3.0<br>2.6    | 0.029<br>0.016<br>0.0083   | 20<br>28<br>31    | 31<br>33<br>34 |   |
| 180 | 0.22 | 0.22<br>0.47<br>1.0 | -               | 2890<br>3860<br>4660    |                 | 1.75<br>1.34<br>1.14 | 0.0140<br>0.0077<br>0.0047 | 24<br>35<br>42    | 33<br>33<br>33 |   |
|     | 0.47 | 0.47<br>1.0<br>2.2  | -               | 6960<br>8450<br>9600    | -               | 0.83<br>0.67<br>0.55 | 0.0075<br>0.0046<br>0.0032 | 31<br>39<br>45    | 31<br>32<br>32 |   |
|     | 0.1  | 0.1<br>0.22<br>0.47 | -               | 974<br>1404<br>2169     |                 | 4.0<br>3.1<br>2.5    | 0.028<br>0.015<br>0.0083   | 37<br>57<br>78    | 34<br>34<br>33 |   |
| 300 | 0.22 | 0.22<br>0.47<br>1.0 | -               | 2510<br>4200<br>4950    |                 | 1.9<br>1.3<br>1.1    | 0.015<br>0.0074<br>0.0046  | 50<br>78<br>85    | 33<br>33<br>32 |   |
|     | 0.47 | 0.47<br>1.0<br>2.2  |                 | 5700<br>8720<br>9700    | 111             | 0.90<br>0.62<br>0.57 | 0.0076<br>0.0041<br>0.0030 | 57<br>81<br>88    | 33<br>32<br>32 |   |
|     | 0.1  | 0.1<br>0.22<br>0.47 | =               | 4200<br>4600<br>4800    | :               | 2.5<br>2.2<br>2.0    | 0.025<br>0.014<br>0.0065   | 5.4<br>7.5<br>9.1 | 22<br>27<br>30 |   |
| 90  | 0.22 | 0.22<br>0.47<br>1.0 | =               | 7000<br>7800<br>8100    | -               | 1.5<br>1.3<br>1.1    | 0.013<br>0.007<br>0.0035   | 7.3<br>10<br>12   | 30<br>34<br>37 |   |
|     | 0.47 | 0.47<br>1.0<br>2.2  | =               | 12000<br>14000<br>15000 | 111             | 0.83<br>0.7<br>0.6   | 0.006<br>0.0035<br>0.002   | 10<br>14<br>16    | 36<br>39<br>41 |   |
|     | 0.1  | 0.1<br>0.22<br>0.47 | =               | 1900<br>2200<br>2500    | =               | 3.6<br>3.1<br>2.8    | 0.027<br>0.014<br>0.0065   | 19<br>25<br>32    | 30<br>35<br>37 |   |
| 180 | 0.22 | 0.22<br>0.47<br>1.0 | =               | 3400<br>4100<br>4600    | =               | 2.2<br>1.7<br>1.5    | 0.014<br>0.0065<br>0.0035  | 24<br>34<br>38    | 38<br>42<br>44 |   |
|     | 0.47 | 0.47<br>1.0<br>2.2  | =               | 6600<br>8100<br>9100    | =               | 1.1<br>0.9<br>0.8    | 0.0065<br>0.0035<br>0.002  | 29<br>38<br>43    | 44<br>46<br>47 |   |
|     | 0.1  | 0.1<br>0.22<br>0.47 | =               | 1500<br>1800<br>2100    | =               | 4.4<br>3.6<br>3.0    | 0.027<br>0.014<br>0.0055   | 40<br>54<br>63    | 34<br>38<br>41 |   |
| 300 | 0.22 | 0.22<br>0.47<br>0.1 | =               | 2600<br>3200<br>3700    | =               | 2.5<br>1.9<br>1.6    | 0.013<br>0.0065<br>0.0035  | 51<br>65<br>77    | 42<br>46<br>48 |   |
|     | 0.47 | 0.47<br>1.0<br>2.2  | =               | 5200<br>6300<br>7200    | =               | 1.2<br>1.0<br>0.9    | 0.006<br>0.0035<br>0.002   | 61<br>74<br>85    | 48<br>50<br>51 |   |

<sup>4)</sup> 

6AB4 12AT7\*

See Circuit Diagram 1

**(5)** 

5T8

6AT6 6CN7 6SL7GT\* 6T8A 12AT6 2SL7GT\*

<sup>•</sup> One triode unit.

<sup>\*</sup> Peak volts.

С

Eo\*

V.G.



Еьь

 $R_p$ 

5879

See Circuit Diagram 3

|     | 0.1  | 0.1<br>0.22<br>0.47 | 0.35 | 1700 | 0.044<br>0.046<br>0.047 | 4.6<br>4.5<br>4.4    | 0.020<br>0.012<br>0.006 | 13<br>17<br>20 | 29<br>39<br>47    |
|-----|------|---------------------|------|------|-------------------------|----------------------|-------------------------|----------------|-------------------|
| 90  | 0.22 | 0.22<br>0.47<br>1.0 | 0.80 | 3000 | 0.034<br>0.035<br>0.036 | 3.2<br>3.1<br>3.0    | 0.010<br>0.005<br>0.003 | 15<br>21<br>24 | 43<br>59<br>67    |
|     | 0.47 | 0.47<br>1.0<br>2.2  | 1.9  | 7000 | 0.021<br>0.022<br>0.023 | 1.8<br>1.7<br>1.7    | 0.005<br>0.003<br>0.002 | 21<br>25<br>28 | 59<br>75<br>87    |
|     | 0.1  | 0.1<br>0.22<br>0.47 | 0.35 | 700  | 0.060<br>0.062<br>0.064 | 7.4<br>7.3<br>7.2    | 0.020<br>0.012<br>0.006 | 24<br>28<br>33 | 39<br>56<br>65    |
| 180 | 0.22 | 0.22<br>0.47<br>1.0 | 0.80 | 1200 | 0.045<br>0.046<br>0.048 | 5.5<br>5.3<br>5.2    | 0.010<br>0.005<br>0.003 | 24<br>31<br>34 | 65<br>87<br>101   |
|     | 0.47 | 0.47<br>1.0<br>2.2  | 1.9  | 2500 | 0.033<br>0.034<br>0.035 | 3.5<br>3.4<br>3.3    | 0.005<br>0.003<br>0.002 | 27<br>32<br>37 | 98<br>122<br>140  |
|     | 0.1  | 0.1<br>0.22<br>0.47 | 0.35 | 300  | 0.075<br>0.077<br>0.080 | 10.8<br>10.6<br>10.5 | 0.020<br>0.012<br>0.006 | 25<br>32<br>35 | 51<br>68<br>83    |
| 300 | 0.22 | 0.22<br>0.47<br>1.0 | 0.80 | 600  | 0.056<br>0.057<br>0.058 | 7.9<br>7.5<br>7.4    | 0.010<br>0.005<br>0.003 | 28<br>37<br>41 | 81<br>109<br>123  |
|     | 0.47 | 0.47<br>1.0<br>2.2  | 1.3  | 1200 | 0.044<br>0.046<br>0.047 | 5.3<br>5.2<br>5.1    | 0.005<br>0.003<br>0.002 | 34<br>42<br>48 | 125<br>152<br>174 |
|     | ·    |                     |      |      | ·                       | ·                    | T                       |                |                   |
|     |      | 0.047               | -    | 1800 | <b>–</b>                | 2.9                  | 0.060                   | 9              | 10                |

 $C_{g2}$ 

Ck

 $R_{g2}$ 

 $R_g$ 

 $R_k$ 

As Triode:

5879

|     |  |       |     |      |   |       | 1     |    |    |
|-----|--|-------|-----|------|---|-------|-------|----|----|
|     |  |       |     |      | 1 | Γ     | T     |    |    |
|     | 1  | 0.047 | -   | 1800 | - | 2.9   | 0.060 | 9  | 10 |
|     | 0.047  | 0.1   | -   | 2100 | - | 2.4   | 0.033 | 12 | 11 |
|     | l l  | 0.22  | 1   | 2200 | - | 2.3   | 0.016 | 14 | 21 |
|     |  | 0.1   | ı   | 3200 | - | 1.8   | 0.027 | 10 | 12 |
| 90  | 0.1  | 0.22  | _   | 3900 | - | 1.3   | 0.015 | 13 | 13 |
|     |  | 0.47  | -   | 4300 | - | 1.0   | 0.007 | 16 | 1: |
|     |  | 0.22  | 1   | 6200 | - | 0.87  | 0.015 | 12 | 13 |
|     | 0.22   | 0.47  | _   | 8100 | _ | 0.53  | 0.006 | 16 | 1. |
|     | *  | 1.00  | _   | 9000 | - | 0.49  | 0.003 | 19 | 14 |
|     | <del>                                     </del> | 0.047 |     | 1200 | _ | 3.5   | 0.063 | 21 | 1  |
|     | 0.047  | 0.047 | -   | 1600 |   | 2.6   | 0.003 | 29 | 13 |
|     | 0.047  |       | _   | 1800 | _ | 2.4   | 0.033 | 35 | 13 |
|     | $\Box$   | 0.22  |     | 1900 |   |       | 0.010 | 33 | 1. |
|     |  | 0.1   | -   | 2200 | - | 1.9   | 0.031 | 26 | 13 |
| 180 | 0.1  | 0.22  | -   | 2900 | - | 1.35  | 0.015 | 33 | 14 |
|     |  | 0.47  | -   | 3400 | - | 1.1   | 0.007 | 40 | 14 |
|     |  | 0.22  | -   | 4500 | - | 0.92  | 0.015 | 28 | 14 |
|     | 0.22   | 0.47  | -   | 6400 | - | 0.61  | 0.006 | 39 | 14 |
|     |  | 1.00  | -   | 8200 | - | 0.52  | 0.003 | 47 | 14 |
|     |  | 0.047 | -   | 1100 | - | 3.9   | 0.063 | 42 | 13 |
|     | 0.047  | 0.1   | _   | 1500 | _ | 2.8   | 0.033 | 65 | 13 |
|     |  | 0.22  | - 1 | 1700 | _ | 2.5   | 0.016 | 71 | 14 |
|     |  | 0.1   | _   | 2000 | _ | 2.1   | 0.032 | 45 | 15 |
| 300 | 0.1  | 0.22  | _   | 3400 | _ | 1.4   | 0.015 | 74 | 15 |
|     |  | 0.47  | _   | 3700 | - | l i.i | 0.007 | 83 | 15 |
|     |  | 0.22  | -   | 4300 | _ | 0.97  | 0.015 | 50 | 15 |
|     | 0.22   |       |     | 7000 |   | 0.62  | 0.007 | 88 | 15 |
|     | 0.22   | 0.47  | -   | 7200 | - | 0.63  | 0.007 | 94 |    |
|     |  | 1.00  | -   | 7400 | - | 0.63  | 0.003 | 94 | 15 |

| Ebb         | Rp    | Rg                   | R <sub>g2</sub> | Rk                      | Cg2         | Ck                   | С                         | Eo*            | V.G.           |
|-------------|-------|----------------------|-----------------|-------------------------|-------------|----------------------|---------------------------|----------------|----------------|
|             | 0.047 | 0.047<br>0.1<br>0.22 | 1 1 1           | 1870<br>2230<br>2500    | <u>-</u>    | 3.1<br>2.5<br>2.1    | 0.063<br>0.031<br>0.016   | 14<br>18<br>20 | 13<br>14<br>14 |
| 90          | 0.1   | 0.1<br>0.22<br>0.47  | -               | 3370<br>4100<br>4800    | -<br>-      | 1.8<br>1.3<br>1.1    | 0.034<br>0.015<br>0.006   | 15<br>20<br>23 | 14<br>14<br>15 |
|             | 0.22  | 0.22<br>0.47<br>1.00 | 1 1 1           | 7000<br>9100<br>10500   | -           | 0.80<br>0.65<br>0.60 | 0.013<br>0.007<br>0.004   | 16<br>22<br>25 | 14<br>14<br>15 |
|             | 0.047 | 0.047<br>0.1<br>0.22 | 1 1             | 1500<br>1860<br>2160    |             | 3.6<br>2.9<br>2.2    | 0.066<br>0.055<br>0.015   | 33<br>41<br>47 | 14<br>14<br>15 |
| 180         | 0.1   | 0.1<br>0.22<br>0.47  |                 | 2750<br>3550<br>4140    |             | 1.8<br>1.4<br>1.3    | 0.028<br>0.015<br>0.007   | 35<br>45<br>51 | 15<br>15<br>16 |
|             | 0.22  | 0.22<br>0.47<br>1.00 | -<br>-          | 5150<br>7000<br>7800    | -<br>-<br>- | 1.0<br>0.71<br>0.61  | 0.016<br>0.007<br>0.004   | 36<br>45<br>51 | 16<br>16<br>16 |
|             | 0.047 | 0.047<br>0.1<br>0.22 | -<br>-          | 1300<br>1580<br>1800    | -           | 3.6<br>3.0<br>2.5    | 0.061<br>0.032<br>0.015   | 59<br>73<br>83 | 14<br>15<br>16 |
| 30 <b>0</b> | 0.1   | 0.1<br>0.22<br>0.47  | -<br>-<br>-     | 2500<br>3130<br>3900    | -           | 1.9<br>1.4<br>1.2    | 0.031<br>0.014<br>0.0065  | 68<br>82<br>96 | 16<br>16<br>16 |
|             | 0.22  | 0.22<br>0.47<br>1.00 | -               | 4800<br>6500<br>7800    | -           | 0.95<br>0.69<br>0.58 | 0.015<br>0.0065<br>0.0035 | 68<br>85<br>96 | 16<br>16<br>16 |
|             | 0.1   | 0.1<br>0.22<br>0.47  | -               | 4400<br>4700<br>4800    | =           | 2.7<br>2.4<br>2.3    | 0.023<br>0.013<br>0.007   | 5<br>6<br>8    | 29<br>35<br>41 |
| 90          | 0.22  | 0.22<br>0.47<br>1.0  | -               | 7000<br>7400<br>7600    |             | 1.6<br>1.4<br>1.3    |                           | 6<br>9<br>11   | 39<br>45<br>48 |
|             | 0.47  | 0.47<br>1.0<br>2.2   | -               | 12000<br>13000<br>14000 | =           | 0.9<br>0.8<br>0.7    | 0.006<br>0.003<br>0.002   | 9<br>11<br>13  | 48<br>52<br>55 |
|             | 0.1   | 0.1<br>0.22<br>0.47  | -               | 1800<br>2000<br>2200    | =           | 4.0<br>3.5<br>3.1    | 0.025<br>0.013<br>0.006   | 18<br>25<br>32 | 40<br>47<br>52 |
| 180         | 0.22  | 0.22<br>0.47<br>1.0  | =               | 3000<br>3500<br>3900    | =           | 2.4<br>2.1<br>1.8    | 0.012<br>0.006<br>0.003   | 24<br>34<br>39 | 53<br>59<br>63 |
|             | 0.47  | 0.47<br>1.0<br>2.2   | =               | 5800<br>6700<br>7400    | =           | 1.3<br>1.1<br>1.0    | 0.006<br>0.003<br>0.002   | 30<br>39<br>45 | 62<br>66<br>68 |
|             | 0.1   | 0.1<br>0.22<br>0.47  |                 | 1300<br>1500<br>1700    | =           | 4.6<br>4.0<br>3.6    | 0.027<br>0.013<br>0.006   | 43<br>57<br>66 | 45<br>52<br>57 |
| 300         | 0.22  | 0.22<br>0.47<br>1.0  |                 | 2200<br>2800<br>3100    | =           | 3.0<br>2.3<br>2.1    | 0.013<br>0.006<br>0.003   | 54<br>69<br>79 | 59<br>65<br>68 |
|             | 0.47  | 0.47<br>1.0<br>2.2   | =               | 4300<br>5200<br>5900    | =           | 1.6<br>1.3<br>1.1    | 0.006<br>0.003<br>0.002   | 62<br>77<br>92 | 69<br>73<br>75 |

**8** 

6CG7' 6FQ7 6SN7GTB' 8CG7 12SN7GTA'

> See Circuit Diagram 1



3AV6 6AV6 6EU7 12AV6 12AX7A 20EZ7 7025

<sup>•</sup> One triode unit. • Peak volts.

4BQ7A\* 4BZ7\* 5BK7A\* 5BQ7A\* 6BK7B\* 6BQ7A\* 6BZ7\*

See Circuit Diagram 1

3BC5 3CB6 3CF6 4CB6 6AG5 6BC5 6CB6 6CB6A

| Ebb | $R_p$ | Rg                    | R <sub>g2</sub>         | Rk                   | Cg2                     | Ck                   | С                          | E <sub>o</sub> * | V.G               |
|-----|-------|-----------------------|-------------------------|----------------------|-------------------------|----------------------|----------------------------|------------------|-------------------|
| 90  | 0.047 | 0.047<br>0.10<br>0.22 | -                       | 1580<br>1760<br>1820 | =                       | 4.0<br>3.5<br>3.0    | 0.058<br>0.032<br>0.015    | 9<br>13<br>16    | 18<br>19<br>20    |
|     | 0.1   | 0.1<br>0.22<br>0.47   | -<br>-                  | 2920<br>3570<br>4020 | -                       | 2.1<br>1.7<br>1.4    | 0.029<br>0.015<br>0.0075   | 12<br>17<br>20   | 19<br>20<br>20    |
|     | 0.22  | 0.22<br>0.47<br>1.0   | -<br>-                  | 6040<br>7500<br>8800 | -<br>-<br>-             | 0.98<br>0.78<br>0.63 | 0.0135<br>0.0075<br>0.0036 | 16<br>21<br>25   | 19<br>20<br>20    |
|     | 0.047 | 0.047<br>0.1<br>0.22  | -                       | 694<br>817<br>905    | =                       | 6.0<br>4.4<br>4.0    | 0.062<br>0.032<br>0.0155   | 25<br>32<br>35   | 23<br>24<br>25    |
| 180 | 0.10  | 0.1<br>0.22<br>0.47   | -                       | 1596<br>1630<br>1860 | =                       | 2.80<br>2.30<br>2.00 | 0.030<br>0.0152<br>0.0073  | 30<br>32<br>38   | 23<br>24<br>24    |
|     | 0.22  | 0.22<br>0.47<br>1.0   | -<br>-                  | 3950<br>4500<br>5530 | -                       | 1.24<br>0.96<br>0.79 | 0.0150<br>0.0072<br>0.0038 | 35<br>41<br>49   | 22<br>23<br>23    |
|     | 0.047 | 0.047<br>0.1<br>0.22  |                         | 438<br>542<br>644    |                         | 6.70<br>5.50<br>4.30 | 0.062<br>0.032<br>0.016    | 38<br>48<br>57   | 26<br>27<br>27    |
| 300 | 0.10  | 0.10<br>0.22<br>0.47  |                         | 1009<br>1332<br>1609 | 111                     | 3.5<br>2.5<br>2.1    | 0.031<br>0.015<br>0.0074   | 42<br>56<br>64   | 25<br>26<br>25    |
|     | 0.22  | 0.22<br>0.47<br>1.0   | =                       | 2623<br>3900<br>4920 | -<br>-                  | 1.5<br>1.1<br>0.88   | 0.015<br>0.0073<br>0.0039  | 50<br>70<br>84   | 24<br>24<br>24    |
|     | 0.22  | 0.22<br>0.47<br>1.0   | 0.480<br>0.480<br>0.500 | 3800<br>3800<br>4400 | 0.046<br>0.049<br>0.045 | 5.5<br>5.5<br>5.3    | 0.0084<br>0.0054<br>0.0034 | 10<br>16<br>23   | 89<br>114<br>128  |
| 90  | 0.47  | 0.47<br>1.0<br>2.2    | 1.04<br>1.04<br>1.10    | 7200<br>7700<br>8400 | 0.033<br>0.033<br>0.031 | 2.9<br>2.8<br>2.6    | 0.0044<br>0.0029<br>0.0020 | 10<br>15<br>18   | 111<br>133<br>152 |
|     | 1.0   | 1.0<br>2.2            | 2.50<br>2.50            | 16000<br>18600       | 0.018<br>0.016          | 1.4<br>1.2           | 0.0023<br>0.0017           | 10<br>11         | 118<br>139        |

| 90  | 1    | 0.22 | 0.480 | 3800  | 0.046 | 5.5  | 0.0084 | 10 | 89  |
|-----|------|------|-------|-------|-------|------|--------|----|-----|
|     | 0.22 | 0.47 | 0.480 | 3800  | 0.049 | 5.5  | 0.0054 | 16 | 114 |
|     |      | 1.0  | 0.500 | 4400  | 0.045 | 5.3  | 0.0034 | 23 | 128 |
|     |      | 0.47 | 1.04  | 7200  | 0.033 | 2.9  | 0.0044 | 10 | 111 |
|     | 0.47 | 1.0  | 1.04  | 7700  | 0.033 | 2.8  | 0.0029 | 15 | 133 |
|     |      | 2.2  | 1.10  | 8400  | 0.031 | 2.6  | 0.0020 | 18 | 152 |
|     |      | 1.0  | 2.50  | 16000 | 0.018 | 1.4  | 0.0023 | 10 | 118 |
|     | 1.0  | 2.2  | 2.50  | 18600 | 0.016 | 1.2  | 0.0017 | 11 | 139 |
|     |      | 0.22 | 0.550 | 1600  | 0.072 | 9.5  | 0.0090 | 30 | 161 |
|     | 0.22 | 0.47 | 0.620 | 1800  | 0.062 | 8.5  | 0.0053 | 36 | 208 |
| 180 | 1    | 1.0  | 0.650 | 1900  | 0.062 | 8.5  | 0.0034 | 43 | 239 |
|     |      | 0.47 | 1.00  | 3400  | 0.059 | 6.0  | 0.0048 | 34 | 183 |
|     | 0.47 | 1.0  | 1.00  | 3500  | 0.059 | 6.0  | 0.0031 | 41 | 229 |
|     |      | 2.2  | 1.00  | 3800  | 0.059 | 5.8  | 0.0020 | 46 | 262 |
|     |      | 1.0  | 2.60  | 7300  | 0.029 | 2.7  | 0.0022 | 33 | 227 |
|     | 1.0  | 2.2  | 2.60  | 7400  | 0.029 | 2.7  | 0.0016 | 38 | 281 |
| 300 |      | 0.22 | 0.600 | 980   | 0.085 | 13.0 | 0.0085 | 51 | 223 |
|     | 0.22 | 0.47 | 0.680 | 1090  | 0.084 | 12.0 | 0.0055 | 64 | 288 |
|     |      | 1.0  | 0.700 | 1150  | 0.081 | 11.0 | 0.0033 | 74 | 334 |
|     |      | 0.47 | 1.25  | 2000  | 0.064 | 7.9  | 0.0045 | 52 | 285 |
|     | 0.47 | 1.0  | 1.34  | 2150  | 0.061 | 7.6  | 0.0029 | 67 | 363 |
|     |      | 2.2  | 1.53  | 2350  | 0.057 | 7.1  | 0.0019 | 79 | 416 |
|     |      | 1.0  | 2.60  | 4000  | 0.044 | 5.2  | 0.0023 | 51 | 334 |
|     | 1.0  | 2.2  | 3.00  | 4700  | 0.038 | 4.3  | 0.0015 | 69 | 427 |

<sup>•</sup> One triode unit.

<sup>\*</sup> Peak volts.

| Еьь | Rp          | Rg                   | R <sub>g2</sub>         | Rk                   | Cg2                     | Ck                   | С                          | E <sub>o</sub> * | V.G.              |
|-----|-------------|----------------------|-------------------------|----------------------|-------------------------|----------------------|----------------------------|------------------|-------------------|
| 90  | 0.22        | 0.22<br>0.47<br>1.0  | 0.560<br>0.600<br>0.640 | 3700<br>3900<br>4200 | 0.046<br>0.043<br>0.039 | 4.50<br>4.30<br>4.00 | 0.0090<br>0.0055<br>0.0033 | 12<br>17<br>19   | 73<br>95<br>109   |
|     | 0.47        | 0.47<br>1.0<br>2.2   | 0.870<br>0.980<br>1.00  | 6000<br>6700<br>6700 | 0.036<br>0.044<br>0.043 | 2.70<br>3.00<br>2.80 | 0.0046<br>0.0030<br>0.0020 | 16<br>22<br>25   | 95<br>113<br>131  |
|     | 1.0         | 1.0<br>2.2           | 2.00<br>2.20            | 12200<br>12800       | 0.021<br>0.024          | 1.44<br>1.74         | 0.0028<br>0.0016           | 15<br>21         | 119<br>167        |
| 180 | 0.22        | 0.22<br>0.47<br>1.0  | 0.530<br>0.600<br>0.650 | 1570<br>1730<br>1820 | 0.069<br>0.064<br>0.061 | 7.50<br>7.40<br>7.30 | 0.0088<br>0.0064<br>0.0034 | 32<br>38<br>45   | 82<br>164<br>190  |
|     | 0.47        | 0.47<br>1.0<br>2.2   | 1.12<br>1.40<br>1.57    | 3200<br>3500<br>3740 | 0.053<br>0.042<br>0.040 | 5.30<br>5.10<br>5.40 | 0.0046<br>0.0028<br>0.0019 | 35<br>40<br>45   | 147<br>209<br>250 |
|     | 1.0         | 1.0<br>2.2           | 2.50<br>3.40            | 6500<br>7500         | 0.039<br>0.026          | 2.80<br>2.30         | 0.0024<br>0.0015           | 34<br>39         | 179<br>277        |
| 300 | 0.22        | 0.22<br>0.47<br>1.0  | 0.600<br>0.670<br>0.720 | 9200<br>1010<br>1100 | 0.086<br>0.076<br>0.076 | 11.2<br>10.5<br>10.0 | 0.0085<br>0.0052<br>0.0033 | 52<br>66<br>77   | 182<br>236<br>257 |
|     | 0.47        | 0.47<br>1.0<br>2.2   | 1.25<br>1.43<br>1.45    | 1950<br>3210<br>2200 | 0.060<br>0.053<br>0.055 | 7.0<br>6.4<br>6.3    | 0.0044<br>0.0027<br>0.0019 | 41<br>72<br>82   | 221<br>296<br>345 |
|     | 1.0         | 1.0<br>2.2           | 3.00<br>3.30            | 4100<br>4340         | 0.040<br>0.037          | 4.2<br>3.6           | 0.0022<br>0.0016           | 57<br>74         | 295<br>378        |
| 90  | 0.047       | 0.047<br>0.1<br>0.22 |                         | 1292<br>1401<br>1470 | =                       | 3.3<br>2.8<br>2.4    | 0.060<br>0.032<br>0.016    | 8<br>10<br>11    | 12<br>13<br>13    |
|     | 0.10        | 0.1<br>0.22<br>0.47  |                         | 2630<br>3090<br>3440 | =                       | 1.60<br>1.24<br>1.10 | 0.029<br>0.015<br>0.008    | 9<br>12<br>14    | 13<br>13<br>14    |
|     | 0.22        | 0.22<br>0.47<br>1.0  |                         | 6550<br>8270<br>9130 | =                       | 0.70<br>0.51<br>0.44 | 0.015<br>0.0077<br>0.0045  | 12<br>16<br>18   | 12<br>12<br>12    |
| 180 | 0.047       | 0.047<br>0.1<br>0.22 | 111                     | 723<br>836<br>948    | -                       | 4.0<br>3.5<br>2.9    | 0.061<br>0.032<br>0.016    | 16<br>20<br>24   | 14<br>14<br>15    |
|     | 0.10        | 0.1<br>0.22<br>0.47  | 111                     | 1543<br>2002<br>2522 | -                       | 2.0<br>1.6<br>1.2    | 0.031<br>0.016<br>0.0082   | 17<br>24<br>30   | 14<br>14<br>13    |
|     | 0.22        | 0.22<br>0.47<br>1.0  |                         | 4390<br>6122<br>8060 | =                       | 0.79<br>0.57<br>0.47 | 0.015<br>0.0078<br>0.0046  | 24<br>33<br>41   | 13<br>12<br>12    |
| 300 | 0.047       | 0.047<br>0.1<br>0.22 |                         | 534<br>726<br>840    | =                       | 4.0<br>3.6<br>3.0    | 0.061<br>0.031<br>0.015    | 27<br>38<br>44   | 15<br>15<br>15    |
|     | 0.10        | 0.1<br>0.22<br>0.47  | 111                     | 1117<br>1613<br>2043 | -<br>-<br>-             | 2.3<br>1.7<br>1.31   | 0.031<br>0.0155<br>0.0078  | 26<br>41<br>51   | 15<br>14<br>14    |
|     | 0.22<br>1.0 | 0.22<br>0.47         |                         | 3133<br>4480<br>4930 | -<br>-                  | 0.93<br>0.69<br>0.56 | 0.015<br>0.0079<br>0.0045  | 36<br>51<br>55   | 13<br>13<br>13    |

(12)

7199

Pentode Unit

See Circuit Diagram 3


**13** 

7199


Triode Unit


<sup>\*</sup> Peak volts.


## Outlines





-1-
























#### Outlines









# Circuits

THE circuits included in this Manual illustrate some of the more important applications of RCA receiving tubes; they are not necessarily examples of commercial practice. These circuits have been conservatively designed and are capable of excellent performance. Electrical specifications are given for circuit components to assist those interested in home construction. Layouts and mechanical details are omitted because they vary widely with the requirements of individual set builders and with the sizes and shapes of the components employed.

Circuits designed for operation from both ac and dc voltage supplies should be installed in non-metallic cabinets or properly insulated from metallic cabinets. Potentiometer shafts and switches should make use of insulated (plastic) knobs. In practical use, no metallic part of an "ac/dc" chassis should be exposed to touch, accidental or otherwise. When such circuits are tested outside of their cabinets, a line isolation transformer such as the RCA WP-25A Isotap should be used.

Performance of these circuits depends as much on the quality of the components selected and the care employed in layout and construction as on the circuits themselves. Good signal reproduction from receivers and amplifiers requires the use of good-quality speakers, transformers, chokes, and input sources (microphones, phonograph pickups, etc).


Coils for the receiver circuits may be purchased at local parts dealers by specifying the characteristics required: for rf coils, the circuit position (antenna or interstage), tuning range desired, and tuning capacitances employed; for if coils or transformers, the intermediate frequency, circuit position (1st if, 2nd if, etc.), and, in some cases, the associated tube types; for oscillator coils, the receiver tuning range, the intermediate frequency, the type of converter tube, and the type of winding used (tapped or transformer-coupled).

The voltage ratings specified for capacitors are the minimum dc working voltages required. Paper, mica, or ceramic capacitors having higher voltage ratings than those specified may be used except insofar as the physical sizes of such capacitors may affect equipment layout. However, if electrolytic capacitors having substantially higher voltage ratings than those specified are used, they may not "form" completely at the operating voltage, with the result that the effective capacitances of such units may be below their rated value. The wattage ratings specified for resistors assume methods of construction that provide adequate ventilation; compact installations having poor ventilation may require resistors of higher wattage ratings.

Circuits which work at very high frequencies or which are required to handle very wide bandwidths demand more than ordinary skill and experience in construction. Placement of component parts is quite critical and may require considerable experimentation. All rf leads to components including bypass capacitors must be kept short and must be properly dressed to minimize undesirable coupling and capacitance effects. Correct circuit alignment and oscillator tracking may require the use of a cathode-ray oscilloscope, a high-impedance vacuum-tube voltmeter, and a signal generator capable of supplying a properly modulated signal at the appropriate frequencies. Unless the builder has had considerable experience with broadband, high-frequency circuits, he should not undertake the construction of such circuits.

(23-1)

#### PORTABLE BATTERY-OPERATED SUPERHETERODYNE RECEIVER



C<sub>1</sub> C<sub>4</sub> = Ganged tuning capacitors:  $C_1$ , 10-274 pf;  $C_4$ , 7.5-122.5 pf  $C_5$  = Trimmer capacitors,  $C_2$   $C_5 =$ 

2-15 pf  $C_0 = 56$  pf, ceramic  $C_0 = 56$  pf, ceramic  $C_0 = 56$  pf, ceramic capacitors for if trans-

formers  $C_8 = 0.05 \mu f$ , paper, 50 v.  $C_9 C_{15} = 0.02 \mu f$ , paper,

100 v.  $C_{12} = 82$  pf, ceramic  $C_{13}$   $C_{16} = 0.002$   $\mu$ f, paper, 150 v.

 $C_{14} = 33$  pf, ceramic

 $C_{17} = 10 \mu f$ , electrolytic,

100 v.  $C_{18} = 0.0022 \mu f$ , paper, 600 v. L<sub>1</sub> = Loop antenna or ferriterod antenna, 540-1600 Kc (with specified values of capacitance for  $C_1$  and  $C_2$ )  $R_1 = 0.1$  megohm, 0.25 watt  $R_2 = 15000$  ohms, 0.25 watt  $R_3 = 3.3$  megohms, 0.25 watt  $R_4 = 68000$  ohms, 0.25 watt  $R_5 = \text{Volume control, poten-}$ tiometer, 2 megohms

 $R_0 = 10$  megohms, 0.25 watt  $R_7 = 4.7$  megohms, 0.25 watt  $R_8 R_9 = 1$  megohm, 0.25 watt  $R_{10} = 390$  ohms, 0.25 watt  $S_1 = Switch$ , double-pole. single-throw


T<sub>1</sub> = Oscillator coil for use with tuning capacitor of 7.5-122.5 µµf, and 455 Kc

if transformer  $T_2 T_3 = Intermediate$ frequency transformers, 455 Kc (permeability-tuned

type may be used) T<sub>4</sub> = Output transformer for matching impedance of voice coil to 10000-ohm tube load

(23-2)

#### PORTABLE 3-WAY SUPERHETERODYNE RECEIVER



 $C_1$   $C_4$   $C_8$  = Ganged tuning capacitors, 20-450 pf  $C_2$   $C_5$   $C_7$  = Trimmer capacitors, 4-30 pf  $C_3$   $C_1$   $C_1$   $C_2$   $C_2$   $C_3$   $C_4$   $C_5$   $C_6$   $C_7$  = 100 pf, ceramic  $C_6 = 82$  pf, ceramic  $C_9 = 560$  pf, ceramic  $C_{11}$   $C_{12}$   $C_{13}$   $C_{16} = Trimmer$ capacitors for if transformers  $C_{13} = 0.01 \mu f$ , paper 400 v.  $C_{18} C_{21} = 0.002 \mu f$ , paper,  $\begin{array}{l} 400 \text{ v.} \\ C_{19} = 270 \text{ pf, ceramic} \\ C_{20} = 0.02 \mu\text{f, paper, } 400 \text{ v.} \\ C_{22} C_{22} = 0.005 \mu\text{f, paper,} \end{array}$ 400 v.  $C_{23} = 0.1 \mu f$ , paper, 400 v.  $C_{24} = 0.05 \mu f$ , paper, 200 v.  $C_{25} = 0.05 \mu f$ , paper, 50 v.  $C_{26} C_{27} C_{28} = 0.05 \mu f$ , paper 400 v  $C_{29} = 40 \mu f$ , electrolytic, 25 v.  $C_{50} = 160 \mu f$ , electrolytic, 25 v.  $C_{51} C_{52} = 20 \mu f$ , electrolytic,

150 v.

 $L_1 = Loop$  antenna or ferriterod antenna, 540-1600 Kc (with specified values of capacitance for C<sub>1</sub> and C<sub>2</sub>)

 $R_1 R_2 R_{11} = 4.7 \text{ megohms,}$ 0.25 watt  $R_3 = 2.2 \text{ megohms, } 0.25 \text{ watt}$  $R_4 = 0.1$  megohm, 0.25 watt R<sub>5</sub> = 5.6 megohms, 0.25 watt R<sub>6</sub> = 27000 ohms, 0.25 watt R<sub>7</sub> = 68000 ohms, 0.25 watt

R<sub>9</sub> = 3.3 megohms, 0.25 watt R<sub>9</sub> = Volume control, potentiometer, 1 megohm

 $R_{10} = 10$  megohms, 0.25 watt  $R_{12} = 0.22$  megohm, 0.25 watt  $R_{13} = 1$  megohm 0.25 watt  $R_{13} \equiv 1$  megohm, 0.25 watt R14 R16 = 1800 ohms, 0.25 watt

 $R_{15} = 0.22$  megohm, 0.5 watt

 $R_{17} = 1000 \text{ ohms}, 0.25 \text{ watt}$  $R_{18} = 2700 \text{ ohms}, 0.25 \text{ watt}$  $R_{19} = 1500 \text{ ohms}, 0.25 \text{ watt}$  $R_{20} = 1800 \text{ ohms}, 10 \text{ watts}$  $R_{21} = 2300 \text{ ohms}, 10 \text{ watts}$ 

 $S_1 = Switch, 4$ -pole doublethrow  $S_2 = Switch, double-pole,$ single-throw

 $T_1 =$ RF transformer, 540-


11 = RF transformer, 340-1600 Kc T<sub>2</sub> = Oscillator coil for use with a 560-μμ padder, 20-450 μμ tuning capacitor, and 455 Kc if transformer

Intermediate-fre-T: T: = quency transformers, 455 Kc (permeability-tuned type may be used)

Ts = Output transformer for matching impedance of voice coil to 10000-ohm tube load

(23-3)

## AC/DC SUPERHETERODYNE RECEIVER



C<sub>1</sub> C<sub>5</sub> = Ganged tuning capacitors; C<sub>1</sub>, 10-365 pf; C<sub>5</sub>, 7-115 pf
C<sub>2</sub> = Trimmer capacitor,

4-30 pf

4-30 pi  $C_3 = 0.05 \mu f$ , paper, 50 v.  $C_4 = 0.1 \mu f$ , paper, 400 v.  $C_6 = Trimmer \ capacitor$ , 2-17 pf  $C_7 = 56 \ pf$ , ceramic  $C_8 = 30 \mu f$ , electrolytic,

 $C_8 = 30$  150 v.

 $C_9$   $C_{10} = 150$  pf, ceramic  $C_{11}$   $C_{14} = 0.02$   $\mu$ f, paper, 400 v.

 $C_{12} = 0.002 \, \mu f$ , paper, 400 v.  $C_{13} = 330 \text{ pf, mica}$ 

 $C_{15} = 0.05 \mu f$ , paper, 400 v.  $C_{16} = 50 \mu f$ , electrolytic,

150 v. L = Loop antenna or ferriterod antenna, 540-1600 Kc with specified values of capacitance for C<sub>1</sub> and C<sub>2</sub>)

pachance for C1 and C2)  $R_1 = 0.22$  megohm, 0.5 watt  $R_2 = 33000$  ohms, 0.5 watt  $R_3 = 100$  ohms, 0.5 watt  $R_4 = 3.3$  megohms, 0.5 watt  $R_5 = 47000$  ohms, 0.5 watt

R<sub>6</sub> = Volume control, potentiometer, 0.5 megohm  $R_7 = 4.7$  megohms, 0.5 watt  $R_8 = 0.47$  megohm,

0.5 watt

 $R_{10}=150$  ohms, 0.5 watt  $R_{11}=1200$  ohms, 1 watt  $T_1=0$  scillator coil for use with 7-115- $\mu\mu$ f tuning capacitor and 455-Kc intermediate-frequency transformer

 $T_2 T_3 = Intermediate$ frequency transformers, 455 Kc (permeability-tuned type may be used)


T<sub>4</sub> = Output transformer for

matching impedance of voice coil to 2500-ohm tube load

NOTE 1: The following tube types are recommended for a 100-ma-heater tube complement: 18FX6A converter, 18FW6A if amplifier, 18FY6A detector and audio amplifier, 34GD5A power amplifier, and 36AM3B rectifier.

(23-4)

#### AM/FM RECEIVER



NOTE: See general considerations for construction of high-frequency and broadband circuits on page 576.

# (23-4)

## AM/FM RECEIVER

 $C_1 = Part of R_1$   $C_2 = Part of R_2$ C: = 36 pf, ceramic, 500 v. C<sub>1</sub> C<sub>11</sub> = Ganged tuning capacitors, tune L1 and T2 pacitors. Une 1; and 1; to 88-108 Mc
Cs. C12 = Trimmer capacitors, 1-7 pf
C6 Cs = 6.8 pf, ceramic, 500 v., N220
C7 C16 C19 = 1000 pf, feed-through, 500 v.  $C_8 = 11$  pf, ceramic, 500 v.  $C_{10} = 68$  pf, ceramic, 500 v.  $C_{13} = 21$  pf, ceramic, 500 v.  $C_{13} = 500$  pf, feedthrough, 500 v  $C_{15} = 0.22 \mu f$ , ceramic disc, 500 v.  $C_{17}$   $C_{54}$   $C_{55} = 2000$  pf, feedthrough. 500 v.  $C_{18} = 0.15 \mu f$ , paper. 200 v.  $C_{20}$   $C_{21} = 2$  pf, feedthrough, 500 v. C<sub>22</sub> = Tuning capacitor; value, with cable capacitance, tunes To 10.7 Mc

Con = 4700 pf, ceramic, 500 v.  $C_{24} C_{20} = 2700 \text{ pf. ceramic.}$ 500 v. C25 C27 = Part of Ta C28 C28 = Part of T5  $C_{29} C_{32} = 100 \text{ pf, ceramic,}$ 500 v., NPO Cm Cm = Part of To C31 C19 = 1000 pf, ceramic, 500 v.  $C_{35}$   $C_{47}$   $C_{51}$   $C_{50} = 0.01 \mu f$ , ceramic, 500 v.

 $C_{26} C_{27} = 330 \text{ pf, mica,}$ 500 v  $C_{38} = 0.01 \mu f$ , paper, 200 v.  $C_{19} = 2 \mu f$ , electrolytic, 50 v.  $C_{40} = 5600 \text{ pf}$ , ceramic, 500 v.  $C_{11} = 0.1 \mu f$ , paper, 200 v.  $C_{12} = 0.022 \mu f$ , paper, 200 v.  $C_{13} C_{15} = Ganged tuning$ capacitors, tune Ts to 540-1650 Kc Trimmer capaci-C14 C16 = tors, 12 pf  $C_{18}$   $C_{50}$  = Part of T<sub>9</sub>  $C_{52}$  = 50  $\mu$ f, electrolytic, 150 v.  $C_{53} = 0.047 \mu f$ , paper, 400 v.  $C_{57} = 80 \mu f$ , electrolytic, 150 v.  $C_{59} = 0.1 \mu f$ , ceramic. 500 v.  $CR_1 = AFC$  crystal diode  $CR_2 = Silicon$  rectifier, IN3756  $L_1 = RF$  coil  $L_2 = Antenna$ , air loop with back cover  $L_2 = 1 \mu f$ , rf choke  $R_1 = 0.5 \text{ megohm}$ (includes C1)  $R_2 = 0.5 \text{ megohm}$ (includes  $C_2$ )  $R_3 = 2200$  ohms, 0.5 watt  $R_4 = 1200$  ohms, 0.5 watt  $R_3 R_{19} = 33000 \text{ ohms},$ 0.5 watt  $R_6 R_{18} = 47000 \text{ ohms},$ 0.5 watt  $R_7 R_{27} R_{29} = 0.47$  megohm, 0.5 watt  $R_8 = 3900$  ohms, 0.5 watt

 $R_9 R_{32} = 22000 \text{ ohms},$ 0.5 watt R<sub>10</sub> R<sub>33</sub> = 1 megohm, 0.5 watt 68 ohms, 0.5 watt R11 R17 =  $R_{12} = 4700$  ohms, 0.5 watt  $R_{13} = 0.33$  megohm, 0.5 watt  $R_{14} = 220$  ohms, 0.5 watt  $R_{15} R_{23} = 1000$  ohms, 0.5 watt
R<sub>10</sub> = 3.3 megohms, 0.5 watt
R<sub>20</sub> = 4.7 megohms, 0.5 watt R<sub>21</sub> = Volume-control potentiometer, 1 megohm, includes S<sub>2</sub>


R<sub>22</sub> = 39000 ohms, 0.5 watt

R<sub>24</sub> = 820 ohms, 0.5 watt  $R_{25} R_{26} = 6800$  ohms, 0.5 watt  $R_{28} = 1500$  ohms, 0.5 watt  $R_{30} = 150$  ohms, 0.5 watt  $R_{31} = 560$  ohms, 2 watts  $R_{34} = 220$  ohms, 0.5 watt  $R_{35} = 100$  ohms, wire-wound, 4 watts  $R_{30} = 0.22$  megohm, 0.5 watt S<sub>1</sub> = Switch, slide, AM-FM-AFC S<sub>2</sub> = Interlock switch S<sub>3</sub> = Switch, ON-OFF, part of R21  $T_1 = Antenna$  transformer  $T_2 = Oscillator$  transformer  $T_3$   $T_4$   $T_5$   $T_9 = IF$  transformers T<sub>6</sub> = Ratio-detector transformer  $T_7 = Audio output trans$ former  $T_8 = Oscillator coil$ 

\* On FM, the ac line serves as an FM antenna by means of a special line cord having a third wire which is not physically connected to the line.

# (23-5)

# CODE-PRACTICE OSCILLATOR




C<sub>1</sub> C<sub>2</sub> = 20  $\mu$ f, electrolytic, 150 v. C<sub>3</sub> = 0.001  $\mu$ f, paper, 200 v. C<sub>4</sub> = 0.03  $\mu$ f, paper, 200 v. F = ½ ampere  $\begin{array}{l} J = \text{Input jack for key} \\ R_1 = 1500 \text{ ohms, 1 watt} \\ R_2 = \text{Potentiometer, 0.1} \\ \text{megohm, 0.5 watt} \end{array}$ 

T<sub>1</sub> = Power transformer, 125 volts rms, 15 ma; 6.3 volts, 0.6 ampere
T<sub>2</sub> = Output transformer, universal

NOTE: Select any two terminals of secondary of T<sub>2</sub> to give desired tone.

(23-6)

#### CITIZENS-BAND TRANSCEIVER



NOTE: See general considerations for construction of high-frequency and broad-band circuits on page 576.

#### CITIZENS-BAND TRANSCEIVER (Cont'd) (23-6)

C1 = 470 pf, ceramic, 500 v.
C2 = 3.3 pf, ceramic, 500 v.
C3 C5 C7 C9 C10 C13 C14 10
C39 C43 C49 C41 = 1000 pf, ceramic, 500 v.
C4 C5 = 5 pf, ceramic, 500 v.
C1 = 18 pf, mica, 500 v.
C1 = 24 pf, mica, 500 v.
C1 = 24 pf, mica, 500 v.
C1 = 50 µf, ceramic, 500 v.
C1 = 8 pf, ceramic, 500 v.
C1 = 8 pf, ceramic, 500 v.
C1 = 8 pf, ceramic, 500 v. C<sub>18</sub> = 1 N750 8 pf, ceramic, 500 v.,  $C_{19}$   $C_{17}$   $C_{87}$   $C_{24}$   $C_{85}$   $C_{36}$   $C_{41}$   $C_{4}$   $C_{17}$   $C_{55}$   $C_{58}$  = 0.01  $\mu$ f,  $C_{11}$   $C_{12}$   $C_{23}$   $C_{23}$   $C_{24}$   $C_{24}$   $C_{24}$   $C_{25}$   $C_{24}$   $C_{25}$   $C_{25}$   $C_{24}$   $C_{25}$   N750  $C_{20} = 56$  pf, ceramic, 500 v. N330 N330
C<sub>27</sub> = 0.015 µf, paper, 400 v.
C<sub>28</sub> = Variable, 2.3-15 pf.
C<sub>29</sub> = Variable, 1.5-10 pf,
ceramic, 600 v.
C<sub>30</sub> C<sub>32</sub> = Part of T<sub>3</sub>
C<sub>37</sub> C<sub>38</sub> = Part of T<sub>4</sub>
C<sub>40</sub> C<sub>46</sub> C<sub>53</sub> C<sub>54</sub> C<sub>59</sub> = 5000 pf,
ceramic, 500 v.
C<sub>32</sub> C<sub>51</sub> = 100 pf, ceramic,
500 v.
C<sub>45</sub> C<sub>46</sub> = Part of T<sub>5</sub>  $C_{45}$   $C_{46}$  = Part of  $T_5$   $C_{50}$  = 3300 pf, paper, 600 v.

 $C_1 = 470$  pf, ceramic, 500 v.

C<sub>52</sub> C<sub>54</sub> = 200 pf, mica, 500 v. C<sub>57</sub> = 10  $\mu$ f, electrolytic, 50 v. C<sub>80</sub> = 150 pf, mica, 500 v. CR = Diode, 1N34 L<sub>1</sub> = Oscillator coil, transmitter, RCA stock No. 226183 or equiv.

L<sub>2</sub> L<sub>4</sub> = 500 \(\mu f\), rf choke

L<sub>3</sub> = Power-amplifier coil, RCA stock No.226184 or equiv. = 2nd-harmonic trap, RCA stock No. 226187 or Roy Stock No. 220137 equiv.

R1 R2 R15 R16 R20 = 47000 ohms, 0.5 watt

R3 = 56 ohms, 0.5 watt

R4 R11 R20 = 27000 ohms, 0.5 watt R<sub>5</sub> R<sub>18</sub> = 56000 ohms, 0.5 watt 0.5 watt  $R_0 = 5600$  ohms, 1 watt  $R_7 = 1000$  ohms, 2 watts  $R_8 = 0.18$  megohm, 0.5 watt  $R_9 = 27000$  ohms, 1 watt  $R_{12} = 4700$  ohms, 1 watt  $R_{13} = 10$  megohms, 0.5 watt

0.5 watt R<sub>14</sub> R<sub>28</sub> R<sub>36</sub> = 2.2 megohms, 0.5 watt R<sub>16</sub> = 39 ohms, 0.5 watt R<sub>17</sub> = 82 ohms, 0.5 watt R<sub>18</sub> = 15000 ohms, 1 watt R<sub>22</sub> R<sub>34</sub> = 1.5 megohms.

0.5 watt  $R_{25}$   $R_{38}$   $R_{45}$   $R_{47}$  = 0.47 megohm, 0.5 watt  $R_{26}$  = 150 ohms, 0.5 watt  $R_{27}$   $R_{30} = 0.1$  megohm, 0.5 watt  $R_{29} = 0.68$  megohm, 0.5 watt  $R_{31} = 27000$  ohms, 2 watts  $R_{32} = 68000$  ohms, 0.5 watt  $\kappa_{82} = 68000$  ohms, 0.5 watt  $R_{23} = 3$  megohms, 0.25 watt  $R_{37} = 0.33$  megohm, 0.5 watt  $R_{89} = 1$  megohm, 0.5 watt  $R_{40} = 2$  megohm, 0.5 watt  $R_{41} = 0.22$  megohm, 0.5 watt  $R_{10} = 330$  ohms, 1 watt  $R_{16} = 8.2$  megohms, 0.5 watt

R₀ = 8.2 megohms, 0.5 watt
 S₁ = Rotary switch, channel
 select transmit, RCA stock
 No. 226189 or equiv.
 S₂ = Rotary switch, channel
 select receive, RCA stock
 No. 226189 or equiv.
 T₁ = RF interstage transformer, RCA stock
 No. 226191 or equiv.
 T₂ = Oscillator coil, receiver.

T<sub>2</sub> = Oscillator coil, receiver, RCA stock No. 226192 or

equiv.


T<sub>3</sub> T<sub>4</sub> T<sub>5</sub> = IF transformers,
RCA stock No. 226193 or

equiv. T<sub>6</sub> = Output and modulation transformer, RCA stock No. 226194 or equiv.

(23-7)

## PREAMPLIFIER FOR AMATEUR RECEIVER FOR 10-METER (30-MEGACYCLE) BAND

Power Gain, 25 to 35 db




C<sub>1</sub> C<sub>7</sub> = 5 pf, 500 v., mica C<sub>2</sub> C<sub>3</sub> C<sub>4</sub> C<sub>5</sub> C<sub>6</sub> C<sub>8</sub> C<sub>9</sub> = 0.001  $\mu$ f, 500 v., ceramic L<sub>1</sub> L<sub>2</sub> = 18 turns of No.32 Enam. copper wire wound on 1/4" I.D. slug-tuned form. L<sub>1</sub> tuned to 32 Mc; L<sub>2</sub> to 29.5 Mc. Input and output link, 1½ turns. Input and output impedance, 75 ohms

 $R_1 R_2 = 100$  ohms, 0.5 watt  $R_3 = 0.47$  megohm, 0.5 watt  $R_4 = 1000$  ohms, 0.5 watt

# (23-8)

#### FM TUNER



equiv.

C<sub>4</sub> C<sub>18</sub> C<sub>16</sub> = Trimmer capacitors, 1-7.5 pf, ceramic, 400 v.

 $C_5 C_{15} C_{27} = 10 \text{ pf, ceramic,}$ 400 v.

 $C_{21} = 1000$  pf, ceramic. 400 v.

 $C_9 C_{28} = 2000 \text{ pf, feedthrough,}$ 400 v. C<sub>14</sub> C<sub>25</sub> = 2000 pf, ceramic, 400 v.

 $C_{17}$   $C_{18} = 22$  pf, ceramic,

C17 C18 = 22  $p_1$ , 400 v. C19 = 2.2 pf, ceramic, 400 v. C20 = 47 pf. ceramic, 400 v. C22 C28 C24 C37 = 0.01  $\mu$ f, disc,

secondary winding of T<sub>2</sub>; value, with cable capaci-tance, tunes input to 10.7 Mc

L<sub>1</sub> = 12 turns No.22 Enam. close-wound on ½-inch coil form; slug 36-inch Moldite No.5101 ferrite or equiv. L<sub>2</sub> = 5 turns No.22 Enam.

close-wound on 1/4-inch coil form

L<sub>3</sub> = 4  $\mu$ f, rf choke, Miller No.70F396A1 or equiv. L<sub>4</sub> = 3 turns No.16 Enam.

double-spaced on 1/4-inch coil form; slug 3/8-inch Moldite No.5101 ferrite or equiv.

equivalent physical size L<sub>8</sub> L<sub>9</sub> = 1 μh, rf choke; 25 turns No.24 Enam. close-wound on a 0.47-megohm, 1-watt Allen-Bradley resistor or resistor of equivalent physical size

 $R_1 = 0.1$  megohm, 0.5 watt  $R_2 R_3 = 47000$  ohms, 0.5 watt  $R_4 R_6 = 0.47 \text{ megohm}, 0.5$ watt

R<sub>5</sub> = 5 ohms, 0.5 watt R<sub>7</sub> = 22000 ohms, 0.5 watt Rs R<sub>9</sub> = 2200 ohms, 0.5 watt R<sub>10</sub> = 4700 ohms, 0.5 watt R<sub>11</sub> = 15000 ohms, 1 watt

S = AM/FM range switch; open position is used for local stations, closed position for distant stations

# (23-8)

## FM TUNER (Cont'd)

T<sub>1</sub> = RF transformer; primary 2 turns No.32 wire with type B nylon insulation, Alpha No.1860 or equiv., center-tapper: secondary 3 turns


No.16 Enam. doublespaced on 1/4-inch coil form; slug 3/8-inch Moldite No. 5101 ferrite or equiv.

T<sub>2</sub> = 10.7-Mc if transformer; J. W. Miller type 1451 (tuning capacitor in secondary should be removed and replaced by C83)

\* A metal shield should be provided between grid and plate terminals on the 6CW4 socket. • If an AFC network is included,  $C_{18}$  must be decreased by the capacitance loading the oscillator tank.

NOTE: See general considerations for construction of high-frequency and broad-band circuits on page 576.

#### THREE-STAGE IF AMPLIFIER/LIMITER AND DETECTOR (23-9)



400 v  $C_0$   $C_{16}$   $C_{10}$   $C_{20}$   $C_{21}$  = 0.01  $\mu$ f, ceramic disc, 400 v.  $C_{10}$  = 1500 pf, ceramic disc, 400 v.

 $C_{11} = Part \text{ of } T_{11}$   $C_{12} C_{13} C_{15} = 330 \text{ pf},$ ceramic disc, 400 v.  $C_{14} = 100$  pf, ceramic disc, 400 v.  $C_{16} = 2 \mu f$ , electrolytic,

400 v.

 $L_1 L_2 L_3 = 1 \mu h$  $R_1 R_2 = 68 \text{ ohms}, 0.5 \text{ watt} R_2 R_4 R_{10} = 3300 \text{ ohms},$ 0.5 watt

 $R_5 = 0.1$  megohm, 0.5 watt  $R_6 R_{10} = 100$  ohms, 0.5 watt  $R_7 = 15000$  ohms, 0.5 watt  $R_8 = 22000$  ohms, 0.5 watt

 $R_0 = 2200$  ohms, 3 watts  $R_{11} = 1200$  ohms, 0.5 watt  $R_{12} = 390$  ohms, 0.5 watt  $R_{14} R_{15} = 6800 \text{ ohms}, 0.5 \text{ watt}$ 


 $R_{16} = 68000$  ohms, 0.5 watt  $\Gamma_1$   $\Gamma_2 = IF$  transformers, 10.7 Mc. T<sub>3</sub> = Ratio-detector

transformer

NOTE: Tube shields may be required if regeneration is encountered. See general considerations for construction of high-frequency and broad-band circuits on page 576.

(23-10)

#### FM STEREO MULTIPLEX ADAPTER



C<sub>1</sub> C<sub>8</sub> C<sub>0</sub> C<sub>12</sub> C<sub>17</sub> C<sub>19</sub> C<sub>20</sub> = 0.01  $\mu$ f, ceramic, 500 v. C<sub>2</sub> C<sub>16</sub> = 2200 pf, film, 500 v., N150 C<sub>4</sub> C<sub>6</sub> C<sub>7</sub> = 270 pf, ceramic,  $\frac{1}{2}$  C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub>10</sub> C<sub></sub>  $c_1 = c_2 = c_3 = c_4 = c_5$ 450 v.  $^{430}$  V.  $^{12}$  V

N150 CR1 CR2 CR5 CR4 = Crystal

diodes. RCA stock No.

11207 or equiv. L<sub>1</sub> L<sub>2</sub> = Coil, 67-Kc trap. RCA stock No. 111047 or equiv.

E = Coil, 38-Kc bandpass, RCA stock No. 11048 or equiv.

 $R_1 = 0.56$  megohm. 0.5 watt  $R_2 = 1500$  ohms, 0.5 watt  $R_3 = 15000$  ohms, 0.5 watt  $R_4 R_9 R_{12} = 22000 \text{ ohms,}$  $R_5 R_6 R_7 R_8 = 0.1$  megohm,

0.5 watt  $R_{10} = 68000$  ohms, 0.5 watt  $R_{11} = 3.9$  megohms. 0.5 watt  $R_{12} = 1$  megohm, 0.5 watt

 $R_{11} R_{10} = 10000$  ohms,

0.5 watt

R<sub>15</sub> = Potentiometer, balance control. 10000 ohms, RCA stock No. 111044 or equiv. R<sub>17</sub> = 4700 ohms, 0.5 watt

R<sub>15</sub> = 330 ohms, 1 watt R<sub>16</sub> = 1.2 megohms, 0.5 watt R<sub>20</sub> = 0.15 megohm, 0.5 watt R21 R22 R23 = 47000 ohms.

0.5 watt

T<sub>1</sub> = Transformer, 19-Kc.

RCA stock No. 111045 or equiv.


= Transformer, 38-Kc. RCA stock No. 111046 or equiv.

NOTE: See general considerations for construction of high-frequency and broad-band circuits on page 576.

(23-11)

#### HIGH-FIDELITY AUDIO AMPLIFIER

Class AB<sub>1</sub>; Power Output, 15 Watts



 $C_1 = 40 \,\mu f$ , electrolytic, 450 v.  $C_2 C_4 C_5 = 0.25 \,\mu f$ , paper, 400 v.  $C_3 = 3.3 \,\mu f$ , ceramic or mica, 600 v.  $C_0 = 150$  pf, ceramic or mica, 400 v.  $C_7 C_8 = 0.05 \mu f$ , paper, 400 v.  $C_0 = 0.02 \mu f$ , paper, 400 v.  $C_{10} = 100 \mu f$ , electrolytic, 50 v.  $C_{11} = 80 \mu f$ , electrolytic, 450 v.  $C_{12} = 40 \mu f$ , electrolytic,

450 v. F = Fuse, 3 amperes L = Choke, 3 h., 160 ma., dc resistance 75 ohms or less R<sub>1</sub> = Volume control, poten-

R<sub>1</sub> = Volume control, potentiometer, 1 megohm
R<sub>2</sub> = 10000 ohms, 0.5 watt
R<sub>4</sub> = 820 ohms, 0.5 watt
R<sub>5</sub> = 0.22 megohm, 0.5 watt
R<sub>6</sub> R<sub>7</sub> = 15000 ohms ± 5 per
cent, 2 watts
R<sub>8</sub> = 3900 ohms, 2 watts
R<sub>8</sub> R<sub>10</sub> = 0.1 megohm,
0.5 watt

0.5 watt

0.5 watt
R<sub>11</sub> R<sub>12</sub> = 1000 ohms, 0.5 watt
R<sub>13</sub> R<sub>14</sub> = 100 ohms, 0.5 watt
R<sub>15</sub> = 8200 ohms, 0.5 watt
R<sub>16</sub> = 15000 ohms, 1 watt
R<sub>17</sub> = 68000 ohms, 0.5 watt
R<sub>18</sub> = 4700 ohms, 2 watts

R<sub>19</sub> = 0.27 megohm, 1 watt

 $R_{20} = 47000 \text{ ohms}, 0.5 \text{ watt}$ R21 = Hum balance adjustment, potentiometer, 100 ohms, 0.5 watt SR = Selenium rectifier, 20

135 volts rms ma., 135 volts rms  $T_1 = Output transformer$ ,


(having 8-ohm tap for feedback connection) for matching impedance of voice coil to 6600-ohm plate-to-plate tube load; 50 watts; fre-quency response, 10 to 50000 cps; Stancor A-8056

3000 cps, stancor A-8000 or equiv. T<sub>2</sub> = Power transformer, 360-0-360 volts rms, 120 ma.; 6.3 v., 3.5 a; 5v., 3a; Stancor 8410 or equiv.

# (23-12)

#### HIGH-FIDELITY AUDIO AMPLIFIER

Class AB<sub>1</sub>: Power Output, 30 Watts



 $C_1 = 25 \mu f$ , electrolytic, 50 v.  $C_2 = 22 pf$ , ceramic or mica, 600 v.

600 v.  $C_3 = 80 \, \mu f$ , electrolytic,  $450 \, v$ .  $C_4 \, C_5 = 0.25 \, \mu f$ , paper,  $600 \, v$ .  $C_6 = 0.01 \, \mu f$ , paper,  $600 \, v$ .  $C_7 \, C_5 = 0.05 \, \mu f$ , paper,  $600 \, v$ .  $C_9 \, C_{11} = 40 \, \mu f$ , electrolytic,  $500 \, v$ .  $C_{10} = 100 \, \mu f$ , electrolytic,  $50 \, v$ .  $C_{12} = 20 \, \mu f$ , electrolytic,

450 v.

F = Fuse, 3 amperes, 150 v. R<sub>1</sub> = Volume control, potentiometer, 1 megohm R<sub>2</sub> = 10000 ohms, 0.5 watt

cent, 2 watts  $R_0 = 1000$  ohms, 0.5 watt  $R_{10} = 22000$  ohms, 0.5 watt  $R_{11} = 2000$  ohms, 2 watts  $R_{12} R_{13} = 0.1 \text{ megohm},$ 0.5 watt R14 R15 = 1000 ohms, 0.5 watt R16 R17 = 56 ohms, 0.5 watt R18 = 270 ohms, 0.5 watt R19 = Hum balance adjustment, potentiometer, 100 ohms, 0.5 watt

 $R_3 = 0.22$  megonm, 0.5 watt  $R_4 = 820$  ohms, 0.5 watt  $R_5 = 10$  ohms, 0.5 watt  $R_6 = 0.18$  megohm, 0.5 watt  $R_7 R_8 = 15000$  ohms  $\pm 5$  per cent, 2 watts

 $R_{20} = 120$  ohms, 100 watts  $R_{21} = 50$  ohms, 10 watts  $R_{22} = 10000$  ohms, 2 watts  $T_1 = Output transformer (hav$ ing 16-ohm tap for feedback ing 16-0hm tap for feedback connection) for matching impedance of voice coil to 6600-0hm plate-to-plate tube load; 50 watts; frequency response, 10 to 50000 cps; Stancor 8410 or equiv.


equivalent  $T_2 = Power transformer, 375-$ 0-375 volts rms, 160 ma.; 6.3 v., 5 a.; 5 v., 3 a.; Thordarson type T22R33 or equivalent

NOTES FOR (23-13): The following adjustments shoul be made before operation: (1) With rectifier out of socket, adjust  $R_{39}$  for -40 volts between junction of  $R_{25}$  and  $R_{29}$  and  $R_{2$ open and R<sub>1</sub> set for maximum volume, adjust R<sub>17</sub> for minimum hum from speaker.

# (23-13)

#### HIGH-FIDELITY AUDIO AMPLIFIER

Class AB; Power Output, 50 Watts



C<sub>1</sub> C<sub>2</sub> = 40  $\mu$ f, electrolytic, 450 v. C<sub>3</sub> C<sub>4</sub> = 0.02  $\mu$ f, paper, 400 v. C<sub>5</sub> C<sub>6</sub> = 1  $\mu$ f, paper, 400 v. C<sub>7</sub> = 0.002  $\mu$ f to 4-ohm tap; 0.0015  $\mu$ f to 8-ohm tap; or, 0.001  $\mu$ f to 16-ohm tap; paper, 400 v. C<sub>8</sub> C<sub>9</sub> = 0.05  $\mu$ f, paper, 600 v. C<sub>10</sub> = 20  $\mu$ f, electrolytic,

450 v.

F = Fuse, 5 amperes
L = Choke, 8 h., 250 ma., dc
resistance 60 ohms, or less
R<sub>1</sub> = Volume control, potentiometer, 0.5 megohm
R<sub>2</sub> = 4700 ohms, 0.5 watt
R<sub>3</sub> = 0.82 megohm, 0.5 wat

 $R_0 = 4700$  ohms, 0.5 watt  $R_3 = 0.82$  megohm, 0.5 watt  $R_4 = 0.22$  megohm, 0.5 watt  $R_5 = 820$  ohms, 0.5 watt  $R_7 = 10$  ohms, 0.5 watt  $R_7 = 10$  ohms, 0.5 watt  $R_7 = 15000$  ohms, 2 watts  $R_8 = 15000$  ohms, 2 watts  $R_8 = 15000$  ohms, 0.5 watt

R<sub>11</sub> = 33000 ohms, 2 watts R<sub>12</sub> R<sub>14</sub> = 1.3 megohms, 0.5 watt  $R_{13} = 47$  ohms, 0.5 watt  $R_{15} R_{19} = 0.15$  megohm, 0.5 watt  $R_{16} R_{18} = 390$  ohms, 0.5

R<sub>10</sub> R<sub>18</sub> = 390 ohms, 0.5 watt R<sub>17</sub> = AC balance control, potentiometer, 500 ohms, Note 4 (p. 588)

Note 4 (p. 588)

R<sub>20</sub> = 0.15 megohm, 1 watt

R<sub>21</sub> R<sub>24</sub> = 0.33 megohm,
1 watt

R<sub>22</sub> R<sub>23</sub> = 0.12 megohm, 2 watts

 $R_{25} R_{26} = 0.1$  megohm, 0.5 watt

R27 R28 = 4700 ohms, 0.5 watt R20 = 600 ohms to 4-ohm tap; 820 ohms to 8-ohm tap; or, 1200 ohms to 16-ohm tap; 0.5 watt

R<sub>30</sub> = Hum balance adjustment, potentiometer, 100 ohms, Note 3 (p. 588)
R<sub>31</sub> = 0.12 megohm, 5 watts
R<sub>32</sub> R<sub>34</sub> R<sub>35</sub> R<sub>37</sub> = 33000 ohms,
2 watts

R<sub>33</sub> = Bias adjustment, potentiometer 5000 ohms,

R<sub>28</sub> = 10000 ohms, 1 watt R<sub>89</sub> = Screen-grid voltage adjustment, potentiometer, 25000 ohms, 2 watts, Note 2

25000 ohms, 2 watts, Note 2 (p. 588)

R<sub>40</sub> = 15000 ohms, 2 watts

R<sub>41</sub> = 12000 ohms, 2 watts

 $R_{41} = 12000$  ohms, 2 watts  $R_{42} = 0.22$  megohm, 2 watts  $R_{43} = 22000$  ohms, 2 watts  $R_{43} = 22000$  ohms, 2 watts  $R_{43} = 22000$  ohms, 2 watts

ma., 135 volts rms
T1 = Output transformer for matching impedance of voice coil to 5000-ohm plate-to-plate tube load; 50 watts; frequency response, 10 to 50000 cps.; Acrosound


TO 340 or equiv.

T<sub>2</sub> = Power transformer,
600-0-600 voits rms, 200
ma., 6.3 v., 5 a.; 5 v., 3 a.;
Thordarson 22R36 or
equiv.

T<sub>3</sub> = Filament transformer, 6.3 volts, center tapped, 1 ampere; Thordarson 21F08 or equiv.


# (23-14) TWO-CHANNEL AUDIO MIXER

Voltage Gain From Each Grid of 6EU7 to Output is Approximately 20



# (23-15) TWO-CHANNEL STEREOPHONIC AMPLIFIER

Power Output, 1 Watt Each Channel



C<sub>1</sub> C<sub>3</sub> = 0.22  $\mu$ f, 400 v., paper C<sub>2</sub> = 0.1  $\mu$ f, 400 v., paper C<sub>4</sub> C<sub>5</sub> = 50  $\mu$ f, 25 v., electrolytic C<sub>6</sub> = 50  $\mu$ f<sub>1</sub> 150 v., electrolytic


C<sub>6</sub> = 50  $\mu$ f, 150 v., electrolytic C<sub>7</sub> C<sub>8</sub> = 50  $\mu$ f, 150 v., electrolytic F = Fuse, 3 amperes R<sub>1</sub> R<sub>2</sub> = Volume control, potentiometer, 1.5 megohms, ganged
R<sub>4</sub> R<sub>4</sub> = 47000 ohms, 0.5 watt
R<sub>5</sub> = Balance control, potentiometer, 2 megohms
R<sub>6</sub> R<sub>7</sub> = 60 ohms, 1 watt

 $\begin{array}{l} R_{S} = 220 \text{ ohms, } 2 \text{ watts} \\ R_{\theta} = 280 \text{ ohms, } 2 \text{ watts} \\ R_{10} = 12 \text{ ohms, } 1 \text{ watt} \\ R_{11} = 0.22 \text{ megohm, } 0.5 \text{ watt} \\ T_{1} T_{2} = \text{ Output transformer} \\ \text{for matching impedance of voice coil to } 3000\text{-ohm tube} \\ \text{load; Triad S-16X or equiv.} \end{array}$ 

# (23-16)

#### TWO-CHANNEL STEREOPHONIC AMPLIFIER

Power Output, 1 Watt Each Channel



C<sub>1</sub>  $\pm$  0.1  $\mu$ f, paper, 400 v. C<sub>2</sub>  $\pm$  25  $\mu$ f. electrolytic, 25 v. C<sub>3</sub> C<sub>4</sub> = 0.047  $\mu$ f, paper, 150 v.

C<sub>5</sub> = 50  $\mu$ f. electrolytic. 25 v. C<sub>6</sub> C<sub>7</sub> = 50  $\mu$ f, electrolytic, 150 v.

 $R_1$   $R_2$  = Volume control, potentiometer, 1 megohm, ganged

 $R_3$   $\dot{R}_5 \pm 1$  megohm. 0.5 watt  $R_4 \pm 3300$  ohms, 0.5 watt  $R_6$   $R_7 = 0.22$  megohm. 0.5 watt

 $R_{\rm s} R_{\rm ii} = 10,000 \text{ ohms,} \\ 0.5 \text{ watt}$ 


R<sub>0</sub> = Balance control, potentiometer, 0.5 megohm R<sub>10</sub> = 33 ohms, 1 watt R<sub>12</sub> = 1000 ohms, 2 watts R<sub>13</sub> = 50 ohms, 10 watts R<sub>14</sub> = 6.8 ohms, 1 watt S = Switch; single-pole, single-throw

T<sub>1</sub> T<sub>2</sub> = Output transformer for matching impedance of voice coil to 3000-ohm tube load; Stancor A-3825 or equiv.

(23-17)

#### MICROPHONE AND PHONOGRAPH AMPLIFIER

Power Output, 8 Watts



```
C<sub>1</sub> C<sub>2</sub> = 100 pf disc-ceramic,

300 v.

C<sub>3</sub> = 0.05 \muf, paper, 200 v.

C<sub>4</sub> = 8 \muf, electrolytic, 450 v.

C<sub>5</sub> = 16 \muf, electrolytic, 450 v.

C<sub>6</sub> = 25 \muf, electrolytic,
C_7 = 0.1 \mu f, paper, 200 v.

C_8 = 0.001 \mu f, disc-ceramic,
        300 v
 C_0 = 0.01 \mu f, disc-ceramic, 300 v.
C_{10} = 470 pf, dis-ceramic, 300 v.
 C_{11} = 4700 pf, dis-ceramic,
JOU V. C<sub>12</sub> = 4 \muf, electrolytic. 450 v. C<sub>13</sub> = 0.05 \muf, paper, 600 v. C<sub>14</sub> = 25 \muf, electrolytic. 25 v. C<sub>15</sub> C<sub>10</sub> C<sub>17</sub> = 20 \muf, electrolytic, 450 v.
       300 v.
```

F = Fuse, 1 ampere  $J_1 = Jack$  for high-impedance crystal microphone input; max. input: 2 millivolts peak

 $J_2 = Jack$  for crystal phonopickup input; max. input:
0.5 volt peak
= Filter choke, 5 henries,

200 ma.

 $R_1 R_{16} = 10000 \text{ ohms}, 0.5$ 

watt
R2 = Volume Control, potentiometer, 1 megohm  $R_3 = 2.2$  megohms, 0.5 watt  $R_4$   $R_8$   $R_{20} = 0.22$  megohm,

0.5 watt  $R_5 = 27000$  ohms, 0.5 watt  $R_6 = 1200$  ohms, 0.5 watt  $R_7 = 1200$  ohms, 0.5 watt  $R_7 = 1200$  ohms, 0.5 watt  $R_7 = 1200$  ohms, 0.5 watt

R<sub>0</sub> R<sub>11</sub> = Tone control, potentiometer, 0.5 megohm
R<sub>10</sub> = 22000 ohms, 0.5 watt  $R_{12} = 12000$  ohms, 0.5 watt  $R_{14} = 1800$  ohms, 0.5 watt  $R_{15} = 0.47$  megohm, 0.5 watt  $R_{17} = 0.15$  megohm, 0.5 watt  $R_{18} = 180$  ohms, 2 watts  $R_{19} = 47000$  ohms, 1 watt R<sub>19</sub> = 47000 onms, 1 watt R<sub>21</sub> = 50 ohms, 10 watts R<sub>22</sub> = 8200 ohms, 2 watts S<sub>1</sub> = Switch, SPST S<sub>2</sub> = Switch, SPDT T<sub>1</sub> = Power transformer, 300-0-300 v., 90 ma.; 6.3 v.,


3.5 a. center tapped; 5 v.,  $T_2 = 0$  Output transformer for

matching impedance of voice coil to 4000-ohm tube load; 10 watts

(23-18)

#### PHONOGRAPH AMPLIFIER


Power Output, 1 Watt



(23-19)

#### PREAMPLIFIER FOR CERAMIC PHONOGRAPH PICKUP


Cathode-Follower (Low-Impedance) Output



(23-20)

#### PREAMPLIFIER FOR MAGNETIC PHONOGRAPH PICKUP

With RIAA Equalization



C<sub>1</sub> C<sub>4</sub> = 25  $\mu$ f, electrolytic, 25 v. C<sub>2</sub> C<sub>5</sub> = 20  $\mu$ f, electrolytic, 450 v. C<sub>2</sub> = 0.1  $\mu$ f, paper, 600 v. C<sub>5</sub> = 0.0033  $\mu$ f  $\pm$  5 per cent, paper, 600 v. C<sub>7</sub> = 0.01  $\mu$ f  $\pm$  5 per cent, paper, 600 v. C<sub>8</sub> = 180 pf ± 5 per cent, ceramic or mica, 500 v. (includes capacitance of output cable)
 C<sub>0</sub> = 0.22 μf, ceramic, 500 v.
 J Input connector, shielded, for high-impedance magnetic phono pickup (10 mv. output, approx.)


of magnetic pickup used. Follow pickup manufacturer's recommendations  $R_2$   $R_7 = 2700$  ohms, 0.5 watt  $R_1$  = 39000 ohms, 0.5 watt  $R_4$  = 39000 ohms, 0.5 watt  $R_6$  = 0.47 megohm, 0.5 watt  $R_8$  = 0.68 megohm, 0.5 watt  $R_9$  = 15000 ohms, 1 watt  $R_{10}$  = 22000 ohms, 0.5 watt

(23-21)

## TWO-STAGE INPUT AMPLIFIER

 $R_1 = Value depends on type$ 

Cathode-Follower (Low-Impedance) Output




C<sub>1</sub> C<sub>2</sub> = 0.1 µf, paper, 400 v. C<sub>2</sub> = 25 µf, electrolytic, 25 v. C<sub>4</sub> = 0.5 µf, paper, 200 v. R<sub>1</sub> = Volume control, potentiometer, 0.5 megohm R<sub>2</sub> = 0.22 megohm, 0.5 watt R<sub>3</sub> = 27000 ohms, 0.5 watt R<sub>4</sub> = 25600 nms, 0.5 watt R<sub>5</sub> = 27000 ohms, 0.5 watt

## (23-22)


#### LOW-DISTORTION PREAMPLIFIER

For Low-Output High-Impedance Microphones



(23-23)

#### BASS AND TREBLE TONE-CONTROL AMPLIFIER STAGE



C<sub>1</sub> C<sub>3</sub> = 20  $\mu$ f, electrolytic, 450 v. C<sub>2</sub> = 0.047  $\mu$ f, paper, 400 v. C<sub>4</sub> = 0.1  $\mu$ f, paper, 400 v. C<sub>5</sub> = 0.22  $\mu$ f, paper, 400 v. C<sub>8</sub> = 0.0022  $\mu$ f, paper, 400 v. C<sub>8</sub> = 0.022  $\mu$ f, paper, 400 v. C<sub>8</sub> = 220 pf, ceramic or mica,  $C_0 = 0.0022 \ \mu f$ , paper, 400 v.  $R_1 = 0.47 \ \text{megohm}$ , 0.5 watt  $R_2 = 1500 \ \text{ohms}$ , 0.5 watt  $R_3 \ R_7 = 15000 \ \text{ohms}$ , 0.5 watt  $R_4 = 22000 \ \text{ohms}$ , 0.5 watt  $R_5 \ R_8 \ R_{11} = 0.1 \ \text{megohm}$ ,


R<sub>5</sub> = 1000 ohms, 0.5 watt
R<sub>0</sub> = Bass control, potentioneter, 1 megohm
R<sub>10</sub> = 10000 ohms, 0.5 watt
R<sub>12</sub> = Treble control, potentiometer, 1 megohm

0.5 watt

(23-24)

#### **AUDIO CONTROL UNIT**

With Volume and Tone Controls



C<sub>1</sub> C<sub>7</sub> = 0.01  $\mu$ f, paper, 400 v. C<sub>2</sub> C<sub>11</sub> = 20  $\mu$ f, electrolytic, 450 v. C<sub>5</sub> C<sub>16</sub> = 0.1  $\mu$ f, paper, 400 v. C<sub>5</sub> C<sub>16</sub> = 25  $\mu$ f, electrolytic, 25 v. C<sub>6</sub> = 0.001  $\mu$ f, paper, 400 v. C<sub>8</sub> = 470 pf, mica, 300 v. C<sub>9</sub> = 4700 pf, mica, 300 v. C<sub>12</sub> C<sub>14</sub> = 0.47  $\mu$ f, paper, 400 v. C<sub>13</sub> = 0.033  $\mu$ f, paper, 400 v. C<sub>13</sub> = 0.033  $\mu$ f, paper, 400 v.

 $R_3 = 1.5$  megohms, 0.5 watt  $R_4 = 2$  megohms, 0.5 watt  $R_5 = Potentiometer$ , 0.5 megohm, audio taper  $R_6 = 0.33$  megohm, 0.5 watt  $R_8 = 1.5000$  ohms, 0.5 watt  $R_0 = 0.56$  megohm. 0.5 watt  $R_{10} = 2200$  ohms, 0.5 watt  $R_{11} = 2200$  ohms, 0.5 watt  $R_{12} = 2200$  ohms, 0.5 watt  $R_{13} = 0.22$  megohm, 0.5 watt  $R_{14} = 0.22$  megohm, 0.5 watt

 $R_1 R_2 R_7 = 0.27 \text{ megohm}, 0.5$ 

watt

 $R_{12} R_{c7} = 1$  megohm, 0.5 watt  $R_{13} R_{c1} = 0.1$  megohm, 0.5 watt  $R_{17} R_{10} = 1200$  ohms, 0.5 watt  $R_{17} R_{10} = Potentiometers, 0.5$  megohm, audio taper  $R_{18} = 2200$  ohms, 0.5 watt  $R_{20} = 2700$  ohms, 0.5 watt  $R_{22} = 5600$  ohms, 0.5 watt  $R_{23} = 27000$  ohms, 0.5 watt  $R_{24} = 0.47$  megohm, 0.5 watt  $R_{26} = Potentiometer, 0.1$  megohm, audio taper

## (23-25)


# **ALL-PURPOSE POWER SUPPLY**

| FI<br>O          | T   (2.6.3 V   TYP  5800   1.5 | TO HEATERS  | TO FILTE                  | - <del>&gt;</del><br>R<br><u>FILT</u> | RI<br>CI                        | L1             |                   | OB+                   |
|------------------|--|---|---------------------------|---------------------------------------|---------------------------------|----------------|-------------------|-----------------------|
| FI<br>II7V<br>AC | 06.3 V   | \$\frac{4}{3}   | TO HEATE                  |                                       | R 3 . =                         | R <sub>2</sub> |                   | ○8+<br>:8*<br>○8-     |
| POWER            | POWER S  | UPPLY 2<br>CHOKE (  | L1) _                     |                                       | C <sub>1</sub> , C <sub>2</sub> | FIL-           | OUTI              |                       |
| SUPPLY<br>(5BC3) | FORMER Stancor PC or PM 8177   | 140 ma, 7h,<br>165 ohms<br>Stancor C1421                    | R <sub>1</sub> 33 ohms 5W | R <sub>2</sub>                        | 40 μf<br>450 Vdc                | TER<br>1       | 360<br>340<br>320 | MA<br>60<br>80<br>120 |
|                  | (300-0-300)<br>or equiv.   | or equiv.   |                           |                                       |                                 | 2              | 235<br>230<br>215 | 60<br>80<br>120       |
| 1<br>(5BC3)      | Stancor<br>PC or PM  | 200 ma, 4h,<br>145 ohms                                     | 56 ohms<br>10W            |                                       | 40 μf<br>600 Vdc                | 1              | 450<br>425<br>410 | 120<br>160<br>200     |
|                  | 8412<br>(400-0-400)<br>or equiv.   | Thordarson<br>20C54<br>or equiv.                            |                           |                                       | •                               | 2              | 310<br>300<br>280 | 120<br>160<br>200     |
| (6X4)            | Stancor<br>P-6358<br>(300-0-300)<br>or equiv.  | 80 ma, 12h,<br>375 ohms<br>Thordarson<br>20C53<br>or equiv. | 500 ohms<br>5W            | 500 ohms<br>3W                        | 40 μf<br>450 Vdc                | 1              | 350<br>300<br>260 | 20<br>40<br>60        |
|                  |  |   |                           |                                       |                                 | 2              | 250<br>230<br>220 | 20<br>40<br>60        |
|                  |  |   |                           |                                       | •                               | 3              | 345<br>300<br>250 | 20<br>40<br>60        |
| (6X4)            | Stancor<br>PM or PC  | 80 ma, 12h,<br>375 ohms                                     | 500 ohms<br>5W            | 500 ohms<br>3W                        | 40 μf<br>450 Vdc                | 1              | 265<br>225<br>190 | 20<br>40<br>60        |
|                  | 8419<br>(240-0-240)<br>or equiv.   | Thordarson<br>20C53<br>or equiv.                            |                           |                                       | -                               | 2              | 200<br>180<br>170 | 20<br>40<br>60        |
|                  | Re can be omi  |   |                           |                                       |                                 | 3              | 260<br>220<br>180 | 20<br>40<br>60        |

<sup>\*</sup> Bleeder RB can be omitted if an external load is permanently connected across the output terminals. Bleeder current should be approximately 10 per cent of the load current.

# (23-26)

#### **AUDIO SIGNAL GENERATOR**



C<sub>1</sub> = 0.1  $\mu$ f, ceramic, 400 v. C<sub>2</sub> C<sub>6</sub> = 0.25  $\mu$ f ceramic, 400 v. C<sub>5</sub> C<sub>6</sub> C<sub>7</sub> = 20  $\mu$ f, electrolytic, 350 v. C<sub>4</sub> = 5-80 pf, trimmer C<sub>5</sub> = 1  $\mu$ f, paper, 200 v. C<sub>8</sub> C<sub>17</sub> = 40  $\mu$ f, electrolytic, 150 v.

C<sub>11</sub> C<sub>10</sub> C<sub>20</sub> = 3-section electrolytic; 20  $\mu$ f. 250 v.; 60  $\mu$ f. 450 v.; 20  $\mu$ f. 450 v. C<sub>12</sub> = 2.2 pf. ceramic C<sub>13</sub> = 3.3 pf. ceramic, 500 v. C<sub>14</sub> = 7.5—8 pf. trimmer C<sub>15</sub> = 27 pf. ceramic, 600 v. C<sub>16</sub> = Variable. 2 gang; RCA stock No.220226 or equiv. C<sub>18</sub> = 50  $\mu$ f, electrolytic, 250 v. I<sub>1</sub> = Lamp, 3 watts, 120 v. Parts list continued on page 599.

 $\begin{array}{lll} I_2 = \text{Pilot lamp, No.47} \\ L_1 = \text{Reactor, RCA stock} \\ \text{No.220215 or equiv.} \\ R_2 = 3900 \text{ ohms, 2 watts} \\ R_2 \text{ R}_{12} \text{ R}_{22} = 1 \text{ megohm,} \\ 0.5 \text{ watt} \\ R_3 = 470 \text{ ohms, 1 watt} \\ R_4 = 3900 \text{ ohms, 1 watt} \\ R_6 = 12000 \text{ ohms, 1 watt} \\ R_6 = \text{Potentiometer, 12000 ohms} \\ \end{array}$ 

 $R_7 = 3300$  ohms, 0.5 watt

# (23-26) AUDIO SIGNAL GENERATOR (Cont'd)

 $\begin{array}{lll} R_{S} & R_{0} & = 22000 \text{ ohms, } 1 \text{ watt} \\ R_{10} & = 56000 \text{ ohms, } 0.5 \text{ watt} \\ R_{11} & = Potentiometer, 2500 \\ \text{ ohms, } 0.5 \text{ watt} \\ R_{12} & R_{14} & = Potentiometer, \\ 5000 \text{ ohms} \\ R_{15} & = 8200 \text{ ohms, } 0.5 \text{ watt} \\ R_{16} & = 12000 \text{ ohms, } 0.5 \text{ watt} \\ R_{17} & = 4700 \text{ ohms, } 1 \text{ watt} \\ R_{18} & = 0.47 \text{ megohm, } 0.5 \text{ watt} \\ R_{10} & = 0.27 \text{ megohm, } 0.5 \text{ watt} \\ R_{20} & = 15000 \text{ ohms, } 2 \text{ watts} \\ R_{21} & = Potentiometer, \\ 750 \text{ ohms} \end{array}$ 


 $R_{23} = 36000$  ohms, 0.5 watt  $R_{24} = 0.36$  megohms, 0.5 watt  $R_{25} = 3.6$  megohms, 0.5 watt  $R_{26} = 36$  megohms, 1 watt  $R_{27} = 8$  megohms, 1 watt  $R_{25} = 0.8$  megohm, 0.5 watt  $R_{25} = 80000$  ohms, 0.5 watt  $R_{25} = 80000$  ohms, 0.5 watt  $R_{25} = 80000$  ohms, 0.5 watt  $R_{25} = 8000$  ohms, 0.5 watt  $R_{25} = 8000$  ohms, 0.5 watt  $R_{25} = 680$  ohms, 0.5 watt  $R_{27} = 750$  ohms, 0.5 watt  $R_{37} = 750$ 

R<sub>38</sub> = Potentiometer, 100 ohms, with switch S-3 S1 = Rotary switch, function selector, 8 position. 3 wafer, RCA stock No.220216 or equiv. S2 = Rotary switch, range selector, 4 position. 2 wafer, RCA stock No.220217 or equiv. T1 = Power transformer, 117 volts rms, 60 cps, RCA stock No.220214 or equiv.

\* In some cases, a small capacitor may be needed to trim the high-frequency end of the band. This capacitor can consist of two lengths of insulated hookup wire twisted together, and connected to the circuit as indicated in the schematic.

# (23-27) INTERCOMMUNICATION SET

With Master Unit and Two or More Remote Units



C<sub>1</sub> C<sub>2</sub> = 0.0022  $\mu$ f, paper, 200 v. C<sub>3</sub> = 0.005  $\mu$ f, paper, 200 v. C<sub>4</sub> C<sub>5</sub> = 60  $\mu$ f, electrolytic, 150 v. F = Fuse, 1 ampere R<sub>1</sub> = Volume control. potentiometer, 0.5 megohm, audio taper R<sub>2</sub> = 6.8 megohms, 0.5 watt R<sub>3</sub> R<sub>4</sub> = 0.47 megohm, 0.5 watt  $R_5 \equiv 10000$  ohms, 0.5 watt  $R_8 R_7 \equiv 68$  ohms, 0.5 watt  $R_5 \equiv 2200$  ohms, 1 watt  $S_1 S_2 S_2 \equiv Speaker$ , permanent-magnet, voice-coil impedance 3-4 ohms  $SW_1 \equiv On$ -off switch, single-pole single-throw, attached to volume control  $R_1$   $SW_2 \equiv Talk$ -listen switch, double-pole double-throw


SW<sub>2</sub> = Station-selector switch, rotary T<sub>1</sub> = Input transformer, 4-ohm primary, 25000-ohm secondary T<sub>2</sub> = Output transformer, 3000-ohm primary, 4-ohm secondary T<sub>3</sub> = Power transformer, 125 volts rms, 50 ma., 6.3 volts

rms, 2 amperes

NOTES: The leads from the LISTEN-TALK switch to  $T_1$  and  $T_2$  should be kept as far apart as possible to prevent undesirable regeneration effects. Connections to the remote speaker units should be made with low-resistance wire, preferably shielded "intercom" cable.

(23-28)

## CATHODE-RAY OSCILLOSCOPE



(23-28)

#### CATHODE-RAY OSCILLOSCOPE (Cont'd)

C<sub>1</sub> C<sub>3</sub> C<sub>6</sub> C<sub>8</sub> C<sub>11</sub> = Trimmer capacitors, 4—40 pf, Arco No.422 or equiv.  $C_2$   $C_{15}$   $C_{21}$   $C_{10}$   $C_{25} = 0.1 \mu f$ , paper, 400 v.  $C_4 = 64$  pf, ceramic disc, 500 v.  $C_5 = 22$  pf, ceramic disc, 500 v.  $C_7 = 140$  pf, ceramic disc,  $C_9 = 410$  pf, ceramic disc, 500 v.  $C_{10}$   $C_{13}$   $C_{40}$   $C_{48} = 20 \mu f$ , electrolytic, 450 v.  $C_{12} = 1500$  pf, ceramic disc, 500 v.  $C_{1i} = 1200$  pf, ceramic disc, 500 v.  $C_{10} C_{24} C_{25} = 0.02 \mu f$ , ceramic disc, 600 v.  $C_{17} C_{28} = 10 \mu f$ , electrolytic, 450 v.  $C_{18}$   $C_{42} = 40 \mu f$ , electrolytic, 450 v.  $C_{20} = 560$  pf, ceramic disc, 500 v  $C_{22} = 0.05 \mu f$ , ceramic disc, 200 v  $C_{23} = 0.05 \mu f$ , paper, 200 v.  $C_{26} = 5 pf$ , ceramic disc, 150 v  $C_{27} = 0.22 \mu f$ , paper, 400 v.  $C_{28} = 0.022 \mu f$ , paper, 400 v.  $C_{29} = 2200 \text{ pf}$ , ceramic disc, 400 V  $C_{80} = 220$  pf, ceramic disc. 400 v Cm = 15 pf, ceramic disc. 500 v.  $C_{82} = 180$  pf, ceramic disc, 200 v  $C_{28} = 150$  pf, ceramic disc,  $C_{34}$   $C_{36}$   $C_{37}$   $C_{41} = 0.1 \mu f$ , paper, 200 v.  $C_{39}$   $C_{45}$   $C_{46} = 0.01 \mu f$ , ceramic disc, 600 v.  $C_{14} = 0.5 \mu f$ , paper, 1000 v.  $C_{47} = 12 pf$ , tubular ceramic, 150 v.

ID<sub>1</sub> = Pilot lamp, No.47 L<sub>1</sub> = Peaking coil, 20  $\mu$ h L<sub>2</sub> L<sub>3</sub> = Peaking coil, 36  $\mu$ h (wound on 10,000-ohm, 0.5-watt resistor)  $R_1 = 0.68$  megohm, 0.5 watt R<sub>2</sub> R<sub>26</sub> R<sub>27</sub> R<sub>68</sub> R<sub>79</sub> = 0.47 megohm, 0.5 watt Reg Reg Reg Reg Reg Reg Lot |
Regolum, 0.5 watt
Rs = 0.91 megohm, 0.5 watt
Rs = 0.11 megohm, 0.5 watt
Rs Rr R12 Re1 R10 R11 = 1
megohm, 0.5 watt
Rs Rs2 Rs2 = 10000
ohms, 0.5 watt
Rs Rs4 Rs2 Rs2 = 10000
ohms, 0.5 watt
Rs Rs2 Rs1 Rs5 = 15000
ohms, 0.5 watt
Rs1 = 47000 ohms, 0.5 watt
Rs1 = 47000 ohms, 0.5 watt
Rs1 = Variable, wire-wound,
5000 ohms, 2 watts, Clarostat A43-5000 or equiv,
Rs1 = 6800 ohms, 1 watt
Rs5 R20 R20 R20 R35 = 1200 ohms,
0.5 watt
Rs6 = 2200 ohms, 0.5 watt R<sub>16</sub> = 2200 ohms, 0.5 watt R<sub>17</sub> = Wire-wound, 2500 ohms, 5 watts, IRC Type ohms, 5 watts, IRC Type PW5 or equiv.

R<sub>18</sub> = 100 ohms, 0.5 watt
R<sub>19</sub> = 4700 ohms, 1 watt
R<sub>22</sub> = 820 ohms, 1 watt
R<sub>23</sub> = 0.22 megohm, 0.5 watt  $R_{24} = 82000$  ohms, 0.5 watt  $R_{25} = 120$  ohms, 0.5 watt  $R_{28} R_{37} = 1800$  ohms, 1 watt  $R_{30} R_{39} = 1000 \text{ ohms},$ 0.5 watt R<sub>31</sub> = Wire-wound, 2400 ohms, 5 watts, IRC Type PW5 or equiv. Rss = 5000 ohms, 0.5 watt  $R_{86} = 1.2$  megohm, 0.5 watt  $R_{41} R_{43} R_{63} R_{66} = 0.82$ R<sub>11</sub> R<sub>13</sub> R<sub>63</sub> R<sub>66</sub> = 0.82 megohm, 0.5 watt R<sub>12</sub> R<sub>18</sub> = Variable, 1 megohm, 0.5 watt R<sub>15</sub> = Variable, 0.1 megohm, 0.25 watt  $R_{i6} = 0.18$  megohm, 0.5 watt


 $R_{47}$   $R_{77}$  = Variable, 0.25 megohm, 0.5 watt megonm, 0.5 watt  $R_{10} = 0.1$  megohm, 1 watt  $R_{50} = 68000$  ohms, 0.5 watt  $R_{51} = 3300$  ohms, 0.5 watt  $R_{51} = 3300$  onms, 0.5 watt  $R_{52} = 0.27$  megohm, 0.5 watt  $R_{53} = 680$  ohms, 0.5 watt  $R_{54} = 39000$  ohms, 0.5 watt  $R_{55} = Variable, 5$  megohms, 0.5 watt  $R_{58} R_{59} R_{67} = 2.7 \text{ megohms.}$ 0.5 watt R<sub>57</sub> = 3.3 megohms, 0.5 watt R<sub>58</sub> R<sub>72</sub> R<sub>75</sub> R<sub>81</sub> = 0.12 megohm, 0.5 watt R<sub>60</sub> R<sub>70</sub> = 10 megohms, 0.5 watt Rei Rei = 2400 ohms, 0.5 watt Rei = Variable, 2 megohms, 0.5 watt Res = Variable, 50000 ohms, 0.5 watt  $R_{73} = 0.1$  megohm, 0.5 watt  $R_{74} = Variable$ , 10000 ohms, 0.25 watt R<sub>76</sub> = 4700 ohms, 0.5 watt R<sub>78</sub> = Wire-wound, 1500 ohms, 7 watts, IRC Type PW7 or equiv. R<sub>80</sub> = Variable, 0.5 megohm, 0.5 watt

Res = Variable, 75000 ohms, 0.5 watt (includes ac switch) S<sub>1</sub> = Rotary switch, vertical range selector, 9 positions, 4 sections, RCA stock No.219199 or equiv. S<sub>2</sub> = Rotary switch, horizontal sweep selector, 6 positions, 5 sections, RCA stock No.219200 or equiv. = Switch, dpdt, sync, Stackpole Type SS-33 or equiv.  $T_1 = Power transformer, 117$ volts, 60 cps, RCA stock No.218122 or equiv. X, Y, Z, = Test points

NOTE: For home construction of this circuit, the complete Kit RCA-WO-33A (K) is recommended because of the large number of special components used. This circuit is also available in wired form as the RCA-WO-33A.

(23-29)

#### ELECTRONIC VOLT-OHM METER



B = Battery, 1.5 v. C<sub>1</sub> = 470 pf, ceramic disc, 1600 v.  $C_2 = 0.001 \mu f$ , ceramic disc, 500 v. C<sub>3</sub> = 0.47  $\mu$ f, tubular, 400 v. C<sub>4</sub> C<sub>5</sub> = 0.02  $\mu$ f, ceramic disc, 400 v. C<sub>0</sub> C<sub>7</sub> = 0.005  $\mu$ f, ceramic disc, 200 v. C<sub>8</sub> = 10  $\mu$ f, electrolytic, 400 v. F = Fuse, 0.5 ampere CR = Selenium rectifier, CR = Selenium rectifier,
Radio Receptor Co.
#8Y1B or equiv.
M<sub>1</sub> = Meter, dc, 0-200 μa
NE<sub>2</sub> = Neon lamp
R<sub>1</sub> = DC-voltage probe
isolating resistor, 1 megohm, 0.25 watt
R<sub>2</sub> = 138000 ohms, 0.25 watt
R<sub>3</sub> = 320000 ohms, 0.5 watt
R<sub>4</sub> = 0.9 megohm, 1 watt
R<sub>5</sub> R<sub>18</sub> = 1 megohm,
0.25 watt

0.25 watt

 $R_6 R_{16} R_{25} R_{27} = 10000 \text{ ohms},$ 0.5 watt  $R_7 = 20000 \text{ ohms}, 0.25 \text{ watt}$ 70000 ohms, 0.25 watt Rs = $R_9 = 0.2$  megohm, 0.25 watt  $R_{10} = 0.7$  megohm, 0.25 watt  $R_{11} = 2$  megohms, 0.25 watt  $R_{12} = 7$  megohms, 0.25 watt  $R_{13} = 8.2$  ohms, wire-wound, 0.5 watt

 $R_{14} = 100$  ohms, 0.25 watt  $R_{15} = 1000$  ohms, 0.25 watt  $R_{17} = 0.1$  megohm, 0.25 watt  $R_{10} = 10$  megohms, 0.25 watt  $R_{20} = 20$  megohms, 0.25 watt  $R_{21} = 91$  megohms, 0.5 watt = 10000 ohms, potentiometer ac calibration, R22 0.5 watt

= 10000 ohms, poten-R₂s tiometer de calibration, 0.5 watt

R<sub>24</sub> = 15000 ohms, potentiometer, ohms adjustment, 0.25 watt

 $R_{20} = 10000$  ohms, potentiometer, zero adjustment. 0.25 watt

0.25 watt R<sub>28</sub> = 3.3 megohms, 0.5 watt R<sub>29</sub> = 6.8 megohms, 0.5 watt R<sub>20</sub> = 15000 ohms, 0.5 watt R<sub>32</sub> = 27000 ohms, 0.5 watt R<sub>34</sub> = 10000 ohms, 0.5 watt tiometer, ac balance,

0.5 watt  $R_{85} = 47000 \text{ ohms}, 0.5 \text{ watt}$  $R_{36} = 0.22$  megohm, 0.5 watt Si = Range selector switch, 7 position, RCA stock No. 217924 or equiv.

S<sub>2</sub> = Function selector switch, 5 position, RCA stock No.217923 or equiv. T<sub>1</sub> = Power transformer, 105-125 volts rms, 50-60 cps, RCA stock No.217921 or equiv.

NOTE: Switches are shown in their maximum counterclockwise positions ( $S_1 = 1.5$  v., R X 1;  $S_2 =$  "OFF"). For home construction of this or a similar circuit, the complete Kit RCA-WV-77E (K) or RCA-WV-98C (K) is recommended because of the large number of special components used.

# Index

| Page   | Page   |
|--|--|
| Absolute Maximum System of Ratings . 74                              | Calculation of:  |
| AC/DC Superheterodyne Receiver 579                                   | amplification factor   |
| Admittance, Input  | cathode (self-bias) resistor 65  |
| All-purpose Power Supply 597   | cathode load resistor 34   |
| AM Detection   | control-grid-plate transconductance . 14   |
| AM/FM Receiver 580   | filament resistor power dissipation . 63   |
| Amplification  | filament (or heater) resistor value . 63   |
| Amplification Factor $(\mu)$   | harmonic distortion 20, 22   |
| Amplifier:   | heater warm-up time  |
| audio control unit, circuit 596                                      | load resistance 20, 26   |
| audio-frequency  | operating conditions from  |
| audio mixer, circuit 590   | conversion nomograph 23  |
| cathode-drive 29   | peak inverse plate voltage 77  |
| cathode-follower 29, 32  | plate efficiency   |
| class A 15, 18   | plate resistance   |
| class AB 15, 24  | power output   |
| class AB <sub>1</sub>  |  |
| class AB <sub>2</sub>  |  |
| class B 15, 28   | transconductance   |
| class C  | Capacitor-Input Filter 70  |
| high-fidelity  | Cathode:   |
| intermediate-frequency 585   | bias 65  |
| limiter  | bypassing  |
| low-distortion input, circuit 595                                    | connection   |
|  | current  |
|  | directly heated  |
| phase-inverter   | drive  |
| push-pull  | follower   |
| radio-frequency  | indirectly heated 4  |
| remote-cutoff  | ionic-heated 6   |
| resistance-coupled   | resistor   |
| sharp-cutoff   | types  |
| sync   | Cathode-Ray Oscilloscope 600   |
| television   | Characteristic Curves, Interpretation of 78  |
| tone-control   | Characteristics:   |
| tone-control, circuit 595  | amplification factor   |
| video 40   | control-grid-plate transconductance . 14   |
| voltage 15   | conversion transconductance 14   |
| volume-expander  | dynamic  |
| Amplitude Modulation (AM) 45   | France Community Control Contr |
| Anode 5  |  |
| Application Guide for RCA  | Charts and Tables:   |
| Receiving Tubes 80   |  |
| Arc-Back Limit   |  |
| Audio Control Unit with Volume and                                   | outline drawings   |
| Tone Controls  | types for renewal use 508  |
| Audio Mixer 590  |  |
| Audio Signal Generator 598   | Chicken Input Chicken Co.  |
| Automatic Frequency Control (AFC) 60 Automatic Gain Control (AGC) 50 |  |
|  | Circuit Diagram of:  |
| Automatic Volume Control (AVC) 60                                    | ac/dc superheterodyne receiver 579   |
| Boss and Tookle Tone Control   | all-purpose power supply   |
| Bass and Treble Tone-Control Amplifier Stage                         | AM/FM receiver   |
| Amplifier Stage  | audio signal generator 598   |
| Bias:  | bass and treble tone-control   |
| battery 65   | amplifier stage  |
| cathode (self)   | cathode-ray oscilloscope 600   |
| diode  | citizens-band transceiver 582  |
| grid-resistor 48, 65   | code practice oscillator 581   |
| Bypassing  | electronic volt-ohm meter 602  |
|  |  |

|   | <b>P</b> age |   | Pag        |
|---|--------------|---|------------|
| FM stereo multiplex adapter   | 586          | Electron:   |            |
| FM tuner  | 584          | considerations  |            |
| high-fidelity, 15-w audio amplifier high-fidelity, 30-w audio amplifier | 589          | secondary   | . 8,       |
| high-fidelity, 30-w audio amplifier                                     | 588          | Electronic Volt-Ohm Meter Electrons, Electrodes, and Electron | 60.        |
| high-fidelity, 50-w audio amplifier                                     |              | Electrons, Electrodes, and Electron                           |            |
| intercommunication set  | 599          | Tubes   |            |
| low-distortion preamplifier   | 595          | Electron Tube Application                                     | 1:         |
| microphone and phonograph   | 592          | Electron Tube Characteristics Electron Tube Installation      |            |
| preamplifier  |              | Electron Tube Testing   |            |
| phonograph amplifierportable 3-way superheterodyne                      | 372          | Electron-Ray Tubes  |            |
| receiver  | 578          | Emission:   | ٠,         |
| preamplifier for 10-m, 30-Mc  | 376          | current   |            |
| amateur receiver  | 583          | secondary   |            |
| preamplifier for ceramic  | 505          | test  |            |
| phonograph-pickup   | 593          |   | -          |
| preamplifier for magnetic   |              | Feedback, Inverse   | 30         |
| phonograph-pickup   | 594          | Filament (also see Heater and Cathode):                       |            |
| three-stage if amplifier/limiter  |              | operation   | 3, 6       |
| and ratio detector  | 585          | resistor  |            |
| two-channel audio mixer   | 590          | series operation  |            |
| two-channel, 1-w stereo amplifier                                       | 591          | shunt resistor  |            |
| two-channel, 1-w stereo amplifier                                       |              | supply voltage  | 62         |
| with tone control   | 590          | Filter:   |            |
| two-stage input amplifier   | 594          | capacitor-input   |            |
| Citizens-Band Transceiver   | 582          | choke-input   | 69         |
| Citizens-Band Transceiver Code Practice Oscillator Color Picture Tubes  | 529          | corrective  | 34<br>69   |
| Color Picture Tubes   | 13           | radio-frequency   |            |
| Color Television  | 41           | smoothing   |            |
| Contact Potential   | 67           | FM Detection  | 586        |
| Conversion Nomograph, Use of  | 23           | FM Tuner  |            |
| Conversion Transconductance   | 14<br>34     | Formulas (see Calculation)                                    | 50-        |
| Corrective Filter   | 18           | Frame Grid  | •          |
| Current:  | 10           | Frequency Conversion  | 58         |
| cathode   | 63           | Frequency Modulation (FM) 4                                   | 15. 48     |
| dc output   | 76           | Full-Wave Diode Detection                                     | 44         |
| grid  | 24           | Full-Wave Rectifier   | 5, 43      |
| peak plate  | 77           | Fuses, Use of   | 65         |
| plate   | 5            |   |            |
| Curves, Interpretation of Characteristic .                              | 78           | Gain (Voltage Amplification)                                  | 16         |
| Cutoff 1  | 8, 80        | Generic Tube Types  | 4          |
|   | •            | Grid:   |            |
| Dark Heater   | 4            | anode   | 59         |
| Deflection Circuits:  |              | bias  | 64         |
| horizontal output   | 57           | bias detection  | 48         |
| vertical output   | 56           | control   | 6, 7<br>24 |
| Degeneration (See Inverse Feedback)                                     | 30           | current   | 66         |
| Delayed Automatic Volume Control  |              | resistor resistor and capacitor detection                     | 48         |
| (DAVC)  | 51           | screen  | 7          |
| Demodulation  | 45           | suppressor  | 8          |
| Design-Center System of Ratings   | 74           | voltage supply  | 64         |
| Design-Maximum System of Ratings  | 74           | Grid-Plate Capacitance  | 7          |
| Detection:  | , -          | Grid-Plate Transconductance                                   | 14         |
| diode   | 45           |   |            |
| discriminator   | 49           | Half-Wave Rectifier   | 5, 43      |
| full-wave diode   | 45           | Harmonic Distortion 20, 2                                     | 2, 27      |
| grid bias   | 47           | Heater:   |            |
| grid resistor and capacitor   | 48           | cathode   | 4          |
| ratio detector  | 49           | cathode bias  | 65         |
| Diode:  | -            | cathode connection  | 65         |
| biasing   | 46           | resistor  | 64         |
| considerations  | 5            | series operation  | 63         |
| detection   | 45           | shunt resistor  | 63         |
| load resistor   | 43           | supply voltage  | 62         |
| Discriminator   | 49           | warm-up time  | 74         |
| Oress of Circuit Leads  | 69           | Hexode Mixer  | 59         |
| Oriver  | 27           | High-Fidelity Amplifiers 2                                    | 8, 71      |
| Dynamic Characteristics   | 13           | High-Fidelity, 15-w Audio Amplifier                           | 587        |
|   |              |   |            |

|  | Page      |   | Page           |
|--|-----------|---|----------------|
| High-Fidelity, 50-w Audio Amplifier        | 589       | Pentagrid Mixer                           | 59             |
| High-Voltage Regulation                    | 57        | Pentode Considerations                    | 8              |
| Horizontal Output Circuits                 | 57        | Phase Inverter                            | 36             |
| Hum and Noise Characteristics              | 78        | Phonograph Amplifier                      | 593            |
|  | ***       | Phonograph and Tape Preamplifiers         | 38             |
| IF Amplifier/Limiter and Ratio Detector    | 585       | Picture Tube:                             | E E C          |
| Impedance, Input                           | 17<br>78  | basing diagrams                           | 556<br>554     |
| Input Capacitance                          | 77        | characteristics chart                     | 73             |
| Intercommunication Set                     | 599       | deflection                                | 10             |
| Interelectrode Capacitances                | 7, 78     | dust considerations                       | 73             |
| Intermediate Frequency, Production of .    | 57        | essential elements                        | 10             |
| Interpretation of Tube Data                | 74        | handling precautions                      | 73             |
| Inverse Feedback:                          |           | high-voltage considerations               | 72             |
| constant-current type                      | 31        | humidity considerations                   | 73             |
| constant-voltage type                      | 30        | safety considerations                     | 73             |
| Warn Brains Diagrams Incide Book C         |           | screen                                    | 10             |
| Key: Basing Diagrams Inside Back C         | 10        | structure                                 | 10<br>73       |
| Kinescopes                                 | 10        | x-ray radiation precautions Plate:        | 13             |
| Limiters                                   | 39        | current                                   | 5              |
| Load:                                      |           | dissipation                               | 75             |
| resistance                                 | 21        | efficiency                                | 14             |
| resistance line                            | 19        | load                                      | 21             |
| Low-Distortion preamplifier                | 595       | resistance                                | 13             |
| Luminance Amplifier                        | 41        | voltage supply                            | _ 64           |
|  |           | Plate-Cathode Capacitance                 | 7, 78          |
| Maximum Ratings                            | 74        | Portable 3-Way Superheterodyne            | 670            |
| Mercury-Vapor Rectifier:<br>considerations | 6         | Receiver Power Output:                    | 578            |
| interference from                          | 70        | calculations                              | 19             |
| Mho-micromho                               | 14        | test                                      | 489            |
| Microphone and Phonograph Amplifier .      | 592       | Power Sensitivity                         | 14             |
| Miniature Tube, Structure of               | 88        | Power Supply                              | 597            |
| Mixer:                                     |           | Preamplifier for Amateur Receiver         | 583            |
| audio hexode pentagrid                     | 590       | Preamplifier for Ceramic Phonograph       |                |
| hexode                                     | 59        | Pickup                                    | 593            |
| pentagrid                                  | 59        | Preamplifier for Magnetic Phonograph      | 504            |
| Modulated Wave 45                          | 45<br>45  | Pickup                                    | 594<br>38      |
| Modulation Modulation-Distortion           | 64        | Push-Pull Operation                       | 19             |
| Multi-Electrode and Multi-Unit Tubes .     | 9         | Tush-Tuh Operation                        | .,             |
| Multiplex Adapter for FM Stereo            | 586       | Radio-Frequency:                          |                |
| Multivibrator                              | 54        | amplifier 1                               | 5, 39          |
| Mutual Conductance                         |           | filter                                    | 69             |
| (see Transconductance)                     |           | Ratings:                                  |                |
| ** * .                                     |           | absolute-maximum system                   | 74             |
| Noise 39                                   | 7, 78     | design-center system                      | 74             |
| Noise Figure                               | 40<br>10  | design-maximum system                     | 74             |
| Novar Novar Tube, Parts of                 | 2         | Ratio Detector                            |                |
| Nuvistor                                   | 10        | Receiving Tube Chart                      | 80             |
|  |           | Rectifiers:                               | 5 /2           |
| Operation, Typical Values                  | 78        |   | 5, 43<br>5, 43 |
| Oscillator:                                |           | ionic-heated cathode                      | 6              |
| considerations                             | 54        | ionic-heated cathodeparallel operation of | 43             |
| multivibrator                              | 54        | plate-characteristics curves              | 78             |
| relaxation                                 | 54        | voltage doubler                           | 44             |
| synchroguide                               | 55<br>600 | Relaxation Oscillator                     | 54             |
| Oscilloscope                               | 572       | Remote-Cutoff Tubes                       | 18             |
| Output Capacitance                         | 78        | Resistance-Coupled Amplifiers 17          | , 563          |
| Output Circuits:                           | . 0       | Resistance Coupling                       | 36             |
| horizontal                                 | 57        | Resistor:                                 |                |
| vertical                                   | 56        | cathode (self-biasing)                    | 66             |
| Output-Coupling Devices                    | 71        | center tap                                | 65             |
|  |           | filament                                  | 65             |
| Parallel Operation                         | , 44      | filter                                    | 69             |
| Peak Inverse Plate Voltage                 | 77        | grid                                      | 16             |
| Peak Plate Current                         | 76<br>9   | plate load                                | 21<br>7. 75    |
| I CHIAKITA COMPETICI                       | 7         | Serecii-Riid D                            | 1, 13          |

# RCA Receiving Tube Manual

| Pa  | age |   | Page |
|---|-----|---|------|
| Saturation Current                        | 5   | grid-plate                              | 14   |
| Screen Grid (Grid No.2):                  |     | test                                    | 560  |
| considerations                            | 7   | Triode Considerations                   | 6    |
| input                                     | 75  | Tube:                                   |      |
| voltage supply                            | 67  | outlines                                | 572  |
| Secondary Electrons 8                     | . 9 | ratings, interpretation of              | 74   |
| Secondary Emission                        | 8   | tester requirements                     | 561  |
| Self Bias (cathode bias)                  | 65  | Tube Types, Technical Data              | 89   |
| Shielding                                 | 68  | Tuners, FM                              | 584  |
| Short-Circuit Test 5                      | 559 | Tuning Indicators                       | 53   |
| Signal Generator 5                        | 98  | Twin diode—triode                       | 46   |
| Signal-to-Noise Ratio                     | 40  | Two-Channel Audio Mixer                 | 590  |
| Space Charge                              | , 9 | Two-Channel Stereophonic Amplifier 590, | 591  |
| Static Characteristics                    | 13  | Two-Stage Input Amplifier, Cathode-     |      |
| Stereo Circuits 586, 590, 5               | 91  | Follower (Low-Impedance) Output .       | 594  |
| Superheterodyne Receiver:                 |     | Typical Operation Values.               |      |
| ac/dc 5                                   | 579 | Interpretation of                       | 78   |
| portable 5                                | 377 |   |      |
|   | 78  | Vertical Output Circuits                | 56   |
| Suppressor Grid (Grid No.3)               | 8   |   | 40   |
| Sync Circuits                             | 42  | Video Amplifiers                        | 40   |
| Synchroguide                              | 55  |   | 15   |
|   |     | amplification, class A                  | 44   |
| Tables and Charts (see Charts and Tables) |     | double rectifier                        | 76   |
| Technical Data for Tube Types             | 89  | peak heater-cathode                     | 77   |
|   | 10  | peak inverse plate                      | 62   |
|   | 39  | Supply                                  | 44   |
|   | 42  | Voltage Doubler Volt-Ohm Meter          | 602  |
| Testing Electron Tubes 5                  | 559 |   | 004  |
| Tetrode Considerations                    | 7   | Volume Control:                         |      |
| Three-Stage IF Amplifier/Limiter          |     | automatic (AVC)                         | 50   |
|   | 85  | by grid-voltage variation               | 65   |
|   | 96  | by screen-grid-voltage variation        | 67   |
| Tone Control                              | 36  | delayed automatic (DAVC)                | 51   |
|   | 82  | Volume Compressor and Expander          | 32   |
| Transconductance:                         |     |   |      |
| conversion                                | 14  | Zero-Bias Operation                     | 65   |
|   |     |   |      |

# **RCA** Technical Publications

# on Electron Tubes, Semiconductor Products, and Batteries

COPIES of the publications listed below may be obtained from your RCA distributor or from Commercial Engineering, Radio Corporation of America, Harrison, N. J.

#### **Electron Tubes**

- RCA ELECTRON TUBE HANDBOOK -HB-3 (73/8" x 55/8"). Five 21/4-inchcapacity binders. Contains over 5000 pages of looseleaf data and curves on RCA receiving tubes, transmitting tubes, cathode-ray tubes, picture tubes, photocells, phototubes, camera tubes, ignitrons, vacuum gas rectifiers, travelingwave tubes, premium tubes, pencil tubes, and other miscellaneous types for special applications. Available on subscription basis. Price \$20.00\* including service for first year. Also available RCA Semiconductor Products Handbook HB-10 at special combination price of \$25.00.\*
- RADIOTRON° DESIGNER'S HAND-BOOK—4th Edition (834" x 5½")—1500 pages. Comprehensive reference covering the design of radio and audio circuits and equipment. Written for the design engineer, student, and experimenter. Contains 1000 illustrations, 2500 references, and cross-referenced index of 7000 entries. Edited by F. Langford-Smith.
- RCA PHOTOTUBE AND PHOTOCELL MANUAL—PT-60 (81/4" x 53/8")—192 pages. Well-illustrated informative manual covering fundamentals and operating considerations for vacuum and gas phototubes, multiplier phototubes, and photocells. Also describes basic applications for these devices. Features easyto-use selection chart for multiplier

phototubes. Data and performance curves given for over 90 photo-sensitive devices. Price \$1.50.\*†

- RCA TRANSMITTING TUBES—TT-5 (8½" x 5½")—320 pages. Gives data on over 180 power tubes having plate-input ratings up to 4 kw and on associated rectifier tubes. Provides basic information on generic types, parts and materials, installation and application, and interpretation of data. Contains circuit diagrams for transmitting and industrial applications. Features lie-flat binding. Price \$1,00.\*†
- RCA INTERCHANGEABILITY DIRECTORY OF INDUSTRIAL-TYPE ELECTRON TUBES—ID-1020D (10%" x 834")—12 pages. Lists more than 1600 basic type designations for 20 classes of industrial tube types; shows the RCA Direct Replacement Type or the RCA Similar Type, when available. Price 35 cents,\*†
- RCA RECEIVING-TYPE TUBES FOR INDUSTRY AND COMMUNICATIONS—RIT 104C (10%" x 8%")—44 pages. Technical information on over 190 RCA "special red" tubes, premium tubes, nuvistors, computer tubes, pencil tubes, glow-discharge tubes, small thyratrons, low-microphonic amplifier tubes, mobile communications tubes, and other special types. Includes socket-connection diagrams. Price 35 cents.\*†
- RCA RECEIVING TUBES AND PICTURE TUBES—1275K (10%" x 83%")—64 pages. New, enlarged, and up-to-date booklet contains classification chart, application guide, characteristics chart, and base and envelope connection diagrams on more than 1050 entertainment receiving tubes and picture tubes. Price 50 cents.\*†

- RCA INTERCHANGEABILITY DIRECTORY OF FOREIGN vs. U.S.A. RECEIVING-TYPE ELECTRON TUBES—1CE-197C (8%" x 10%")—8 pages. Covers approximately 800 foreign tube types used principally in AM and FM radios. TV receivers, and audio amplifiers. Indicates U.S.A. direct replacement type or similar type if available. Price 10 cents.\*
- RCA PHOTOCELLS—1CE-261A (10%" x 83%")—32 pages. Contains a selection of photocell-circuit diagrams; technical data and characteristic curves of RCA photoconductive, photojunction, and photovoltaic cells; interchangeability information. Also contains 22 representative circuits. Price 50 cents.\*†
- RCA NUVISTOR TUBES FOR INDUSTRIAL AND MILITARY APPLICATIONS—1CE-280 (107%" x 37%")—16 pages. Describes unique features of nuvistors and includes tabular data, dimensional outlines, curves, terminal diagrams, and socket information. Price 25 cents.\*†
- TECHNICAL BULLETINS—Authorized information on RCA receiving tubes, transmitting tubes, and other tubes for communications and industry. Be sure to mention tube-type bulletin desired. Single-copy on any type free on request.

#### **Semiconductor Products**

- RCA SEMICONDUCTOR PRODUCTS HANDBOOK—HB-10. Two binders, each 73%" L x 55%" W x 23%" D. Contains over 1000 pages of loose-leaf data and curves on RCA semiconductor devices such as transistors, silicon rectifiers, and semiconductor diodes. Available on a subscription basis. Price \$10.00\* including service for first year. Also available with RCA Electron Tube Handbook HB-3 at special combination price of \$25.00.\*
- RCA TRANSISTOR MANUAL—SC-11 (83%" x 53%")—384 pages. Contains up-to-date definitive data on over 600 semiconductor devices including tunnel diodes, silicon controlled rectifiers, varactor diodes, conventional rectifiers,

- and many classes of transistors. Features easy-to-understand text chapters, as well as tabular data on RCA discontinued transistors. Contains over 40 practical circuits, complete with parts lists, highlighting semiconductor-device applications. Price \$1.50.\*†
- RCA TUNNEL DIODE MANUAL—TD-30 (8%" x 5%")—160 pages. Describes the microwave and switching capabilities of tunnel diodes. Contains information on theory and characteristics, and on tunnel-diode applications in switching circuits and in microwave oscillator, converter, and amplifier circuits. Includes data for over 40 RCA germanium and gallium arsenide tunnel diodes and tunnel rectifiers. Price \$1.50.\*†
- RCA SEMICONDUCTOR PRODUCTS GUIDE—3L1010/1L1147 (10%" x 83%")—12 pages. Contains classification chart, index, and ratings and characteristics on RCA's line of transistors, silicon rectifiers, semiconductor diodes, and photocells. Single copy free on request.

#### **Batteries**

- RCA BATTERY MANUAL—BDG-111 (10%" x 8¾")—64 pages. Contains information on dry cells and batteries [carbon zinc (Leclanché), mercury, and alkaline types]. Includes battery theory and applications, detailed electrical and mechanical characteristics, a classification chart, dimensional outlines, and terminal connections on each battery type. Price 50 cents.\*†
- RCA BATTERIES—BAT-134F (107%" x 83%")—24 pages. Technical data on 113 Leclanché, alkaline, and mercurytype dry batteries for radios, industrial applications, flashlights, lanterns, and for photoflash service. Price 35 cents.\*†

<sup>°</sup> Trade Mark Reg. U.S. Pat. Off.

<sup>\*</sup> Prices shown apply in U.S.A. and are subject to change without notice.

<sup>†</sup> Suggested price.

#### KEY: BASING DIAGRAMS (Bottom Views)

| ●<br>BC | Gas-Type Tube<br>Base Sleeve | F-                        | Filament (negative only) | LC | Do Not Use,<br>Except As<br>Specified in |
|---------|------------------------------|---------------------------|--------------------------|----|--|
| BS      | Base Shell                   | $F_{M}$                   | Filament Tap             |    | Data                                     |
| С       | External Con-                | G                         | Grid                     | NC | No Internal                              |
|         | ductive Coating              | Н                         | Heater                   |    | Connection-                              |
| CL      | Collector                    | $\mathbf{H}_{\mathrm{L}}$ | Heater Tap for           |    | May Be Used                              |
| DJ      | Deflecting Elec              |                           | Panel Lamp               |    | As Tie Point                             |
| ES      | trode<br>External Shield     | $H_{\mathrm{M}}$          | Heater Tap               | P  | Plate (Anode)                            |
| ES<br>F | Filament                     | IC                        | Do Not Use               | RC | Ray-Control<br>Electrode                 |
| F-+-    | Filament                     | IS                        | Internal Shield          | S  | Shell                                    |
| - '     | (positive only)              | K                         | Cathode                  | TA | Target                                   |

Subscripts for multi-unit types: B, beam unit; D, diode unit; HP, heptode unit; HX, hexode unit; P, pentode unit; T, triode unit; TR, tetrode unit.

Many tube types are available in addition to the home-entertainment types described in this manual. For industrial and specialized applications, other small receiving-type tubes are available, such as nuvistor tubes, "premium" tubes, thyratrons, cold-cathode (glow-discharge) tubes, computer tubes, tubes for mobile communications applications, and Special Red tubes. Other lines of RCA electron devices include:

#### POWER TUBES

Transmitting and Industrial Types

#### **TELEVISION CAMERA TUBES**

Image Orthicons, Vidicons, and Monoscopes

#### **PHOTOTUBES**

Single-Unit, Twin-Unit, and Multiplier Types

#### **PHOTOCELLS**

Photoconductive and Photojunction Types

#### THYRATRONS and IGNITRONS

#### MICROWAVE TUBES

Magnetrons, Traveling-Wave Tubes, Pencil Tubes

#### CATHODE-RAY TUBES

Special-Purpose Kinescopes, Storage Tubes, and Oscillograph Types

#### SPECIAL TYPES

Vacuum Gauge Tubes, Image Converters

#### SEMICONDUCTOR DEVICES

Germanium and Silicon
Transistors, Silicon Rectifiers,
Tunnel Diodes, Varactor Diodes,
Silicon Controlled Rectifiers,
Memory Devices

## RADIO CORPORATION OF AMERICA

ELECTRONIC COMPONENTS AND DEVICES

HARRISON, N. J.

RCA RECEIVING TUBE MANUAL